

Quote

115 Sourwood Lane, Ste D Groveland, FL 34736 Phone – (352) 638-0416

Date: May 13, 2025

Quote# 1030

Expiration Date: June 13, 2025

To Talichet Lift station Rehab

Qty.	Description	Unit Price	Line Total
	Labor -Remove existing panel and install new Panel including control components and integrate into City's SCADA System 1- Duplex Pump Control Panel 230 Vac 3 phase 10 HP, 29A to include-Nema 3R 304 SS gasketed enclosure powder coated white with inner door, back panel and 3 point latch, Main breaker, 230 Vac 3 phase, Square D Emergency breaker, 230 Vac 3 phase, Generator receptacle with angle adapter, Surge arrestor 230 Vac, Incoming power phase monitor with fuses, (2) Circuit breaker sized for 10 HP 230 Vac 3, (2) FVNR motor starter (size 2), sized for 10 HP 230 Vac 3 phase pump motors (Square D), Current switch, Surge arrestor 120 Vac, 120 Vac control circuit breakers, (2) 3 Position selector switches Hand-Off-Auto, (2) Pilot lights, Non-PTT, Pump Run, (2) Pilot lights, Non-PTT Pump Seal Fail, (1) Pushbutton, Alarm Silence, (2) Run Time meters, (2) Seal Fail relays, (2) Pushbutton, Pump Reset, Float back up control (24 Vac), Alternator, (1) Pushbutton, Float Reset, (1) Pilot light, In Float Backup, PLC, Allen Bradley MicroLogix 1400, Analog input module (Allen Bradley), Operator interface, Cellular modem, Cellular antenna, Transformer (24VAC), GFI receptacle, DC power supply, Battery back-up, Vent drain, Alarm horn, Alarm light, Misc. panel components, nameplates, wire duct, terminals, etc., UL listing, Vega ultrasonic level transmitter, (4) Floats, Float hanger		\$67,178.10
	2- Install 160 LF of 6' black vinyl chain-link fence, (1) 14' wide double gate. (City to provide survey and provide boundary markers)		\$6,240.00
	3- Excavate 6-inches down remove grass and dirt within fenced area, install a mesh weed barrier, spread 29 cubic yards of stone 6-inches thick. ****12-14-week lead time on the panel****		\$9,775.20
	12-14-week lead time on the paner	Total	\$83,193.30

Quotation prepared by: Steve Guba	
To accept this quotation, sign here and return:	

Thank you for your business!

Utility Repair Experts 115 Sourwood Lane, Ste D, Groveland, FL 34736