

Proposal

To: Travis Foley
City of Independence
2018 3 Elms Park Road
Independence, IA 50644
319-334-3750

From: Bob Moen
Visu-Sewer, LLC.
1065 15th Street SW
Mason City, IA 50401
(641) 424-8044

Date: 8/24/2025

Project: 2025 Sanitary Sewer CIPP Installation

Visu-Sewer is pleased to provide the following quotation for CIPP installation:

| | |
|--|-------------|
| 1.) Install 2,043 linear feet of 8" X 6mm National Liner @ \$43.00 per linear foot | \$87,849.00 |
| 2.) Install 650 linear feet of 12" X 6mm National Liner @ \$69.00 per linear foot | \$44,850.00 |

The above listed prices are based on a current video inspection and assumes the current pipe condition is suitable for CIPP installation utilizing air pressure for the inversion and hot air/ steam for curing. Pricing includes:

- Labor, material, and equipment.
- Mobilization and Traffic Control
- One (1) pass jet cleaning and televising of sewers prior to installation.
- Bypass pumping of existing flow.
- Installation of National Liner per manufacturer's instructions, ASTM 1216.
- Reinstatement of all active service connections
- Televising sewers after installation.

NOTE: Due to volatility in material pricing and availability this proposal is valid for 30 days from the date of origination. If a signed proposal has not been received within 30 days price(s) may be adjusted upon mutual agreement, or the proposal may be withdrawn by either party. If needed, grouting of active leaks), and heavy cleaning will be quoted separately. If needed removal of obstructions (e.g., roots, deposits, and protruding taps will be completed at a T&M rate of \$350.00 per hour. If it is determined that current pipe conditions are not suitable for an air inversion and hot air/ steam cure, pricing may be adjusted to reflect alternate installation methods. Mobilization and/or time on site will be billed at a T&M rate of \$350.00 per hour for pipe sections not suitable for CIPP installation.

The City of Independence shall provide drivable equipment access to all manholes, water from nearby hydrants (without charge), a dump site for captured debris, and traffic control beyond cones and signs.

Thank you for the opportunity to quote on this project. Please do not hesitate to call if you have any questions.

All material is guaranteed to be as specified. All work to be completed in a substantial workmanlike manner according to standard practices or specifications submitted. Any alteration or deviation from the above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. The owner to carry fire, tornado, and other necessary insurance. If a collapse of the original pipe results during the lining process, Visu-Sewer, LLC. will not be held liable for costs associated with excavation, repairs, or restoration. Our workers are fully covered by Workmen's Compensation Insurance. Time and material rates are charged "port to port". This proposal may be withdrawn if not accepted within 30 days of issue. Terms - Net 30 days.

Acceptance of Proposal

The above prices / conditions are satisfactory and are hereby accepted. Visu-Sewer, LLC. is authorized to do the work as specified.

Date: _____ Signature: _____

www.visu-sewer.com