

Monday, July 14, 2025

Joel Vitela  
Civil-Con Consultants, LLC  
1445 North Loop West, Suite 325  
Houston, TX 77008  
[jv@civilcontx.com](mailto:jv@civilcontx.com)

Re: Parkway Kia Preliminary Plat  
Letter of Recommendation to Approve  
COIC Project No. 5868  
Adico, LLC Project No. 710-25-002-026


Dear Mr. Vitela:

On behalf of the City of Iowa Colony, Adico, LLC has reviewed the second submittal of Parkway Kia Preliminary Plat, received on or about July 10, 2025. The review of the plat is based on the City of Iowa Colony Subdivision Ordinance dated August 2002, and as amended.

Based on our review, we have no objection to the plat as resubmitted on July 10, 2025. Please provide ten (10) folded copies of the plat to Kayleen Rosser, City Secretary, by no later than Tuesday, July 29, 2025, for consideration at the August 5, 2025, Planning and Zoning meeting.

Should you have any questions, please do not hesitate to call our office.

Sincerely,  
Adico, LLC

  
Dinh V. Ho., P.E.  
TBPE Firm No. 16423

Cc: Rachel Patterson  
Kayleen Rosser  
File 710-25-002-026



WE, DURDIN FAMILY PROPERTIES, LLC, A TEXAS LIMITED LIABILITY COMPANY, ACTING BY AND THROUGH FORBES DURDIN, SOLE MANAGER, OWNERS OF THE PROPERTY SUBDIVIDED, IN THIS PLAT OF PARKWAY KIA, DO HEREBY MAKE SUBDIVISION OF SAID PROPERTY FOR AND ON BEHALF OF SAID CORPORATION, ACCORDING TO THE LINES, LOTS, BUILDING LINES, STREETS, ALLEYS, PARKS AND EASEMENTS AS SHOWN HEREON AND DEDICATE FOR PUBLIC USE, THE STREETS, ALLEYS, PARKS AND EASEMENTS SHOWN HEREON FOREVER, AND DO HEREBY WAIVE ALL CLAIMS FOR DAMAGES OCCASIONED BY THE ESTABLISHMENT OF GRADES AS APPROVED FOR THE STREETS AND DRAINAGE EASEMENTS DEDICATED, OR OCCASIONED BY THE ALTERATION OF THE SURFACE, OR ANY PORTION OF THE STREETS OR DRAINAGE EASEMENTS TO CONFORM TO SUCH GRADES, AND DO HEREBY BIND OURSELVES, OUR HEIRS, SUCCESSORS AND ASSIGNS TO WARRANT AND DEFEND THE TITLE TO THE LAND SO DEDICATED.

FURTHER, LIENHOLDERS MUST EXECUTE A SUBORDINATION AGREEMENT SUBORDINATING THEIR LIENS TO ALL PUBLIC STREETS, ALLEYS, PARKS, SCHOOL SITES AND OTHER PUBLIC AREAS SHOWN ON THE PLAT OF SUCH SUBDIVISION OR RESUBDIVISION AS BEING SET ASIDE FOR PUBLIC USE OR PURPOSE.

FURTHER, OWNERS HAVE DEDICATED AND BY THESE PRESENTS DO DEDICATE TO USE OF THE PUBLIC UTILITY PURPOSES FOREVER UNOBSTRUCTED AERIAL EASEMENTS. THE AERIAL EASEMENTS SHALL EXTEND HORIZONTALLY AN ADDITIONAL ELEVEN FEET, SIX INCHES (11'6") FOR TEN FEET (10'0") PERIMETER GROUND EASEMENTS, OR SEVEN FEET, SIX INCHES (7'6") FOR FOURTEEN FEET (14'0") PERIMETER GROUND EASEMENTS, OR FIVE FEET, SIX INCHES (5'6") FOR SIXTEEN FEET (16'0") PERIMETER GROUND EASEMENTS, FROM A PLANE SIXTEEN FEET (16'0") ABOVE GROUND LEVEL UPWARD, LOCATED ADJACENT TO AND ADJOINING SAID PUBLIC UTILITY EASEMENTS THAT ARE DESIGNATED WITH AERIAL EASEMENTS (U.E. AND A.E.) AS INDICATED AND DEPICTED, HEREON, WHEREBY EACH AERIAL EASEMENT TOTALS TWENTY ONE FEET, SIX INCHES (21'6") IN WIDTH.

FURTHER, OWNERS HAVE DEDICATED AND BY THESE PRESENTS DO DEDICATE TO USE OF THE PUBLIC FOR PUBLIC UTILITY PURPOSES FOREVER UNOBSTRUCTED AERIAL EASEMENTS. THE AERIAL EASEMENTS SHALL EXTEND HORIZONTALLY AN ADDITIONAL TEN FEET (10'0") FOR TEN FEET (10'0") BACK-TO-BACK GROUND EASEMENTS, OR EIGHT FEET (8'0") FOR FOURTEEN FEET (14'0") BACK-TO-BACK GROUND EASEMENTS, OR SEVEN FEET (7'0") FOR SIXTEEN FEET (16'0") BACK-TO-BACK GROUND EASEMENTS, FROM PLAN SIXTEEN FEET (16'0") ABOVE GROUND LEVEL UPWARD, LOCATED ADJACENT TO AND ADJOINING SAID PUBLIC UTILITY EASEMENTS THAT ARE DESIGNATED WITH AERIAL EASEMENTS (U.E. AND A.E.) AS INDICATED AND DEPICTED, HEREON, WHEREBY EACH AERIAL EASEMENTS TOTALS THIRTY FEET (30'0") IN WIDTH.

IN TESTIMONY, HERETO, DURDIN FAMILY PROPERTIES, LLC HAS CAUSED THESE PRESENTS TO BE SIGNED BY FORBES DURDIN, ITS SOLE MANAGER, THEREUNTO AUTHORIZED, AND ITS COMMON SEAL HEREUNTO AFFIXED, THIS \_\_\_\_ DAY OF \_\_\_\_\_, 2025.

DURDIN FAMILY PROPERTIES, LLC  
A TEXAS LIMITED LIABILITY COMPANY

FORBES DURDIN, SOLE MANAGER

STATE OF TEXAS  
COUNTY OF HARRIS


BEFORE ME, THE UNDER SIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED FORBES DURDIN, SOLE MANAGER OF DURDIN FAMILY PROPERTIES, LLC, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENTS, AND ACKNOWLEDGED TO ME THAT THE SAME WAS THE ACT OF SAID CORPORATION, FOR THE PURPOSE AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITIES THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_ DAY OF \_\_\_\_\_, 2025.

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS

I, GRACE CERVIN, AM REGISTERED UNDER THE LAWS OF THE STATE OF TEXAS TO PRACTICE THE PROFESSION OF SURVEYING AND HEREBY CERTIFY THAT THE ABOVE SUBDIVISION IS TRUE AND CORRECT; WAS PREPARED FROM AN ACTUAL SURVEY OF THE PROPERTY MADE UNDER MY SUPERVISION ON THE GROUND; THAT ALL CORNERS AND ANGLE POINTS OF THE BOUNDARIES OF THE ORIGINAL TRACT TO BE SUBDIVIDED OF REFERENCE WILL BE MARKED WITH IRON RODS HAVING A DIAMETER OF NOT LESS THAN FIVE EIGHTHS (5/8) INCH AND A LENGTH OF NOT LESS THAN (3) FEET WITHIN A MAXIMUM OF ONE YEAR AFTER RECORDING OF THE PLAT OR AFTER CONSTRUCTION OF THE PUBLIC IMPROVEMENTS ARE COMPLETE, UNLESS OTHERWISE SHOWN HEREON; AND THAT THE PLAT BOUNDARY CORNERS HAVE BEEN TIED TO THE TEXAS COORDINATE SYSTEM, SOUTH CENTRAL ZONE (4204) NORTH AMERICAN DATUM OF 1983 (NAD83) CORRS. ADJUSTMENT.

GRACE CERVIN, R.P.L.S.  
TEXAS REGISTRATION No. 5564



METES AND BOUNDS DESCRIPTION

BEING A 25.72 ACRES (1,120,165 SQUARE FEET) TRACT OF LAND SITUATED IN THE H.T.&B. RR. CO. SURVEY, SECTION 51, ABSTRACT NO. 288, BRAZORIA COUNTY, TEXAS, BEING OUT OF AND PART OF LOTS 608, 609, 622, 623, 624 & 625 AND PORTIONS OF TWO 40-FOOT WIDE UNNAMED AND UNIMPROVED ROADS, OF THE EMIGRATION LAND COMPANY PLAT OF SECTIONS 50, 51, & 56 H.T.&B. AND OF 2, 3, & 4 L&N., A SUBDIVISION OF RECORD ACCORDING TO THE MAP OR PLAT THEREOF RECORDED UNDER VOLUME 2, PAGE 133 OF THE PLAT RECORDS OF BRAZORIA COUNTY, TEXAS AND BEING ALL OF A CALLED 3.979 ACRES (TRACT 3) OF LAND AND OUT OF AND A PORTION OF A CALLED 45.63 ACRES (TRACT 1) OF LAND AS DESCRIBED IN A SPECIAL WARRANTY DEED WITH VENDOR'S LIEN AS CONVEYED TO SIERRAVISTA-383 INVESTMENTS, LLC, A TEXAS LIMITED LIABILITY COMPANY AND RECORDED UNDER BRAZORIA COUNTY CLERK'S FILE (B.C.C.F.) NO. 2019045563 OF THE OFFICIAL PUBLIC RECORDS OF BRAZORIA COUNTY, TEXAS (O.P.R.B.C.T.); SAID 12.00 ACRE TRACT BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS (BEARING BASIS BASED ON TEXAS COORDINATE SYSTEM OF 1983, SOUTH CENTRAL ZONE NO. 4204 (NAD 1983)):

BEGINNING AT A 5/8-INCH IRON ROD WITH CAP STAMPED "BASELINE" FOUND ON THE WEST RIGHT-OF-WAY LINE OF STATE HIGHWAY 288 (VARIABLE WIDTH AS RECORDED UNDER VOLUME 1043, PAGE 908 OF THE BRAZORIA COUNTY DEED RECORDS, TEXAS (B.C.D.R.T.)) AND BEING THE SOUTHEAST CORNER OF RESTRICTED RESERVE E, BLOCK 2, OF KARSTEN BOULEVARD PHASE I STREET DEDICATION AS RECORDED UNDER DOCUMENT NO. 2018053860 OF THE PLAT RECORDS OF BRAZORIA COUNTY, TEXAS, AND BEING THE NORTHEAST CORNER OF SAID 3.979 ACRE TRACT (TRACT 3) AND THE NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT, AND THE BEGINNING OF A CURVE TO THE RIGHT FROM WHICH ITS RADIUS POINT BEARS SOUTH 59°26'23" WEST, 1273.24 FEET;

THENCE, IN A SOUTHEASTERLY DIRECTION, ALONG THE WEST RIGHT-OF-WAY LINE OF STATE HIGHWAY 288 AND THE EAST LINE OF SAID 3.979 ACRE TRACT (TRACT 3) AND SAID CURVE TO THE RIGHT, ALONG AN ARC LENGTH OF 405.17 FEET, A RADIUS DISTANCE OF 1273.24 FEET, HAVING A CENTRAL ANGLE OF 181°5'58", AND WHOSE CHORD BEARING AND DISTANCE BEARS SOUTH 21°28'38" EAST, 403.47 FEET TO A POINT OF TANGENCY, FROM WHICH A 3/4-INCH ROD FOUND BEARS SOUTH 70°19'49" EAST, 0.14 FEET AND A T&DOT CONCRETE MONUMENT FOUND BEARS SOUTH 16°20'35" EAST, 2.84 FEET;

THENCE, SOUTH 12°19'41" EAST, CONTINUING ALONG THE WEST RIGHT-OF-WAY LINE OF STATE HIGHWAY 288 AND THE EAST LINE OF SAID 3.979 ACRE TRACT (TRACT 3), PASS AT A DISTANCE OF 18.24 FEET THE SOUTHEAST CORNER OF SAID 3.979 ACRE TRACT (TRACT 3) AND THE NORTHEAST CORNER OF SAID 45.63 ACRE TRACT (TRACT 1), AND CONTINUING WITH THE EAST LINE OF SAID 45.63 ACRE TRACT (TRACT 1) FOR A TOTAL DISTANCE OF 584.87 FEET TO A 5/8-INCH STEEL ROD WITH CAP STAMPED "ALLY" SET FOR AN ANGLE POINT OF THE HEREIN DESCRIBED TRACT;

THENCE, SOUTH 02°19'40" EAST, CONTINUING ALONG THE WEST RIGHT-OF-WAY LINE OF STATE HIGHWAY 288 AND THE EAST LINE OF SAID 45.63 ACRE TRACT (TRACT 1), A DISTANCE OF 868.85 FEET TO A 5/8-INCH STEEL ROD FOUND FOR THE NORTHEAST CORNER OF A CALLED 22.3121 ACRE TRACT (TRACT A) AS DESCRIBED IN A GIFT DEED AS CONVEYED TO TEXAS MEDICAL CENTER, A TEXAS NONPROFIT CORPORATION AS RECORDED UNDER B.C.C.F. NO. 02-043288 SAME BEING THE SOUTHEAST CORNER OF SAID 45.63 ACRE TRACT (TRACT 1) AND THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, SOUTH 87°16'10" WEST, DEPARTING THE WEST RIGHT-OF-WAY LINE OF STATE HIGHWAY 288 ALONG THE SOUTH LINE OF SAID 45.63 ACRE TRACT (TRACT 1), A DISTANCE OF 868.85 FEET TO A 5/8-INCH STEEL ROD FOUND FOR THE NORTHEAST CORNER OF A CALLED 22.3121 ACRE TRACT (TRACT A) AS DESCRIBED IN A GIFT DEED AS CONVEYED TO TEXAS MEDICAL CENTER, A TEXAS NONPROFIT CORPORATION AS RECORDED UNDER B.C.C.F. NO. 02-043288 SAME BEING THE SOUTHEAST CORNER OF SAID 45.63 ACRE TRACT (TRACT 1) AND THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;



THENCE, NORTH 02°32'26" WEST, WITH THE WEST LINE OF SAID 80-FOOT CENTERPOINT ENERGY EASEMENT, AND THROUGH THE INTERIOR OF SAID 45.63 ACRE TRACT (TRACT 1), A DISTANCE OF 1,897.78 FEET TO A 5/8-INCH STEEL ROD WITH CAP STAMPED "ALLY" SET AND BEING THE NORTHWEST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, NORTH 87°27'34" EAST, CROSSING THROUGH THE SAID 80-FOOT CENTERPOINT ENERGY EASEMENT, PASS AT A DISTANCE OF 65.00 FEET FOR THE SOUTHWEST CORNER OF UNRESTRICTED RESERVE E, BLOCK 2 OF KARSTEN BOULEVARD PHASE I STREET DEDICATION SUBDIVISION AND BEING A CORNER ON THE EAST LINE OF SAID 45.63 ACRE TRACT (TRACT 1), AND CONTINUING WITH THE SOUTH LINE OF UNRESTRICTED RESERVE E AND THE EAST LINE OF SAID 45.63 ACRE TRACT (TRACT 1), FOR A TOTAL DISTANCE OF 72.27 FEET TO A 5/8-INCH IRON ROD WITH CAP STAMPED "BASELINE" FOUND FOR AN ANGLE POINT;

THENCE, NORTH 68°18'22" EAST, CONTINUING WITH THE SOUTH LINE OF UNRESTRICTED RESERVE E AND THE EAST LINE OF SAID 45.63 ACRE TRACT (TRACT 1), PASS AT A DISTANCE OF 818 FEET A 5/8-INCH IRON ROD WITH CAP STAMPED "BASELINE" FOUND AND BEING THE NORTHWEST CORNER OF SAID 3.979 ACRE TRACT (TRACT 3), AND CONTINUING WITH THE NORTH LINE OF SAID 3.979 ACRE TRACT (TRACT 3) AND THE SOUTH LINE OF UNRESTRICTED RESERVE E FOR A TOTAL DISTANCE OF 399.80 FEET TO THE POINT OF BEGINNING AND CONTAINING 25.72 ACRES (1,120,165 SQUARE FEET) OF LAND.


NOTES:

- BEARINGS ARE BASED FROM THE TEXAS COORDINATE SYSTEM, SOUTH CENTRAL ZONE (4204). NAD 83 CORRS ADJUSTMENT BASED FROM REDUNDANT RTK GPS OBSERVATIONS. DISTANCES HEREON ARE SURFACE DATUM. TO CONVERT TO GRID MULTIPLY BY A COMBINED PROJECT ADJUSTMENT FACTOR OF 0.99988213. COORDINATES HEREON ARE GRID DATUM. TO CONVERT TO SURFACE DIVIDE BY A COMBINED PROJECT ADJUSTMENT FACTOR OF 0.99988213.
- THIS TRACT OF LAND LIES WITHIN UNSHADED ZONE 'X'. AREAS DETERMINED TO BE OUTSIDE THE 500-YEAR FLOODPLAIN ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP No. 48039C0110H AND 48039C0120H, BOTH DATED JULY 5, 1989.
- THIS TRACT OF LAND LIES WITHIN THE EXTRA-TERRITORIAL JURISDICTION OF THE CITY OF IOWA COLONY AND BRAZORIA DRAINAGE DISTRICT NO. 5 IS SUBJECT TO ITS CODE OF ORDINANCES.
- ALL STORM SEWERS WILL BE MAINTAINED BY PROPERTY OWNER.
- OWNER WILL PROVIDE EASEMENTS FOR POWER LINES WHERE SUCH ARE REQUIRED, EITHER AS SHOWN ON THE PLAT OR BY SEPARATE INSTRUMENT DEDICATION.
- ALL WATER AND WASTEWATER FACILITIES SHALL CONFORM TO THE CITY OF IOWA COLONY'S ENGINEERING DESIGN CRITERIA MANUAL.
- SURVEY MONUMENTS SHALL BE SET TO THE STANDARDS OF THE TEXAS SOCIETY OF PROFESSIONAL LAND SURVEYING PRACTICES ACT AND THE GENERAL RULES OF PROCEDURES AND PRACTICES OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING AND SHALL BEAR REFERENCE CAPS AS INDICATED.



LEGEND

B.L.	BUILDING LINE
C.M.	CONTROLLING MONUMENT
ESMT.	EASEMENT
F.C.	FILE CODE
FND.	FOUND
H.C.D.R.	HARRIS COUNTY DEED RECORDS
H.C.M.R.	HARRIS COUNTY MAP RECORDS
H.C.C.F.	HARRIS COUNTY CLERK FILE
HOMUD	HARRIS COUNTY MUNICIPAL DISTRICT
I.R.C.	IRON ROD CAPPED
I.P.	IRON PIPE
O.P.R.R.P.H.C.T.	OFFICIAL PUBLIC RECORDS OF REAL PROPERTY HARRIS COUNTY TEXAS
SET	SET 5/8-INCH STEEL ROD WITH CAP STAMPED "ALLY" SQUARE FEET
SO FT	SQUARE FEET
STM	STORM
SAN. S.E.	SANITARY SEWER EASEMENT
U.V.E.	UNOBSTRUCTED VISIBILITY EASEMENT



CERTIFICATE OF PLANNING COMMISSION

THIS IS TO CERTIFY THAT CITY PLANNING COMMISSION OF THE CITY OF IOWA COLONY, TEXAS THIS THE \_\_\_\_ DAY OF \_\_\_\_\_, 2025, HAS APPROVED THIS PLAT AND SUBDIVISION OF PARKWAY KIA AS SHOWN HEREON.

DAVID HURST	BRENDA DILLON
LES HOSEY	BRIAN JOHNSON
TERRY HAYES	ROBERT WALL
WARREN DAVIS	

APPROVED BY CITY ENGINEER

DINH V. HO, P.E. DATE

CERTIFICATE OF CITY COUNCIL

THIS IS TO CERTIFY THAT CITY COUNCIL OF THE CITY OF IOWA COLONY, TEXAS THIS THE \_\_\_\_ DAY OF \_\_\_\_\_, 2025, HAS APPROVED THIS PLAT AND SUBDIVISION OF PARKWAY KIA AS SHOWN HEREON.

WILL KENNEDY, MAYOR	NIKKI BROOKS
ARNETTA HICKS-MURRAY	MARQUETTE GREENE-SOOTT
TIMOTHY VARLACK	KAREEM BOYCE
SYDNEY HARGRODER	

BRAZORIA COUNTY DRAINAGE DISTRICT #5

LEE WALDEN PRESIDENT	KERRY OSBURN VICE PRESIDENT
-------------------------	--------------------------------

BRANDON MIDDLETON  
SECRETARY / TREASURER

DINH V. HO, P.E.  
DISTRICT ENGINEER

BRAZORIA COUNTY DRAINAGE DISTRICT No. 5 NOTES

- SLAB ELEVATIONS SHALL BE A MINIMUM OF 12" ABOVE THE CROWN OF THE ROAD AND/OR 2' ABOVE THE BFE.
- ALL DRAINAGE EASEMENTS SHOWN HEREON SHALL BE KEPT CLEAR OF FENCES, BUILDINGS, PLANTINGS, AND OTHER OBSTRUCTIONS TO THE OPERATION AND MAINTENANCE OF DRAINAGE FACILITIES.
- ALL PROPERTY SHALL DRAIN INTO THE DRAINAGE EASEMENT ONLY THROUGH AN APPROVED DRAINAGE STRUCTURE.
- ALL DRAINAGE EASEMENTS AND DETENTION POND RESERVES SHOWN ON THIS PLAT WILL BE MAINTAINED BY THE PROPERTY OWNERS AND/OR BUSINESS OWNERS; PROVIDED HOWEVER, ANY GOVERNMENTAL ENTITY HAVING JURISDICTION, INCLUDING, WITHOUT LIMITATION, BRAZORIA COUNTY, TEXAS AND BRAZORIA COUNTY DRAINAGE DISTRICT #5, SHALL HAVE THE RIGHT, BUT NOT THE OBLIGATION TO ENTER UPON THE DRAINAGE EASEMENT TO PERFORM MAINTENANCE OPERATIONS AT ANY TIME AFTER DATE HEREOF.
- THE PROPERTY IDENTIFIED IN THE FOREGOING PLAT LIES WITHIN BRAZORIA COUNTY DRAINAGE DISTRICT #5.
- OTHER THAN SHOWN HEREON, THERE ARE NO PIPELINE EASEMENTS OR PIPELINES WITHIN THE BOUNDARIES OF THIS PLAT.
- ALL STORM WATER DRAINAGE PIPES, CULVERTS, TILES, OR OTHER (INCLUDING DRIVEWAY CULVERTS) WILL BE MINIMUM 24" I.D. OR EQUAL.
- PROHIBITED USE OF "METAL" PIPE IN STORM WATER/SEWER APPLICATIONS (SEE DISTRICT RESOLUTION NO. 2007-08).
- PROHIBITED USE OF "RIP-RAP" IN STORM WATER/SEWER APPLICATIONS (DISTRICT POLICY).
- PIPELINES, UTILITY LINES AND OTHER CROSSINGS UNDER ANY BRAZORIA COUNTY DRAINAGE DISTRICT #5 DITCH REQUIRE APPROVAL AND PERMITTING PRIOR TO CONSTRUCTION.
- ALL DEDICATED STORM WATER DRAINAGE AND/OR ACCESS EASEMENTS TO BE GRANTED TO BRAZORIA COUNTY DRAINAGE DISTRICT #5 BY PROPERTY OWNER WILL BE INITIATED AND RECORDED AT PROPERTY OWNER'S EXPENSE IN BRAZORIA COUNTY, TEXAS WITH A "RECORDED DOCUMENT NUMBER" AFFIXED TO SAID EASEMENT PRIOR TO FINAL PROJECT APPROVAL GRANTED BY BRAZORIA COUNTY DRAINAGE DISTRICT #5 BOARD OF COMMISSIONERS.
- PROJECT FIELD START-UP WILL START WITHIN 365 CALENDAR DAYS FROM DATE SHOWN HERE. CONTINUOUS AND REASONABLE FIELD SITE WORK IS EXPECTED. SEE BRAZORIA COUNTY DRAINAGE CRITERIA MANUAL SECTION 1, INTRODUCTION; SUB-SECTION 1.5. PLAT AND PLAN APPROVAL PROCESS, AND DRAINAGE ACCEPTANCE PROCEDURES. TIME LIMIT FOR APPROVAL AND BRAZORIA COUNTY DRAINAGE DISTRICT #5 RESOLUTION 2011-1, ALLOWABLE TIME(S) AND PROCEDURES FOR STARTING-UP APPROVED PROJECTS.

## PRELIMINARY PLAT PARKWAY KIA

A SUBDIVISION OF 25.72 ACRES OF LAND  
SITUATED IN  
THE H.T.&B. R.R. CO. SURVEY, SECTION 51, ABSTRACT NO. 288  
BRAZORIA COUNTY, TEXAS

CONTAINING: 1 RESTRICTED RESERVE AND 1 BLOCK

DATE: JULY 2025

OWNER:	ENGINEER:	SURVEYOR:
DURDIN FAMILY PROPERTIES, LLC 22251 TX-249 TOMBALL, TEXAS 77375 (832) 717-1706	CIVIL-CON CONSULTANTS, LLC TBPE FIRM REGISTRATION NO. 22251 1445 NORTH LOOP WEST, SUITE 325 HOUSTON, TEXAS 77008 (713) 992-4148	AGS ENGINEERING & CONSTRUCTION TBPELS FIRM NO. 10194392 5300 HOLLISTER RD, SUITE 111 HOUSTON, TEXAS 77040 (281) 888-7682