

Materials Cost Estimate for Project: Cr 57

A05-0034

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
from coral reef 6000- ft	1.14	0	Alv	Nor	4	IS	2026

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ARE-68 Recycling Emulsion	1.14	22		1.4	Gal/SqYd	20,533	Gal	2.96	60,779
Base - crushed concr.	1.14	22	6			4,818	Ton	28.00	134,904
CSS1 for prime	1.50	20		0.1	Gal/SqYd	1,760	Gal	3.18	5,597
Asphalt - HMAC Type D	1.50	20	2			1,927	Ton	86.00	165,739

Project Cost:	367,019
----------------------	---------