



OFFICE OF AUDITOR OF STATE
STATE OF IOWA

Rob Sand
Auditor of State

State Capitol Building
Des Moines, Iowa 50319-0004
Telephone (515) 281-5834

March 16, 2026

Kristi Onstot
Executive Council
L O C A L

Subject: Flood Damages to Rock Creek State Park in Jasper County on May 21, 2024
FEMA Declared Disaster DR4784
Department of Natural Resources
Claim dated March 9, 2026
AOS Claim ID: 3759

In accordance with Executive Council policy, we have examined the claim for 29C.20 funds for the above-mentioned damage. The estimated repair costs total \$341,399.68 with FEMA approving grants for 75% of the total. The FEMA share totals \$256,049.76 and the State's share is \$85,349.92. The Department of Natural Resources is requesting an allocation for the State's share.

It is our conclusion that the above damage incurred by the Department of Natural Resources is covered by Chapter 29C.20 of the Code of Iowa. Therefore, we recommend an Executive Council allocation in the amount of \$85,349.92, subject to an audit of actual invoices.

Sincerely,

A handwritten signature in black ink, appearing to read "Brian R. Brustkern".

Brian R. Brustkern, CPA
Deputy Auditor of State

cc: Kayla Lyon, Director, Department of Natural Resources
Sherry Arntzen, Bureau Chief, Parks, Forests and Preserves Bureau, Department
of Natural Resources
Kara Bryant, Budget & Finance, Department of Natural Resources
Heather Hackbarth, Department of Management

March 12, 2026

Kristi Onstot
Executive Council
State Capitol
LOCAL

Tammy Hollingsworth
Auditor's Office
Lucas Building
LOCAL

RE: Rock Creek Flooding

Dear Kristi and Tammy:

On Tuesday, May 21, 2024, a major flood event occurred at Rock Creek State Park in Jasper County. This damage was reported by Elizabeth Thacker on May 21, 2024, and is deemed eligible for FEMA funding under Disaster #4784DR-IA. DNR is requesting 25% of the total cost to cover the damages. FEMA will be covering the remaining 75% of the cost.

The supporting documents include:

- FEMA Finalized PW 256 for PA 4784

This information is being submitted to the Executive Council as a request for allocation of \$85,349.92 for AOS ID #3759.

I thank you and the Executive Council members for your time and consideration in reviewing this material. Please inform me if it would be advantageous to participate in the Executive Council meeting in order to answer any questions.

Sincerely,

Sherry L. Arntzen, Bureau Chief
Parks, Forests and Preserves Bureau

Cc: Kara Bryant, DNR Budget and Finance

Attachments: 1

Department of Homeland Security Federal Emergency Management Agency

General Info

Project #	802631	PW #	256	Project Type	Estimated Costs
Project Category	G - Parks, Recreational Facilities, and Other Items			Applicant	Iowa Department of Natural Resources - Parks Bureau (000-0011A-00)
Project Title	4784 IDNR Parks - Rock Creek Park			Event	4784DR-IA (4784DR)
Project Size	Small			Declaration Date	5/24/2024
Activity Completion Date	5/24/2028			Incident Start Date	5/20/2024
Process Step	Obligated			Incident End Date	5/31/2024

Damage Description and Dimensions

The Disaster # 4784DR, which occurred between **05/20/2024** and **05/31/2024**, caused:

Damage #1413293; East Trail 1

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** East Trail 1 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74680, -92.83885

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major flooding to overtop the trail and scour the downstream side of the culvert.

Facility Damage:

- Trail, 6 CY of 20-foot long 24-inch corrugated poly culvert with 6-inch minus roadstone, 8 FT long x 10 FT wide x 2 FT deep, excessive rain caused flooding to overtop the trail and scour the 6-inch roadstone from the culvert, 0% work completed.

Damage #1413294; East Trail 2

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was

dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.

- **Year Built:** 1952
- **Location Description:** East Trail 2 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74534, -92.83614

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major flooding.

Facility Damage:

- Trail, 27.8 CY of unclassified fill supporting a 20-foot 24-inch corrugate poly culvert, 25 FT long x 10 FT wide x 3 FT deep, flooding caused by excessive rain overtopped the trail and displaced the roadstone, 0% work completed.
- Trail, 9.3 CY of 6-inch roadstone minus, 25 FT long x 10 FT wide x 1 FT deep, surface flooding washed out the outlet protection, 0% work completed.

Damage #1413296; East Trail

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** East Trail Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74513, -92.86263

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain caused flooding which caused severe erosion of the river bank threatening the trail.

Facility Damage:

- Trail, 55.6 CY of unclassified fill from river bank erosion is threatening the East Trail, 125 FT long x 2 FT wide x 6 FT deep, caused by flood waters from excessive rain, 0% work completed.

Damage #1413297; South End Trail 1

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** South End Trail 1 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74262, -92.84448

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major flooding.

Facility Damage:

- Trail, 1 each of 16-foot long of 8-inch PVC pipe culvert, flooding scoured the unclassified fill surrounding the culvert, 0% work completed.

Damage #1413298; South End Trail 2

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** South End Trail 2 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.73773, -92.84867

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major flooding.

Facility Damage:

- Trail, 1 each of 20-foot long 24-inch CMP culvert, the culvert was completely washed out and destroyed by the flood water, 0% work completed.
- Trail, 9.7 CY of Unclassified fill, 14 FT long x 8 FT wide x 28 IN deep, Flood water washed out the support for the 20-foot long 24-inch culvert, 0% work completed.

Damage #1413300; South Ouerlook Trail

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** South Overlook Trail Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.73773, -92.86087

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** trail was washout due to excessive rain with 9-inches of rain in 6 hours caused major flooding

Facility Damage:

Trail, 9.7 CY of Unclassified fill, 14 FT long x 8 FT wide x 28 IN deep, Flood water washed out the support for the 20-foot long 24-inch culvert, 0% work completed.

- Trails, 9.5 CY of Hiking trail consisting of unclassified fill, 30 FT long x 17 FT wide x 6 IN high, Unclassified fill was washed out during the flood event , 0% work completed.

Damage #1413301; SW Trail

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** SW Trail Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.73921, -92.86482

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** excessive rain with 9-inches of rain in 6 hours caused major flooding.

Facility Damage:

- Trail, 4.5 CY of 24-inch corrugated poly culvert with class E 24-inch riprap, 4 FT long x 10 FT wide x 3 FT deep, excessive rain with 9-inches of rain in 6 hours caused major flooding which overtopped the trail and caused the riprap to be displaced., 0% work completed.

Damage #1413302; West Trail 1

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 1 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74793, -92.85969

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Trail washout caused by flooding from excessive rain with 9-inches of rain in 6 hours

Facility Damage:

- Trail, 11.2 CY of hiking and equestrian trail, 120 FT long x 15 FT wide x 2 IN deep, 3/4-inch roadstone minus was washed away during the flooding event , 0% work completed.

Damage #1413303; West Trail 2

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was

dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.

- **Year Built:** 1952
- **Location Description:** West Trail 2 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74824, -92.86037

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** excessive rain with 9-inches of rain in 6 hours caused major flooding.

Facility Damage:

- Trail culvert, 12.5 CY of unclassified fill supporting 20-foot corrugated poly culvert under a hiking and equestrian trail, 6 FT long x 14 FT wide x 4 FT deep, Flooding from excessive rain caused scouring of the culvert, 0% work completed.
- Trail culvert, 6 CY of 6-inch roadstone minus armoring a 20-foot 24-inch corrugated poly culvert under a hiking and equestrian trail, 4 FT long x 10 FT wide x 4 FT deep, 6-inch roadstone was scoured by flooding caused by excessive rain, 0% work completed.

Damage #1413304; West Trail 3

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 3 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74829, -92.86071

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Trail, 8.7 CY of 3/4-inch roadstone minus, 140 FT long x 10 FT wide x 2 IN deep, trail surface was washed out/displaced by surface flooding, 0% work completed.
- Trail, 17.4 CY of 3-inch roadstone minus, 140 FT long x 10 FT wide x 4 IN deep, trail base was washed out/displaced by surface flooding, 0% work completed.

Damage #1413305; West Trail 4

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 4 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135

- **GPS Latitude/Longitude:** 41.75170, -92.86323

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Trail, 14.9 CY of 3/4-inch roadstone minus, 120 FT long x 10 FT wide x 4 IN deep, surface flooding washed-out/displaced the trail surface, 0% work completed.

Damage #1413306; West Trail 5

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 5 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 42.75322, -92.86914

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Trail, 6 CY of unclassified fill supporting a 20-foot long 24-inch corrugated poly culvert, 12 FT long x 20 FT wide x 4 FT deep, excessive rain caused significant surface flooding washing out the culvert, 0% work completed.
- Trail, 3.6 CY of 6-inch roadstone minus, 19 FT long x 10 FT wide x 6 IN deep, significant surface flooding washed out and displaced the roadstone armor, 0% work completed.

Damage #1413307; West Trail 6

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 6 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74735, -92.87020

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** excessive rain with 9-inches of rain in 6 hours caused major surface flooding causing overtopping of the trail and washout of the culvert

Facility Damage:

- Trail, 8 CY of unclassified fill was washed out on outlet face of a 20-foot 24-inch corrugated poly culvert, 12 FT long x 12 FT wide x 9 FT deep, excessive rain caused surface flooding to overtopped the trail, 0% work completed.

Damage #1413308; West Trail 7

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 7 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74689, -92.86617

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Trail, 14.7 CY of Unclassified fill at outlet of 20-foot long 18-inch corrugated poly culvert, 18 FT long x 11 FT wide x 2 FT deep, surface flooding overtopped the trail and scoured the unclassified fill from the culvert outlet, 0% work completed.
- Trail, 3.7 CY of 6-inch roadstone minus armor at outlet of 18-inch corrugated poly culvert, 18 FT long x 11 FT wide x 6 IN deep, the 6-inch roadstone armor was washed away due to surface flooding overtopping the trail, 0% work completed.

Damage #1413309; West Trail 8

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 8 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74447, -92.86184

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours caused surface flooding.

Facility Damage:

- Trail, 5.6 CY of unclassified fill at 20-foot long 24-inch corrugated poly culvert , 14 FT long x 16 FT wide x 4 FT deep, surface water flooding from excessive rain caused overtopping of the trail and washout of the outlet, 0% work completed.
- Trail, 4.2 CY of 6-inch roadstone minus , 14 FT long x 16 FT wide x 6 IN deep, excessive rain caused surface flooding and overtopping of the trail and washed out the armor from culvert outlet, 0% work completed.

Damage #1413310; West Trail 9

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Trail 9 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74418, -92.86167

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6-hours, caused surface flooding.

Facility Damage:

- Trail, 9.3 CY of 3/4-inch roadstone minus, 125 FT long x 12 FT wide x 2 IN deep, surface flooding scoured the trail surface, 0% work completed.
- Trail, 18.6 CY of unclassified fill, 125 FT long x 12 FT wide x 4 IN deep, surface flooding scoured the trail surface, 0% work completed.

Damage #1413311; 24 hr trail

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** 24 hour Trail Bridge Replacement
- **GPS Latitude/Longitude:** 41.76140, -92.84453

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain caused flooding on the 24-hour Trail

Facility Damage:

- Trail, 1 each of 30-foot x 6-foot wood cantilever bridge with steel girders and wood sleeper supports, excessive rain caused flood waters to rise and damage the bridge, 0% work completed.

Damage #1413312; Interp trail 1

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park

is a popular spot for cross-country skiing and snowmobiling.

- **Year Built:** 1952
- **Location Description:** Interp Trail 1
- **GPS Latitude/Longitude:** 41.75715, -92.83576

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rains, 9-inches in 6 hours caused surface flooding.

Facility Damage:

- Trail , 9.5 CY of unclassified fill supporting a 16-foot x 5-foot wooden bridge, 17 FT long x 3 FT wide x 5 FT deep, surface flooding caused embankment erosion under the bridge, 0% work completed.

Damage #1413313; Interp trail 2

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Interp Trail 2
- **GPS Latitude/Longitude:** 41.75673, -92.83561

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Trail, 3.2 CY of 6-inch roadstone minus, 9 FT long x 19 FT wide x 6 IN deep, surface flooding overtopped the trail and displaced the roadstone, 0% work completed.
- Trail, 1.1 CY of 3/4-inch roadstone minus , 9 FT long x 19 FT wide x 2 IN deep, surface flooding washed out the trail and displaced the roadstone, 0% work completed.

Damage #1413314; Interp trail 3

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Interp Trail 3
- **GPS Latitude/Longitude:** 41.75793, -92.82811

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding

Facility Damage:

- Trail, 0.7 CY of 3/8-inch roadstone minus, 21 FT long x 5 FT wide x 2 IN deep, excessive rain caused surface flooding which washed away the roadstone surface, 0% work completed.

Damage #1413315; South Overlook Parking**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** South Overlook Parking Gravel Road Washout Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.73663, -92.86122

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain caused surface flooding

Facility Damage:

- Road, 1 each of South Overlook Parking Gravel Road , flooding caused the gravel road to washout, but construction installing shoreline riprap protection further damaged the road, 0% work completed.

Damage #1413316; West Boat Ramp**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Boat Ramp Gravel Road Washout
- **GPS Latitude/Longitude:** 41.75499, -92.84338

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding.

Facility Damage:

- Parking Lots, 9.6 CY of 3/4-inch roadstone minus, 110 FT long x 14 FT wide x 2 IN deep, Surface flooding washed out the surface roadstone, 0% work completed.

Damage #1413317; 24 hr pull in**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park

- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** 24 Hour Pull in Gravel Road Washout Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.76183, -92.84394

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding

Facility Damage:

- Parking Lots, 22.3 CY of 3/4-inch roadstone minus, 120 FT long x 30 FT wide x 2 IN deep, surface flooding scoured and removed the surface, 0% work completed.

Damage #1413318; west shop rd

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Shop Road Gravel Road Washout
- **Start GPS Latitude/Longitude:** 41.74775, -92.84763
- **End GPS Latitude/Longitude:** 41.74852, -92.84822

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain caused surface flooding and scouring of road surface.

Facility Damage:

- Road, 24 CY of 3/4-inch roadstone minus, 324 FT long x 12 FT wide x 2 IN deep, surface flooding caused scouring of road surface., 0% work completed.

Damage #1413319; 24 Hr pull off

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling
- **Year Built:** 1952
- **Location Description:** 24 hour Pull Off Gravel Road Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.76212, -92.84345

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding.

Facility Damage:

- Road, 21.7 CY of 3/4-inch roadstone minus, 70 FT long x 50 FT wide x 2 IN deep, surface flooding caused scouring of road surface, 0% work completed.

Damage #1413320; Below West Shelter**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Below West Shelter Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74808, -92.84683

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours caused surface flooding.

Facility Damage:

- Parking Lots, 10.4 CY of 3/4-inch roadstone minus, 140 FT long x 12 FT wide x 2 IN deep, surface flooding caused scouring of road surface, 0% work completed.

Damage #1413321; office gravel lot**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Office Gravel Lot Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.75867, -92.83441

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain with 9-inches of rain in 6 hours caused major surface flooding

Facility Damage:

- Parking Lots, 6.5 CY of 3/4-inch roadstone minus, 70 FT long x 15 FT wide x 2 IN deep, Surface flooding caused scouring of parking lot surface, 0% work completed.

Damage #1413322; 1st picnic area rd

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** 1st Picnic Area Rd Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.75150, -92.83878

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6-hours, caused surface flooding.

Facility Damage:

- Parking Lots, 16.1 CY of 3/4-inch roadstone minus, 130 FT long x 20 FT wide x 2 IN deep, Surface flooding caused scour of the parking lot surface, 0% work completed.

Damage #1413323; West Rd Pull off

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** West Road Pull Off Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.75648, -92.84400

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding

Facility Damage:

- Road, 4.9 CY of 3/4-inch roadstone minus, 65 FT long x 12 FT wide x 2 IN deep, Surface flooding caused scouring of the road surface, 0% work completed.

Damage #1413324; 3Rd Picnic area Parking lot

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park

is a popular spot for cross-country skiing and snowmobiling.

- **Year Built:** 1952
- **Location Description:** 3rd Picnic area Parking Lot Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74819, -92.83965

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding.

Facility Damage:

- Parking Lots, 4.7 CY of 3/4-inch Roadstone minus, 50 FT long x 30 FT wide x 2 IN deep, Surface flooding caused scouring of triangular parking lot surface, 0% work completed.

Damage #1413325; Campground 1

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Campground 1 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.75633, -92.84013

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding.

Facility Damage:

- Boat Ramp, 1 each of 16 1/2 -foot X 5-foot dock with roto-molded floats with 2-inch pipe railing, rising flood waters lifted and twisted the dock section causing structural damage, 0% work completed.
- Docks, 1 each of 20-foot x 5-foot dock section with roto-molded floats, rising flood waters structurally damaged the dock, 0% work completed.

Damage #1413327; Campground 3

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Campground 3

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding.

Facility Damage:

- Parking Lots, 7.5 CY of 3-4-inch roadstone minus at campground pad 82, GPS 41.75633, -92.83879, 80 FT long x 15 FT wide x 2 IN deep, surface flooding caused scouring of the gravel pad, 0% work completed.
- Parking Lots, 5.2 CY of 3/4-inch roadstone minus at campground pad 71, GPS 41.75633, -92.83879, 56 FT long x 15 FT wide x 2 IN deep, surface flooding caused scouring of gravel surface, 0% work completed.
- Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 81, GPS 41.75633, -92.83879, 48 FT long x 15 FT wide x 2 IN deep, surface flooding caused scouring of gravel surface, 0% work completed.
- Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 97, GPS 41.75620, -92.83831, 48 FT long x 15 FT wide x 2 IN deep, surface flooding caused scouring of gravel surface, 0% work completed.
- Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 98, GPS 41.75620, -92.83831, 48 FT long x 15 FT wide x 2 IN deep, surface flooding caused scouring of gravel surface, 0% work completed.

Damage #1413330; Southend 3**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Southend 3 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74403, -92.84287

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain caused lake level to rise causing floating dock sections to pull up the securing poles and augurs.

Facility Damage:

- Docks, 8 each of 8-foot poles and augurs, flood waters caused the docks to rise and pull out the 8-foot poles and 2-foot augurs, 0% work completed.

Damage #1413331; Beach 1**General Facility Information:**

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Beach 1 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74394, -92.84983

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rains and flooding caused lake levels to rise and damage the dock sections.

Facility Damage:

- Docks, 1 each of 20-foot x 5-foot floating dock section with roto-molded floats., Rising lake levels pulled dock section loose and structurally damaged the dock, 0% work completed.
- Docks, 1 each of 16 1/2-foot X 5-foot aluminum floating dock ramp with roto-molded floats, rising lake levels caused by flooding structurally damaged the dock ramp section, 0% work completed.
- Docks, 1 each of 20-foot x 10-foot floating fish cleaning station, Rising lake levels caused by flooding structurally damaged the , 0% work completed.

Damage #1413332; Beach 2

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Beach 2 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74367, -92.85003

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rains caused surface flooding and overflowing of a latrine.

Facility Damage:

- Latrine, 1 each of Concrete Block unisex latrine., Applicant stated that the flood waters filled the latrine and required pump out, and that there was no damage., 0% work completed.

Damage #1413333; Beach 3

General Facility Information:

- **Facility Type:** Parks, Cemeteries, and Recreational Facilities
- **Facility:** Rock Creek State Park
- **Facility Description:** Rock Creek State Park is a state park in Jasper County, Iowa, United States, managed by the Iowa Department of Natural Resources – Parks Bureau. The 1,697-acre (687 ha) park was dedicated in 1952 and includes numerous boat launches and docks, picnic grounds, camping grounds, and trails for horseback riding and hiking. In the winter, the 602-acre (244 ha) lake may freeze over, and the park is a popular spot for cross-country skiing and snowmobiling.
- **Year Built:** 1952
- **Location Description:** Beach 3 Rock Creek State Park 5627 Rock Creek East Kellogg, IA 50135
- **GPS Latitude/Longitude:** 41.74275, -92.85198

General Damage Information:

- **Date Damaged:** 5/21/2024
- **Cause of Damage:** Excessive rain, 9-inches in 6 hours, caused surface flooding.

Facility Damage:

- Beach, 78.3 CY of Play sand/Coarse sand, 176 FT long x 24 FT wide x 6 IN deep, surface flooding caused beach erosion and the loss of sand., 0% work completed.

Final Scope

1413293 East Trail 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trail, 6 CY of 20-foot long 24-inch corrugated poly culvert with 6-inch minus roadstone, 8 FT long x 10 FT wide x 2 FT deep.

Work to be Completed Total: \$7,154.54

Total Damage Inventory: \$324,024.68

Project Notes:

1. In accordance with FEMA's Simplified Procedures, the project scope and cost were developed from RS Means and will be certified by the Applicant using the Small Permanent Work Project Certifications and Acknowledgements form. See attachment labeled: 802631 - 4784DR-IA - CRC Costing Spreadsheet.xlsx
2. All work will be completed within the applicants ROW. If staging of equipment and materials would be needed, that work will be staged within the applicants ROW.
3. All borrow or fill material must come from pre-existing stockpiles, material reclaimed from maintained roadside ditches (provided the designed width or depth of the ditch is not increased), or commercially procured material from a source existing prior to the event. For any FEMA-funded project requiring the use of a non-commercial source or a commercial source that was not permitted to operate prior to the event (e.g. a new pit, agricultural fields, road ROWs, etc.) in whole or in part, regardless of cost, the Applicant must notify FEMA and the Recipient prior to extracting material. FEMA must review the source for compliance with all applicable federal environmental planning and historic preservation laws and executive orders prior to a subrecipient or their contractor commencing borrow extraction. Consultation and regulatory permitting may be required. Non-compliance with this requirement may jeopardize receipt of federal funding. Documentation of borrow sources utilized is required at closeout.
4. Disposal is expected to be deposited at a licensed landfill. Location will be provided by Applicant once work commences.
5. DI # 1413332 has no damages caused by the incident. This was an incidental emergency work done to pump out the latrine. Please see DDD and comment section for confirmation.
6. CRC EHP note: Applicant's coordination and or permits with any local/state/federal regulatory agency may be required for this project.

1413294 East Trail 2

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 27.8 CY of unclassified fill supporting a 20-foot 24-inch corrugate poly culvert, 25 FT long x 10 FT wide x 3 FT deep.
- B. Repair Trail, 9.3 CY of 6-inch roadstone minus, 25 FT long x 10 FT wide x 1 FT deep.

Work to be Completed Total: \$8,000.54

1413296

East Trail

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity within the existing footprint.

Facility Damage:

- A. Repair Trail, 55.6 CY of unclassified fill from riverbank erosion is threatening the East Trail, 125 FT long x 2 FT wide x 6 FT deep.

Work to be Completed: \$8,348.13

406 HMP Scope

Public Assistance
Hazard Mitigation Proposal

For template instructions, turn paragraph marks on. Press “¶” or “Ctrl/Shift+/8”					
Applicant Name	Iowa Department of Natural Resources - Parks Bureau	GM Project #	802631	HMP Date	October 15, 2025
Site Name	East Trail				

DR-	4784	- IA	D#	1413296
HMP Writer and Title:		Emmanuel Adekunle HM PA 406 Section Chief		
This HMP is based on the following Grants Manager project report, see attachment.				
PRJ_Report_802631_20251017.pdf				
Select Work Completed Status:		Work to be Completed		
I. Related Damaged Items to be Protected				
During the declared incident period of May 20, 2024, through May 31, 2024, the sub-recipient Iowa Department of Natural Resources - Parks Bureau was impacted by Excessive rain resulting in the severe erosion of the riverbank threatening the trail damaged items that will be mitigated. As a direct result of this event, GPS Latitude/Longitude: 41.74513, -92.86263: Trail, 55.6 CY of unclassified fill from riverbank erosion is threatening the East Trail, 125 FT long x 2 FT wide x 6 FT deep.				
Total repair cost of damaged elements being protected by the HMP at this site* =				\$ 8,348.13
*Before Cost Estimating Format (CEF) factors if a large project.				
Comments:	Enter Text			
II. Hazard Mitigation Proposal (HMP) Scope of Work				

The mitigation consists of armoring the riverbank upstream of the bridge and along the trail edge to prevent erosion and protect critical infrastructure. This includes placing **79 tons of Class "E" riprap** to stabilize the right bridge footing and the left trail edge, along with mobilization for the work.

Mitigation Scope and Cost:

Upstream of the bridge, armor the right bank for 35 feet to prevent undermining of the right bridge footing using Class "E" riprap (35' x 6' x 2' ~ 30 tons). At the trail edge, armor the left bank (70' x 5' x 2' ~ 49 tons).

Quantities and costs:

- Class "E" riprap: 79 tons @ \$75/ton = \$5,925
- Mobilization: \$500

Total Mitigation Cost: **\$6,425**

The mitigation measures will reduce the risk of future damage by stabilizing the riverbank and preventing erosion that threatens the bridge footing and trail edge. The placement of riprap will dissipate water energy, minimize scouring, and protect the structural integrity of the bridge and trail during future flooding events.

III. Hazard Mitigation Proposal (HMP) Cost: Worksheet

- Reference and attach a detailed, itemized cost estimate and/or CEF.

A. Cost of items if the HMP is approved=	\$6,425.00
--	------------

B. Cost of items deducted from the repair scope of work (SOW)=	0
--	---

C. Net Hazard Mitigation Cost (before CEF factors) =	\$6,425.00
--	------------

D. Is there a CEF?	?Yes ?No
--------------------	----------

E. Net Hazard Mitigation Cost (after CEF factors)=	\$6,425.00
--	------------

F. What is the CEF ratio (CEF Total Cost/Base Cost)?			NA			
Comments:	Enter Text					
Hazard Mitigation Proposal Cost: Summary						
Net Hazard Mitigation Cost =		\$6,425.00				
See attachment(s).		DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf				
Comments:	The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost					
IV. Cost Effectiveness Calculation (Net HMP Cost/Total Repair Cost of the damaged portions of the facility for which the mitigation measure applies) x 100						
	\$ 6,425.00	/	\$ 8,348.13	x 100 =	76.96 %	= 100%
The Benefit-Cost Analysis (BCA) ratio is					N/A	= 1.0

V. HMP Cost-Effectiveness

The mitigation measures meet the cost effectiveness criteria based on:

a) Mitigation measure is listed in Appendix J and is within 100% of the total eligible repair cost of the facility or facilities for which the mitigation applies.
In accordance with Expansion of Cost-Effective Hazard Mitigation Measures and Applicability to Current Disasters January 6, 2025, Chapter 8. Section IV and Appendix J. Section I. Drainage Structures B, this mitigation measure does not exceed 100 percent of the eligible repair cost and is considered to be cost-effective.

VI. Compliances and Assurances

For 'work to be completed,' this HMP is for estimating purposes only. If the site's final placement and configuration are different than the preliminary estimate, the Applicant should submit a change in scope request. This HMP is subject to further review prior to award.

The Applicant is responsible for final design, placement, configuration, procurement, permits and compliance with all regulatory codes and standards.

Eligibility and funding for the mitigation at this site on this project will be subject to the compliance of all environmental laws, regulations, and executive orders applicable to the site(s).

HMP Notes

1. The mitigation proposal estimates were generated using Insert Text. See attachment labeled DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf

1413297 South End Trail 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trail, 1 each of 16-foot long of 8-inch PVC pipe culvert.

Work to be Completed Total: \$7,803.16

1413298 South End Trail 2

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity within the existing footprint.

Facility Damage:

A. Repair Trail, 1 each of 20-foot long 24-inch CMP culvert.

B. Repair Trail, 9.7 CY of Unclassified fill, 14 FT long x 8 FT wide x 28 IN deep.

Work to be Completed Total: \$8,108.67

406 HMP Scope

Public Assistance

Hazard Mitigation Proposal

For template instructions, turn paragraph marks on. Press “¶” or “Ctrl/Shift/+8”					
Applicant Name	Iowa Department of Natural Resources - Parks Bureau	GM Project #	802631	HMP Date	October 15, 2025
Site Name	South End Trail 2				
DR-	4784	– IA	D#	1413298	

HMP Writer and Title:	Emmanuel Adekunle HM PA 406 Section Chief	
This HMP is based on the following Grants Manager project report, see attachment.		
	PRJ_Report_802631_20251017.pdf	
Select Work Completed Status:	Work to be Completed	
I. Related Damaged Items to be Protected		
During the declared incident period of May 20, 2024, through May 31, 2024, the sub-recipient Iowa Department of Natural Resources - Parks Bureau was impacted by Excessive rain resulting in the severe erosion of the riverbank threatening the trail damaged items that will be mitigated. As a direct result of this event, GPS Latitude/Longitude: 41.73773, -92.84867: Trail, 1 each of 20-foot long 24-inch CMP culvert, and Trail, 9.7 CY of Unclassified fill, 14 FT long x 8 FT wide x 28 IN deep, Flood water washed out the support for the 20-foot long 24-inch culvert.		
Total repair cost of damaged elements being protected by the HMP at this site*= *Before Cost Estimating Format (CEF) factors if a large project.		\$ 8,108.67
Comments:	Enter Text	
II. Hazard Mitigation Proposal (HMP) Scope of Work		

The mitigation consists of replacing the damaged **24" x 20' CMP culvert** with a **smooth metal pipe (SMP)**, building up the trail 3 feet over the culvert to prevent erosion, and importing **50 cubic yards of fill dirt** to stabilize the area. Mobilization is included to facilitate the work.

Mitigation scope and cost:

Replace the existing 24-inch by 20-foot culvert with a smooth metal pipe (SMP). Build up the trail by 3 feet over the culvert to prevent erosion and import 50 cubic yards of fill dirt.

Quantities and costs:

- 24" SMP, 20 feet @ \$60/LF = \$1,200
- 50 CY fill dirt @ \$20/CY = \$1,000
- Mobilization = \$500

Total Mitigation Cost: **\$2,700**

The mitigation measures will reduce the risk of future damage by stabilizing the trail and culvert, preventing erosion and washout during future flood events. The raised trail and additional fill dirt will provide enhanced support for the culvert, while the smooth metal pipe improves water flow and durability, reducing the likelihood of future structural failures.

III. Hazard Mitigation Proposal (HMP) Cost: Worksheet

- Reference and attach a detailed, itemized cost estimate and/or CEF.

A. Cost of items if the HMP is approved=	\$2,700.00
--	------------

B. Cost of items deducted from the repair scope of work (SOW)=	0
--	---

C. Net Hazard Mitigation Cost (before CEF factors) =	\$2,700.00
--	------------

D. Is there a CEF?	?Yes ?No
--------------------	----------

E. Net Hazard Mitigation Cost (after CEF factors)=		\$2,700.00
F. What is the CEF ratio (CEF Total Cost/Base Cost)?		NA
Comments:	Enter Text	
Hazard Mitigation Proposal Cost: Summary		
Net Hazard Mitigation Cost =		\$2,700.00
See attachment(s).		DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf
Comments:	The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost	
IV. Cost Effectiveness Calculation (Net HMP Cost/Total Repair Cost of the damaged portions of the facility for which the mitigation measure applies) x 100		
	\$ 2,700.00	/ \$ 8,108.67 x 100 = 33.30% = 100%
The Benefit-Cost Analysis (BCA) ratio is		N/A = 1.0

V. HMP Cost-Effectiveness

The mitigation measures meet the cost effectiveness criteria based on:

a) Mitigation measure is listed in Appendix J and is within 100% of the total eligible repair cost of the facility or facilities for which the mitigation applies.

In accordance with Expansion of Cost-Effective Hazard Mitigation Measures and Applicability to Current Disasters January 6, 2025, Chapter 8. Section IV and Appendix J. Section I. Drainage Structures B, this mitigation measure does not exceed 100 percent of the eligible repair cost and is considered to be cost-effective.

VI. Compliances and Assurances

For 'work to be completed,' this HMP is for estimating purposes only. If the site's final placement and configuration are different than the preliminary estimate, the Applicant should submit a change in scope request. This HMP is subject to further review prior to award.

The Applicant is responsible for final design, placement, configuration, procurement, permits and compliance with all regulatory codes and standards.

Eligibility and funding for the mitigation at this site on this project will be subject to the compliance of all environmental laws, regulations, and executive orders applicable to the site(s).

HMP Notes

1. The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost. See attachment labeled DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf

1413300 South Ouerlook Trail

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trails, 9.5 CY of Hiking trail consisting of unclassified fill, 30 FT long x 17 FT wide x 6 IN high.

Work to be Completed Total: \$7,047.85

1413301 SW Trail

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Trail, 4.5 CY of 24-inch corrugated poly culvert with class E 24-inch riprap, 4 FT long x 10 FT wide x 3 FT deep

Work to be Completed Total: \$9,305.12

1413302 West Trail 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trail, 11.2 CY of hiking and equestrian trail, 120 FT long x 15 FT wide x 2 IN deep.

Work to be Completed Total: \$7,424.91

1413303 West Trail 2

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trail culvert, 12.5 CY of unclassified fill supporting 20-foot corrugated poly culvert.

B. Repair Trail culvert, 6 CY of 6-inch roadstone minus armoring a 20-foot 24-inch corrugated poly culvert.

Work to be Completed Total: \$7,468.45

1413304 West Trail 3

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 8.7 CY of 3/4-inch roadstone minus, 140 FT long x 10 FT wide x 2 IN deep.
- B. Repair Trail, 17.4 CY of 3-inch roadstone minus, 140 FT long x 10 FT wide x 4 IN deep.

Work to be Completed Total: \$8,200.13

1413305 West Trail 4

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 14.9 CY of 3/4-inch roadstone minus, 120 FT long x 10 FT wide x 4 IN deep.

Work to be Completed Total: \$7,525.56

1413306 West Trail 5

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 6 CY of unclassified fill supporting a 20-foot long 24-inch corrugated poly culvert, 12 FT long x 20 FT wide x 4 FT deep.
- B. Repair Trail, 3.6 CY of 6-inch roadstone minus, 19 FT long x 10 FT wide x 6 IN deep.

Work to be Completed Total: \$6,994.01

Scope Note:

1. The GPS coordinates on DDD for DI 1413306 are incorrect. **GPS Latitude/Longitude:** 42.75322, -92.86914 should be 41.75322, -92.86914 per SIR

1413307

West Trail 6

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity within the existing footprint.

Facility Damage:

- A. Trail, 8 CY of unclassified fill was washed out on outlet face of a 20-foot 24-inch corrugated poly culvert, 12 FT long x 12 FT wide x 9 FT deep.

Work to be Completed Total: \$6,925.56

406 HMP Scope

Public Assistance
Hazard Mitigation Proposal

For template instructions, turn paragraph marks on. Press “¶” or “Ctrl/Shift+/8”					
Applicant Name	Iowa Department of Natural Resources - Parks Bureau	GM Project #	802631	HMP Date	October 17, 2025
Site Name	West Trail 6				

DR-	4784	- IA	D#	1413307
HMP Writer and Title:		Emmanuel Adekunle HM PA 406 Section Chief		
This HMP is based on the following Grants Manager project report, see attachment.				
	PRJ_Report_802631_20251017.pdf			
Select Work Completed Status:		Work to be Completed		
I. Related Damaged Items to be Protected				
During the declared incident period of May 20, 2024, through May 31, 2024, the sub-recipient Iowa Department of Natural Resources - Parks Bureau was impacted by excessive rain with 9-inches of rain in 6 hours resulting in major surface flooding causing overtopping of the trail and washout of the culvert that will be mitigated. As a direct result of this event, GPS Latitude/Longitude: 41.74735, -92.87020: Trail, 8 CY of unclassified fill was washed out on outlet face of a 20-foot 24-inch corrugated poly culvert, 12 FT long x 12 FT wide x 9 FT deep.				
Total repair cost of damaged elements being protected by the HMP at this site*=				\$ 6,925.56
*Before Cost Estimating Format (CEF) factors if a large project.				
Comments:	Enter Text			
II. Hazard Mitigation Proposal (HMP) Scope of Work				

Replacing the existing culvert with a 30-inch diameter, 50-foot smooth metal pipe (SMP) and mobilization to perform the work.

Mitigation Scope and cost

Replace the culvert with a 30-inch diameter, 50-foot smooth metal pipe. Quantities and costs: 50 linear feet at \$100 per LF = \$5,000; mobilization = \$500.

Total Mitigation = **\$5,500.**

The mitigation measures will reduce the risk of future damage by increasing conveyance capacity to minimize overtopping during heavy rain events, using a smooth interior to lower head loss and improve flow-through to reduce backup and scour risk, and extending the culvert length to better carry flow through the embankment.

III. Hazard Mitigation Proposal (HMP) Cost: Worksheet

- Reference and attach a detailed, itemized cost estimate and/or CEF.

A. Cost of items if the HMP is approved=

\$5,500

B. Cost of items deducted from the repair scope of work (SOW)=

0

C. Net Hazard Mitigation Cost (before CEF factors) =

\$5,500

D. Is there a CEF?

?Yes ?No

E. Net Hazard Mitigation Cost (after CEF factors)=

\$5,500

F. What is the CEF ratio (CEF Total Cost/Base Cost)?

NA

Comments:	Enter Text				
Hazard Mitigation Proposal Cost: Summary					
Net Hazard Mitigation Cost =			\$5,500		
See attachment(s).			DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details - Updated Cost For D#1413307.pdf		
Comments:	The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost.				
IV. Cost Effectiveness Calculation					
(Net HMP Cost/Total Repair Cost of the damaged portions of the facility for which the mitigation measure applies) x 100					
	\$ 5,500	/	\$ 6,925.56	x 100 =	79.42% = 100%
The Benefit-Cost Analysis (BCA) ratio is			N/A		= 1.0
V. HMP Cost-Effectiveness					
The mitigation measures meet the cost effectiveness criteria based on:					

a) Mitigation measure is listed in Appendix J and is within 100% of the total eligible repair cost of the facility or facilities for which the mitigation applies. In accordance with Expansion of Cost-Effective Hazard Mitigation Measures and Applicability to Current Disasters January 6, 2025, Chapter 8. Section IV and Appendix J. Section I. Drainage Structures B, this mitigation measure does not exceed 100 percent of the eligible repair cost and is considered to be cost-effective.
VI. Compliances and Assurances For 'work to be completed,' this HMP is for estimating purposes only. If the site's final placement and configuration are different than the preliminary estimate, the Applicant should submit a change in scope request. This HMP is subject to further review prior to award. The Applicant is responsible for final design, placement, configuration, procurement, permits and compliance with all regulatory codes and standards. Eligibility and funding for the mitigation at this site on this project will be subject to the compliance of all environmental laws, regulations, and executive orders applicable to the site(s).
HMP Notes
1. The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost.. See attachment labeled DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details - Updated Cost For DI#1413307.pdf

1413308 West Trail 7

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 14.7 CY of Unclassified fill at outlet of 20-foot long 18-inch corrugated poly culvert, 18 FT long x 11 FT wide x 2 FT deep.
- B. Repair Trail, 3.7 CY of 6-inch roadstone minus armor at outlet of 18-inch corrugated poly culvert, 18 FT long x 11 FT wide x 6 IN deep.

Work to be Completed Total: \$7,385.96

1413309 West Trail 8

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 5.6 CY of unclassified fill at 20-foot long 24-inch corrugated poly culvert , 14 FT long x 16 FT wide x 4 FT deep.
- B. Repair Trail, 4.2 CY of 6-inch roadstone minus , 14 FT long x 16 FT wide x 6 IN deep.

Work to be Completed Total: \$7,039.28

1413310 West Trail 9

310

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 9.3 CY of 3/4-inch roadstone minus, 125 FT long x 12 FT wide x 2 IN deep.
- B. Trail, 18.6 CY of unclassified fill, 125 FT long x 12 FT wide x 4 IN deep.

Work to be Completed Total: \$7,703.61

1413311 24 hr trail

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Trail, 1 each of 30-foot x 6-foot wood cantilever bridge with steel girders and wood sleeper supports.

Work to be Completed: \$6,929.59

1413312

Interp trail 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity within the existing footprint.

Facility Damage:

A. Repair Trail , 9.5 CY of unclassified fill supporting a 16-foot x 5-foot wooden bridge, 17 FT long x 3 FT wide x 5 FT deep.

Work to be Completed Total: \$6,987.14

406 HMP Scope

Public Assistance
Hazard Mitigation Proposal

For template instructions, turn paragraph marks on. Press “¶” or “Ctrl/Shift/+8”					
Applicant Name	Iowa Department of Natural Resources - Parks Bureau	GM Project #	802631	HMP Date	October 15, 2025
Site Name	Interp trail 1				
DR-	4784	– IA	D#	1413312	
HMP Writer and Title:	Emmanuel Adekunle HM PA 406 Section Chief				

This HMP is based on the following Grants Manager project report, see attachment.	
PRJ_Report_802631_20251017.pdf	
Select Work Completed Status:	Work to be Completed
I. Related Damaged Items to be Protected	
During the declared incident period of May 20, 2024, through May 31, 2024, the sub-recipient Iowa Department of Natural Resources - Parks Bureau was impacted by Excessive rain resulting in flood water rising 9-inches in 6 hours damaged embankment and cause erosion under the bridge that will be mitigated. As a direct result of this event, GPS Latitude/Longitude: 41.75715, -92.83576: Trail, 9.5 CY of unclassified fill supporting a 16-foot x 5-foot wooden bridge, 17 FT long x 3 FT wide x 5 FT deep.	
Total repair cost of damaged elements being protected by the HMP at this site*=	\$ 6,987.14
*Before Cost Estimating Format (CEF) factors if a large project.	
Comments:	Enter Text
II. Hazard Mitigation Proposal (HMP) Scope of Work	

The mitigation consists of placing **30 tons of Class "E" riprap**, with **15 tons upstream** and **15 tons downstream** of the bridge, to stabilize the area and prevent head-cut erosion. Mobilization is included to facilitate the work.

Mitigation scope and cost:

Install 15 tons of Class "E" riprap upstream and 15 tons downstream of the bridge to stop headcutting.

Quantities and costs:

- Class "E" riprap: 30 tons @ \$75/ton = \$2,250
- Mobilization: \$500

Total mitigation cost: **\$2,750**

The mitigation measures will reduce the risk of future damage by stabilizing the riverbank and protecting the bridge from erosion caused by head cutting. The riprap will dissipate water energy, prevent scouring, and reinforce the structural integrity of the bridge, ensuring long-term resilience against future flooding events.

III. Hazard Mitigation Proposal (HMP) Cost: Worksheet

- Reference and attach a detailed, itemized cost estimate and/or CEF.

A. Cost of items if the HMP is approved=	\$2,750.00
--	------------

B. Cost of items deducted from the repair scope of work (SOW)=	0
--	---

C. Net Hazard Mitigation Cost (before CEF factors) =	\$2,750.00
--	------------

D. Is there a CEF?	?Yes ?No
--------------------	----------

E. Net Hazard Mitigation Cost (after CEF factors)=	\$2,750.00
--	------------

F. What is the CEF ratio (CEF Total Cost/Base Cost)?		NA	
Comments:	Enter Text		
Hazard Mitigation Proposal Cost: Summary			
Net Hazard Mitigation Cost =		\$2,750.00	
See attachment(s).		DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf	
Comments:	The mitigation proposal estimates were generated using the sub-recipient provided mitigation scope and cost.		
IV. Cost Effectiveness Calculation (Net HMP Cost/Total Repair Cost of the damaged portions of the facility for which the mitigation measure applies) x 100			
	\$ 2,750.00	/	\$ 6,987.14
		x 100 =	39.36%
			= 100%
The Benefit-Cost Analysis (BCA) ratio is		N/A	= 1.0

V. HMP Cost-Effectiveness

The mitigation measures meet the cost effectiveness criteria based on:

a) Mitigation measure is listed in Appendix J and is within 100% of the total eligible repair cost of the facility or facilities for which the mitigation applies.
In accordance with Expansion of Cost-Effective Hazard Mitigation Measures and Applicability to Current Disasters January 6, 2025, Chapter 8. Section IV and Appendix J. Section I. Drainage Structures B, this mitigation measure does not exceed 100 percent of the eligible repair cost and is considered to be cost-effective.

VI. Compliances and Assurances

For 'work to be completed,' this HMP is for estimating purposes only. If the site's final placement and configuration are different than the preliminary estimate, the Applicant should submit a change in scope request. This HMP is subject to further review prior to award.

The Applicant is responsible for final design, placement, configuration, procurement, permits and compliance with all regulatory codes and standards.

Eligibility and funding for the mitigation at this site on this project will be subject to the compliance of all environmental laws, regulations, and executive orders applicable to the site(s).

HMP Notes

1. The mitigation proposal estimates were generated using sub-recipient provided mitigation scope and cost.. See attachment labeled DR4784-IA-Iowa Department of Natural Resources Parks- 802631-Rock Creek Mitigation Details.pdf

1413313 Interp trail 2

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 3.2 CY of 6-inch roadstone minus, 9 FT long x 19 FT wide x 6 IN deep.
- B. Repair Trail, 1.1 CY of 3/4-inch roadstone minus , 9 FT long x 19 FT wide x 2 IN deep.

Work to be Completed Total: \$6,919.02

1413314 Interp trail 3

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Trail, 0.7 CY of 3/8-inch roadstone minus, 21 FT long x 5 FT wide x 2 IN deep.

Work to be Completed Total: \$2,702.24

1413315 South Overlook Parking

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Road, 1 each of South Overlook Parking Gravel Road.

Work to be Completed Total: \$7,710.88

1413316 West Boat Ramp

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 9.6 CY of 3/4-inch roadstone minus, 110 FT long x 14 FT wide x 2 IN deep.

Work to be Completed Total: \$8,787.23

1413317 24 hr pull in

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 22.3 CY of 3/4-inch roadstone minus, 120 FT long x 30 FT wide x 2 IN deep.

Work to be Completed Total: \$10,229.59

1413318 west shop rd

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Road, 24 CY of 3/4-inch roadstone minus, 324 FT long x 12 FT wide x 2 IN deep.

Work to be Completed Total: \$9,579.38

1413319 24 Hr pull off

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Road, 21.7 CY of 3/4-inch roadstone minus, 70 FT long x 50 FT wide x 2 IN deep.

Work to be Completed Total: \$10,195.82

1413320 Below West Shelter

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 10.4 CY of 3/4-inch roadstone minus, 140 FT long x 12 FT wide x 2 IN deep.

Work to be Completed Total: \$8,797.93

1413321 office gravel lot

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 6.5 CY of 3/4-inch roadstone minus, 70 FT long x 15 FT wide x 2 IN deep.

Work to be Completed Total: \$8,608.36

1413322 1st picnic area rd

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 16.1 CY of 3/4-inch roadstone minus, 130 FT long x 20 FT wide x 2 IN deep.

Work to be Completed Total: \$9,126.65

1413323 West Rd Pull off

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Road, 4.9 CY of 3/4-inch roadstone minus, 65 FT long x 12 FT wide x 2 IN deep

Work to be Completed Total: \$8,837.45

1413324 3Rd Picnic area Parking lot

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Parking Lots, 4.7 CY of 3/4-inch Roadstone minus, 50 FT long x 30 FT wide x 2 IN deep.

Work to be Completed Total: \$7,892.03

1413325 Campground 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

A. Repair Boat Ramp, 1 each of 16 1/2 -foot X 5-foot dock with roto-molded floats with 2-inch pipe railing.

B. Repair Docks, 1 each of 20-foot x 5-foot dock section with roto-molded floats.

Work to be Completed Total: \$23,027.43

1413327 Campground 3

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Parking Lots, 7.5 CY of 3-4-inch roadstone minus at campground pad 82, GPS 41.75633, -92.83879, 80 FT long x 15 FT wide x 2 IN deep
- B. Repair Parking Lots, 5.2 CY of 3/4-inch roadstone minus at campground pad 71, GPS 41.75633, -92.83879, 56 FT long x 15 FT wide x 2 IN deep.
- C. Repair Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 81, GPS 41.75633, -92.83879, 48 FT long x 15 FT wide x 2 IN deep.
- D. Repair Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 97, GPS 41.75620, -92.83831, 48 FT long x 15 FT wide x 2 IN deep.
- E. Parking Lots, 4.5 CY of 3/4-inch roadstone minus at campground pad 98, GPS 41.75620, -92.83831, 48 FT long x 15 FT wide x 2 IN deep.

Work to be Completed Total: \$10,540.03

1413330 Southend 3

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Docks, 8 each of 8-foot poles and augurs, flood waters caused the docks to rise and pull out the 8-foot poles and 2-foot augurs.

Work to be Completed Total: \$2,987.08

1413331 Beach 1

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Docks, 1 each of 20-foot x 5-foot floating dock section with roto-molded floats.
- B. Repair Docks, 1 each of 16 1/2-foot X 5-foot aluminum floating dock ramp with roto-molded floats.
- C. Repair Docks, 1 each of 20-foot x 10-foot floating fish cleaning station.

Work to be Completed Total: \$39,876.37

1413332 Beach 2

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Latrine, 1 each of Concrete Block unisex latrine.

Work to be Completed Total: \$0.00

1413333 Beach 3

Work to be Completed

The applicant will utilize contract and (or) force account for repairs to Rock Creek State Park to restore this facility back to its pre-disaster design, function, and capacity (in-kind) within the existing footprint.

Facility Damage:

- A. Repair Beach, 78.3 CY of Play sand/Coarse sand, 176 FT long x 24 FT wide x 6 IN deep.

Work to be Completed Total: \$11,854.98

Cost

Code	Quantity	Unit	Total Cost	Section
9001 (Contract)	1.00	Lump Sum	\$7,154.54	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,000.54	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,348.13	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,803.16	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,108.67	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,047.85	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$9,305.12	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,424.91	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,468.45	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,200.13	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,525.56	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$6,994.01	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$6,925.56	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,385.96	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,039.28	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,703.61	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$6,929.59	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$6,987.14	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$6,919.02	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$2,702.24	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,710.88	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,787.23	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$10,229.59	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$9,579.38	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$10,195.82	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,797.93	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,608.36	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$9,126.65	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$8,837.45	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$7,892.03	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$23,027.43	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$10,540.03	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$2,987.08	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$39,876.37	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$0.00	Uncompleted
9001 (Contract)	1.00	Lump Sum	\$11,854.98	Uncompleted

CRC Gross Cost

\$324,024.68

Award Information	Total 406 HMP Cost	\$17,375.00
	Total Insurance Reductions	\$0.00

Version Information

CRC Net Cost	\$341,399.68
Federal Share (75.00%)	\$256,049.76
Non-Federal Share (25.00%)	\$85,349.92

Version #	Eligibility Status	Current Location	Bundle Number	Project Amount	Cost Share	Federal Share Obligated	Date Obligated
-----------	--------------------	------------------	---------------	----------------	------------	-------------------------	----------------

Drawdown History

EMMIE Drawdown Status As of Date	IFMIS Obligation #	Expenditure Number	Expended Date	Expended Amount
No Records				

Obligation History

Version #	Date Obligated	Obligated Cost	Cost Share	IFMIS Status	IFMIS Obligation #
0	2/12/2026	\$256,049.76	75%	Accepted	4784DRIAP00002561

Subgrant Conditions

- As described in Title 2 Code of Federal Regulations (C.F.R.) § 200.333, financial records, supporting documents, statistical records and all other non-Federal entity records pertinent to a Federal award must be retained for a period of three (3) years from the date of submission of the final expenditure report or, for Federal awards that are renewed quarterly or annually, from the date of the submission of the quarterly or annual financial report, respectively, as reported to the Federal awarding agency or pass-through entity in the case of a subrecipient. Federal awarding agencies and pass-through entities must not impose any other record retention requirements upon non-Federal entities. Exceptions are stated in 2 C.F.R. §200.333(a) – (f)(1) and (2). All records relative to this project are subject to examination and audit by the State, FEMA and the Comptroller General of the United States and must reflect work related to disaster-specific costs.
- In the seeking of proposals and letting of contracts for eligible work, the Applicant/Subrecipient must comply with its Local, State (provided that the procurements conform to applicable Federal law) and Federal procurement laws, regulations, and procedures as required by FEMA Policy 2 CFR Part 200, Procurement Standards, §§ 317-326.
- The Recipient must submit its certification of the subrecipient's completion of all of its small projects and compliance with all environmental and historic preservation requirements within 180 days of the applicant's completion of its last small project, or the latest approved deadline, whichever is sooner.
- When any individual item of equipment purchased with PA funding is no longer needed, or a residual inventory of unused supplies exceeding \$5,000 remains, the subrecipient must follow the disposition requirements in Title 2 Code of Federal Regulations (C.F.R.) § 200.313-314.
- The terms of the FEMA-State Agreement are incorporated by reference into this project under the Public Assistance award and the applicant must comply with all applicable laws, regulations, policy, and guidance. This includes, among others, the Robert T. Stafford Disaster Relief and Emergency Assistance Act; Title 44 of the Code of Federal Regulations; FEMA Policy No. 104-009-2, Public Assistance Program and Policy Guide; and other applicable FEMA policy and guidance.
- The DHS Standard Terms and Conditions in effect as of the declaration date of this emergency declarations or major disaster, as applicable, are incorporated by reference into this project under the Public Assistance grant, which flow down from the Recipient to subrecipients unless a particular term or condition indicates otherwise.
- The Uniform Administrative Requirements, Cost Principles, and Audit Requirements set forth at Title 2 Code of Federal Regulations (C.F.R.) Part 200 apply to this project award under the Public Assistance grant, which flow down from the Recipient to all subrecipients unless a particular section of 2 C.F.R. Part 200, the FEMA-State Agreement, or the terms and conditions of this project award indicate otherwise. See 2 C.F.R. §§ 200.101 and 110.
- The subrecipient must submit a written request through the Recipient to FEMA before it makes a change to the approved scope of work in this project. If the subrecipient commences work associated with a change before FEMA approves the change, it will jeopardize financial assistance for this project. See FEMA Policy No. 104-009-2, Public Assistance Program and Policy Guide.
- Pursuant to section 312 of the Stafford Act, 42 U.S.C. 5155, FEMA is prohibited from providing financial assistance to any entity that receives assistance from another program, insurance, or any other source for the same work. The subrecipient agrees to repay all duplicated assistance to FEMA if they receive assistance for the same work from another Federal agency, insurance, or any other source. If an subrecipient receives funding from another federal program for the same purpose, it must notify FEMA through the Recipient and return any duplicated funding.
- The Applicant certifies the following: **IMPARTIAL DELIVERY OF PUBLIC ASSISTANCE:** All work claimed was delivered in an impartial manner as required by Title VI of the Civil Rights Act, Section 308 of the Stafford Act, 42 U.S.C. § 5151, and applicable provisions of laws and authorities prohibiting discrimination. **DAMAGE:** All damage claimed was a direct result of the Presidential emergency and major disaster declaration. The damage did not result from a lack of maintenance. **WORK:** All work claimed to restore the facility back to its pre-disaster design function and capacity was required as a direct result of the major disaster declaration, is located within the designated area, and is the Applicant's legal responsibility. **CODE AND STANDARD COMPLIANCE:** All facilities are being restored in accordance with all federal and SLTT code and standard requirements. **PROCUREMENT AND CONTRACTING:** The Applicant is using the most restrictive of either its own documented policies and procedures for procurement or federal procurement and contracting laws in accordance with 2 C.F.R. Part 200. The Applicant is following Environmental Protection Agency guidelines for procurement of recovered materials; and including all applicable required contract provisions. **COST REASONABLENESS:** All costs claimed are reasonable and of a type recognized as ordinary and necessary for the type of facility and work as required by 44 C.F.R. §

206.228 and 2 C.F.R. §200.404. TRUE AND CORRECT STATEMENTS: All information provided is true and correct. Upon submittal this project application becomes a legal document. The False Claims Act (31 U.S.C. §§3729-3733) prohibits the submission of false or fraudulent claims for payment to the federal government. It is a violation of federal law to intentionally make false statements or hide information when applying for Public Assistance. This can carry severe criminal and civil penalties including a fine of up to \$250,000, imprisonment, or both (18 U.S.C. §§ 287, 1001, 1040, and 3571). The Applicant acknowledges: NON-DISCRIMINATION IN FEDERALLY ASSISTED PROGRAMS: The Applicant acknowledges it must comply with all federal civil rights laws and authorities prohibiting discrimination, including but not limited to, Section 308 of the Stafford Act, 42 U.S.C. § 5151, which requires the impartial delivery of disaster services and activities without discrimination. INSURANCE: When FEMA provides assistance for permanent work to repair or restore a facility, Stafford Act § 311 requires the applicant to ensure the facility and contents with the types and extent of insurance that is reasonably available, adequate, and necessary to protect the facility against future loss. FEMA refers to this as the requirement to "obtain and maintain" insurance requirement. If the Applicant does not comply with this insurance requirement, FEMA will deny or deobligate PA funding for that facility and the facility is ineligible for PA funding in any subsequent disaster. DOCUMENTATION REQUIREMENTS: The Applicant acknowledges it must continue to retain all source documentation, including project eligibility records and financial records, for three years after the date the Recipient submits to FEMA certification of completion of the last Small Project. SLTT government laws may require longer retention periods. Real property and equipment disposition, audits, and litigation may also require longer retention periods. If requested, Applicants must provide documentation to FEMA. Recipients may require documentation not otherwise required by FEMA (such as actual cost documentation for Small Projects). In such cases, the Applicant must provide the documentation to the Recipient.

Insurance

Additional Information

10/17/2025

Property insurance coverage for the facilities represented on this project are not insured or insurable. No insurance relief is anticipated.

FEMA requires the Applicant to take reasonable efforts to pursue claims to recover insurance proceeds that it is entitled to receive from its insurer(s). In the event that any insurance proceeds are received for these expenses those proceeds must be reduced from FEMA Public Assistance funding to ensure no duplication of benefits has occurred.

No duplication of benefits from insurance is anticipated for work described in this application. In the event any part or all costs are paid by an insurance policy, a duplication of benefits from insurance will occur. Applicant must notify grantee and FEMA of such recoveries and the Sub-Grant award amount must be reduced by actual insurance proceeds.

No insurance requirements will be mandated for the damages included in this project. Insurance requirements are specific to permanent work to replace, restore, repair, reconstruct, or construct buildings, contents, equipment, or vehicles. (FEMA Recovery Policy FP 206-086-1).

No insurance Narrative will be produced or uploaded into documents or attachments.

(For Flood Perils)

A standard NFIP flood policy is the primary factor used to determine if a structure or item can be reasonably insured for the peril of flood. As a result, the requirement to obtain and maintain insurance is not being mandated for the work described in this project.

No O&M is required for the facilities represented on this project.

Kevin Calles, PA Insurance Specialist

CRC West, Sacramento, CA

O&M Requirements

There are no Obtain and Maintain Requirements on **4784 IDNR Parks - Rock Creek Park**.

406 Mitigation

There is no additional mitigation information on **4784 IDNR Parks - Rock Creek Park**.

Environmental Historical Preservation

Is this project compliant with EHP laws, regulations, and executive orders?

Yes

EHP Conditions

- Any change to the approved scope of work will require re-evaluation for compliance with NEPA and other Laws and Executive Orders.
- This review does not address all federal, state and local requirements. Acceptance of federal funding requires recipient to comply with all federal, state and local laws. Failure to obtain all appropriate federal, state and local environmental permits and clearances may jeopardize funding.
- If ground disturbing activities occur during construction, applicant will monitor ground disturbance and if any potential archaeological resources are discovered, will immediately cease construction in that area and notify the State and FEMA.

EHP Additional Info

There is no additional environmental historical preservation on **4784 IDNR Parks - Rock Creek Park**.

Final Reviews

Final Review

Reviewed By CURRAN, JENNIFER A.

Reviewed On 10/21/2025 2:05 PM CST

Review Comments

Field review completed. Recommend recipient's final review.

Recipient Review

Reviewed By Brown, Heidi

Reviewed On 11/05/2025 10:22 AM CST

Review Comments

No comments available for the Recipient Review step

Project Signatures

Signed By Thacker, Elizabeth

Signed On 11/13/2025