

CHANGE ORDER No. 2

CONTRACTOR: Fronabarger Concreters, Inc.
 PROJECT NAME: US 61 and Deerwood Lane Roundabout

LPA: City of Jackson
 PROJECT NO.: STP-3005(0031)

The Contractor is hereby directed to make the following changes from the contract:

1. DESCRIPTION AND REASON FOR CHANGE:
 To correct contract quantities and address field changes. See page 2 for Change Order reasons.

2. COST OF WORK AFFECTED BY THIS CHANGE ORDER.

EST. LINE NO.	CONTRACT ITEM NO.	ITEM DESCRIPTION	UNITS PREVIOUSLY PROVIDED FOR	UNITS TO BE CONSTRUCTED	UNITS OVERRUN, UNDERRUN, CONTINGENT	UNIT PRICE	AMOUNT OF OVERRUN OR PLUS CONTINGENT	AMOUNT OF UNDERRUN OR MINUS CONTINGENT
27	6143013	Manhole Frame and Cover Type 1-A	2.00	0.00	2.00	EA \$450.00		\$900.00
35	7311053	PreCast Concrete Drop Inlet 5 FT x 3 FT	18.00	19.00	1.00	LF \$675.00	\$675.00	
41	N 50-2W	Pole 50' Class 2 Wood	2.00	3.00	1.00	EA \$10,800.00	\$10,800.00	
5003	7319913A	Set Over Manhole, with Frame and Lid	0.00	22.00	22.00	LF \$755.45	\$16,619.90	
5004	6141024	Grate and Bearing Plate (5 FT x 3 FT)	0.00	1.00	1.00	EA \$3,750.00	\$3,750.00	
5005	6143013	Manhole Frame and Cover Type 3	0.00	3.00	3.00	EA \$450.00	\$1,350.00	
5006	9031241	Breakaway Assembly (PSST, 2 IN)	0.00	20.00	20.00	EA \$145.00	\$2,900.00	
TOTALS:							\$36,094.90	\$900.00

3. SETTLEMENT FOR COST OF THE ABOVE CHANGE TO BE MADE AT CONTRACT UNIT PRICES, EXCEPT AS NOTED:
 N/A

4 COMMENTS:

5 COST ADJUSTMENTS TO THE CONTRACT:

1. CONTRACT AMOUNT	1006496.87
2. OVERRUN THIS ORDER	\$36,094.90
3. OVERRUN PREVIOUS	\$7,500.00
4. UNDERRUN THIS ORDER	\$900.00
5. UNDERRUN PREVIOUS	\$4,555.00
6. PROJECT TOTAL	\$1,044,636.77

THE TERMS OF SETTLEMENT OUTLINED ABOVE ARE HEREBY AGREED TO:

APPROVED: (OWNER)	DATE		APPROVED: (CONTRACTOR)		DATE
APPROVED: MODOT	DATE	APPROVED: (CONSTRUCTION ENGINEER)	DATE		

CHANGE ORDER No. 2

CONTRACTOR: Fronabarger Concreters, Inc.
PROJECT NAME: US 61 and Deerwood Lane Roundabout

LPA: City of Jackson
PROJECT NO.: STP-3005(0031)

Line No. 27 **Manhole Frame and Cover, Type 1-A**

This change underruns Manhole Frame and Cover, Type 1-A in its entirety due to the incorrect type being specified for the work. See contingent line number 5005 for more information.

Line No. 35 **PreCast Concrete Drop Inlet 5 FT x 3 FT**

This change adds 1 FT of length to the PreCast Drop Inlet 5 FT x 3 FT contract quantity. Upon review of the Drop Inlet quantities, it was discovered the the plan quantity of 18 LF was in error. The total PreCast Concrete Drop Inlet quantity measures 19 LF.

Line No. 41 **Pole 50' Class 2 Wood**

This change adds one Pole 50' Class 2 Wood. Pole location NP3 was originally installed per plans and specifications with a new 45' Class 3 Wood Pole. After installation it was determined by the City Of Jackson the pole needed to be a 50' Class 2 Wood Pole. The contractor removed the 45' pole and replaced it with a new 50' pole.

Line No. 5003 **Set Over Manholes**

This change adds two, (2) Set Over Manholes. The plans call for relocating a section of sanitary sewer and installing two Set Over Manholes to reconnect the relocated section of sanitary sewer line. This change adds 2 Set Over Manholes that were not included in the bid items in the NE quadrant of the project and located approximately at station 3+70 LT, 40' of US 61 and near 4+38 LT, 24' of Deerwood Drive East. The Precast manhole sections shall be constructed in accordance with the City of Jackson standard detail S-01. The Set Over Manholes shall be measured per foot of depth of the structure and constructed where shown on the plans. The contract unit price shall include all labor, materials, and other costs necessary to construct the manhole including but not limited to the frame and lid. See JSP FF for details. Settlement of costs: Agreed price of \$755.45/LF.

Line No. 5004 **Grate and Bearing Plate, 5' x 3'**

One Grate and Bearing Plate, 5' x 3' is being added to the contract. The plans include new storm drain pipe and drop inlets at various locations. The plans added a new Type S-1 drop inlet at Sta 809+90.00 33.98 RT, but did not include the grate and bearing plate to cover the inlet top. This change adds 1 EA 5' x 3' grate and bearing plate. Settlement of costs: \$3,750.00/EA.

Line No. 5005 **Manhole Frame and Cover, Type 3**

This change adds 3 Manhole Frame and Cover, Type 3. The design plans included 2 Manhole Frame and Cover, Type 1-A. This change corrects both the type and quantity required of Manhole Frame and Cover Type 3 to what is required to complete the work. Settlement of costs: Agreed price of \$450.00/EA.

Line No. 5006 **Breakaway Assemble, Perforated Square Steel Tube, 2 IN.**

This change adds Breakaway Assembly, Perforated Square Steel Tube, 2 IN. to the contract. The original plans called for driven anchors for all posts. This change provides the hardware to surface mount posts and signs to the concrete median where required. Settlement of costs: \$145.00/EA.