

# Proposal #135 - Jefferson City Fire Station 2 - Low Voltage



## Secufire, LLC

9111 Cross Park Dr Suite D200 Knoxville TN  
37923

P: 8657701484

License #: TNLV# 2501, TN Extinguisher#  
547, TN Sprinkler# 611, KYLV# FAR2008, KY

Sprinkler# SC00070, ALLV# 0953

Proposal Date: 03-31-2026

### Prepared By

Noah Keebler

[noahk@secufire.com](mailto:noahk@secufire.com)

### Prepared For

Jefferson City Fire Station 2

Odyssey Rd Jefferson City TN 37760

Allen Gillespie

[agillespie@jeffersoncitytn.gov](mailto:agillespie@jeffersoncitytn.gov)

--

## Summary

Quote for installation of access control, camera system and data drops for newly constructed fire station.

## Scope Of Work

### Scope of Work – Camera & Access Control Installation

**Project:** Jefferson City Fire Station 2

**Location:** Jefferson City, TN

### Overview

SecuFire will provide installation services for camera and access control systems at Jefferson City Fire Station 2. This scope includes furnishing select access control components, installation of structured cabling, and full installation of the camera system. Work will be coordinated with the Jefferson City IT Department and the project electrical contractor.

### 1. Access Control System Installation

#### Equipment Provided by SecuFire:

- Access control door controller(s)
- Key card proximity readers
- Network communication module

#### Installation Scope:

- Provide and install all low-voltage cabling required for access control, including:
  - 16/4 shielded cable
  - 18/4 cable
- Terminate and install all provided access control hardware
- Coordinate device locations and final terminations with project stakeholders

#### By Others:

- All conduit and pathway installation for access control wiring to be provided by the Electrical Contractor
- Final system programming, network configuration, and integration to be completed by the Jefferson City IT Department

### 2. Video Surveillance (Camera System)

**System Scope:**

- Installation of **17 security cameras**

**Equipment Provided by Owner (Jefferson City):**

- All cameras
- All camera cabling
- All RJ45 connectors
- All keystone jacks and associated connectivity hardware

**Services Provided by SecuFire:**

- Mounting and installation of all cameras in designated locations
- Installation and routing of owner-provided cabling
- All required wall penetrations and routing
- Installation of conduit where required for proper protection and routing of camera cabling
- Termination of cabling using owner-provided RJ45 and keystone components
- Testing and verification of camera connectivity

**3. Structured Cabling (Data & Low Voltage)**

**Data Drops:**

- Provide labor and materials for installation of **25 data drops** for:
  - TVs
  - Wall-mounted data outlets

**Wireless Access Points:**

- Provide labor and cabling for **5 ceiling-mounted wireless access points (WAPs)**

**Scope Includes:**

- Cable routing, support, and termination
- Installation of data jacks and device boxes as required
- Testing and verification of all installed cabling

**4. Coordination & Responsibilities**

- SecuFire will coordinate with:
  - Jefferson City IT Department for network integration and system programming
  - Electrical Contractor for conduit pathways and rough-in requirements
- All work will be performed in accordance with applicable low-voltage standards and best practices

**Notes**

- Final device locations to be confirmed prior to installation
- Any additional work required due to unforeseen site conditions or changes in scope will be quoted separately
- Work will be scheduled in coordination with other trades to ensure efficiency and minimize disruption

DISCOUNT APPLIED TO DATA DROP LABOR FOR THE ASSISTANCE OF JEFFERSON CITY IT DEPT. ASSISTANCE

Description	Quantity	Unit Price	Total
Keyscan CA8500 - With Can	1.0	\$4,329.00	\$4,329.00
Keyscan Prox Reader	8.0	\$181.00	\$1,448.00
Keyscan Net Card	1.0	\$480.00	\$480.00

Description	Quantity	Unit Price	Total
16/4 Shielded, 18/4 Wire	1.0	\$575.00	\$575.00
Labor - Access Control Installation	1.0	\$5,360.00	\$5,360.00
Labor - Camera System Installation	1.0	\$6,700.00	\$6,700.00
Labor - WAP Cable Runs & Install (5 AP's / 25 Data Drops - as marked on plan set)	1.0	\$2,350.00	\$2,350.00
Conduit Materials	1.0	\$675.00	\$675.00
<b>Total Amount</b>			\$21,917.00

---

**Exclusions**

**Exclusions**

- Access control system network configuration
- Conduit installation for access control (by Electrical Contractor)
- Cameras, camera cabling, RJ45 connectors, and keystone jacks (provided by Jefferson City)
- Network switches, servers, or IT infrastructure unless otherwise specified
- Patch cords, rack equipment, or head-end equipment unless specifically noted
- Any core drilling, firestopping, or specialty penetrations unless otherwise noted

**Approval**

I approve this proposal and agree to the terms and conditions.

\_\_\_\_\_  
**Name**

\_\_\_\_\_  
**PO (if required)**

\_\_\_\_\_  
**Signature**

\_\_\_\_\_  
**Date**