	Ar	ea 1 - 25 ·	- 34			
Yellow Areas - Mill 2", place 2" (GR SX 75 PG 64-22 w/fiber). Green Area - Mill 2" and place 2" (GR SX 75 PG 64-22 w/fiber).						
ltem	Unit of Measure	Estimated Bid Qty.	UNIT PRICE BID	EXTENDED VALUE		
Mobilization	LS	1		\$ -		
Yellow Area - Removal of Asphalt Mat (Planing) (2")	SY	2,589		\$ -		
Emulisified Asphalt	GAL	130		\$ -		
Yellow Area - 2" HMA w/fiber (SX)(75)(PG 64-22)	Ton	300		\$ -		
Green Area - Removal of Asphalt Mat (Planing) (2")	SY	13,580		\$ -		
Emulisified Asphalt	GAL	679		\$-		
Green Area - 2" HMA w/fiber (SX)(75)(PG 64-22)	Ton	1,575		\$-		
Re-stripe to match existing layout with Epoxy	LS	1		\$ -		
Traffic Control (Roundabout full night closure 9PM - 5AM)	LS	1		\$ -		
Traffic Control remainder of project	LS	1		\$ -		
				Ý		

Area 1 - Total Bid \$	-
-----------------------	---




Area 2 - CR 13

Blue Area- Remove existing material to a depth of 7", Place and compact 5" (GR S) and 2" (GR SX). Green Area - Mill 2" from RR Tracks South to CR 46, Place 4" (GR SX 75 PG 64-22 w/fiber). Include 2" risers for valve box utilities. Haul milliings to Town dump site (CR 17 & CR 46 1/2)

Item	Unit of Measure	Estimated Bid Qty.	UNIT PRICE BID	EXTENDED VALUE
Mobilization	LS	1		\$-
Blue Area - Remove 7" existing material	SY	560		\$-
Blue Area - HMA (S) (75) (PG 64-22)	Ton	155		\$ -
Blue Area - HMA w/fiber (SX)(75)(PG 64- 22)	Ton	62		\$ -
Green Area - Removal of Asphalt Mat (Planing) (2") Haul millings to Town Site - CR 17 and CR 46 1/2	SY	7,549		\$ -
Emulisified Asphalt	GAL	377		\$
Green Area - Place 4" HMA w/fiber (SX)(75)(PG 64-22)	Ton	1,751		\$ -
Valve box risers	EA	8		\$-
Re-stripe to match existing layout with Expoxy	LS	1		\$-
Traffic Control (PH 1 - Full closure from RR tracks north and from RR tracks south to Roosevelt Pkwy. Phase 2 - Full closure from Roosevelt Pkwy south to CR 46.)	LS	1		\$-

Area 2 - Total Bid \$ -









Area 3 - CR 15


Green Area - Mill 2" on East lane from W. South 1st Street to RR Tracks, Place 2" (GR SX 75 PG 64-22 w/fiber). White Area - Full Width Overlay 2" (GR SX 75 PG 64-22 w/fiber). Include 2" Risers for Valve Box Utilities. Haul milliings to Town dump site (CR 17 & CR 46 1/2). Striping to be completed by others.

Item	Unit of Measure	Estimated Bid Qty.	UNIT PRICE BID	EXTENDED VALUE
Mobilization	LS	1		\$-
Green Area - Removal of Asphalt Mat (Planing) (2") (East Lane) Haul millings to Town Site - CR 17 and CR 46 1/2	SY	3,256		\$-
Emulisified Asphalt	GAL	163		\$-
Green Area - 2" HMA (SX)(75)(PG 64-22) with fiber (East Lane)	Ton	378		\$ -
Emulisified Asphalt	GAL	276		\$-
White Area (5525 SY) - 2" HMA (SX)(75)(PG 64-22) with fiber (Full width from Mountain View Drive)	Ton	641		\$-
Traffic Control - 2 phases with full closure (North of Mountainview Drive to SH 60 and south of Mountain View Drive to RR tracks)	LS	1		\$-

Area 3 - Total Bid \$	-
-----------------------	---









ADDITIONAL SCOPE OF WORK ALTERNATE 3" MILL and OVERLAY



ADDITIONAL SCOPE OF WORK ALTERNATE 3" OVERLAY

