

FRFR STATION 1 ZONING MAP

SITUATE IN THE SOUTHEAST QUARTER OF SECTION 6, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF WELD, STATE OF COLORADO.

PROPERTY DESCRIPTION

A tract of land, being part of that parcel described in the Quitclaim Deed recorded October 23, 2020, as Reception No. 4643684 of the records of the Weld County Clerk and Recorder (WCCR), situate in the Southeast Quarter (SE1/4) of Section Six (6), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, and being more particularly described as follows:

COMMENCING at the Southeast corner of said Section 6, monumented by a #6 rebar with 3.25" aluminum cap stamped LS 38346 and assuming the East line of said SE1/4 as bearing North 00°38'10" West, being a Grid Bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983/2011, a distance of 2650.75 feet, monumented by a #6 rebar with 3.25" aluminum cap stamped LS 23520 at the East Quarter corner and with all other bearings contained herein relative thereto;

THENCE North 00°38'10" West, along said East line, a distance of 749.89 feet;
 THENCE South 89°13'36" West a distance of 30.00 feet to a point on the West Right of Way (ROW) of Weld County Road 15, said point being the Northeast corner of said Reception No. 4643684 and to the POINT OF BEGINNING;

THENCE South 00°38'10" East, along said West ROW, a distance of 89.05 feet to the Southeast corner of the Excepted Parcel described in Rolling Hills Ranch Annexation to the Town of Johnstown, recorded October 4, 1996, as Reception No. 2514298 of the records of the WCCR;
 THENCE North 47°50'25" West, along the Southwesterly line of said Excepted Parcel, a distance of 130.73 feet to the North line of said Reception No. 4643684;
 THENCE North 89°13'36" East, along said North line, a distance of 95.93 feet to the POINT OF BEGINNING;

Said described parcel of land contains 4,271 Square Feet or 0.098 Acres, more or less (±).

OWNER: Front Range Fire Rescue Fire Protection District, as the successor entity to Johnstown Fire Protection District

By: _____ As: _____

Witness my hand and seal this _____ day of _____, 20 ____.

NOTARIAL CERTIFICATE

STATE OF COLORADO)
 COUNTY OF LARIMER)
 The foregoing instrument was acknowledged before me by _____ as _____ this _____ day of _____, 20 ____.
 Witness my Hand and Official Seal.
 My commission expires: _____.

TOWN COUNCIL APPROVAL

This Map to be known as FRFR STATION 1 ZONING MAP is approved and accepted to the Town of Johnstown, Colorado by Ordinance Number _____, passed and adopted on final reading at a regular meeting of the Town Council of the Town of Johnstown, Colorado held on the _____ day of _____, 20 ____.



Attest: _____
 Gary Lebsack, Mayor Town Clerk

SURVEYOR'S CERTIFICATE

I, Steven Parks, a Colorado Licensed Professional Land Surveyor, do hereby state that this Zoning Map is an accurate representation of the property to the best of my knowledge, information, belief, and in my professional opinion. I further state that this certificate does not extend to any unnamed parties or the successors and/or assigns.

LEGEND

- ALIQUOT CORNER AS DESCRIBED
- ZONING BOUNDARY
- - - - - EASEMENT LINE
- - - - - RIGHT OF WAY LINE
- - - - - SECTION LINE
- - - - - CENTERLINE
- PARCEL LINE



Owner: Front Range Fire Rescue Fire Protection District
 101 S. Irene Ave
 Milliken, CO 80543

Applicant: Bernie Covillo
 101 S. Irene Ave
 Milliken, CO 80543
 970-587-4464

Surveyor: Majestic Surveying, LLC
 C/O Steven Parks, PLS
 1111 Diamond Valley Drive, Suite 104
 Windsor, CO 80550
 970-833-5698

BASIS OF BEARINGS AND LINEAL UNIT DEFINITION

Assuming the East line of the Southeast Quarter of Section 6, Township 4 North, Range 67 West of the 6th P.M. monumented as shown on this drawing, as bearing North 00°38'10" West, being a Grid Bearing of the Colorado State Plane, North Zone, North American Datum 1983/2011, a distance of 2650.75 feet and with all other bearings contained herein relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".


TITLE COMMITMENT NOTE

For all information regarding easements, rights-of-way and title of records, Majestic Surveying, LLC relied upon Title Commitment Number FCIF25197625, dated May 2, 2022, as prepared by Land Title Guarantee Company to delineate the aforesaid information.

This survey does not constitute a title search by Majestic Surveying, LLC to determine ownership or easements of record.

NOTICE

According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event may any action based upon any defect in this survey be commenced more than ten years from the date of the certification shown hereon. (13-80-105 C.R.S. 2012)



PRELIMINARY

Steven Parks - On Behalf of Majestic Surveying, LLC
 Colorado Licensed Professional Land Surveyor #38348



PROJECT NO: 2022198	PROJECT NAME: 100 TELEP AVE.	REVISIONS:	DATE:
DATE: 7-15-2022	CLIENT: FRFR	REDLINES	8-8-22
DRAWN BY: MAK	FILE NAME: 2022198_ZONE		
CHECKED BY: SIP	SCALE: 1" = 40'		