

March 21, 2022

Mayor Bradshaw and City Councilors City of Ketchum Ketchum, Idaho

Mayor Bradshaw and City Councilors:

Briefing on Sun Valley Road Rehabilitation and Pedestrian Improvement Project

Recommendation and Summary

On March 15th one qualified bid (Idaho Materials & Construction – IMC) was received for the Sun Valley Road rehabilitation project which is being jointly managed between the cities of Ketchum and Sun Valley. Staff has reviewed the bid and is investigating areas for potential value engineering to reduce overall costs. Staff will review the areas during the meeting to receive feedback from Council.

"I move to accept the initial bid for the Ketchum portion of the Sun Valley Road Rehabilitation Project and instruct staff to negotiate outlined value engineering opportunities and return to Council with final not to exceed contract amount at the April 4th Meeting."

<u>Introduction and History</u>

The bid documents called for the following five components (attachment #1):

- 1. Full rebuild of roadway from Main Street to Spruce Street
 - \$1,552,943.40
- 2. Pedestrian improvements
 - \$666,346.90
- 3. Alternate <u>add</u> option for new bike path from SV Road adjacent to Spruce Street to 4th Street \$86,495.00
- 4. Alternate <u>deduct</u> option to <u>only</u> rebuild intersections \$622,603.50 savings
- 5. Alternate <u>deduct</u> option to complete mill/inlay versus full rebuild of road \$262,539.00 savings

During the previous Council briefing, staff presented an estimated worst case total construction cost of \$2,233,557. Should the Council support moving forward with full scope of the roadway and pedestrian improvements, the total contract amount would be \$2,219,290.30. Staff is still working to finalize a contract with Jacobs Engineering to provide construction oversight as they served as the design engineer. Staff has not been able to acquire the necessary easement with the LDS Church to implement item #3. Staff has evaluated the two alternate deductions (#4 and #5) and does not recommend proceeding from a return on investment (ROI) perspective.

Staff, in concert with Jacobs Engineering, has identified the following bid line items to investigate further during a workshop with IMC on March 29th to determine if cost savings could be achieved:

- Traffic control (\$182,189.50)
- Mobilization (\$200,500.00)
- Demolition (\$445,368.00)

Staff will return on April 4th for approval of a final not-to-exceed amount. Members of the public are encouraged to visit www.projectketchum.org to learn more about this project and provide feedback.

Sustainability Impact

Improved pedestrian and bike facilities along the roadway encourage locals and visitors to utilize alternative transportation.

Financial Requirement/Impact

As presented previously, the City Council could access fund balance in order to complete full scope of the project. Staff will also be presenting to the URA Board ahead of the Council meeting with a funding request of fifty percent of total pedestrian improvement costs.

Attachment:

Bid schedules

Visual of planned pedestrian improvements

ADDENDUM NO. 4
TO THE CONTRACT DOCUMENTS
for the construction of
2022 SUN VALLEY ROAD REHABILIATION

Date: March 9, 2022 Project No.: D3489600

To All Planholders and/or Prospective Bidders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of 2022 Sun Valley Road Rehabilitation dated February 2022 as fully and completely as if the same were fully set forth therein:

A. PART 1, PROCUREMENT REQUIREMENTS

- 1. Section 00 11 13, Advertisement for Bid, Page 1, First Paragraph, First Sentence: REVISES "3:00 P.M., local time, on March 10, 2022" to "10:00 A.M., local time, on March 15, 2022"
- 2. Section 00 41 13, Bid Form, 6. Basis of Bids, 6.2 Unit Price Bid Schedule:
 - a. DELETE tables and REPLACE with the following:

Item No.	Description	Estimated Quantity	Unit	Unit Price	Extended Uni Price
303330	TEMPORARY		-11	JB1997	
1	Mobilization (≤10% of schedule bid total)	1	LS	\$ 145,000.00	\$ 145,000.00
2	Construction Survey	1	LS	\$ 28,500.00	\$ 28,500.00
3A	Traffic Signs	110	EA	\$ 250 00	\$ 27,500.00
3B	Portable Tubular Markers	240	EA	\$ 12.50	\$ 3,000.00
3C	Type II Barricades	6	EA	\$ 34.50	\$ 207.00
3D	Type III Barricades	6	EA	\$ 105.00	\$ 630.00
3E	PCMS	147	Day	\$ 115.00	\$ 16,905.00
3F	Pilot Car	0	HR	\$ 90.00	\$ 0.00
3G	Traffic Control Supervisor	315	HR	\$ 53.50	\$ 16,852.50
3H	Flagging	1,260	HR	\$ 49.00	\$ 61,740.00
4	Temporary Erosion & Sedlment Control	1	LS	\$ 23,500.00	\$ 23,500.00
5	Dust Control	1	LS	\$ 33,000.00	\$ 33,000.00
	DEMOLITION			is it	36. "
6	Excavation	3,339	CY	\$ 50.50	\$ 168,619.50
7	Removal of Curb & Gutter	258	LF	\$ 48.50	\$ 12,513.00
8	Removal of Asphaltic Concrete - Roadway	6,478	SY	\$ 20.50	\$ 132,799.00
9	Removal of Asphaltic Concrete - Pathway	74	SY	\$ 20.50	\$ 1,517.00
10	Removal of Concrete Sidewalk	22	SY	\$ 365.00	\$ 8,030.00
11	Remove, Retain and Replace Signage	7	EA	\$ 500.00	\$ 3,500,00

item No.	Description	Estimated Quantity	Unit	Unit Price	Extended Unit
12	Demolish and Remove Existing Dry Well, Catch Basin	6	EA	\$ 2,950.00	\$ 17,700.00
13	Remove and Discard Existing Sign Post, Stop Sign and Foundation	2	EA	\$ 290.00	\$ 580.00
14	Remove, Retain and Reinstall RRFB, PPB and Light Pole	1	LS	\$ 28,500.00	\$28,500.00
	ROADWAY/PATHWAY MATERIALS				
15	3/4" minus Aggregate Base Course	1,078	CY	\$ 120.00	\$ 129,360.00
16	Aggregate Subbase Course	1,443	CY	\$ 105.00	\$ 151,515.00
17	AC Pavement, SuperPave SP-3, PG584-28, 1/2" (Pathways)	5	TN	\$ 405.00	\$ 2,025.00
18	AC Pavement, SuperPave SP-3, PG64-28, 3/4" (Roadways)	1,601	TN	\$ 215.00	\$ 344,215.00
19	Concrete Sidewalk/ADA Ramps	443	SF	\$ 30.00	\$ 13,290.00
20	Curb Transition	14	LF	\$ 54.50	\$ 763.00
21	Zero-Reveal Curb	39	LF	\$ 54.50	\$ 2,125.50
22	3" Rolled Curb	61	LF	\$ 54.50	\$ 3,324.50
23	6" Vertical Curb	72	LF	\$ 54.50	\$ 3,924.00
24	Valley Gutter	42	LF	\$ 90.50	\$ 3,801.00
25	Pavement Markings	7,643	LF	\$ 0.80	\$ 6,114.40
	UTILITIES				Total Control of
26	Catch Basin	6	EA	\$ 3,200.00	\$ 19,200.00
27	Dry Well	6	EA	\$ 5,300.00	\$ 31,800.00
28	New Solid Lids	6	EA	\$ 585.00	\$ 3,510 00
29	12" RCP Culvert	71	LF	\$ 160.00	\$ 11,360.00
30	Whirly gig/Grade Ring Adjustment - Manhole	10	EA	\$ 2,100.00	\$ 21,000 00
31	Adjust Gas Valve Box & Lid	6	EA	\$ 2,100.00	\$ 12,600.00
32	Adjust Pullbox (Traffic Rated)	1	EA	\$ 685.00	\$ 685.00
33	Adjust Water Valve Box & Lid	18	EA	\$ 2,100.00	\$ 37,800.00
34	Trench for 2 - 2" PVC Conduit	279	LF	\$ 42.00	\$ 11,718.00
35	Handhole - 13" x 18" x 24"	4	EA	\$ 1,300.00	\$ 5,200.00
	WARNING SYSTEMS	1		170.0	
36	TUFTILE Truncated Domes	10	EA	\$ 600.00	\$ 6,000.00
37	New Sign (Stop Sign and Post)	2	EA	\$ 360.00	\$ 720.00
38	Install Sign Post Base	1	EA	\$ 300.00	\$ 300.00
	SCHEDULE 1 - Total of Ex	ctended Unit	Prices		\$1,552,943.40

	SCHEDULE 2 - MAIN STREET TO SPRUCI (CITY OF	E AVENUE - KETCHUM)	PEDES	TRIAN IMPROV	'EMENTS
Item No.	Description	Estimated Quantity	Unit	Unit Price	Extended Unit
	TEMPORARY				
1	Mobilization (≤10% of schedule bid total)	1	LS	\$ 56,500.00	\$ 56,500.00
2	Construction Survey	1	LS	\$ 15,500.00	\$ 15,500.00
3A	Traffic Signs	50	EA	\$ 250.00	\$ 12,500.00
3B	Portable Tubular Markers	180	EA	\$ 12.50	\$ 2,250.00
3C	Type II Barricades	10	EA	\$ 34,50	\$ 345.00
3D	Type III Barricades	0	EA	\$ 105.00	\$ 0.00
3E	PCMS	154	Day	\$ 115.00	\$ 17,710.00
3F	Pilot Car	0	HR	\$ 90.00	\$ 0.00
3G	Traffic Control Supervisor	220	HR	\$ 53.50	\$ 11,770.00
3H	Flagging	220	HR	\$ 49.00	\$ 10,780.00
4	Temporary Erosion & Sediment Control	1	LS	\$ 6,150.00	\$ 6,150.00
5	Dust Control	1	LS	\$ 8,000.00	\$ 8,000.00
	DEMOLITION				
6	Excavation	702	CY	\$ 54.50	\$ 38,259.00
7	Removal of Curb & Gutter	587	LF	\$ 48.50	\$ 28,469.50
8	Removal of Asphattic Concrete - Roadway	1,376	SY	\$ 20.50	\$ 28,208.00
9	Removal of Concrete Sidewalk	78	SY	\$ 365.00	\$ 28,470.00
10	Remove and Retain Pavers	140	SY	\$ 545.00	\$ 76,300.00
11	Remove Tree	1	EA	\$ 1,800.00	\$ 1,800.00
	ROADWAY/PATHWAY MATERIALS				1,000.00
12	3/4" minus Aggregate Base Course	221	CY	\$ 100.00	\$ 22,100.00
13	Aggregate Subbase Course	330	CY	\$ 85.00	\$ 28,050.00
14	AC Pavement, SuperPave SP-3, PG64- 28, 3/4" (Roadways)	298	TN	\$ 210 00	\$ 62,580.00
15	Concrete Sidewalk/ADA Ramps	3,407	SF	\$ 30.00	\$ 102,210.00
16	Curb Transition	217	LF	\$ 54.50	\$ 11,826.50
17	Zero-Reveal Curb	129	LF	\$ 54.50	\$ 7,030.50
18	6" Vertical Curb	289	LF	\$ 54,50	\$ 15,750.50
19	Valley Gutter	23	LF	\$ 90.50	\$ 2,081.50
20	Pavement Markings	6,608	LF	\$ 0.80	\$ 5,286.40
	WARNING SYSTEMS	-		1	
36	TUFTILE Truncated Domes	107	EA	\$ 600.00	\$ 64,200.00
37	New Sign (Stop Sign and Post)	2	EA	\$ 360,00	\$ 720.00
38	Install Sign Post Base	5	EA	\$ 300.00	\$ 1,500.00
	SCHEDULE 2 - Total of Ex				\$ 664,346.90

Item No.	Description	Estimated Quantity	Unit	Unit Price	Extended Unit
24	6" Rolled Curb	177	LF	\$ 66.50	\$ 11,770.50
25	4' Concrete Valley Gutter	64	LF	\$ 90.50	\$ 5,792.00
26	Infiltration Swale	1	LS	\$ 10,500.00	\$ 10,500.00
27	Pavement Markings	54,500	LF	\$ 0.70	\$ 38,150.00
28	Landscape Restoration	1	LS	\$ 240,000.00	\$ 240,000.00
28A	Construct Stairs	1	LS	\$ 3,850.00	\$ 3,850.00
	UTILITIES			=9 Gio	is CM page 1
29	Sediment Catch Basin	1	EA	\$ 6,850.00	\$ 6,850.00
30	New 14" CMP Culvert	8	LF	\$ 98.00	\$ 784.00
31	New 16" CMP Culvert	61	LF	\$ 100.00	\$ 6,100.00
32	New 24" CMP Culvert	10	LF	\$ 175.00	\$ 1,750.00
33	16" End Section	1,500	EA	\$ 650 00	\$ 650.00
34	Whirly gig/Grade Ring adjustment - Manhole	2	EA	\$ 2,100 00	\$ 4,200.00
35	Adjust Inlet	1	EA	\$ 1,600.00	\$ 1,600.00
36	Adjust Gas Valve Box & Lid	1	EA	\$ 2,100.00	\$ 2,100.00
37	Adjust Pullbox (Traffic Rated)	2	EA	\$ 685.00	\$ 1,370.00
38	Adjust Water Valve Box & Lid	11	EA	\$ 2,100 00	\$ 23,100.00
39	Concrete Collar - Valve	12	EA	\$ 1,400.00	\$ 16,800.00
40	Concrete Collar - Manhole	4	EA	\$ 1,400.00	\$ 5,600.00
	SCHEDULE 3 - Total of	f Extended Unit	Prices	678 (400 pm/) FR	\$ 3,379,818.00

Item No.	Description	Estimated Quantity	Unit	Unit Price	Extended Unit
	TEMPORARY	-			Tanada I II
1	Mobilization (≤10% of schedule bld total)	11	LS	\$ 8.500.00	\$ 8,500 00
2	Construction Survey	1	LS	\$ 7,250.00	\$ 7,250.00
3A	Traffic Signs	10	EA	\$ 250.00	\$ 2,500 00
3B	Portable Tubular Markers	30	EA	\$ 12.50	\$ 375.00
3C	Type II Barricades	4	EA	\$ 34.50	\$ 138.00
3D	Type III Barricades	0	EA	\$ 105.00	\$ 0.00
3E	PCMS :	0	Day	\$ 115.00	\$ 0.00
3F	Pilot Car	0	HR	\$ 90.00	\$ 0.00
3G	Traffic Control Supervisor	300	HR	\$ 53.50	\$ 16,050.00
3H	Flagging	0	HR	\$ 49.00	\$ 0.00
4	Temporary Erosion & Sediment Control	1	LS	\$ 1,800.00	\$ 1,800.00
5	Dust Control	= 1 1	LS	\$ 5,100.00	\$ 5,100.00
	DEMOLITION		2777	WALL TO SERVICE THE PROPERTY OF THE PROPERTY O	= = = = = = = = = = = = = = = = = = = =

Store 5 9, 2012

PW\DEN003\D3489600 ADDENDUM NO. 4
March 9, 2022 00 91 13 - 5
©COPYRIGHT 2022 JACOBS

ltem No.	Description	Estimated Quantity	Unit	Unit Price	Extended Uni Price
6	Excavation	20	CY	\$ 100.00	\$ 2,000.00
7	Removal of Curb & Gutter	64	LF	\$ 48.50	\$ 3,104.00
8	Removal of Asphaltic Concrete - Roadway	41	SY	\$ 26.00	\$1,086.00
9	Removal of Concrete Sidewalk	31	SY	\$ 365.00	\$ 11,315.00
10	Remove, Retain and Replace Signage	1	EA	\$ 500.00	\$ 500 00
	ROADWAY/PATHWAY MATERIALS				
11	3/4" minus Aggregate Base Course	28	CY	\$ 105.00	\$ 2,940.00
12	Aggregate Subbase Course	6	CY	\$ 185.00	\$ 1,110.00
13	AC Pavement, SuperPave SP-3, PG584-28, 1/2" (Pathways)	16	TN	\$ 225.00	\$ 3,600.00
14	AC Pavement, SuperPave SP-3, PG64-28, 3/4" (Roadways)	4	TN	\$ 345.00	\$ 1,380.00
15	Concrete Sidewalk/ADA Ramps	150	SF	\$ 42.00	\$ 6,300.00
16	Curb Transition	6	LF	\$ 54.50	\$ 327.00
17	Zero-Reveal Curb	22	LF	\$ 54.50	\$ 1,199.00
18	3" Rolled Curb	45	LF	\$ 54.50	\$ 2,452.50
19	1' Wide 6" Vertical Curb	25	LF	\$ 54.50	\$ 1,362.50
20	Pavement Markings	66	LF	\$ 11.00	\$ 726.00
	WARNING SYSTEMS				
21	TUFTILE Truncated Domes	9	EA	\$ 600.00	\$ 5,400.00
	ADDITIVE ALTERNATE - Total of E	xtended Unit	Prices	700	\$ 86,495.00

tem No.	Description	Estimated Quantity (See Note 1)	Unit	
	TEMPORARY			Property of the second
1	Mobilization (≤10% of schedule bid total)	1	LŞ	Inches de la companya della companya de la companya de la companya della companya
2	Construction Survey	1	L\$	
ЗА	Traffic Signs	50	EA	
3B	Portable Tubular Markers	80	EA	DESCRIPTION OF THE PERSON.
3C	Type II Barricades	2	EA	Maria Day
3D	Type III Barricades	2	EA	
3E	PCMS	49	Day	
3F	Pilot Car	0	HR	Elimina Physics
3G	Traffic Control Supervisor	0	HR	
3H	Flagging	630	HR	
4	Temporary Erosion & Sediment Control	1	LS	
5	Dust Control	1	LS	Total City

ADDENDUM NO. 4 PW\DEN003\D3489600 00 91 13 - 6 March 9, 2022 ©COPYRIGHT 2022 JACOBS

item No.	Description	Estimated Quantity (See Note 1)	Unit		
	DEMOLITION	1 222		COLUMN TO SERVICE	
6	Excavation	2,487	CY	THE RESERVE THE PERSON NAMED IN	15 SAIL
7	Removal of Asphaltic Concrete - Roadway	4,840	SY		NO.
	ROADWAY/PATHWAY MATERIALS				
8	3/4" minus Aggregate Base Course	807	CY		STATE OF THE PARTY.
9	Aggregate Subbase Course	1,076	CY	Relation of the	LAS
10	AC Pavement, SuperPave SP-3, PG64-28, 3/4" (Roadways)	1,201	TN	1024 (THE T

Note 1: Quantities are provided for Bidders estimation.

Note 2: Bidders are to provide a Lump Sum for Deduct A.

Item No.	Description	Estimated Quantity (See Note 1)	Unit	
	TEMPORARY			Maria Company
1	Mobilization (≤10% of schedule bid total)	1	LS	
2	Construction Survey	1	LS	MICHAEL BOOKER
3A	Traffic Signs	50	EA	
3B	Portable Tubular Markers	80	EA	Symples Committee
3C	Type II Barricades	2	EA	PRINTED BONDS
3D	Type ill Barricades	2	EA	
3E	PCMS	49	Day	MARKET COLUMN
3F	Pilot Car	0	HR	PRINTED AND MAKE TO
3G	Traffic Control Supervisor	0	HR	
3H	Flagging	630	HR	TO 100 Pd 100 Pd.
4	Temporary Erosion & Sediment Control	1	LS	
5	Dust Control	1	LS	THE RESERVE
in .	DEMOLITION			
6	Removal of Asphaltic Concrete - Roadway	4,840	SY	Con Liston
	ROADWAY/PATHWAY MATERIALS			THE RESERVE OF THE RE
10	AC Pavement, SuperPave SP-3, PG64-28, 3/4" (Roedways)	534	TN	
	Deduct A - (Negative)	1	LS	


Note 1: Quantities are provided for Bidders estimation.

Note 2: Bidders are to provide a Lump Sum for Deduct B.

PW\DEN003\D3489600 ADDENDUM NO. 4 March 9, 2022 00 91 13 - 7 ©COPYRIGHT 2022 JACOBS



Sun Valley Road







Scope

- Currently being designed & construction set for summer/fall 2022
- Road rebuild vs. original scope of mill and overlay
 - New ped crossings/ADA ramps
- Bike path connection Sun Valley/Spruce Street to 4th Avenue

Schedule

- Initial public open houses January
- Final design submittal January 31
- Bid advertising February 14
- Bid opening March 2
- Construction kickoff (weather depending) late April/early May³



Capital Improvements Update

Mobility – Sun Valley Road





Capital Improvements Update

Mobility – Sun Valley Road

