



**City of Ketchum
Planning & Building**

IN RE:)
)
Highway 75 Trail Creek Bridge) KETCHUM PLANNING AND ZONING COMMISSION
Floodplain Development Permit) FINDINGS OF FACT, CONCLUSIONS OF LAW, AND
File Number: P24-066) DECISION
)
Date: November 12, 2024)
)

PROJECT: Highway 75 Trail Creek Bridge
APPLICATION TYPE: Floodplain Development Permit
FILE NUMBER: P24-066
PROPERTY OWNER: Idaho Transportation Department (ITD)
REPRESENTATIVE: Mike Schubert, HDR Engineering
LOCATION: Highway 75 Bridge over Trail Creek
ZONING: Tourist (T) & Floodplain Management Overlay District (FMOD)

RECORD OF PROCEEDINGS

The Planning and Zoning Commission considered the 450 Wood River Drive Floodplain Development Review Application File No. P24-066 during their meeting on October 22, 2024. After considering the project plans, staff’s analysis, the applicant’s presentation, and holding the required public hearing, the Planning and Zoning Commission approved the request with a vote of 5-0.

Public Hearing Notice & Public Comment

A public meeting notice for the project was mailed to all owners of property within 300 feet of the project site and all political subdivisions on October 2, 2024. The notice was published in the Idaho Mountain Express on October 2, 2024. A notice was posted on the city’s website on October 7, 2024.

BACKGROUND

The project is part of the Highway 75 rebuild stretching from the intersection of River St & Main St south to the bridge crossing the Big Wood River just north of St Luke’s Hospital. The highway is undergoing a rebuild due to its current degraded condition. The proposed improvements include pedestrian enhancements (sidewalks and bike lane) and road widening. The northbound side of the

new bridge is expected to be constructed between August 1 and mid-November in 2025 with the southbound side of the new bridge expected to be constructed between Presidents Day and Memorial Day in 2026.

Process to Date

The Planning and Building Department received the Floodplain Development application for the project on July 24th, 2024. Following receipt of the application, staff routed the application materials to all city departments for review. The application was scheduled for hearing after all city department comments were resolved.

FINDINGS OF FACT

The Planning and Zoning Commission having reviewed the project record, provided notice, and conducted the required public hearing does hereby find that the project does conform to applicable standards and criteria as set forth in Ketchum Municipal Code Chapter 17.88 – Floodplain Management Overlay Zoning District (FP). The Commission discussed the geosynthetic grid, floodway standards, and aesthetic beauty pertaining to the project. After deliberation, the Commission found the project to be in conformance with the floodplain development criteria. Therefore, the Commission does hereby make and set forth these Findings of Fact, Conclusions of Law, and Decision as follows: make and set forth these Findings of Fact, Conclusions of Law, and Decision as follows:

Floodway Standards

There are special provisions for development within the floodway as they are extremely hazardous areas due to the velocity of floodwaters that have erosion potential and carry debris and potential projectiles. Permanent development in the floodway is prohibited with limited exceptions pursuant to KMC 17.88.050.E3. Pursuant to KMC 17.88.050.E19, the work proposed for stream alterations must be, “for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation.” The project proposes to replace the Trail Creek Bridge along State Highway 75 (“SH-75”). SH-75 is a Minor Arterial that serves as a connecting route to other Wood River Valley communities located to the north and south of Ketchum including critical resources such as St Luke’s Hospital and the Friedman Memorial Airport. Additionally, development can occur in the floodway if associated with “stream restoration and bank stabilization constructed in accordance with a floodplain development permit”. The project looks to provide streambank stabilization work both at the bridge and upstream in order to protect the newly constructed Highway 75.

There are special review requirements for development in the floodway due to its dangerous nature. These requirements include that the project meet all applicable flood hazard reduction provisions in Chapter 17.88 as well as provide no-rise certification. A no-rise certification must be supported by technical data and signed by a registered professional engineer stating that the project will not increase flood heights. The proposed project has been submitted with a no-rise certification by the project engineer stating that no increase in flood heights will occur as a result of the project’s development within the floodway with accompanying data reviewed and verified by the City’s

floodplain consultant, Harmony Design & Engineering. The project also submitted a HEC-RAS (Hydrologic Engineering Center River Analysis System) model which showed no adverse impact would occur on adjacent properties. After reviewing all accompanying application materials, the Commission found the project to meet standards for development withing the floodway.

Aesthetic Beauty

There are multiple streambank alteration criteria which speak to maintaining aesthetic beauty including 17.88.050.E.17 which states “the recreational use of the stream including access along any and all public pedestrian/fisher’s easements and the aesthetic beauty shall not be obstructed or interfered with by the proposed work.” Both locations of the project do not feature pedestrian/fisher easements and are largely inaccessible due to the topography of the sites or due to the crossing of private property so the Commission did not have concern that recreational use of Trail Creek at these locations would be interfered by the proposed work.

Staff worked with the applicant to ensure that the project did not deter from the aesthetic beauty of Trail Creek at the two locations where streambank stabilization was occurring. At the bridge location, riparian vegetation is proposed outside of the riprap and willow shoots planted within the riprap to provide for a healthy streambank as well as maintain the aesthetic beauty at this location. In the case of the streambank stabilization upstream of the bridge, staff supports the proposed wrapped face geosynthetic grid (Figure 4 & 5) that will provide landscaping along the entirety of the bank opposite of the Trail Creek Crossing Condominiums. This continuous vegetation is a better alternative than a soldier pile wall (Figure 6) which was initially contemplated to stabilize the bank at this location. This geosynthetic grid will allow for plantings along the streambank to help with erosion control as well as ensure the area looks as natural as possible.

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)1	The proposal preserves or restores the inherent natural characteristics of the river, floodplain, and riparian zone, including riparian vegetation and wildlife habitat. Development does not alter river channel unless all stream alteration criteria for evaluation are also met.
			<i>Staff Comments</i>	<i>The project preserves the inherent characteristics of the river and floodplain as it was shown that a no-rise will be achieved by the project. Riparian plantings are proposed at both locations of the project with quality bank stabilization species. Stream alteration criteria have been met, allowing for alteration of the river channel.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)2	No temporary construction activities, encroachment or other disturbance into the 25-foot riparian zone, including encroachment of below grade structures, shall be permitted, with the exception of

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
				approved stream stabilization work and restoration work associated with a riparian zone that is degraded.
			<i>Staff Comments</i>	<i>No temporary construction, other than the scope of streambank stabilization work approved by this permit, shall occur within the riparian zone.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)3	No permanent development shall occur within the 25-foot riparian zone, with the exception of approved stream stabilization work and restoration work associated with permit issued under this title, or exceptions as described below: a. Access to a property where no other primary access is available; b. Emergency access required by the fire department; c. A single defined pathways or staircases for the purpose of providing access to the river channel and in order to mitigate multiple undefined social paths; d. Development by the City of Ketchum.
			<i>Staff Comments</i>	<i>No development, other than the scope of streambank stabilization work approved by this permit, shall occur. No pathway or staircase through the riparian is associated with this permit.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)4	New or replacement planting and vegetation in the riparian zone shall include plantings that are low growing and have dense root systems for the purpose of stabilizing stream banks and repairing damage previously done to riparian vegetation. Examples of such plantings most commonly include: red osier dogwood, common chokecherry, serviceberry, elderberry, river birch, skunk bush sumac, Beb's willow, Drummond's willow, little wild rose, gooseberry, and honeysuckle. However, in rare instances the distance from the top-of-bank to the mean high water mark is significant and the native vegetation appropriate for the riparian zone are low growing, drought resistant grasses and shrubs. Replacement planting and vegetation shall be appropriate for the specific site conditions. Proposal does not include vegetation within the 25-foot riparian zone that is degraded, not natural, or which does not promote bank stability.
			<i>Staff Comments</i>	<i>Riparian vegetation proposed for the project include willow shoots, cottonwood trees, quaking aspen and woods rose.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)5	Landscaping and driveway plans to accommodate the function of the floodplain allow for sheet flooding. Surface drainage is controlled and shall not adversely impact adjacent properties including driveways drained away from paved roadways. Culvert(s) under driveways may be required. Landscaping berms shall be designed to not dam or

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
				otherwise obstruct floodwaters or divert same onto roads or other public pathways.
			<i>Staff Comments</i>	<i>N/A. No driveway or landscaping berms are proposed with the project</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)6	Flood water carrying capacity is not diminished by the proposal.
			<i>Staff Comments</i>	<i>As shown in the no-rise certificate, no increase in floodwaters is shown by the project showing that the carrying capacity is not diminished.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)7	Impacts of the development on aquatic life, recreation, or water quality upstream, downstream or across the stream are not adverse.
			<i>Staff Comments</i>	<i>There is no impact to recreation as the project areas are inaccessible due to topography. Aquatic life and water quality are not impacted due to plantings proposed as part of the project in the riprap and in the riparian area.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)8	Building setback in excess of the minimum required along waterways is encouraged. An additional ten-foot building setback beyond the required 25-foot riparian zone is encouraged to provide for yards, decks and patios outside the 25-foot riparian zone.
			<i>Staff Comments</i>	<i>N/A, no new building is proposed with this application.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)9	The top of the lowest floor of a building located in, or partially within, the SFHA shall be at or above the flood protection elevation (FPE). A building is considered to be partially within the SFHA if any portion of the building or appendage of the building, such as footings, attached decks, posts for upper story decks, are located within the SFHA. See section 17.88.060 , figures 1 and 2 of this chapter to reference construction details. See chapter 17.08 of this title for definition of "lowest floor." a. In the SFHA where base flood elevations (BFEs) have been determined, the FPE shall be 24 inches above the BFE for the subject property; 24 inches or two feet is the required freeboard in Ketchum City Limits. b. In the SFHA where no BFE has been established, the FPE shall be at least two feet above the highest adjacent grade.
			<i>Staff Comments</i>	<i>N/A, no new building is proposed with this application.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)10	The backfill used around the foundation in the SFHA floodplain shall provide a reasonable transition to existing grade but shall not be used to fill the parcel to any greater extent.

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
				<p>a. Compensatory storage shall be required for any fill placed within the floodplain.</p> <p>b. A CLOMR-F shall be obtained prior to placement of any additional fill in the floodplain.</p>
			<i>Staff Comments</i>	<i>N/A, no new building is proposed with this application.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)1 1	All new buildings located partially or wholly within the SFHA shall be constructed on foundations that are designed by a licensed professional engineer.
			<i>Staff Comments</i>	<i>N/A, no new building is proposed with this application.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)1 2	Driveways shall comply with City of Ketchum street standards; access for emergency vehicles has been adequately provided for by limiting flood depths in all roadways to one foot or less during the one percent annual chance event.
			<i>Staff Comments</i>	<i>N/A, no new driveway is proposed with this application.</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.88.050(E)1 3	Landscaping or revegetation shall conceal cuts and fills required for driveways and other elements of the development.
			<i>Staff Comments</i>	<i>N/A, no new driveway is proposed with this application.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)1 4	(Stream Alteration) The proposal is shown to be a permanent solution and creates a stable situation.
			<i>Staff Comments</i>	<i>The streambank stabilization as proposed shows to be a permanent solution as it will deter any further bank erosion or scour to occur at both project locations.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)1 5	(Stream alteration.) No increase to the one percent annual chance flood elevation at any location in the community, based on hydrologic and hydraulic analysis performed in accordance with standard engineering practice and has been certified and submitted with supporting calculations and a No Rise Certificate, by a registered Idaho engineer.
			<i>Staff Comments</i>	<i>The project engineer Spencer Savage, P.E., has submitted a No Rise Certification.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)1 6	(Stream alteration.) The project has demonstrated no adverse impact or has demonstrated all impacts will be mitigated.
			<i>Staff Comments</i>	<i>As shown in the HEC-RAS models, the project shows no impact on adjacent properties and will maintain flow conditions of Trail Creek.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)1 7	(Stream alteration.) The recreational use of the stream including access along any and all public pedestrian/fisher's easements and the

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
				aesthetic beauty shall not be obstructed or interfered with by the proposed work.
			<i>Staff Comments</i>	<i>Work is primarily being done in place of where existing bridge is located and upstream in one location where bank is very steep. Both locations are not areas where recreational use occurs. Aesthetic beauty is not obstructed or interfered with by the proposed work. Riprap will have vegetation dispersed throughout and the steep bank will be revegetated.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)18	(Stream alteration) Fish habitat is maintained or improved as a result of the work proposed.
			<i>Staff Comments</i>	<i>Fish habitat is maintained by the proposal. Willow barbs are proposed within riprap to soften the banks and trees to provide shading are proposed as well.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)19	(Stream alteration.) The proposed work shall not be in conflict with the local public interest, including, but not limited to, property values, fish and wildlife habitat, aquatic life, recreation and access to public lands and waters, aesthetic beauty of the stream and water quality.
			<i>Staff Comments</i>	<i>The proposed work in the public interest: the subject bridge is the main vehicular bridge connecting Ketchum with communities to the south. A functioning bridge in good repair is critical to public safety and property values.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)20	(Stream alteration.) The work proposed is for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation.
			<i>Staff Comments</i>	<i>The purpose of the project is to replace the existing bridge and protect against bank erosion further upstream where Highway 75 will be widened. The bridge serves as primary access for communities to the south into Ketchum.</i>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.88.050(E)21	(Wetlands) Where development is proposed that impacts any wetland the first priority shall be to move development from the wetland area. Mitigation strategies shall be proposed at time of application that replace the impacted wetland area with an equal amount and quality of new wetland area or riparian habitat improvement.
			<i>Staff Comments</i>	<i>As seen in project plans, Wetland A and Wetland B will be impacted by the proposed project. Mitigation will occur to plant cottonwoods, willows, aspens and rose bushes along the streambank. In total the</i>

Floodplain Development Permit Requirements				
1. Evaluation Standards: 17.88.050€				
Compliant			Standards and Staff Comments	
Yes	No	N/A	Guideline	City Standards and <i>Staff Comments</i>
				<i>project will disturb 51 sf of Wetland A and will be mitigated by an equal amount of riparian plantings along the streambank.</i>

CONCLUSIONS OF LAW

1. The City of Ketchum is a municipal corporation established in accordance with Article XII of the Constitution of the State of Idaho and Title 50 Idaho Code and is required and has exercised its authority pursuant to the Local Land Use Planning Act codified at Chapter 65 of Title 67 Idaho Code and pursuant to Chapters 3, 9 and 13 of Title 50 Idaho Code to enact the ordinances and regulations, which ordinances are codified in the Ketchum Municipal Code (“KMC”) and are identified in the Findings of Fact and which are herein restated as Conclusions of Law by this reference and which City Ordinances govern the applicant’s Floodplain Development Permit application for the development and use of the project site.
2. The Commission has authority to hear the applicant’s Floodplain Development Permit Application pursuant to Chapter 17.88 of Ketchum Municipal Code Title 17.
3. The City of Ketchum Planning Department provided notice for the review of this application in accordance with Ketchum Municipal Code §17.88.050.D.2.b.
4. The Floodplain Development Permit application is governed under Ketchum Municipal Code Chapters 17.88.
5. The 450 Wood River Floodplain Development Permit Application File No. P23-111 meets all applicable standards specified in Title 17 of Ketchum Municipal Code, as more fully described in the Findings of Fact above.

DECISION

THEREFORE, the Ketchum Planning and Zoning Commission approves this Floodplain Development Permit Application File No. P24-066 this Tuesday, November 12, 2024, subject to the following conditions of approval.

CONDITIONS OF APPROVAL

1. This approval is subject to the scope of work described in the documents shown in Attachment A & B. The Trail Creek Planting Plan found in Attachment A is voided due to being out of date.

2. Any modification to approved plans as referenced in this approval shall be subject to a written amendment to this permit approval. If construction or improvements differ from the approved plans, such work may be subject to removal at the applicant's expense.
3. Follow up site visits to ensure compliance with the approved Trail Creek Slope Planting Plan & Trail Creek Planting Plan, are required for the three (3) years following the initial site visit that occurs in conjunction with issuance of the Certificate of Occupancy.
 - a. If, upon an annual inspection, 80% or fewer of the plants indicated on Trail Creek Slope Planting Plan & Trail Creek Planting Plan have not survived, the property owner shall re-install new plantings.
4. The Administrator shall conduct site inspections of work in progress. The Administrator shall make as many inspections of the work as may be necessary to ensure that the work is being done according to the terms of this permit, approved plans, and KMC 17.88. In exercising this power, the Administrator has a right, upon presentation of proper credentials, to enter the property at any reasonable hour for the purposes of inspection or other enforcement action.
5. Floodplain Development Permit approval shall expire one (1) year from the date of signing of approved Findings of Fact per the terms of KMC, Section 17.88.050.G, Terms of Approval, if construction has not commenced. Once a building permit has been issued, the approval shall be valid for the duration of the building permit.
6. No use of restricted use chemicals or soil sterilants will be allowed within one hundred feet (100') of the mean high-water mark on any property within the city limits at any time (KMC 17.88.040.C.3);
7. All applications of herbicides and/or pesticides within one hundred feet (100') of the mean high water mark, but not within twenty five feet (25') of the mean high water mark, must be done by a licensed applicator and applied at the minimum application rates (KMC 17.88.040.C.4);
8. Application times for herbicides and/or pesticides will be limited to two (2) times a year; once in the spring and once in the fall unless otherwise approved by the City Arborist (KMC 17.88.040.C.5);
9. It shall be unlawful to dump, deposit or otherwise cause any trash, landscape debris or other material to be placed in any stream, channel, ditch, pond or basin that regularly or periodically carries or stores water.

Findings of Fact **adopted** this 12th day of November 2024.

Neil Morrow, Chair
 City of Ketchum
 Planning and Zoning Commission

Attachments:

- A. Floodplain Development Permit Application Materials & Plans
- B. Trail Creek Bridge Planting Plans

Attachment A:
Floodplain Development
Permit Materials & Plans

OFFICIAL USE ONLY
File Number:
Date Received:
By:
Fee Paid:
Approved Date:
Denied Date:
By:

Floodplain Development Permit Application

Submit completed application and documentation to planningandzoning@ketchumidaho.org Or hand deliver to Ketchum City Hall, 191 5th St. W. Ketchum, ID If you have questions, please contact the Planning and Building Department at (208) 726-7801. To view the Development Standards, visit the City website at: www.ketchumidaho.org and click on Municipal Code. You will be contacted and invoiced once your application package is complete.

When is a Floodplain Development Permit Application required?

The Floodplain Management Overlay Zoning District boundaries are represented on the official zoning map of the City.

All land within the external boundary of the special flood hazard area (SFHA) and all parcels with any portion thereof affected by said SFHA shall be considered to be within the Floodplain Management Overlay Zoning district.

All land areas within the external boundary of the SFHA shall be considered to be within the floodplain subdistrict of the Floodplain Management Overlay Zoning District. The City may make necessary interpretations of the boundary based upon the recommendation of the City Engineer or other expert.

All land areas within the external boundary of the regulatory floodway shall be considered to be within the floodway subdistrict of the Floodplain Management Overlay Zoning District. The City may make necessary interpretations of the boundary based upon the recommendation of the City Engineer or other expert.

NOTE: This permit is required for all properties containing 100 year floodplain area and Riparian Setbacks

PROPERTY OWNER INFORMATION
Property Owner Name(s):
Property Owner's Mailing Address:
Phone:
Email:
PROJECT INFORMATION
Project Name:
Project Representative's Name (main point of contact for project):
Project Representative's Phone:
Project Representative's Mailing Address:
Project Representative's Email:
Architect's name, phone number, e-mail:
Landscape Architect's name, phone number, e-mail:
Environmental consultant's name, phone number, e-mail:
Engineer's name, phone number, e-mail:
Project Address:
Legal Description of parcel:
Lot Size:
Zoning District:
Overlay Zones – indicate all that apply: <input type="checkbox"/> Floodplain <input type="checkbox"/> Floodway <input type="checkbox"/> Riparian Zone <input type="checkbox"/> Avalanche <input type="checkbox"/> Mountain
Brief description of project scope:
Value of Project: \$
TYPE OF PROJECT – indicate all that apply:

<input type="checkbox"/> New Building in Floodplain	<input type="checkbox"/> Building Addition in Floodplain	<input type="checkbox"/> Emergency Streambank Stabilization / Stream Alteration	<input type="checkbox"/> Other. Please describe: Replace bridge
<input type="checkbox"/> Floodplain Development	<input type="checkbox"/> Streambank Stabilization / Stream Alteration		
PROPOSED SETBACKS – if project is a new building or an addition to an existing building			
Front:	Side:	Side:	Rear:
ADDITIONAL INFORMATION			
Will fill or excavation be required in floodplain, floodway or riparian zone? Yes <input type="checkbox"/> No <input type="checkbox"/>			
If Yes, Amount in Cubic Yards: Fill: CY Excavation: CY			
Will Existing Trees or Vegetation be Removed? Yes <input type="checkbox"/> No <input type="checkbox"/>			
Will new trees or vegetation be planted? Yes <input type="checkbox"/> No <input type="checkbox"/>			

Applicant agrees in the event of a dispute concerning the interpretation or enforcement of the Floodplain Management Overlay Application, in which the City of Ketchum is the prevailing party, to pay reasonable attorney fees, including attorney fees on appeal, and expenses of the City of Ketchum. I, the undersigned, certify that all information submitted with and upon this application form is true and accurate to the best of my knowledge and belief.

Signature of Owner/Representative

Date

FLOODPLAIN MANAGEMENT OVERLAY EVALUATION STANDARDS

Please provide a narrative to address each of the criteria below.

Criteria for Evaluation of Applications: The criteria of floodplain development permit applications shall be as follows:

1. The proposal preserves or restores the inherent natural characteristics of the river, floodplain, and Riparian Zone, including riparian vegetation and wildlife habitat. Development does not alter river channel unless all stream alteration criteria for evaluation are also met.
2. No temporary construction activities, encroachment, or other disturbance into the twenty-five foot (25') Riparian Zone, including encroachment of below grade structures, shall be permitted, except for approved stream stabilization work and restoration work associated with a riparian zone that is degraded.
3. No permanent development shall occur within the twenty-five foot (25') Riparian Zone, except for approved stream stabilization work and restoration work associated with permit issued under this title, or exceptions as described below:
 - a. Access to a property where no other primary access is available.
 - b. Emergency access required by the Fire Department.
 - c. A single defined pathways or staircases for the purpose of providing access to the river channel and in order to mitigate multiple undefined social paths.
 - d. Development by the City of Ketchum
4. New or replacement planting and vegetation in the Riparian Zone shall include plantings that are low growing and have dense root systems for the purpose of stabilizing stream banks and repairing damage previously done to riparian vegetation. Examples of such plantings most commonly include red osier dogwood, common chokecherry, serviceberry, elderberry, river birch, skunk bush sumac, Beb's willow, Drummond's willow, little wild rose, gooseberry, and honeysuckle. However, in rare instances the distance from the top-of-bank to the mean high-water mark is significant and the native vegetation appropriate for the Riparian Zone are low growing, drought resistant grasses and shrubs. Replacement planting and vegetation shall be appropriate for the specific site conditions. Proposal does not include vegetation within the twenty-five foot (25') Riparian Zone that is degraded, not natural, or which does not promote bank stability.
5. Landscaping and driveway plans to accommodate the function of the floodplain allow for sheet flooding. Surface drainage is controlled and shall not adversely impact adjacent properties including driveways drained away from paved roadways. Culvert(s) under driveways may be required. Landscaping berms shall be designed to not dam or otherwise obstruct floodwaters or divert same onto roads or other public pathways.
6. Floodwater carrying capacity is not diminished by the proposal.
7. Impacts of the development on aquatic life, recreation, or water quality upstream, downstream or across the stream are not negative.
8. Building setback in excess of the minimum required along waterways is encouraged. An additional ten-foot (10') building setback beyond the required twenty-five foot (25') Riparian Zone is encouraged to provide for yards, decks and patios outside the twenty five foot (25') Riparian Zone.
9. The top of the lowest floor of a building located in, or partially within, the SFHA shall be at or above the Flood Protection Elevation (FPE). A building is considered to be partially within the SFHA if any portion of the building or appendage of the building, such as footings, attached decks, posts for upper story decks, are located within the SFHA. See section 17.88.060, figures 1 and 2 of this chapter to reference construction details. See Chapter 17.08 of this title for definition of "lowest floor."
 - a. In the SFHA where Base Flood Elevations (BFEs) have been determined, the FPE shall be twenty-four inches (24") above the BFE for the subject property; twenty-four inches (24") or two (2) feet is the required freeboard in Ketchum city limits.
 - b. In the SFHA where no BFE has been established, the FPE shall be at least two (2) feet above the highest adjacent grade.
10. The backfill used around the foundation in the SFHA floodplain shall provide a reasonable transition to existing grade but shall not be used to fill the parcel to any greater extent.
 - a. Compensatory storage shall be required for any fill placed within the floodplain.
 - b. A CLOMR-F shall be obtained prior to placement of any additional fill in the floodplain.
11. All new buildings located partially or wholly within the SFHA shall be constructed on foundations that are designed by a licensed professional engineer.

12. Driveways shall comply with City of Ketchum street standards; access for emergency vehicles has been adequately provided for by limiting flood depths in all roadways to one foot (1-ft) or less during the 1% annual chance event.
13. Landscaping or revegetation shall conceal cuts and fills required for driveways and other elements of the development.
14. (Stream alteration.) The proposal is shown to be a permanent solution and creates a stable situation.
15. (Stream alteration.) No increase to the one percent (1%) annual chance flood elevation at any location in the community, based on hydrologic and hydraulic analysis performed in accordance with standard engineering practice and has been certified and submitted with supporting calculations and a No Rise Certificate, by a registered Idaho engineer.
16. (Stream alteration.) The project has demonstrated No Adverse Impact or has demonstrated all impacts will be mitigated.
17. (Stream alteration.) The recreational use of the stream including access along any and all public pedestrian/fisher's easements and the aesthetic beauty shall not be obstructed or interfered with by the proposed work.
18. (Stream alteration.) Fish habitat shall be maintained or improved as a result of the work proposed.
19. (Stream alteration.) The proposed work shall not be in conflict with the local public interest, including, but not limited to, property values, fish and wildlife habitat, aquatic life, recreation and access to public lands and waters, aesthetic beauty of the stream and water quality.
20. (Stream alteration.) The work proposed is for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation.
21. (Wetlands) Where development is proposed that impacts any wetland the first priority shall be to move development from the wetland area. Mitigation strategies shall be proposed at time of application that replace the impacted wetland area with an equal amount and quality of new wetland area or riparian habitat improvement.

APPLICATION CHECKLIST

Please utilize and submit the checklist on the following pages to ensure a complete application.

Floodplain management overlay application certification of completeness is based on submittal of all applicable items on this checklist.

Project name: _____

Reviewed by: _____

DOCUMENTS

- One (1) digital copy of all application materials
- Application form
- Evaluation criteria narrative
- Description of proposed development
- Specifications for building construction and materials, flood proofing, filling, grading, dredging, channel improvement/changes and utilities
- Elevation and/or flood proofing certification prepared by a professional engineer for existing and proposed residential and nonresidential structures located partially or wholly in the regulatory floodplain. Said floodproofing methods shall meet the criteria in subsection 17.88.060.B of the Ketchum Municipal Code.
- Copy of letter of map amendment based on fill (LOMA-F) application for any proposed fill in the floodplain. LOMA-F approval shall be obtained from FEMA prior to issuance of a floodplain development permit.
- Signed, notarized, original copy of the Acknowledgement of Floodplain Management Overlay District and Waterways Design Review District Affidavit.

SITE SURVEY OF EXISTING CONDITIONS (prepared and stamped by a licensed engineer or surveyor) – REQUIRED FOR NEW BUILDINGS OR ADDITIONS TO BUILDINGS IN THE FLOODPLAIN AND ANY WORK WITHIN THE FLOODWAY

- Exterior boundary lines of the property together with dimensions
- Topographic survey of the real property at a minimum of one (1) foot contour intervals, significant hillsides may be a minimum of ten (10) foot contour intervals
- Location of any existing dwelling units, other structures, fill, storage of materials, drainage facilities and all improved areas (pavement) with dimensions thereof showing the setback of each structure from the nearest property line
- Location of existing channels and ditches and other significant natural features, boundaries of floodway and floodplain, including Base Flood Elevation (BFE) and other site specific information from the studies referred to in Ketchum Municipal Code, subsection 17.88.040.A.3
- Location and elevations of adjacent streets, water supply and sewer lines, including private wells and/or septic systems
- Elevation of the lowest floor (including basement) of all structures existing and proposed partially or wholly located in the one percent (1%) annual chance floodplain, including elevation to which any structure has been or will be floodproofed
- Identification of the riparian zone and the "mean high water mark," as defined in Ketchum Municipal Code
- Location of previous stream alterations upstream, downstream and along both banks from subject lot
- Location of drainage ways, intermittent and year-round, including potential overflow channels or channel movement
- Location and dimensions of easements, private and public, within and adjacent to the proposed project together with the purpose thereof
- Location of all existing trees to be preserved and significant trees to be removed
- Indication of any zoning district overlay which affects the property (floodplain, mountain overlay or avalanche)
- Location of existing structures on adjacent properties

SITE PLAN – REQUIRED FOR ALL PROJECTS.

- Vicinity map
- Proposed excavation or land fill including resulting slope grades for the building pad(s), driveways and any other element of the proposed development where excavation or fill will take place
- Drainage plan including offsite improvements such as borrow ditches and culverts and including a plan for on- and off-site improvements to provide for unobstructed conveyance of floodwaters
- Location of on-site parking spaces and access thereto, including the dimensions of the spaces and the width and length of access and curb cuts
- Location and dimensions of snow storage areas
- Location of dumpster and/or garbage and recycling can storage areas, including the dimensions and proposed fencing or other screening
- Location and type of any electrical power transformers, switches and/or sectors
- Location and type of all heating, ventilation, air conditioning and other mechanical units
- Drip line of all buildings
- Percentage of the lot coverage by proposed building and parking areas together with the total square footage of the parcel of property
- Location of all proposed structures (buildings) and all improved areas (pavement, sidewalk) with dimensions thereof showing the setback of each structure from the nearest property line
- Designation of the zoning district in which the project is located
- Location of any zoning district boundary line within the proposed project or the immediate vicinity thereof
- For any building in the floodplain with an area below the lowest floor that is below the base flood elevation and has a ceiling height of five feet (5') or greater, the building owner shall sign a non-conversion agreement, that shall run with the property, promising not to improve, finish or otherwise convert the area below the lowest floor to living area and granting the city the right to inspect the enclosed area at its discretion. Such agreement shall be recorded at Blaine County's recorder's office

ARCHITECTURAL PLANS – REQUIRED FOR NEW BUILDINGS OR ADDITIONS TO EXISTING BUILDINGS

- Floor plans of all floors at not less than one-eighth (1/8) scale
- All exterior elevations
- Roof plan including direction of snow sliding and snow clips if applicable. Location and type of all mechanical equipment and rooftop appurtenances
- Cross-section(s) of the property and proposed building adequately establishing the natural grade, finished grade, slope of land, slope of proposed accesses and grades to all public rights-of-way
- Location and type (cut sheets) of all exterior lighting
- Model or computer simulation renderings, if required at pre-application design review meeting

LANDSCAPE PLAN – REQUIRED FOR ANY PROJECT PROPOSING TO ALTER VEGETATION IN THE RIPARIAN ZONE OR SPECIAL FLOOD HAZARD AREA

- All existing vegetation over 2 inches in caliper, including size and species
- Proposed landscaping of the project including types, quantities and sizes of trees, shrubs, ground cover and other vegetation
- Proposed landscaping or other improvements within any public rights-of-way
- Location, type (materials and colors) and height of walls or fences
- Location of parking areas
- Location of vehicular and pedestrian circulation patterns, easements and proposed improvements with regard thereto
- Irrigation system for landscaping
- Drainage plan including off-site improvements

STREAM ALTERATIONS / STREAMBANK STABILIZATION

- Copies of the Joint Application for Permits submitted to the U.S. army corps of engineers (USACE) and Idaho department of water resources (IDWR). Please note, USACE and IDWR approvals shall be obtained prior to issuance of a stream alteration permit.
- Copy of the USACE permit approval.
- Copy of the IDWR permit approval.
- Cross section of proposed work

- Length of stream to be worked, type of work to be done, type of equipment to be used and starting and completion dates of work
- A valley cross section showing stream channel, floodway limits, elevations of adjacent land areas, Special Flood Hazard Area boundary, floodway boundary, existing Mean High Water mark, proposed Mean High Water mark, Riparian Zone regulated by the City of Ketchum, proposed excavation, proposed fill. A profile showing the slope of the bottom of the channel or flow line of the stream may be required upon review of all other material submitted.
- For any work proposed to occur in the regulatory floodway: A no net rise certificate, including supporting calculations, prepared and stamped by an Idaho registered professional hydraulic engineer
- For any work proposed to occur in the floodway: HEC-RAS model

NO ADVERSE IMPACT STATEMENT – WHERE APPLICABLE

- No Adverse Impact Statement
 - See definition of “No Adverse Impact” in section 17.08.020 of Ketchum Municipal Code.



Acknowledgement of Floodplain Affidavit

Pursuant to Ketchum Municipal Code §17.88.040 D1, prior to the issuance of any floodplain development permit for development within the Floodplain Management Overlay District and the Waterways Review District as defined under to Ketchum Municipal Code §17.08, the property owner shall submit to the Planning and Building Department a written affidavit on a form provided by the City, signed by the property owner under seal of a notary public, of the property owner's actual knowledge that the property is located within the Floodplain Management Overlay District or the Waterways Review District. The property owner will also acknowledge that he or she is aware of the flood hazard potential for the property and is aware of the regulations the Floodplain Management Overlay Zoning District and Waterways Review District no work shall occur in these areas without city permits and approvals

Instructions

1. Property owner shall complete the attached affidavit.
2. Property Owner shall sign before a notary public and have the affidavit notarized.
3. Property Owner shall return original notarized affidavit to the City of Ketchum Planning & Building Department.
4. The Planning & Building Department shall have the notarized affidavit recorded in the records of Blaine County for the property.
5. A copy of the recorded document will be delivered to the Property Owner and filed in the City records with the building permit documents.

RECORDING REQUESTED BY AND WHEN RECORDED RETURN TO: City Clerk, City of Ketchum PO Box 2315 Ketchum Idaho, 83340	
--	--

(Space Above Line For Recorder's Use)

Acknowledgement of Floodplain Management Overlay District and Waterways Design Review District Affidavit

Property Owner:
Building Permit Number:
Property Address:
Legal Description:
Parcel Number: RPK
Scope of Work:

Please initial and fill below:

_____ I acknowledge that this development and the parcel of land, or portion thereof, on which the development will be situated are within the Floodplain Management Overlay District.

_____ I acknowledge this property is within the Waterways Review District.

_____ I have thoroughly read and fully understand Ketchum Municipal Code Title 17, Chapter 17.88 "Floodplain Management Overlay District", to include regulations for the Waterways Design Review District including regulations on activities within 100 feet of the mean high-water mark.

_____ I fully understand and agree to comply with Ketchum Municipal Code Title 17, Chapter 17.88.040 C.

_____ I fully understand and agree to comply with all conditions of approval associated with floodplain development permit #P_____

_____ I, on behalf of myself, my personal representatives and my heirs, successors, and assignees, acknowledge by this written *affidavit* that said property is located within the one percent annual chance floodplain (SFHA) as defined herein, and/or said property is within the Waterways Design Review District and that a violation of the terms of Ketchum Municipal Code 17.88 shall cause the City to seek legal remedies.

_____ I, on behalf of myself, my personal representatives and my heirs, successors, and assignees, acknowledge by this written *affidavit* that said property is located within the one percent annual chance floodplain (SFHA) as defined herein, that such floodplain and floodway boundaries and restrictions and requirement for development on the property may change and I will comply with all requirements that may be in effect at the time of development.

_____ I acknowledge that the City of Ketchum Planning & Building Department shall have the notarized affidavit recorded in the records of Blaine County for the property.

 Property Owner Signature _____
Date

STATE OF _____, County of _____

On this _____ day of _____, _____, before me, the undersigned, a Notary Public in and for said State, personally appeared _____, known or identified to me to be the person whose name is subscribed to the within instrument.

WITNESS my hand and seal the day and year in this certificate first above written.

 Notary Public for _____ Residing at: _____
 Commission Expires: _____

(State)

City of Ketchum accepts this Affidavit from (insert owner's name).

ATTEST, CITY CLEK

JOINT APPLICATION FOR PERMITS

U.S. ARMY CORPS OF ENGINEERS - IDAHO DEPARTMENT OF WATER RESOURCES - IDAHO DEPARTMENT OF LANDS

Authorities: The Department of Army Corps of Engineers (Corps), Idaho Department of Water Resources (IDWR), and Idaho Department of Lands (IDL) established a joint process for activities impacting jurisdictional waterways that require review and/or approval of both the Corps and State of Idaho. Department of Army permits are required by Section 10 of the Rivers & Harbors Act of 1899 for any structure(s) or work in or affecting navigable waters of the United States and by Section 404 of the Clean Water Act for the discharge of dredged or fill materials into waters of the United States, including adjacent wetlands. State permits are required under the State of Idaho, Stream Protection Act (Title 42, Chapter 38, Idaho Code and Lake Protection Act (Section 58, Chapter 13 et seq., Idaho Code). In addition the information will be used to determine compliance with Section 401 of the Clean Water Act by the appropriate State, Tribal or Federal entity.

Joint Application: Information provided on this application will be used in evaluating the proposed activities. Disclosure of requested information is voluntary. Failure to supply the requested information may delay processing and issuance of the appropriate permit or authorization. **Applicant will need to send a completed application, along with one (1) set of legible, black and white (8½"x11"), reproducible drawings that illustrate the location and character of the proposed project / activities to both the Corps and the State of Idaho.**

See Instruction Guide for assistance with Application. Accurate submission of requested information can prevent delays in reviewing and permitting your application. Drawings including vicinity maps, plan-view and section-view drawings must be submitted on 8-1/2 x 11 papers.

Do not start work until you have received all required permits from both the Corps and the State of Idaho

FOR AGENCY USE ONLY

USACE NWW-	Date Received:	<input type="checkbox"/> Incomplete Application Returned	Date Returned:
Idaho Department of Water Resources No.	Date Received:	<input type="checkbox"/> Fee Received DATE:	Receipt No.:
Idaho Department of Lands No.	Date Received:	<input type="checkbox"/> Fee Received DATE:	Receipt No.:

INCOMPLETE APPLICANTS MAY NOT BE PROCESSED

1. CONTACT INFORMATION - APPLICANT Required:				2. CONTACT INFORMATION - AGENT:			
Name: Jesse Barrus (District Engineer) or Scott Malone (Engineer Manager)				Name: Nathan Jerke			
Company: Idaho Transportation Department (ITD) District 4				Company: Idaho Transportation Department (ITD) District 4			
Mailing Address: 216 South Date Street				Mailing Address: 216 South Date Street			
City: Shoshone		State: ID	Zip Code: 83352-1521	City: Shoshone		State: ID	Zip Code: 83352-1521
Phone Number <i>(include area code)</i> : 208-886-7800		E-mail: scott.malone@itd.idaho.gov		Phone Number <i>(include area code)</i> : 208-886-7809		E-mail: nathan.jerke@itd.idaho.gov	

3. PROJECT NAME or TITLE: SH-75, Elkhorn Rd to River St				4. PROJECT STREET ADDRESS: SH-75 MP 126.4 to MP 128.2				
5. PROJECT COUNTY: Blaine		6. PROJECT CITY: Ketchum		7. PROJECT ZIP CODE: 83340		8. NEAREST WATERWAY/WATERBODY: Trail Creek		
9. TAX PARCEL ID#:		10. LATITUDE: 43.667041 (approx. center) LONGITUDE: -114.355657		11a. 1/4:	11b. 1/4:	11c. SECTION: 18, 19, 30	11d. TOWNSHIP: 4N	11e. RANGE: 18E
12a. ESTIMATED START DATE: Jan 1, 2025		12b. ESTIMATED END DATE: Oct 31, 2027		13a. IS PROJECT LOCATED WITHIN ESTABLISHED TRIBAL RESERVATION BOUNDARIES? <input checked="" type="checkbox"/> NO <input type="checkbox"/> YES Tribe:				
13b. IS PROJECT LOCATED IN LISTED ESA AREA? <input type="checkbox"/> NO <input checked="" type="checkbox"/> YES				13c. IS PROJECT LOCATED ON/NEAR HISTORICAL SITE? <input checked="" type="checkbox"/> NO <input type="checkbox"/> YES				

14. DIRECTIONS TO PROJECT SITE: Include vicinity map with legible crossroads, street numbers, names, landmarks.

The Project begins on SH-75 at approximately mile post (MP) 126.4 and ends near MP 128.2 at the intersection of River Street. The Project may be accessed from I-84 by taking US-93 (which transitions to SH-75) north to Ketchum, Idaho. From the City of Ketchum, take Main St south which transitions to SH-75.

15. PURPOSE and NEED: Commercial Industrial Public Private Other

Describe the reason or purpose of your project; include a brief description of the overall project. Continue to Block 16 to detail each work activity and overall project.

This Project aims to improve safety and capacity on SH-75 between the Big Wood River Bridge near Elkhorn Road and River Street in the City of Ketchum in Blaine County, mileposts (MP) 126.4 to 128.2. Project development will include roadway widening with curb, gutter, sidewalk, intersection improvement, retaining walls, drainage, public involvement, and replacing a box culvert and constructing a reinforced slope along Trail Creek.

16. DETAILED DESCRIPTION OF EACH ACTIVITY WITHIN OVERALL PROJECT. Specifically indicate portions that take place within waters of the United States, including wetlands: Include dimensions; equipment, construction, methods; erosion, sediment and turbidity controls; hydrological changes: general stream/surface water flows, estimated winter/summer flows; borrow sources, disposal locations etc.:

The wetland and stream impacts are a result of road widening, bridge replacement (construction of a reinforced slope to stabilize the stream bank on Trail Creek and construction of wildlife bench), and the installation of a stormwater facility. Work within wetlands consists of fill placement for roadway widening, scour protection, and stream bank grading to increase hydraulic flow. Additionally, culvert work will be required. This will include installation of a concrete box and headwalls, modification of stormwater pond, and replacement of three irrigation culverts and irrigation crossing. Construction equipment will include rollers, backhoes, excavators, cranes, and other construction equipment typical for a roadway and bridge construction project. All materials sources will be determined by the contractor and approved by the project engineer. Waste materials will be disposed of in an approved upland location. All bridge improvements will be located outside of the existing and proposed stream channels. The project is designed to restore a more natural channel gradient, bed, and width, and improved bank stability through the structure. New bridge footings will be constructed outside OHWM. (See Attachment C, page 6 and 7). Equipment will include an excavator operating from the bank/existing roadway. The construction area within the OHWM of the open waters will be dewatered using sandbags or another similar temporary dewatering method. A qualified Biologist will capture and remove fish from the dewatered work area if needed. A pump with a fish screen will be used to transfer water. The in-water work window will be observed for construction from July 15 to March 15, which was confirmed by Idaho Department of Water Resources (IDWR) and Idaho Department of Fish and Game (IDFG). An ITD approved Storm Water Pollution Prevention Plan (SWPPP) will be prepared for this project to comply with the Construction General permit. The SWPPP will include measures to address sediment and erosion control with both temporary and permanent measures. Critical areas including wetlands will be marked to retain and protect on Design Plans and SWPPP Plans except as allowed in 404 and other permits. The perimeter of the wetlands that are not permitted to be impacted will be clearly marked with high visibility silt fence.

17. DESCRIBE ALTERNATIVES CONSIDERED to AVOID or MEASURES TAKEN to MINIMIZE and/ or COMPENSATE for IMPACTS to WATERS of the UNITED STATES, INCLUDING WETLANDS: See Instruction Guide for specific details.

The do nothing alternative is not practicable because it does not meet the purpose and need of the project. Improvements that will not result in wetland impacts are not prudent or practicable since the highway must be widened in order to build the alternative and improve safety and capacity on SH-75 as described in the SH-75 Timmerman to Ketchum Environmental Impact Statement (FEIS) and Record of Decision (ROD) which was approved in August 2008. The FEIS-ROD was reevaluated in 2023 and approved by FHWA.

Tree removal along the riparian corridor will be minimized by using retaining walls and a reinforced slope along Trail Creek. The disturbed riparian area and reinforced slope will be planted with native plant species. The existing box culvert at Trail Creek will be replaced with a clear span bridge which will improve hydrological flow and increase the amount of available aquatic habitat.

18. PROPOSED MITIGATION STATEMENT or PLAN: If you believe a mitigation plan is not needed, provide a statement and your reasoning why a mitigation plan is NOT required. Or, attach a copy of your proposed mitigation plan.

The total wetland impacts are 1,956 square ft (0.0449 acre) and the total open water impacts are 1,555 square feet (0.0358 acre). Wetland impact acreage is less than 0.1 acre; therefore, mitigation is not required through the US Army Corps of Engineers (USACE) but still required under FHWA Executive Order (EO) 11990. While the total acres of impact to open water exceeds the 0.03 acre threshold for mitigation through USACE the project impacts to Trail Creek due to the bridge replacement will increase aquatic habitat under the Trail Creek Bridge by 175 sqft and stabilization will be through a vegetated wall along the stream bank (716 sqft) which are improvements and self-mitigating; therefore, mitigation is not required through the USACE.

The mitigation plan for FHWA is available upon request.

19. TYPE and QUANTITY of MATERIAL(S) to be discharged below the ordinary high water mark and/or wetlands:

Dirt or Topsoil: _____ cubic yards
 Dredged Material: _____ cubic yards
 Clean Sand: _____ cubic yards
 Clay: _____ cubic yards
 Gravel, Rock, or Stone: _____ cubic yards
 Concrete: _____ cubic yards
 Other (describe): See Attachments : _____ cubic yards
 Other (describe): _____ : _____ cubic yards

TOTAL: _____ cubic yards

20. TYPE and QUANTITY of impacts to waters of the United States, including wetlands:

Filling: _____ acres _____ sq ft. _____ cubic yards
 Backfill & Bedding: _____ acres _____ sq ft. _____ cubic yards
 Land Clearing: _____ acres _____ sq ft. _____ cubic yards
 Dredging: _____ acres _____ sq ft. _____ cubic yards
 Flooding: _____ acres _____ sq ft. _____ cubic yards
 Excavation: _____ acres _____ sq ft. _____ cubic yards
 Draining: _____ acres _____ sq ft. _____ cubic yards
 Other: See Attachments : _____ acres _____ sq ft. _____ cubic yards

TOTALS: _____ acres _____ sq ft. _____ cubic yards

21. HAVE ANY WORK ACTIVITIES STARTED ON THIS PROJECT? NO YES If yes, describe ALL work that has occurred including dates.

22. LIST ALL PREVIOUSLY ISSUED PERMIT AUTHORIZATIONS:
 Floodplain Management Permit (3/30/2020 application, pending). A final floodplain permit application would be approved by the City of Ketchum Floodplain Administrator within 180 days prior to construction under authority of FEMA's National Flood Insurance Program (NFIP) and the City of Ketchum's floodplain management ordinance (Ordinance 1120 §17.88.070 C.1).
 USACE identifies this job as --SH-75, Elkhorn Rd. to River St. (KN 20033), NWW-2020-0050 from the PJD issued January 2024.

23. YES, Alteration(s) are located on Public Trust Lands, Administered by Idaho Department of Lands

24. SIZE AND FLOW CAPACITY OF BRIDGE/CULVERT and DRAINAGE AREA SERVED: 69 Square Miles

25. IS PROJECT LOCATED IN A MAPPED FLOODWAY? NO YES If yes, contact the floodplain administrator in the local government jurisdiction in which the project is located. A Floodplain Development permit and a No-rise Certification may be required.

26a WATER QUALITY CERTIFICATION: Pursuant to the Clean Water Act, anyone who wishes to discharge dredge or fill material into the waters of the United States, either on private or public property, must obtain a Section 401 Water Quality Certification (WQC) from the appropriate water quality certifying government entity.
 See *Instruction Guide for further clarification and all contact information.*

The following information is requested by IDEQ and/or EPA concerning the proposed impacts to water quality and anti-degradation:
 NO YES Is applicant willing to assume that the affected waterbody is high quality?
 NO YES Does applicant have water quality data relevant to determining whether the affected waterbody is high quality or not?
 NO YES Is the applicant willing to collect the data needed to determine whether the affected waterbody is high quality or not?

26b. BEST MANAGEMENT PRACTICES (BMP's): List the Best Management Practices and describe these practices that you will use to minimize impacts on water quality and anti-degradation of water quality. All feasible alternatives should be considered - treatment or otherwise. Select an alternative which will minimize degrading water quality

1. Measures will be taken to minimize the potential for debris (e.g., dirt, concrete, etc.) to enter the area of wetlands not being impacted while removing and constructing structures.
2. A spill plan will be prepared by the construction contractor and approved by ITD D4 prior to project implementation.
3. An ITD approved SWPPP will be prepared for this project. The SWPPP will include measures to address sediment and erosion control with both temporary and permanent measures. All requirements of the Water Quality Certification issued by IDEQ will be followed.
4. All disturbed soils will be reseeded following construction.
5. On-site mitigation will consist of native plantings, and retention walls at Trail Creek restoration area.
6. Dewatering may be accomplished by draining, pumping, bailing, or cribbing. If needed, temporary sump holes may be installed within the footings and abutment areas to be dewatered to create a more suitable pumping area. The water removed during footing and abutment construction will be pumped to a temporary storage location where the water will be cleaned to standards specified by Idaho Department of Environmental Quality (IDEQ) to meet the current State of Idaho requirements. If appropriate, water from the dewatering activities may be pumped to a temporary storage/treatment site, or into upland areas and allowed to flow/filter through vegetation prior to reentering the stream channel. The water behind the barrier may be pumped directly back into the stream providing the pumped water meets applicable in stream turbidity criteria.
7. Turbidity monitoring will be conducted while working on or adjacent to Trail Creek

Through the 401 Certification process, water quality certification will stipulate minimum management practices needed to prevent degradation.


27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location.

Activity	Name of Water Body	Intermittent Perennial	Description of Impact and Dimensions	Impact Length Linear Feet
See attached narrative				
TOTAL STREAM IMPACTS (Linear Feet):				

28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.

Activity	Wetland Type: Emergent, Forested, Scrub/Shrub	Distance to Water Body (linear ft)	Description of Impact Purpose: road crossing, compound, culvert, etc.	Impact Length (acres, square ft linear ft)
See attached narrative				
TOTAL WETLAND IMPACTS (Square Feet):				

Attachment A. Vicinity Map



Attachment B.

- 19. TYPE and QUANTITY of MATERIAL(S) to be discharged below the ordinary high water mark and/or wetlands:
- 20. TYPE and QUANTITY of impacts to waters of the United States, including wetlands:
- 27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location.
- 28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.
- 29. ADJACENT PROPERTY OWNERS NOTIFICATION REQUIREM: Provide contact information of ALL adjacent property owners below.

BLOCK 19

TYPE and QUANTITY of MATERIALS to be discharged
below ordinary high water mark and/or wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Wetland G</i>							
-Sand and Topsoil for Pond			1100	0.5	26.2	2	1' Sand/6" Topsoil on Bottom; 6" Topsoil on Sides
-Backfill Wetland G	-	-	350.0	2	25.9	2	Backfill Remaining Area of Wetland G
<i>Fill Sub-Total</i>					<i>52.1</i>		
Gravel, Rock, or Stone							
<i>Wetland G</i>							
-Gravel Access Road			220	0.5	4.1	2	6" of 3/4" Aggregate for Access Road
-Riprap/Erosion Control	-	-	102	1.5	5.7	2	Stone Riprap for Outfall to Pond
<i>Fill Sub-Total</i>					<i>9.7</i>		
Concrete, Metal, & Plastic							
<i>Wetland G</i>							
-New 24" Pipe	70	1.5	-	-	3.9	2	
-New Outlet	-	-	5.0	4	0.7	2	
-New 12" Pipe	30	0.5	-	-	0.6	2	
<i>Fill Sub-Total</i>					<i>5.2</i>		
Dirt or Topsoil							
<i>Ditch 3</i>							
-Backfill Ditch 3	55	2	-	-	4.1	2	Backfill Ditch 3 Including Access Road
<i>Fill Sub-Total</i>					<i>4.1</i>		
Concrete, Metal, & Plastic							
<i>Ditch 3</i>							
-New Concrete Manhole (TY D)	-	-	8.6	4.5	1.4	2	
-New Sediment and Oil Trap	-	-	45	6.0	10.0	2	
<i>Fill Sub-Total</i>					<i>11.4</i>		
Dirt or Topsoil							
<i>Wetland F</i>							
-Backfill Wetland F	-	-	180	1.5	10.0	3	Backfill Wetland F During Roadway Slope Construction
<i>Fill Sub-Total</i>					<i>10.0</i>		
Concrete, Metal, & Plastic							
<i>Ditch 2</i>							
-New Concrete 18" Pipe with Steel Aprons	15	0.9	-	-	1.5	4	Install New Concrete 18" Pipe with Aprons
-New Concrete 18" Pipe with Steel Aprons	21	0.9	-	-	1.7	4	Install New Concrete 18" Pipe with Aprons
-New Concrete 18" Pipe with Steel Aprons	22	0.9	-	-	1.7	4	Install New Concrete 18" Pipe with Aprons
-New Concrete Structure	-	-	25	5.5	5.1	4	New 5'x5' Concrete Irrigation Box
<i>Fill Sub-Total</i>					<i>10.0</i>		
Concrete, Metal, & Plastic							
<i>Ditch 1</i>							
-New Concrete 24" Pipe	94	1.5	-	-	5.2	5	Install New Concrete 24" Pipe
-New Concrete Headwall	-	-	-	-	1.3	5	Install New Concrete 24" Headwall Rt.
-New Concrete Headwall	-	-	-	-	1.3	5	Install New Concrete 24" Headwall Lt.
<i>Fill Sub-Total</i>					<i>7.8</i>		

BLOCK 19

TYPE and QUANTITY of MATERIALS to be discharged
below ordinary high water mark and/or wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Trail Creek Bridge Replacement</i>							
Fill Soil Above Rip Rap	-	-	574.4	3	63.8	6	Soil above rip w/i OHW at Trail Creek Bridge
Fill Bench	80	3.2	-	-	9.5	6	Fill for south bench
<i>Fill Sub-Total</i>					<i>73.3</i>		
Gravel, Rock, or Stone							
<i>Trail Creek Bridge Replacement</i>							
Install Riprap	-	-	574.4	3	71.4	6	Rip rap installation w/i OHW at Trail Creek Bridge
Install Geotextile Fabric under Riprap	-	-	574.4	0	0.0	6	Geotextile fabric installation w/i OHW at Trail Creek Bridge
<i>Fill Sub-Total</i>					<i>71.4</i>		
Dirt or Topsoil							
<i>Wetland A</i>							
Wetland A Disturbed for Planting, Fill			51.2	0.5	0.9	6	Native plantings for riparian area restoration in wetland A, fill
Wetland A Temp Disturbed for Planting, Fill			22	0.5	0.4	6	Fill below OHW for Planting plan in wetland A
<i>Fill Sub-Total</i>					<i>0.9</i>		
Gravel, Rock, or Stone							
<i>Wetland A</i>							
Riprap installation in wetland			0.5	3	0.1	6	Rip rap installation w/i OHW at Trail Creek Bridge
Geotextile Fabric under Riprap in wetland			0.5	0	0.0	6	Geotextile fabric installation within Wetland, permanent
<i>Fill Sub-Total</i>					<i>0.1</i>		
Dirt or Topsoil							
<i>Trail Creek Slope Stabilization</i>							
Water Diversion (Sandbags), Temporary	125	9.0	-	-	41.7	7	Temporary water diversion
Earth Fill Above RipRap			716	0.5	13.3	7	Earth Fill Above RipRap
<i>Fill Sub-Total</i>					<i>13.3</i>		
Gravel, Rock, or Stone							
<i>Trail Creek Slope Stabilization</i>							
Installation for RipRap			716	4	106.1	7	Riprap installation in front of reinforced slope
Install Geotextile Fabric under Riprap			716	0	0.0	7	Geotextile fabric installation w/i OHW at Trail Creek Slope
<i>Fill Sub-Total</i>					<i>106.1</i>		
Total Project Fill					375.4		
Total Project Net Materials Discharged Below OHW/Wetlands					375.4		

BLOCK 20

TYPE and QUANTITY of impacts to waters of the United States, including wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Wetland G</i>							
-Excavate for New Riprap, Perm	-	-	102.0	1.5	-5.7	2	
-Excavate for New 24" Pipe, Temp	70	3.2	-	-	-8.3	2	Temporary excavation for pipe installation
-Excavate for New 24" Pipe, Perm	70	1.5	-	-	-3.9	2	Permanent excavation for pipe installation
-Excavate for New Outlet, Temp	-	-	45	4	-6.7	2	Temporary excavation for outlet installation
-Excavate for New Outlet, Perm	-	-	5	4	-0.7	2	Permanent excavation for outlet installation
-Excavate for New 12" Pipe, Temp	30	0.8	-	-	-0.9	2	Temporary excavation for pipe installation
-Excavate for New 12" Pipe, Perm	30	0.5	-	-	-0.6	2	Permanent excavation for pipe installation
-Excavate for Pond Expansion, Perm	-	-	1100	7	-285.2	2	
-Excavate for Access Road, Perm	-	-	300	2	-22.2	2	Permanent excavation for access road
Permanent Excavation Sub-Total					-318.3		
<i>Ditch 3</i>							
-Excavate for New Manhole, Temp	-	-	20	5	-3.7	2	Temporary excavation for manhole installation
-Excavate for New Manhole, Perm	-	-	8.6	4.5	-1.4	2	Permanent excavation for manhole installation
-Excavate for New Sed and Oil Trap, Temp	-	-	81	7	-21.0	2	Temporary excavation for sed trap installation
-Excavate for New Sed and Oil Trap, Perm	-	-	45	6	-10.0	2	Permanent excavation for sed trap installation
Permanent Excavation Sub-Total					-11.4		
Dirt or Topsoil							
<i>Wetland F</i>							
-Excavate Wetland F			180	1.5	-10.0	3	Excavate Wetland F During Roadway Slope Construction
Permanent Excavation Sub-Total					-10.0		
Dirt or Topsoil							
<i>Ditch 2</i>							
-Excavate for new Concrete Structure, Temp	-	-	77	6	-17.1	4	Temporary Excavation for New 5'x5' Irrigation Box
-Excavate for new Concrete Structure, Perm	-	-	25	5.5	-5.1	4	Permanent excavation for New 5'x5' Irrigation Box
Permanent Excavation Sub-Total					-5.1		
Concrete, Metal, & Plastic							
<i>Ditch 2</i>							
-Remove Ex. CMP 18" Pipe	10	0.9	-	-	-0.3	4	Remove Existing CMP 18" Pipe
-Remove Ex. CMP 18" Pipe	21	0.9	-	-	-0.7	4	Remove Existing CMP 18" Pipe
-Remove Ex. CMP 18" Pipe	20	0.9	-	-	-0.7	4	Remove Existing CMP 18" Pipe
Permanent Excavation Sub-Total					-1.7		
Dirt or Topsoil							
<i>Ditch 1</i>							
-Excavate for Concrete Headwall, Temp	-	-	40.0	3.5	-5.2	5	Temporary excavation for 24" Concrete Headwall Rt.
-Excavate for Concrete Headwall, Perm	-	-	-	-	-1.3	5	Permanent excavation for 24" Concrete Headwall Rt.
-Excavate for Concrete Headwall, Temp	-	-	40.0	3.5	-5.2	5	Temporary excavation for 24" Concrete Headwall Lt.
-Excavate for Concrete Headwall, Perm	-	-	-	-	-1.3	5	Permanent excavation for 24" Concrete Headwall Lt.
-Regrade Ditch 1	-	-	15	2	-1.1	5	Temporay Excavation - Regrade Ditch 1 after Headwall Installation
Permanent Excavation Sub-Total					-2.6		
Concrete, Metal, & Plastic							
<i>Ditch 1</i>							
-Remove 24" CMP	94	1.5	-	-	-5.2	5	Remove Existing 24" Pipe
Permanent Excavation Sub-Total					-5.2		
Dirt or Topsoil							
<i>Wetland D</i>							
-Regrade Ditch 1	-	-	20	2	-1.5	5	Temporary Excavation - Regrade Ditch 1 after Headwall Install
Permanent Excavation Sub-Total					0.0		
Dirt or Topsoil							
<i>Trail Creek Bridge Replacement</i>							
Excavate to Remove Bridge & Install Riprap			574.4	6	-127.6	6	Excavation for bridge removal and riprap installation w/i OHW
Excavate Channel to Install Riprap, Temporary			1428.0	5.1	-269.7	6	Temporary excavation for rip rap installation w/i OHW, fill back
Permanent Excavation Sub-Total					-127.6		
<i>Wetland A</i>							
Wetland A Disturbed for Planting, Excavation			51.2	0.5	-0.9	6	Native plantings for riparian area restoration in wetland A, excavation
Permanent Excavation Sub-Total					-0.9		
Dirt or Topsoil							
<i>Trail Creek Slope Stabilization</i>							
Excavation for Riprap installation			716	4.5	-119.4	7	Riprap excavation in front of reinforced slope
Excavation for Riprap, Temporary			883	2	-65.4	7	Temporary excavation for rip rap installation
Permanent Excavation Sub-Total					-119.4		
Total Project Excavation					-602.3		
Total Quantity of Excavation in WOTUS					-602.3		

Block 20

TYPE and QUANTITY of impacts to
waters of the United States, including wetlands

Fig. #	Backfill and Bedding	Area (AC)	Impact Area (SF)	Volume (CY)	
2	Wetland G	0.0391	1,705	67.0	Pond Expansion, Access Road and Storm Drain
2	Ditch 3	0.0037	160	15.5	Pond Expansion, Access Road and Storm Drain
3	Wetland F	0.0041	180	10.0	Roadway and Slope Construction
4	Ditch 2	0.0014	60	10.0	Install new concrete box and Replace 3 Irrigation culverts
5	Ditch 1	0.0010	45	7.8	Replace Irrigation Crossing and Add Headwalls
6	Trail Creek Bridge Replacement	0.0132	574	144.7	Install Riprap & Bench for Bridge Abutments
6	Bridge - Geotextile	0.0132	574	0.0	Install Geotextile under Riprap at Bridge Abutments
6	Wetland A	0.0005	23	1.0	Install Riprap For Bridge Abutments/Native Plantings Area
6	Wetland A - Geotextile	0.0000	1	0.0	Install Geotextile under Riprap at Bridge Abutments
7	Trail Creek Slope Stabilization	0.0164	716	119.3	Riprap installation in front of Reinforced Slope
7	Trail Creek Slope - Geotextile	0.0164	716	0.0	Riprap installation in front of Reinforced Slope
<i>Bedding and Backfill Sub-Total</i>				375.4	

Fig. #	Excavation	Area (AC)	Impact Area (SF)	Volume (CY)	
					Pond Expansion, Access Road and Storm Drain
2	Wetland G	0.0391	1,705	-318.3	Pond Expansion, Access Road and Storm Drain
2	Ditch 3	0.0037	160	-11.4	Pond Expansion, Access Road and Storm Drain
3	Wetland F	0.0041	180	-10.0	Roadway and Slope Construction
4	Ditch 2	0.0014	60	-6.8	Install new concrete box and Replace 3 Irrigation culverts
5	Ditch 1	0.0010	45	-7.8	Replace Irrigation Crossing and Add Headwalls
5	Wetland D	0.0005	20	0.0	Replace Irrigation Crossing and Add Headwalls-Temporary impact only
6	Trail Creek Bridge Replacement	0.0132	574	-127.6	Excavate for Bridge Removal and Riprap Installation
6	Wetland A	0.0012	51	-0.9	Native plantings for riparian area restoration in wetland A
7	Trail Creek Slope Stabilization	0.0164	716	-119.4	Excavate for riprap in front of Reinforced Slope
<i>Excavation Sub-Total</i>				-602.3	
<i>Project Net Materials Total</i>				-226.9	

27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location

Table 1: Waterbody Impacts

Resource	Figure	Activity	Cowardin	Intermittent/ Perennial	Description of Impact	Permanent Impacts (SF)	Permanent Impacts (Acres)	Impact Length (LF)
Ditch 1	5	Pipe/headwalls installation	R4EM	Intermittent	Replace Irrigation Crossing and Add Headwalls	45	0.0010	22
Ditch 2	4	Pipe/Box installation	R4EM	Intermittent	Install new concrete box and Replace 3 Irrigation culverts	60	0.0014	30
Ditch 3	2	Pond Expansion & Storm Drain	R4EM	Intermittent	Pond Expansion, Access Road and Storm Drain	160	0.0037	80
Trail Creek*	6	Riprap installation	R2UB	Perennial	Bench for bridge abutments	574	0.0132	82
Trail Creek	7	Slope Stabilization (vegetated wall)	R2UB	Perennial	Riprap installation for Reinforced Slope	716	0.0164	98
Total						1,555	0.0358	312
*175 SF increase in hydraulic opening (full opening of old culvert to full opening of new bridge)								

28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.

Table 2: Wetland Impacts

Resource	Figure	Activity	Cowardin	Distance to waterbody (lin. feet)	Description of Impact	Total Impact (Sq Ft)	Total Impact (Acres)
Wetland A	6	Riprap installation	PFO	0	Install Riprap for bridge abutments, native riparian planting area	51	0.0012
Wetland D	5	Pipe/headwalls installation	PEM	0	Replace Irrigation Crossing and add headwalls	20	0.0005
Wetland F	3	Roadway Construction	PEM	120	Roadway and Slope Construction	180	0.0041
Wetland G	2	Pond Expansion & Storm Drain	PSS	0	Pond Expansion, Access Road and Storm Drain	1,705	0.0391
Total						1,956	0.0449


29. ADJACENT PROPERTY OWNERS NOTIFICATION: Provide contact information of ALL adjacent property owners

Table 3. Adjacent Property Owners

Assessor's Parcel No.	Adjacent Impacted Resources	Contact Name	Phone	Email	Mailing Address
RPK05030000010	Wetland F	Joseph Reali	Not Provided	Joe.reali@gmail.com	100 Neils Way, PO Box 88, Hauley, ID 83333
RPS05200050000	Wetland G Ditch 3	Weyyakin Ranch Property Owner Association	208-726-3858	scm@suncountrysv.com	PO Box 728 Ketchum, ID 83340
RPK4N180190790 RPK4N180190780	Ditch 2	Idaho Park Foundation Inc Kendra Kenyon	208-860-0311	office@idaholands.org	5657 WARM SPRINGS AVE BOISE, ID 83716
RPK4N180190820	Ditch 2 Ditch 1 Wetland D	Douglas Bradshaw Trustee	775-782-1959	DJBradshaw1@live.com	PO Box 7180 Gardnerville, NV 89460
RPK4N17024662M	Ditch 1 Wetland D	Sun Valley Resorts Tim Silva	208-622-2042	tsilva@sunvalley.com	PO BOX 10 SUN VALLEY, ID 83353
RPK07070030000	Trail Creek	Andora Villa Condos Will Schuckert	602-524-1797	will@edgescottsdale.com	15100 N 78 th Way #207 Scottsdale, AZ 85250
RPK0000082003A	Trail Creek Wetland A	PEG Ketchum Hotel LLC	801-655-1998	Not Provided	145 W 200 N Ste 100 Provo, UT 84601
RPK0000082022A	Trail Creek	Jeffrey Barber	206-795-9321	Jeffbarber7@gmail.com	PO Box 2174 Sun Valley, ID 83353
RPK07770000000	Trail Creek	Habitat 2000 Condo Owners Tamara Code	208-726-8584	mgr.habitatontrailcreek@gmail.com	219 S 1 st Ave St 101 Hailey, ID 83333
RPK09590000000	Trail Creek	Trail Creek LLC John Sahlberg	Not Provided	johntsahlberg@gmail.com	PO Box 2251 Ketchum, ID 83340



Assessor's Parcel No.	Adjacent Impacted Resources	Contact Name	Phone	Email	Mailing Address
RPK00000830020	Trail Creek	Harriman Ketchum Hotel LLC Jack Bariteau	Not Provided	jack@waypointsunvalley.com	PO Box 84 Sun Valley, ID 83353

Attachment C. Plan Sheets with Impacts




**SH 75, ELKHORN RD
TO RIVER ST, KETCHUM
KEY NO. 20033**



SH-75, ELKHORN RD TO
RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050



- LEGEND**
- Existing Pipe
 - F/L --- Existing Ditch
 -)SS --- Existing Storm Sewer
 -)SS --- Proposed Storm Sewer
 -)IRR --- Proposed Irrigation Pipe
 - Wetland Boundary
 - R/W --- Existing Right-of-Way
 - P/L --- Property Line
 - **R/W** --- Acquired ITD Right-of-Way




SH-75, ELKHORN RD TO RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: DITCH 3 & WETLAND G
 Proposed Activity: Pond Expansion & Storm Drain
 Lat.: 43.667° N Long.: 114.356° W



- LEGEND**
- Existing Pipe
 - F/L — Existing Ditch
 -)SS — Existing Storm Sewer
 -)SS — Proposed Storm Sewer
 -)IRR — Proposed Irrigation Pipe
 - Wetland Boundary
 - R/W — Existing Right-of-Way
 - P/L — Property Line
 - **R/W** — Acquired ITD Right-of-Way

Wetland F
 180 SF, +10.0 CY
 Excavate -10.0 CY

WETLAND F
 Permanent
 Impact Area: 180 SF
 (0.0041 AC)
 Filled with 10.0 CY of
 Backfill and Bedding




SECTION A-A

WETLAND F

FIGURE 3

MAY 13
 2024

SH-75, ELKHORN RD TO
 RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: WETLAND F
 Proposed Activity: Roadway Construction
 Lat.: 43.667° N Long.: 114.356° W
 Sheet 3 of 7



DITCH 2 TOTALS


Temporary
Impact Length: 92 LF
Impact Area: 184 SF

Permanent
Impact Length: 30 LF
Impact Area: 60 SF
(0.0014 AC)
Filled with 10.0 CY of
Backfill and Bedding


SCALE: 1"=50'

LEGEND


- Existing Pipe
- F/L — Existing Ditch
-)SS — Existing Storm Sewer
-)ss — Proposed Storm Sewer
-)IRR — Proposed Irrigation Pipe
- ▬▬▬▬ Wetland Boundary
- R/W — Existing Right-of-Way
- P/L — Property Line
- R/W — Acquired ITD Right-of-Way



SH-75, ELKHORN RD TO RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: DITCH 2
 Proposed Activity: Pipe/Box Installation
 Lat.: 43.667° N Long.: 114.356° W



SCALE: 1"=50'



LEGEND

- Existing Pipe
- F/L - Existing Ditch
-)SS - Existing Storm Sewer
-)SS - Proposed Storm Sewer
-)IRR - Proposed Irrigation Pipe
- Wetland Boundary
- R/W - Existing Right-of-Way
- P/L - Property Line
- R/W - Acquired ITD Right-of-Way



DITCH 1 TOTALS

Permanent
 Impact Length: 22 LF
 Impact Area: 45 SF
 (0.0010 AC)
 Filled with 7.8 CY of
 Backfill and Bedding

WETLAND D TOTALS

Temporary
 Impact Area: 20 SF
 (0.0005 AC)


SH-75, ELKHORN RD TO
 RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: DITCH 1 & WETLAND D
 Proposed Activity: Pipe/Headwalls Installation
 Lat.: 43.667° N Long.: 114.356° W



WETLAND A
 PERMANENT IMPACT = 51 SF
 EXCAVATION = 0.9 CY
 FILL W/ PLANTING = 0.9 CY
 ROCK FILL = 0.1 CY
 GEOTEXTILE IMPACT = 0.5 SF
 TEMPORARY IMPACT = 22 SF
 TEMPORARY EXCAVATION = 0.4 CY
 TEMPORARY FILL = 0.4 CY

IMPACTS FOR BRIDGE REMOVAL AND
 RIPRAP INSTALLATION
 PERMANENT IMPACT AREA = 574 SF
 GEOTEXTILE IMPACT AREA = 574 SF
 EXCAVATION = 127.6 CY
 ROCK FILL = 73.4 CY
 TEMPORARY IMPACT AREA = 1428 SF
 TEMPORARY EXCAVATION = 269.7 CY
 TEMPORARY EARTH FILL = 269.7 CY

PLAN
 1"=30'-0"



ELEVATION
 1"=30'-0"

LEGEND

- ORDINARY HIGH WATER (OHW) BOUNDARY
- DELINEATED WETLAND BOUNDARY
- EXISTING RIGHT-OF-WAY
- ACQUIRED RIGHT-OF-WAY
- PERMANENT IMPACTS BELOW OHW (574 S.F., 0.013 ACRE)
- TEMPORARY IMPACTS BELOW OHW (1428 S.F., 0.033 ACRE)
- PERMANENT IMPACTS TO WETLANDS (51 S.F., 0.001 ACRE)
- TEMPORARY IMPACTS TO WETLANDS (22 S.F., 0.001 ACRE)

EXISTING
 HYDRAULIC OPENING = 158 S.F., 0.003 ACRE

PROPOSED
 HYDRAULIC OPENING = 333 S.F., 0.008 ACRE

HYDRAULIC
 OPENING CHANGE = INCREASE 175 S.F., 0.004 ACRE

SH-75, ELKHORN RD TO
 RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(003) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: Trail Creek
 Proposed Activity: Bridge Replacement
 Lat.: 43.667° N Long.: 114.356° W

Memo

Date: Friday, March 29, 2024

Project: ITD SH-75 Bridge & Stabilization Slope on Trail Creek

To: Adam Crutcher – City of Ketchum Floodplain Administrator

From: Idaho Transportation Department District 4
Mike Schubert, PE – HDR
Spencer Savage, PE – HDR
Kyler Ashby, EIT - HDR

Subject: **Floodplain Development Permit / No-Rise Analysis**

1 Background

In 2020, HDR submitted a floodplain development permit application and hydraulic report regarding the SH-75 Trail Creek bridge. This application was reviewed by the City of Ketchum. The City provided a formal statement of concurrence on February 8, 2021, but indicated that the package would need to be resubmitted prior to the start of the project. Construction is scheduled to take place from 2025 – 2026. This package is ITD’s formal request for the floodplain development permit.

During final design, the roadway design team recognized that the roadway realignment requires bank stabilization upstream of the bridge where SH-75 would be widened. This bank stabilization has been discussed and reviewed by the City. This document also serves as an addendum to the previously submitted floodplain development permit, including the bank stabilization.

2 Project Description

State Highway 75 (SH-75) is the primary north-south highway in the Wood River Valley serving the cities of Bellevue, Hailey, Ketchum, and Sun Valley in Blaine County. The proposed SH-75 Elkhorn to River Street project is the third and northernmost roadway construction project to be developed from the *Timmerman to Ketchum Environmental Impact Statement Record of Decision* issued in August of 2008 (ITD 2008). The purpose of the project is to improve safety and capacity on SH-75 between Elkhorn Road, north of the Big Wood River Bridge, and River Street in the city of Ketchum. The approximate project milepost limits are from 126.5 to 128.2 on SH-75.

The proposed project includes replacing the existing SH-75 bridge over Trail Creek and stabilizing a portion of the right bank upstream of the bridge to accommodate widening of SH-75. These locations are shown in Figure 1 for reference.




Figure 1: Project area for Trail Creek bridge and bank stabilization

Since the project is located in Zone AE Special Flood Hazard Area (SFHA), a floodplain development permit is required along with a no-rise analysis. The following sections describe the no-rise analysis, summarizes floodplain requirements, and provides discussion on how the project will address the floodplain requirements.

3 Hydraulic/No-Rise Analysis

The existing structure is a 20-foot clear span stiffleg box culvert. The proposed bridge replaces this structure with a 54-foot clear-span bridge. As is expected when making a significant increase in the span at a stream crossing, there is a significant hydraulic improvement upstream of the structure. This improvement is summarized in Table 1.




Figure 2: Existing box culvert bridge design compared to proposed clear-span bridge

Table 1: Summary of hydraulic improvement

Structure	Dimensions (Clear Span) (ft)	Channel Invert at Inlet (ft)	Low Chord Elevation (ft)	Headwater Elevation at Q50 of 900 cfs (ft)	Clearance at Q50 of 900 cfs (ft)	Headwater Elevation at Q100 of 1,020 cfs (ft)	Clearance at Q100 of 1,020 cfs (ft)
Existing	20	5795.03	5804.31	5802.14	2.17	5802.64	1.67
Proposed	54	5795.03	5804.91	5801.63	3.28	5801.95	2.96

During the development of this project, a concern was raised about the stabilization of the existing Trail Creek bank near the east side of SH-75, between the Trail Creek bridge and River Street. There is concern that removing the mature trees and vegetation to widen SH-75 could cause the bank to be unstable. To mitigate this concern, the bank will be stabilized. This includes designing scour protection and the use of a wrapped face geosynthetic slope.




Figure 3: Standard detail for wrapped face geosynthetic slope

The existing and proposed bank conditions were simulated using a hydraulic model. The results conclude that the proposed design of the bridge and bank will result in a no-rise. The hydraulic results are summarized in Table 2.

Table 2: Comparison of existing and proposed water surface elevations

River Station	Existing 100-yr WSE (ft)	Proposed 100-yr WSE (ft)	Existing 100-yr Floodway WSE (ft)	Proposed 100-yr Floodway WSE (ft)	Notes
2075	5800.47	5800.40	5800.50	5800.48	Downstream Trail Creek bridge
2147	5802.64	5801.95	5802.64	5801.90	Upstream Trail Creek bridge
2205	5802.91	5802.14	5802.91	5802.13	
2247	5803.39	5802.99	5803.30	5802.89	
2300	5803.51	5803.19	5803.50	5803.16	
2389	5803.73	5803.54	5803.71	5803.51	
2415	5804.26	5804.15	5804.25	5804.14	Proposed bank edits
2432	5804.25	5804.10	5804.25	5804.09	Proposed bank edits
2439	5804.45	5804.38	5804.44	5804.37	Proposed bank edits
2462	5805.53	5805.49	5805.53	5805.49	Proposed bank edits
2490	5805.59	5805.56	5805.59	5805.55	Proposed bank edits
2531	5805.77	5805.75	5805.78	5805.75	



Figure 4: Location of cross sections along Trail Creek

4 Floodplain Permit Requirements

The SH-75 Trail Creek Project is in a mapped flood hazard area (Panel 16013C0461E, November 26, 2010) and crosses the floodway. Since the project is within a floodplain and a floodway, a floodplain development permit is required from the floodplain administrator for consistency with the community's floodplain ordinance requirements. Issuance of the permit will require a no-rise certificate. The City of Ketchum's floodplain administrator must confirm the project meets floodplain ordinance requirements:

Prohibit encroachments, including fill, new construction, substantial improvements, and other development unless certification with supporting calculation, by a registered professional hydraulic engineer is provided demonstrating that encroachments shall not result in any increase in flood level during the occurrence of the base flood discharge. Uses in the floodway shall be restricted to that which are required by public necessity (for example, bridges, water pumps), recreational use (for example, paths), wildlife habitat improvements (for example, vegetation, nesting structures, pool/riffle improvements), and gravel extractions; provided that the use/encroachment meets the approval of the Federal Emergency Management and Nation Flood Insurance Program and does not jeopardize the city's participation in the National Flood Insurance Program. (Ordinance 1120 §17.88.070 C.1).

HDR requested the effective regulatory model from FEMA, but FEMA was unable to produce model input files. Therefore, based on coordination with the City of Ketchum, HDR completed floodplain and floodway analyses using an alternative model which considers the floodway as delineated in the communities' FIRM, and the existing channel geometry, as surveyed for this project. The hydraulic analysis completed for this project is described in detail in the attached hydraulic report.

4.1 Floodplain Management Overlay Evaluation Standards

The City of Ketchum lists several criteria as requirements for issuing a Floodplain Development Permit. This section of the memo attempts to address each of the applicable standards.

- 1. The proposal preserves or restores the inherent natural characteristics of the river, floodplain, and Riparian Zone, including riparian vegetation and wildlife habitat. Development does not alter river channel unless all stream alteration criteria for evaluation are also met.**

The project removes the most substantial man-made constriction in Trail Creek. Project will remove existing vegetation within the bank stabilization area. However, the proposed design consists of restoring the vegetation and mitigating future stream channel migration by installing a wrapped face geosynthetic slope and inserting willow plantings and installing toe scour countermeasures. A planting plan was also prepared near the bridge to show how the area will be revegetated and to serve as mitigation for loss of wetlands. An additional planting plan will be prepared along the new wall.

- 2. No temporary construction activities, encroachment, or other disturbance into the twenty-five foot (25') Riparian Zone, including encroachment of below grade structures, shall be permitted, except for approved stream stabilization work and restoration work associated with a riparian zone that is degraded.**

Removing the culvert, which constricts the channel and disconnects the upstream and downstream riparian areas, as well as adjusting the bank slope and armoring the bank toe may disturb adjacent riparian areas. Measures will be taken to reduce the amount of disturbance to these areas. Disturbed areas will be restored in accordance with ITD specifications and the City of Ketchum's requirements.

While there will be work done within the Riparian Zone, the proposed work should improve the conditions within the riparian area and prevent further degradation.

- 3. No permanent development shall occur within the twenty-five foot (25') Riparian Zone, except for approved stream stabilization work and restoration work associated with permit issued under this title, or exceptions as described below:**
 - a. Access to a property where no other primary access is available.**
 - b. Emergency access required by the Fire Department.**
 - c. A single defined pathways or staircases for the purpose of providing access to the river channel and in order to mitigate multiple undefined social paths.**
 - d. Development by the City of Ketchum**

This restriction should not apply to the SH-75 Trail Creek project, as the roadway for the bridge is critical for emergency access.

- 4. New or replacement planting and vegetation in the Riparian Zone shall include plantings that are low growing and have dense root systems for the purpose of stabilizing stream banks and repairing damage previously done to riparian vegetation. Examples of such plantings most commonly include red osier dogwood, common chokecherry, serviceberry, elderberry, river birch, skunk bush sumac, Beb's willow, Drummond's willow, little wild rose, gooseberry, and honeysuckle. However, in rare instances the distance from the top-of-bank to the mean high-water mark is significant and the native vegetation appropriate for the Riparian Zone are low growing, drought resistant grasses and shrubs. Replacement planting and vegetation shall be appropriate for the specific site conditions. Proposal does not include vegetation within the twenty-five foot (25') Riparian Zone that is degraded, not natural, or which does not promote bank stability.**

The seeding for the bank stabilization phase of the project is being developed in accordance with ITD specifications and the City of Ketchum's requirements. The seed mix has been coordinated with Idaho Fish and Game. The planting plan near the bridge has black cottonwood, coyote willow, quaking aspen, serviceberry and woods rose. Willow plantings will be included in the toe stabilization.

5. **Landscaping and driveway plans to accommodate the function of the floodplain allow for sheet flooding. Surface drainage is controlled and shall not adversely impact adjacent properties including driveways drained away from paved roadways. Culvert(s) under driveways may be required. Landscaping berms shall be designed to not dam or otherwise obstruct floodwaters or divert same onto roads or other public pathways.**

Roadway drainage design will control surface drainage, in accordance with ITD specifications and the City of Ketchum's requirements.

6. **Floodwater carrying capacity is not diminished by the proposal.**

The proposed project will improve flood flow conveyance.

7. **Impacts of the development on aquatic life, recreation, or water quality upstream, downstream or across the stream are not negative.**

This project provides a clear span and wildlife access reconnection. This project will result in a net benefit to aquatic life and recreation and will not adversely affect water quality. Best management practices during construction will be implemented to mitigate water quality impacts.

8. **Building setback in excess of the minimum required along waterways is encouraged. An additional ten-foot (10') building setback beyond the required twenty-five foot (25') Riparian Zone is encouraged to provide for yards, decks and patios outside the twenty five foot (25') Riparian Zone.**

This requirement does not apply to this project.

9. **The top of the lowest floor of a building located in, or partially within, the SFHA shall be at or above the Flood Protection Elevation (FPE). A building is considered to be partially within the SFHA if any portion of the building or appendage of the building, such as footings, attached decks, posts for upper story decks, are located within the SFHA. See section 17.88.060, figures 1 and 2 of this chapter to reference construction details. See Chapter 17.08 of this title for definition of "lowest floor."**
 - a. **In the SFHA where Base Flood Elevations (BFEs) have been determined, the FPE shall be twenty-four inches (24") above the BFE for the subject property; twenty-four inches (24") or two (2) feet is the required freeboard in Ketchum city limits.**
 - b. **In the SFHA where no BFE has been established, the FPE shall be at least two (2) feet above the highest adjacent grade.**

This requirement does not apply to this project.

- 10. The backfill used around the foundation in the SFHA floodplain shall provide a reasonable transition to existing grade but shall not be used to fill the parcel to any greater extent.**
 - a. Compensatory storage shall be required for any fill placed within the floodplain.**
 - b. A CLOMR-F shall be obtained prior to placement of any additional fill in the floodplain.**

While fill material is being placed into the floodplain, the proposed design will ensure a no-rise scenario is met and restores the bank to its pre-project condition.

- 11. All new buildings located partially or wholly within the SFHA shall be constructed on foundations that are designed by a licensed professional engineer.**

This requirement does not apply to this project.

- 12. Driveways shall comply with City of Ketchum street standards; access for emergency vehicles has been adequately provided for by limiting flood depths in all roadways to one foot (1-ft) or less during the 1% annual chance event.**

This requirement does not apply to this project.

- 13. Landscaping or revegetation shall conceal cuts and fills required for driveways and other elements of the development.**

This requirement does not apply to this project.

- 14. (Stream alteration.) The proposal is shown to be a permanent solution and creates a stable situation.**

The project will stabilize the banks and maintain flood carrying capacity for the river.

- 15. (Stream alteration.) No increase to the one percent (1%) annual chance flood elevation at any location in the community, based on hydrologic and hydraulic analysis performed in accordance with standard engineering practice and has been certified and submitted with supporting calculations and a No Rise Certificate, by a registered Idaho engineer.**

A no-rise certificate is attached.

- 16. (Stream alteration.) The project has demonstrated No Adverse Impact or has demonstrated all impacts will be mitigated.**

This project will maintain flow conditions and improve bank stabilization. It is anticipated that there will be no adverse impacts as a result of this project.

- 17. (Stream alteration.) The recreational use of the stream including access along any and all public pedestrian/fisher's easements and the aesthetic beauty shall not be obstructed or interfered with by the proposed work.**

There are no recreational amenities around the proposed project site. The project will reconnect riparian areas upstream and downstream of the structure. The aesthetic beauty will be maintained by constructing a slope with vegetation.

18. (Stream alteration.) Fish habitat shall be maintained or improved as a result of the work proposed.

Fish habitat will not be impacted as a result of the construction done for the project.

19. (Stream alteration.) The proposed work shall not be in conflict with the local public interest, including, but not limited to, property values, fish and wildlife habitat, aquatic life, recreation and access to public lands and waters, aesthetic beauty of the stream and water quality.

There are no known conflicts with this project and the public interest.

20. (Stream alteration.) The work proposed is for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation.

The Trail Creek bridge is critical for emergency access for the community and bank stabilization is necessary to mitigate future channel migration and scour.

21. (Wetlands) Where development is proposed that impacts any wetland the first priority shall be to move development from the wetland area. Mitigation strategies shall be proposed at time of application that replace the impacted wetland area with an equal amount and quality of new wetland area or riparian habitat improvement.

Wetland A on the east side of the bridge is partially within the permanent easement and is assumed to be permanently impacted (0.002 acres). The permanent wetland loss will be mitigated under the FHWA Executive Order (EO) 11990 as described in the wetland mitigation plan included with the attached 404 permit.

5 Scour Analysis

HDR performed a bend scour analysis to determine the scour depth that would occur at the project location. Using equations from the U.S. Army Corps of Engineers (USACE) HEC-RAS User manual, HDR concluded the estimated scour depth to be approximately 3 feet.

$$\Delta y := D_{US} \cdot \left(-1.62 \log \left(\frac{R_c}{W} \right) + 3.375 \right) - D_{Max} = 2.94 \text{ ft}$$

Where:

D_{US} = average cross section depth at upstream, reference cross section, 3.89 ft


R_c = radius of curvature, 137 ft

W = flow width (within the banks), 30.87 ft

D_{Max} = maximum cross section depth before scour at evaluation cross section, 6.11 ft



6 Conclusions

The project involves replacing the SH-75 bridge over Trail Creek and stabilizing the bank of Trail Creek upstream where SH-75 will be widened. HDR's analysis concludes that the proposed design to ensure bank stability will result in a no-rise. The hydraulic analysis also includes that bend scour of approximately 3 feet can be anticipated at the bank stabilization area. An appropriate scour design will be implemented to prevent erosion and destabilization of the bank.



- NOTES**
- SEE DESIGN AND GENERAL NOTES SHEET FOR RETAINING WALL GENERAL NOTES.
 - SEE SLOPE 4 SECTION DETAIL SHEET FOR TYPICAL SECTION AND EMBEDMENT REQUIREMENTS.
 - SLOPE 4 IS A WRAPPED-FACE GEOSYNTHETIC REINFORCED SLOPE.
 - *4. DEPTH OF EXISTING RETAINING WALL AND EXISTING PEDESTRIAN BRIDGE ABUTMENT IS UNKNOWN. PRIOR TO EXCAVATING, VERIFY EXISTING CONDITIONS AND PROVIDE TEMPORARY SHORING AS REQUIRED.

HORIZONTAL ALIGNMENT CURVE DATA
 Q SH-75
 CURVE 6A
 PI=477+11.2721
 Δ=43°41'58" LT.
 T=208.85'
 L=397.26'
 R=520.86'
 S=2%



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED
K. VASQUEZ

DESIGN CHECKED
P. ESCHBACHER

DETAILED
J. CULIAN

DRAWING CHECKED
P. ESCHBACHER

SCALES SHOWN
ARE FOR 11" X 17"
PRINTS ONLY

CADD FILE NAME
20033brRW_001-3C.dgn

DRAWING DATE:
MAY 2024

IDAHO TRANSPORTATION DEPARTMENT

YOUR Safety → YOUR Mobility → YOUR Economic Opportunity

HR

PROJECT NO.
A020(033)

SITUATION AND LAYOUT - SLOPE 4
SH-75, ELKHORN RD
TO RIVER ST, KETCHUM

ENGLISH

COUNTY
BLAINE


KEY NUMBER
20033

SHEET 204 OF 364

NOT APPROVED
DATE ORIGINAL SIGNED
PRELIMINARY
CONSTRUCTION

NOTES

- *1. ITEM TO BE DESIGNED BY THE REINFORCED SLOPE MANUFACTURER.
2. PROVIDE WRAPPED-FACE GEOSYNTHETIC REINFORCED SLOPE IN ACCORDANCE WITH S501-35A.
3. BOTTOM OF SLOPE LAYOUT AND ELEVATIONS ARE SHOWN FOR ESTIMATING PURPOSES AND MAY BE ADJUSTED AS REQUIRED BY THE REINFORCED SLOPE MANUFACTURER AND APPROVED BY THE ENGINEER AT NO ADDITIONAL COST TO THE STATE.
4. PRIMARY REINFORCEMENT LENGTH, L, MUST BE A MINIMUM 70 PERCENT OF THE HEIGHT, H, MEASURED FROM THE BOTTOM OF REINFORCED SLOPE TO TOP OF SLOPE REFERENCE LINE AND NOT LESS THAN 10'-0". ACTUAL PRIMARY REINFORCEMENT LENGTH MUST BE DETERMINED BY THE REINFORCED SLOPE MANUFACTURER.
5. GRANULAR SUBBASE (301-010A), COMPACTING BACKFILL (210-015A), AND EXCAVATION ARE INCIDENTAL TO BID ITEM S501-35A.
6. FOR 3-TUBE CURB MOUNT RAIL DETAILS, SEE 3-TUBE CURB MOUNT RAIL DETAILS SHEETS.
7. FOR MOMENT SLAB, SEE WALL 2 MOMENT SLAB DETAILS SHEET.



SLOPE 4 TYPICAL SECTION
(LOOKING UPSTATION)
1/4" = 1'-0"

REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED
K. VASQUEZ
DESIGN CHECKED
P. ESCHBACHER
DETAILED
J. CULIAN
DRAWING CHECKED
P. ESCHBACHER

SCALES SHOWN
ARE FOR 11" X 17"
PRINTS ONLY
CADD FILE NAME
20033brRW_002-3C.DGN.dgn
DRAWING DATE:
MAY 2024

IDAHO
TRANSPORTATION
DEPARTMENT

YOUR Safety→YOUR Mobility→YOUR Economic Opportunity



HR

PROJECT NO.

A020(033)

SLOPE 4 SECTION DETAIL

SH-75, ELKHORN RD
TO RIVER ST, KETCHUM

ENGLISH
COUNTY
BLAINE
KEY NUMBER
20033
SHEET 205 OF 364

NOT APPROVED
DATE ORIGINAL
PRELIMINARY
SIGNED FOR CONSTRUCTION

U:\Bois\Projects\Clients\4006-ITD\314-4006-071\SH-75 Elkhorn to River\955vcs\CADD\DCN\sheets\20033_land_001.dgn
 2/14/2022 4:04:36 PM




Table 1: Native Planting

Scientific Name	Common Name	Type	Percent by cover	Appx. Spacing (ft)
Planting Area 1-Shoreline				
<i>Populus trichocarpa</i>	Black Cottonwood	live stakes/poles	50	10
<i>Salix exigua</i>	Coyote Willow	live stakes/poles	50	5
Total Zone 1-Shoreline			100	
Planting Area 2-Riparian-Upland				
<i>Populus tremuloides</i>	Quaking Aspen	1-2-gallon or bareroot	50	8
<i>Rosa Woodsii</i>	Woods Rose	1-2-gallon or bareroot	50	8
Total Zone 2-Riparian			100	


*Planting Area 1- Within 5-10 ft of the stream (Roots should reach below the water table), Planting Area 2- Upslope from Planting Area 1

Construction Notes:

- Live stakes/pole plantings to appx. 24-36" and buried so that the bottom of the stakes/poles are below the OHWM of Trail Creek. Should be buried with shoots upward and at least ¾ of the pole should be buried.
- Plants should be placed at a recommended spacing of and clustered with like species as possible

LEGEND

- Zone 1 Planting Area (Shoreline) With Riparian Seeding
- Zone 2 Planting Area (Riparian) With Riparian Seeding
- Riprap areas



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED	JLJ	SCALES SHOWN ARE FOR 11" X 17" PRINTS ONLY CADD FILE NAME 20033_land_001.dgn DRAWING DATE: February 2022
DESIGN CHECKED	TMJ	
DETAILED	TM	
DRAWING CHECKED	JLJ	

IDAHO TRANSPORTATION DEPARTMENT
 YOUR Safety→YOUR Mobility→YOUR Economic Opportunity

Parametrix


PROJECT NO.	A020(033)
-------------	-----------

TRAIL CREEK PLANTING PLAN
SH-75, ELKHORN RD TO RIVER ST, KETCHUM

ENGLISH
COUNTY Blaine
KEY NUMBER 20033
SHEET 200 OF 249

NOT APPROVED
 PRELIMINARY
 FOR CONSTRUCTION

5/13/2024 4:25:17 PM
 U:\Bois\Projects\Clients\4006-ITD\314-4006-071\SH-75 Elkhorn to River\955\cvs\CADD\DCN\sheet\20033_land_003.dgn



- 620-020A PLANTING TREE (SEEDLING OR CONTAINER)
25 EACH 476+28.00 (47.00 R) - 476+95.00 (52.00 R)
 - 620-025A PLANTING SHRUB (BARE ROOT OR CONTAINER)
14 EACH 476+30.00 (45.00 R) - 476+90.00 (44.00 R)
- NOTE:
SEE SWPP PLAN SHEETS FOR RIPARIAN SEED QUANTITIES

Table 1: Native Planting


Scientific Name	Common Name	Type	Percent by cover	Appx. Spacing (ft)
Planting Area 1-Shoreline				
<i>Salix exigua</i>	Coyote Willow	live stakes/poles	100	5
Total Zone 1-Shoreline			100	
Planting Area 2-Riparian-Upland				
<i>Amelanchier</i>	Serviceberry	1-2-gallon	50	8
<i>Rosa Woodsii</i>	Woods Rose	1-2-gallon	50	8
Total Zone 2-Riparian			100	

*Planting Area 1- Within 5-10 ft of the stream (Roots should reach below the water table), Planting Area 2- Upslope from Planting Area 1

- Construction Notes:**
- Live stakes/pole plantings to appx. 24-36" and buried so that the bottom of the stakes/poles are below the OHWM of Trail Creek. Should be buried with shoots upward and at least 3/4 of the pole should be buried.
 - Plants should be placed at a recommended spacing of and clustered with like species as possible

LEGEND

- Zone 1 Planting Area (Shoreline)
- Zone 2 Planting Area (Riparian)
- Riparian Seeding
- Riprap Areas



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED	JLJ	SCALES SHOWN ARE FOR 11" X 17" PRINTS ONLY
DESIGN CHECKED	TMJ	
DETAILED	JRA	CADD FILE NAME 20033_land_003.dgn
DRAWING CHECKED	PSA	DRAWING DATE: April 2024

IDAHO TRANSPORTATION DEPARTMENT
 YOUR Safety→YOUR Mobility→YOUR Economic Opportunity

Parametrix

PROJECT NO.	A020(033)
-------------	-----------

TRAIL CREEK SLOPE PLANTING PLAN
SH-75, ELKHORN RD TO RIVER ST, KETCHUM

ENGLISH
COUNTY Blaine
KEY NUMBER 20033
SHEET 257 OF 367

NOT APPROVED
FINAL DESIGN
 FOR CONSTRUCTION

This guide specification has been prepared by Propex Operating Company, LLC (Propex) to assist design professionals in the preparation of a specification section covering the use of Engineered Wrap-Face Vegetated Solutions for constructing reinforced-soil walls and steepened slopes. It may be used as the basis for developing either a project specification or an office master specification. Since it has been prepared according to the principles established in the Manual of Practice published by The Construction Specifications Institute (CSI) including the use of section numbers and titles from the 2011 Edition of MasterFormat, this guide specification may be used in conjunction with most commercially available master specifications sections with minor editing.

The following should be noted in using this guide specification:

- *Optional text requiring a selection by the user is enclosed within brackets, e.g.: “Section [01 33 00] [____].”*
- *Items requiring user input are enclosed within brackets, e.g.: “Section [____ - ____].”*
- *Optional paragraphs are separated by an “OR” statement, e.g.:*

***** OR *****

This guide specification is available in both hard copy and a variety of electronic formats to suit most popular word processing programs and operating platforms. Please contact Propex at (800) 621-1273 for additional copies or for information on available electronic formats.

The information, including technical and engineering data, figures, tables, designs, drawings, details, suggested procedures, and suggested specifications, presented in this publication are for general information only. The information contained herein is subject to change without notice. While every effort has been made to ensure its accuracy, this information should not be used or relied upon for any specific application without independent professional examination and verification of its accuracy, suitability and applicability. The user shall be solely responsible for the selection, use, efficiency, and suitability of the information and anyone making use of the information does so at his own risk and assumes any and all liability resulting from such use. The information is provided on an “as is” basis and Propex disclaims any and all express or implied warranties of merchantability, fitness for any general or particular purpose or freedom from infringement of any patent, trademark, copyright, or proprietary right in regard to information or products contained or referred to herein. Nothing herein contained shall be construed as granting a license, express or implied under any patent, trademark, or copyright. In no event shall Propex be liable to user for any indirect, special, consequential or incidental damages arising out of the use, the results of use or inability to use the information.

1 GENERAL

1.1 SUMMARY

- A. The work for this section shall consist of furnishing all materials, equipment, and labor necessary for the installation of an Engineered Wrap-Face Vegetated Solution for constructing reinforced-earth walls and steepened slopes.

1.2 RELATED SECTIONS

Edit the following paragraphs to coordinate with other sections of the Project Manual.

- A. SECTION [01 33 00 SUBMITTAL PROCEDURES] [____ - ____]
- B. SECTION [31 00 00 EARTHWORK] [____ - ____]
- C. SECTION [31 05 19 GEOTEXTILE] [____ - ____]
- D. SECTION [31 25 00 EROSION AND SEDIMENTATION CONTROLS] [____ - ____]
- E. SECTION [32 92 19 SEEDING AND SODDING] [____ - ____]

1.3 UNIT PRICES

Include the following article only for unit price contracts or lump sum contract with unit price adjustments. Delete for lump sum contracts.

- A. Method of Measurement: By the square meter (or square foot - as indicated in contract documents) of wall face including seams, overlaps, and wastage.
- B. Basis of Payment: By the square meter (or square foot - as indicated in contract documents) of wall face installed.

1.4 REFERENCES

The following article assumes that the date of each reference standard will be the latest edition as of the date of the project specification. This provision must be defined in Division 1; coordinate with Division 1 statements.

- A. American Society for Testing and Materials (ASTM):
 - 1. D 1557 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort
 - 2. D 4354 - Standard Practice for Sampling of Geosynthetics and Rolled Erosion Control Products(RECPs) for Testing.
 - 3. D 4355 - Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture and Heat in a Xenon Arc Type Apparatus.

4. D 4439 - Standard Terminology for Geosynthetics.
 5. D 4759 - Standard Practice for Determining the Specification Conformance of Geosynthetics.
 6. D 4873 - Standard Guide for Identification, Storage, and Handling of Geosynthetic Rolls and Samples.
 7. D 6818 - Standard Test Method for Ultimate Tensile Properties of Rolled Erosion Control Products.
 8. D 6524 - Standard Test Method for Measuring the Resiliency of Turf Reinforcement Mats (TRMs).
 9. D 6525 - Standard Test Method for Measuring Nominal Thickness of Rolled Erosion Control Products.
 10. D 6567 - Standard Test Method for Measuring the Light Penetration of a Rolled Erosion Control Product (RECP).
 11. D 6575 – Standard Test Method for Determining Stiffness of Geosynthetics Used as Turf Reinforcement Mats (TRMs).
- B. Geosynthetic Accreditation Institute - Laboratory Accreditation Program (GAI-LAP).
- C. Greenhouse Gas (GHG) Protocol
- D. International Standards Organization (ISO):
1. 9001:2015 - Quality System Certification.
 2. 14001:2015 – Environmental Management System Certification
 3. 14064-3:2006 – Environmental Management – Life Cycle Assessment
 4. 17025:2005 – Laboratory Testing and Calibration
- E. Publicly Available Specification (PAS) 2050:2011 – Specification for the assessment of the life cycle greenhouse gas emissions

1.5 DEFINITIONS

- A. *Certificate of Compliance (COC)*: An official document certified by an authorized representative within the manufacturer’s company that the manufactured synthetic turf reinforcement mat product(s) meet designated property values as manufactured in a facility having achieved ISO 9001:2015 certification, and tested in accordance with GAI-LAP procedures.
- B. *Internal Bracing*: Bracing members designed to interlace through the HPTRM and provide internal support during construction and through the project design life.

- C. *High Performance Turf Reinforcement Mat (HPTRM)*: A long-term, non-degradable RECP composed of UV-stabilized, non-degradable, synthetic fibers, nettings and/or filaments processed into three-dimensional reinforcement matrices designed for permanent and critical hydraulic applications where design discharges exert velocities and shear stresses that exceed the limits of mature natural vegetation. HPTRMs provide sufficient thickness, strength and void space to permit soil filling and/or retention and the development of vegetation within the matrix. The HPTRM MARV tensile strength per ASTM D-6818 is 3000 lbs/ft in the weakest principle direction.
- D. *Manufacturer*: Entity that produces synthetic turf reinforcement mats through a process directly utilizing obtained raw materials, in a facility owned and operated by said entity, using equipment and assemblies owned and operated by said entity, subject to a certified Manufacturing Quality Control (MQC) Program. Upon completion of production, the manufacturer may sell the turf reinforcement mat product(s) directly to the customer, or through a vendor entity.
- E. *Manufacturing Quality Control (MQC) Program*: A certified and documented program initiated and operated by the manufacturer that outlines the operational techniques and activities which sustain a quality of the synthetic turf reinforcement mat product(s) that will satisfy given needs.
- F. *Minimum Average Roll Value (MARV)*: Property value calculated as typical minus two standard deviations. Statistically, it yields a 97.7 percent degree of confidence that any sample taken during quality assurance testing will exceed value reported.
- G. *Engineered Wrap-Face Vegetated Solution*: A reinforced-earth wall and/or steepened slope system that provides permanent erosion protection and is comprised of consecutive layers of soil-filled wraps using an HPTRM and fiber-composite internal bracing.
- H. *Rolled Erosion Control Product (RECP)*: A temporary degradable or long-term non-degradable material manufactured or fabricated into rolls designed to reduce soil erosion and assist in the growth, establishment and protection of vegetation.
- I. *Securing Pin*: A device designed to temporarily hold the HPTRM in place while either vegetation establishes, or the installation of the HPTRM occurs. The securing pin offers no long term value to permanent tie-down of the HPTRM in an armoring solution.
- J. *Trilobal Monofilament Yarn*: A multi-dimensional polymer fiber consisting of a minimum of three points, providing increased surface area and grooves/channels along the fiber to capture additional moisture and sediment to enhance vegetative growth.
- K. *Typical Roll Value*: Property value calculated from average or mean obtained from test data.
- L. *Vendor*: An entity that provides synthetic turf reinforcement mat product(s) to a customer, on behalf of an independent manufacturer. A vendor does not manufacture the actual synthetic turf reinforcement mat product(s), and therefore is not subject to provisions of a certified MQC Program.

1.6 SUBMITTALS

Edit the following to coordinate with Division 1.

A. Submit under provisions of Section [01 33 00] [____]:

1. Qualifications:

The following documentation shall be submitted to the engineer of record and/or project owner for review and approval prior to installation.

- a) A Certificate of Compliance (COC) stating the name of the manufacturer, product name, style, chemical compositions of filaments or yarns and other pertinent information to fully describe the Engineered Wrap-Face Vegetated Solution. The COC shall state that the furnished material meets the requirements of the specification and shall be attested to by a person having legal authority to bind the Manufacturer.
- b) The Manufacturer's Manufacturing Quality Control (MQC) Program to assure compliance with the requirements of the specification.
- c) A project list demonstrating a documented history of installations of the HPTRM component totaling more than 2,000,000 square yards, with over 500,000 square yards having been installed in the marketplace for more than five (5) years. Past project documentation submitted for evaluation shall include project name, date of installation, and size of the project.
- d) A certification demonstrating that the HPTRM component is manufactured in a facility that has been ISO 14001 certified for measuring environmental impact and continuously looking for ways to improve it for a minimum of ten (10) years.
- e) A certification demonstrating that the HPTRM component is manufactured in a facility that has been ISO 9001:2015 certified and tested in a laboratory that has been both GAI-LAP and ISO 17025:2005 certified.
- f) Third party / Independent Testing values demonstrating UV resistance testing on the HPTRM component for two consecutive years including most recent year. Testing and reporting of the results shall follow ASTM D-4355, showing the percent tensile strength retained in both machine and cross-machine direction.
- g) Documentation of functional longevity for the HPTRM component demonstrating the material's durability in the field. The documentation shall demonstrate a minimum retained tensile strength of 70% per ASTM D-6818 after a minimum of ten (10) years of exposure in an area having a minimum solar radiation of 21.70 MJ/m²-day. The documentation shall include photos and date of the initial installation and field sampling, and the test results of the field sampling.
- h) A certification demonstrating that the HPTRM component has been evaluated and certified by an independent third party to have a maximum cradle-to-grave carbon footprint of 2.7 kg CO₂e/m² when tested per GHG Protocol, ISO 14064-3:2006, and PAS 2050:2011.

1.7 DELIVERY, STORAGE, AND HANDLING

A. HPTRM labeling, shipment and storage shall follow ASTM D-4873.

- B. Product labels shall clearly show the manufacturer or supplier name, style name, and roll number.
- C. Each shipping document shall include a notation certifying that the material is in accordance with the manufacturer's certificate.
- D. Each HPTRM roll shall be wrapped with a material that will protect the geotextile from damage due to shipment, water, sunlight, and contaminants. Individual roll wrapping will not be required for HPTRMs exceeding the UV Resistance requirements per ASTM D-4355 in Section 2.2.A.6. The protective wrapping shall be maintained during periods of shipment and storage.
- E. During storage, HPTRM rolls shall be elevated off the ground and adequately covered to protect them from the following: Site construction damage, extended exposure to ultraviolet (UV) radiation, precipitation, chemicals that are strong acids or strong bases, flames, sparks, temperatures in excess of 71 deg C (160 deg F) and any other environmental condition that might damage the HPTRM.

1.8 **QUALITY ASSURANCE SAMPLING, TESTING, AND ACCEPTANCE**

- A. HPTRM component shall be subject to sampling and testing to verify conformance with this specification. Sampling for testing shall be in accordance with ASTM D-4354.
- B. Acceptance shall be in accordance with ASTM D-4759 based on testing of either conformance samples obtained using Procedure A of ASTM D-4354, or based on manufacturer's certifications and testing of quality control samples obtained using Procedure B of ASTM D-4354.
- C. Quality Assurance Sampling and Testing will be waived for ISO 9001:2015 Certified Manufacturing Facilities. Documentation of ISO 9001:2015 Certification shall be provided per the requirements of Section 1.6.A.

2 PRODUCTS

2.1 **MANUFACTURERS**

- A. All components of the armoring solution shall be furnished by a single manufacturer as a complete system.
- B. Approved Engineered Wrap-Face Vegetated Solution Manufacturers:
 - 1. Propex Operating Company, LLC
4019 Industry Drive
Chattanooga, TN 37416
(800) 621-1273
- C. Approved Engineered Wrap-Face Vegetation Solution:
 - 1. PYRAWALL Engineered Vegetated Wall System
- D. Alternate Engineered Wrap-Face Vegetation Solution Manufacturers:

1. Alternate manufacturers seeking pre-approval shall be submitted to the engineer of record and/or owner a minimum of ten (10) work days prior to the bid date and must meet the requirements outlined within this document.
2. For consideration, alternate systems meeting the material specification within Section 2 seeking pre-approval shall submit the following for evaluation.
 - a) Documentation demonstrating a history of installations designed for erosion control meeting the requirements of Section 1.6.A.1.c.
 - b) Documentation demonstrating local representation within the state in which the project is being constructed.
 - c) Documentation demonstrating the alternative engineering design for engineered wrap-face vegetated solution. The following shall be submitted:
 - 1) Overall alternative engineered wrap-face vegetated solution design methodology
 - 2) Input parameters
 - 3) Calculations / Model output
 - 4) Factor of Safety for Sliding, Overturning, and Bearing Capacity to support the wrap-face vegetated solution design; with the conditions analyzed and documented for the proposed project
 - 5) Alternative engineered wrap-face vegetated solution product sample including all components.
3. Manufacturers seeking pre-approval must also have a manufacturer's representative present at the pre-bid meeting.
4. Alternate manufacturers that do not provide documentation meeting or exceeding the requirements of Section 1.6.A will not be approved.

2.2 MATERIALS

A. HPTRM:

1. Three-dimensional, high tensile strength, long term non-degradable lofty woven polypropylene HPTRM specially designed for erosion control applications that exhibits very high interlock and reinforcement capacity with both soil and vegetative root systems.
2. A homogeneous woven matrix composed of Trilobal monofilament yarns woven into uniform configuration of resilient pyramid-like projections to improve interlock and minimize yarn displacement around internal bracing and pins, which also results in greater flexibility for improved conformance to uneven surfaces.
3. A material not comprised of layers, composites, or discontinuous materials, or otherwise loosely held together by stitched or glued netting.
4. The HPTRM component should meet the following values:

Property	Test Method	Test Parameters	Units	Property Requirement
Thickness ¹	ASTM D-6525	Minimum	mm (in)	10.2 (0.40)

Light Penetration ¹ (% Passing)	ASTM D-6567	Maximum	percent	10
Tensile Strength ¹	ASTM D-6818	Minimum	kN/m (lb/ft)	58.4 x 43.8 (4,000 x 3,000)
Tensile Elongation ¹	ASTM D-6818	Maximum	percent	40 x 35
Resiliency ¹	ASTM D-6524	Minimum	percent	80
Flexibility ^{2,3}	ASTM D-6575	Maximum	mg-cm (in-lb)	615,000 (0.534)
UV Resistance ²	ASTM D-4355	Minimum	percent	90 at 3,000 hrs ⁴ 90 at 6,000 hrs
Carbon Footprint ²	ISO 14064-3 GHG Protocol PAS 2050:2011	Maximum	Kg CO ₂ e	2.7 per 1 m ²

Note:

1. Minimum Average Roll Value (MARV).
 2. Typical Value.
 3. A smaller value for flexibility denotes a more flexible material.
 4. Third party / Independent Testing values must be provided showing UV resistance testing for two consecutive years including most recent year.
5. Hydraulic Performance Properties:
- a) Flume Testing: The HPTRM component must meet the following at a minimum when subjected to at least 0.5 hrs of continuous flow producing the following conditions.
 - 1) Unvegetated HPTRM
 - Permissible velocity: 9 ft/sec (2.7 m/sec)
 - Permissible shear stress: 2.8 psf (130 Pa)
 - 2) Partially Vegetated HPTRM
 - Permissible velocity: 15 ft/sec (4.6 m/sec)
 - Permissible shear stress: 8 psf (383 Pa)
 - 3) Fully Vegetated HPTRM
 - Permissible velocity: 25 ft/sec (7.6 m/sec)
 - Permissible shear stress: 16 psf (766 Pa)
6. Functional Longevity: In addition to the UV resistance per ASTM D-4355 stated above, the HPTRM component must have a documented installation showing a minimum retained tensile strength of 70% per ASTM D-6818 after a minimum of 10 years of exposure to a minimum solar radiation of 21.70 MJ/m²-day.
7. Environmental Impact: The HPTRM component shall be evaluated and certified by an independent third party to have a maximum cradle-to-grave carbon footprint of 2.7 kg CO₂e/m² when tested per GHG Protocol, ISO 14064-3:2006, and PAS 2050:2011.

8. Manufacturing Impact: The HPTRM component shall be manufactured in a facility that is ISO 14001 certified for measuring environmental impact and continuously looking for ways to improve it for a minimum of ten (10) years.
9. Manufacturing Quality Control: Testing shall be performed at a laboratory accredited by GAI-LAP for tests required for the HPTRM, at frequency exceeding ASTM D-4354, with following minimum acceptable testing frequency:

Property	Test Frequency m ² (yd ²)
Thickness	1/12,291 (1/14,700)
Light Penetration (% Passing)	1/12,291 (1/14,700)
Tensile Strength	1/12,291 (1/14,700)
Tensile Elongation	1/12,291 (1/14,700)
Resiliency	1/12,291 (1/14,700)
Flexibility	1/12,291 (1/14,700)
UV Resistance	Annually

B. Internal Bracing and Securing:

1. The internal brace assembly comprises 3 nonmetallic polymer bars specially designed, whereby 2 of the bars are threaded through the pyramidal projections of the HPTRM to form a semi-rigid base and upright member, which both are then connected using the third bar as a transverse member. These braces shall be installed for each lift at a horizontal spacing along the wall not to exceed 68 mm (27 inches). For curved wall applications, this spacing typically ranges from 53 to 61 mm (21 to 24 in).
2. Wood or plastic stakes, or steel pins are used to pin-down the geotextile near the back of the reinforcement zone to hold the geotextile taut while aligning the wall face and placing soil backfill. These are installed as needed along the HPTRM, but at a frequency no less than 1 per 2-3 lineal meters (6.5-10 lineal feet). The stakes or pins shall be 225 to 305 mm long (9 to 12 in) and shall be approved by the Engineer before installation.

3 EXECUTION

3.1 SUBGRADE PREPARATION

- A. Excavate a shallow, level trench at least 1.3 m (4.3 ft.) wide and 15 to 23 cm (6 to 9 in) deep below finished grade using an excavator with smooth bucket to reduce disturbance at the defined subgrade elevation.

- B. The cut-slope excavation width shall not exceed the lines and grades shown on the Plans, and care shall be taken to avoid encroachment near bordering properties. As necessary, to account for grade variations along the wall base line, the trench shall have level sections separated by 30 cm (12 in) steps to allow for grade alignment with the 30 cm (12 in) wrapped lifts.
- C. Deleterious material (overly wet soil, uncontrolled loose fill, construction debris, organics, etc.) encountered during this excavation shall be over-excavated, removed, and replaced with compacted granular fill or approved backfill soil. Compact the subgrade as specified by the Engineer.
- D. If specified by the engineer, a perforated drainage pipe shall be installed at the back of the trench and connected to a prescribed outlet for draining groundwater.
- E. Granular soil is defined as:
 - 1. Classified as GM, GW, SM, SW, GW-GM, SW-SM referencing the USCS (Unified Soil Classification System).
 - 2. Contains maximum particle size of 3.8 cm (1-1/2 in) and less than 12 percent fines passing 0.074 mm (No. 200 sieve).
 - 3. Inert earth material with less than 3 percent organics or other deleterious substances (wood, metal, plastic, waste, etc).

OR

- 4. Meets the untreated base grading requirements for 3.8 cm (1-1/2 in) maximum nominal size crushed aggregate per typical state construction standards.
- A. For clay subgrade soils, line the trench with GEOTEX[®] 801 nonwoven geotextile. Place a 10 cm (4 in) thick loose lift of granular soil on top of the filter fabric and compact it to at least 90 percent of the specified modified Procter dry density per ASTM D 1557. Smooth the surface of the compacted soil to provide a level pad needed for the first layer of HPTRM.

3.2 INSTALLATION

- A. Install the armoring solution at elevation and alignment indicated.
- B. Starting with the lowest portion of the wall alignment, roll out the first layer of the HPTRM along the trench line, with the inboard 1.2 m (4 ft.) of the 2.6 m (8.5 ft.) wide roll laid along the trench footprint. At each terminus of this lowest section of the wall alignment, curve the wall face slightly into the slope so the ends of this run can be buried, leaving no HPTRM edges exposed at the ground surface. Concave curves in the wall are formed by cutting and overlapping the fabric in the 1.2 m (4 ft.) backfill zone; convex curves are formed by spreading the fabric.
- C. Weave the bottom and upright internal bracing components (bars) through the interior pyramidal projections of the HPTRM toward the 1.2 m (4 ft.) fold line, being sure to catch 4-8 yarns with the bracing bar at each pyramid. Fold the fabric and stand-up the face, then connect the bars using a T-slot at the 4-ft fold line. While holding the face near vertical, connect those 2 bars with the third bar, aligned transverse to the other two using 2 T-slots. Do not allow the vertical face segment to lay down prior to installing this transverse bar, because the vertical bar likely will be damaged and require replacement. Install these braces at a maximum uniform spacing of 68 mm (27 inches) along the wall face; a lesser spacing of 60 mm (24 inches) may be desirable for tighter face liners. Loose fabric at the outboard side is laid out away from the backfill area.

- D. Pull the fabric fairly taut in both directions, then drive stakes or pins 225 to 305 mm long (9 to 12 in) through the HPTRM near the front and rear of the 1.2 m (4 ft.) backfill zone to hold the fabric in place for subsequent soil backfilling at a frequency no less than 1 per 2-3 lineal meters (6.5-10 lineal feet). Exercise extreme caution when driving or operating equipment across this HPTRM, as sudden turns or braking may deform or damage the HPTRM, or pull the wall face out of proper alignment.
- E. Place a 17 to 20 cm (7 to 8 in) thick loose lift of backfill soil approved by the Engineer along the 1.2 m (4 ft.) backfill zone using hand shovels to place soil around the braces first, and then filling the space in-between braces along the face. Compact the soil lift to the specified modified Proctor dry density per the Engineer's recommendation, but never less than 85% of the maximum dry density per ASTM 1557.
 - 1. The internal-braced design of the geosynthetic wrap allows mechanical compaction of the backfill zone immediately adjacent to the face without the use of temporary bracing and without the use of external support at the wall face.
 - 2. Vibratory plate compactors should not be used within 7 cm (3 in) of the face; ramming compactors ("jumping jack" style) should not be used within 30 cm (12 in) of the face.
- F. Place a second lift of backfill soil along the backfill zone and compact it to bring the total height up to 30 cm (12 in) at the face. Cohesive soils may tend to deform laterally more than granular soils and may require additional loose-lift height to achieve the final compacted height. The compacted lift thickness away from the face should be approximately 28 cm (11 in) to allow for a thin soil layer to be placed between the consecutive HPTRM wraps.
- G. Fold the 1.1 m (3.5 ft.) outboard portion of the HPTRM wrap layer back over the backfill zone, stretch it taut to remove wrinkles, and pin it down. Spread approximately 2 cm (1 in) of fine backfill soil with no coarse gravel or larger particles evenly across the fabric in preparation for the next wrapped lift.
- H. To splice onto the end of a HPTRM roll (previous roll), install a brace at 0.45 m (1.5 ft) from the end of the roll. For the new roll to be added, insert a brace close to the roll end, then slide the new roll end into the previous roll end until the new roll end abuts against the final brace of the previous roll. After placing and compacting backfill, fold the top wrap back over the fill and stretch taut to provide an end-to-end overlap of 0.45 m (1.5 ft).
- I. Repeat Steps A. through H. for each subsequent backfill lift. Incorporate a setback with each lift to provide the desired overall slope angle.
- J. To form a curve in the wall alignment, cut the fabric laydown flaps perpendicular to the wall face. Cuts should extend from the back of the flap to not closer than 10 cm (4 in) from the wall face. Spread the fabric at the cuts to form a concave face curve or overlap the fabric at the cuts to form a convex face curve. Add an additional braces within the curve if needed.
- K. For taller walls, the geosynthetic-reinforced zone behind the wrap-face will need to be widened by using supplemental geosynthetic layers sandwiched in-between the upper fabric layer of a given lift and the lower fabric layer of the subsequent lift. Apply a thin layer of soil at fabric interfaces to eliminate complete fabric-to-fabric contact. Alternatively, the supplemental geosynthetic layers can be placed at mid-lift height after the first 15 cm (6 in) lift is compacted.
- L. Where each wrap-face lift ends at the lateral project limits, the wall face should be curved slightly into the slope and buried, leaving no HPTRM loose ends exposed at the ground surface. Overall wall layout and foundation steps are specified in the Construction Plans, but foundation grade elevations may need to be modified to match actual field conditions during construction. Damage to the Engineered Wrap-Face Vegetated Solution resulting from Contractor vehicles, equipment, or operations shall be repaired.

END OF SECTION

FLOODWAY "NO-RISE / NO-IMPACT" CERTIFICATION

This document is to certify that I am duly qualified engineer licensed to practice in the State of

Idaho
(State)

. It is to further certify that the attached technical data supports

the fact that proposed SH-75 Trail Creek will not impact the base flood
(Name of Development)

elevations, floodway elevations, and floodway widths on Trail Creek at published
(Name of Stream)

cross sections in the Flood Insurance Study for, City of Ketchum, dated November 26, 2010
(Name of community) *(Date)*

and will not impact the base flood elevations, floodway elevations, and floodway widths at the

unpublished cross-sections in the area of the proposed development.



SEAL, SIGNATURE AND DATE

Spencer J. Savage

Name

Water Resource Engineer

Title

412 E. Parkcenter Blvd., Suite 100

Boise, ID 83706-6659

Address

FOR COMMUNITY USE ONLY:

Community Approval

Approved Disapproved

Community Official's Name

Community Official's Signature

Title

SH-75 Trail Creek Bridge

Project No. A020(033)

Key No. 20033

Blaine County, Idaho

April 28, 2021

Prepared for
The Idaho Transportation Department



Prepared by
HDR
412 E Parkcenter Blvd, Ste 100
Boise, ID 83706



Table of Contents

1	Introduction	1
2	Existing Conditions	1
2.1	Vicinity Sketch	1
2.2	Problems and Adverse Conditions including Scour	1
2.3	Stream Stability.....	2
2.4	Aerial and Ground Photographs.....	3
3	Hydrology	5
3.1	Floods and Peak Flow	6
3.2	Methods.....	6
3.3	Floodplain	7
4	Hydraulics	10
4.1	Design Constraints and Freeboard Requirements.....	10
4.2	Hydraulic Analysis.....	10
4.2.1	Hydraulic Structure Survey	10
4.2.2	Hydraulic Analysis Methodology	10
5	Existing Structure	14
6	Proposed Structure	14
6.1	Structure Summary	14
6.2	Hydraulic Performance	15
6.3	Channel Stability Considerations	19
6.4	Review of additional conditions.....	22
7	Outlet Protection and Riprap Recommendations	23
7.1	Riprap Calculations.....	23
8	ITD Forms	23
9	Consistency to Flood Insurance Requirements	24
10	References	24

Figures

Figure 1. Vicinity Sketch with Aerial, SH-75 Trail Creek Bridge	2
Figure 2. FEMA Flood Insurance Rate Map for Vicinity of SH-75 Bridge	8
Figure 3. FEMA Flood Insurance Rate Map for Project Location: SH-75 Bridge.....	9
Figure 4. FIS and HEC-RAS DEM Thalweg and Water Surface Elevation Comparison	12

Photos

Photo 1. Looking upstream at Trail Creek from SH-75 Bridge on July 28, 2019.	3
Photo 2. Looking upstream face of SH-75 Bridge over Trail Creek from left bank on July 28, 2019.	4
Photo 3. Looking downstream face of SH-75 Bridge over Trail Creek from right bank on October 8, 2019.	4
Photo 4. Looking upstream under SH-75 Bridge over Trail Creek on October 8, 2019.....	5
Photo 5. Looking downstream at Trail Creek from SH-75 Bridge on July 28, 2019.....	5
Photo 6. Reach of Trail Creek Upstream of SH-75 Crossing.....	21
Photo 7. Stable natural stream bed and bank rock along the right (north) bank of Trail Creek upstream of the SH-75 Crossing.....	22
Photo 8. Bank Protection and Tree Roots along the left (south) bank of Trail Creek Upstream of SH-75 Bridge.....	22

Tables

Table 1. Summary of Design Discharges for SH-75 Bridge over Trail Creek.....	7
Table 2. Comparison of FIS WSE and Floodway Elevations Cross-Sections to HEC-RAS Model Results, without and with Floodway Encroachments	12
Table 3. Summary of Selected Hydraulic Model Input Parameters.....	13
Table 4. Summary of Structures in SH-75 Bridge HEC-RAS Model	14
Table 5. Summary of Existing and Proposed Structures and Water Surface Elevations Modeled	15
Table 6. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures.....	16
Table 7. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures Considering Floodway Encroachments.....	18
Table 8. Summary of 2-year Velocity and Top Width Upstream and Downstream of the SH-75 Crossing for Existing and Proposed Conditions	20



Appendices

- Appendix A. Site Map with Contours Type Size and Location
- Appendix B. HEC-RAS Model Inputs including Cross-Sections
- Appendix C. HEC-RAS Output: Existing Conditions
- Appendix D. HEC-RAS Output: Proposed Conditions
- Appendix E. HEC-RAS Output: Existing vs. Proposed Conditions
- Appendix F. Scour and Riprap
- Appendix G. ITD 210 Form
- Appendix H. ITD Pontis Field Inspection Report
- Appendix I. City of Ketchum Floodplain Permit Status

Acronyms

ACE	annual chance exceedance
cfs	cubic feet per second
CSU	Colorado State University
DEM	duplicate effective model
FEMA	Federal Emergency Management Agency
FIS	flood insurance study
FIRM	Flood Insurance Rate Map
fps	feet per second
HEC-RAS	Hydrologic Engineering Center River Analysis System program
ITD	Idaho Transportation Department
NAVD 88	North American Vertical Datum of 1988
SH-75	State Highway 75
USACE	U.S. Army Corps of Engineers
USGS	U.S. Geological Survey
WSE	water surface elevation



1 Introduction

State Highway 75 (SH-75) is the primary north-south highway in the Wood River Valley serving the cities of Bellevue, Hailey, Ketchum, and Sun Valley in Blaine County. The proposed SH-75 Elkhorn to River Street project is the third and northernmost roadway construction project to be developed from the *Timmerman to Ketchum Environmental Impact Statement Record of Decision* issued in August of 2008 (ITD 2008a). The purpose of the project is to improve safety and capacity on SH-75 between Elkhorn Road, north of the Big Wood River Bridge, and River Street in the city of Ketchum. The approximate project milepost limits are from 126.5 to 128.2 on SH-75. The Idaho Transportation Department (ITD) is replacing the SH-75 Bridge at Trail Creek to meet the purpose of this project.

2 Existing Conditions

2.1 Vicinity Sketch

Figure 1 is a map of the project vicinity. SH-75 runs approximately south to north. Trail Creek flows from approximately northeast to south/southwest. There are five structures in the project vicinity (three upstream of SH-75 and one downstream of SH-75). A site map with contours is shown in Appendix A.

2.2 Problems and Adverse Conditions including Scour

The bridge inspection report from 2016 notes the following (ITD 2016a):

- **EMBANKMENT:** Earth fill in good condition. Minor erosion under outside porta-rail, abutment 2 left side.
- **CHANNEL:** Rock channel is in good condition. Inlet and outlet has rock riprap protection.

Based on field reconnaissance completed in the summer and fall of 2019 and the survey data, indications of scour were not observed at the abutments or in the channel. The survey data suggest some aggradation of materials in the channel.




Figure 1. Vicinity Sketch with Aerial, SH-75 Trail Creek Bridge

2.3 Stream Stability

The stream in the study area appears to be stable. The reach has banks that have been stabilized with riprap, retaining walls, and a well-established vegetation riparian zone. The stream may be sediment starved due to the upstream Sun Valley Lake. Some down cutting could be possible due to the steep gradient of this mountain stream. The 2010 Federal



Emergency Management Agency (FEMA) *Flood Insurance Study* (FIS) prepared for this reach of Trail Creek states the following (FEMA 2010):

The Trail Creek floodplain is extensively developed, with residential dwellings lining the stream from one end of the city to the other. As in many other areas, stream-front property is considered prime residential land in Sun Valley.

The Trail Creek Valley runs northeast to southwest, sloping toward the southwest. The creek has an average overall slope of 200 feet per mile (fpm) and, within Sun Valley, a slope of 80 fpm. The channel is narrow and well incised.

2.4 Aerial and Ground Photographs

An aerial is included in Figure 1. Photographs of Trail Creek and SH-75 Bridge are shown in Photo 1 through Photo 5.



Photo 1. Looking upstream at Trail Creek from SH-75 Bridge on July 28, 2019.



Photo 2. Looking upstream face of SH-75 Bridge over Trail Creek from left bank on July 28, 2019.



Photo 3. Looking downstream face of SH-75 Bridge over Trail Creek from right bank on October 8, 2019.



Photo 4. Looking upstream under SH-75 Bridge over Trail Creek on October 8, 2019.




Photo 5. Looking downstream at Trail Creek from SH-75 Bridge on July 28, 2019.

3 Hydrology

There are U.S. Geological Survey (USGS) gaging stations located upstream (13137300 Trail Creek near Sun Valley, Idaho) and downstream (13137500 Trail Creek at Ketchum, Idaho) of the SH-75 Bridge. Both gages have stream records of less than 5 years. A FEMA FIS (16013CV001A, Blaine County, Idaho and Incorporated Areas, November 26, 2010) has been prepared for this reach of Trail Creek (FEMA 2010).

Flows on Trail Creek may be influenced by Sun Valley Lake, which is located upstream of the SH-75 Bridge. However, no mention of the hydrologic effects of the Lake are included in the stated record from the FIS (FEMA 2010):

Past floods in Ketchum from Trail Creek, Warm Springs Creek, and the Big Wood River have all been due to spring snowmelt conditions, generally during years marked by heavy snowpack with rapid melting during warm-weather periods. These conditions have sometimes been accompanied in the past by warm spring rains, which hasten the snowmelt, leading to more rapid runoff and higher stream stages. Future floods are likely to occur from similar conditions, although there is a possibility of winter floods caused by heavy, unseasonably warm rainfall on top of a deep snowpack.

No records exist concerning flooding on Trail Creek. Because the stream channel is relatively steep and well-incised, past flooding would have been limited in extent and severity, attracting little attention. No damage reports were found for flooding on Trail Creek for any year, and no dollar estimates of past flood damage were found for any of the three study streams.

The likelihood of hydraulic modifications to the Dam at Sun Valley Lake is unknown. No additional investigation or analysis was performed to evaluate the impacts of the Lake or removal of the Dam.

3.1 Floods and Peak Flow

The selected design flow and flood insurance consistency flow is the 100-year from Table 1. The scour design flow is the 500-year from Table 1.

3.2 Methods

The USGS gage has annual peak stream flow records from 2012 to 2018. Recorded annual peak flows during this period vary between 255 cubic feet per second (cfs) and 750 cfs. The USGS stream gage data consist of fewer than 20 years of records. Therefore, these data were not used to develop design flows. The Blaine County FIS includes 10-, 2-, 1- and 0.2-percent annual chance exceedance (ACE) (10-, 50-, 100-, and 500- year) flows for Trail Creek. Therefore, these flows were used as design flows. The FIS does not include a 50-percent ACE (2-year) flow. StreamStats was used to estimate the 50-percent flow based on regional regression equations (USGS 2009). Flows from the FIS, StreamStats, and the existing plans were similar for all return periods and were used to estimate the 2-year flow. Design flows are summarized in Table 1. A comparison of these flows to range of recorded peak flows at the USGS gage indicate that these are reasonable design flows and that adjustments to the FIS flows are not warranted.



Table 1. Summary of Design Discharges for SH-75 Bridge over Trail Creek

Flooding Source and Location	Drainage Area (square miles) ¹	50-percent annual chance (2-year) ²	10-percent annual-chance (10-year)	2-percent-annual-chance (50-year)	1-percent-annual-chance (100-year)	0.2-percent-annual-chance (500-year)
Trail Creek At Mouth	69	360	600	900	1,020	1,300

¹Using StreamStats drainage area at SH-75 Bridge is approximately 64 square miles

²Estimated using FIS flow, StreamStats, and Existing Plans

3.3 Floodplain

The SH-75 Bridge is in a mapped flood hazard area (Panel 16013C0461E, November 26, 2010) (FEMA 2010) and crosses the floodway. A portion of the Flood Insurance Rate Map (FIRM) for the vicinity is shown in Figure 2 and for the area near the SH-75 Bridge in Figure 3. Since the project is within a floodplain and a floodway, a floodplain development permit is required from the floodplain administrator for consistency with the community’s floodplain ordinance requirements. Issuance of the permit will require a no-rise certificate. The City of Ketchum floodplain administrator must confirm flood ordinance requirements (Ketchum 2014):

Prohibit encroachments, including fill, new construction, substantial improvements, and other development unless certification with supporting calculation, by a registered professional hydraulic engineer is provided demonstrating that encroachments shall not result in any increase in flood level during the occurrence of the base flood discharge. Uses in the floodway shall be restricted to that which are required by public necessity (for example, bridges, water pumps), recreational use (for example, paths), wildlife habitat improvements (for example, vegetation, nesting structures, pool/riffle improvements), and gravel extractions; provided that the use/encroachment meets the approval of the Federal Emergency Management and Nation Flood Insurance Program and does not jeopardize the city’s participation in the National Flood Insurance Program. (Ordinance 1120 §17.88.070 C.1).

HDR requested the effective regulatory model from FEMA, but FEMA was unable to produce model input files. Therefore, based on coordination with the City of Ketchum, HDR completed floodplain and floodway analyses using an alternative model that considers the floodway as delineated in the communities’ FIRM, and the existing channel geometry, as surveyed for this project.




Figure 2. FEMA Flood Insurance Rate Map for Vicinity of SH-75 Bridge




Figure 3. FEMA Flood Insurance Rate Map for Project Location: SH-75 Bridge

4 Hydraulics

4.1 Design Constraints and Freeboard Requirements

ITD sets waterway clearances for bridges and culverts (ITD, 2008b, ITD 2016b). For this location, the appropriate requirement is for bridges/culverts over waterways other than canals is as follows:

- All bridges/culverts with a clear span of 20 feet or greater shall have a minimum of 2-foot clearance above the Q_{50} flow (50-year flow in Table 1), and;
- In addition, the Q_{100} flow (100-year flow in Table 1) must pass beneath the lowest chord of the structure.

Additional constraints at this location are as follows:

- Provide 3-foot or wider paths on both sides of the channel at an elevation of 2-year flow (ordinary high water) water surface elevation or higher.
- Provide 5-foot or higher of clearance between the paths and the low chord of the bridge.
- Highway geometrics may impose a limit on the height the low chord may be raised.
- Result in no rise the flood elevation (no-rise certificate)

4.2 Hydraulic Analysis

4.2.1 Hydraulic Structure Survey

Parametrix surveyed Trail Creek in the fall of 2019. Parametrix surveyed cross-sections of Trail Creek from approximately 1,500 feet upstream to 2,000 feet downstream of the existing SH-75 Bridge. The survey included two pedestrian bridges upstream and the upstream bridge at Leadville Avenue along with one downstream bridge at 2nd Avenue S. Channel shape is generally V- or U-shaped. The channel bottom and sides are earthen with abundant native vegetation. The channel has side slopes generally ranging from 1V:2H to 1V:3H.

4.2.2 Hydraulic Analysis Methodology

The hydraulic analysis methodology followed FEMA's procedures for "No-Rise" certification (FEMA 2013). The hydraulic analysis involved using the Hydrologic Engineering Center River Analysis System (HEC-RAS) to create models of the existing condition and the proposed condition (the pre- and post-project condition). The HEC-RAS geometry is shown in Appendix B.

4.2.2.1 FLOODPLAIN ANALYSIS

The U.S. Army Corps of Engineers (USACE) used a HEC-2 computer program for Trail Creek for the FIS (FEMA 2010). This is the current effective model. In response to a request for this model, FEMA indicated that they were unable to recover model files or inputs for the effective regulatory model (Greene 2020). The City of Ketchum and HDR agreed that since the effective model was unavailable, that floodplain and floodway analyses should be completed using an



alternative hydraulic model that considers the floodway as delineated in the communities' FIRM, and the existing channel geometry, as surveyed for this project (Zung 2020). Floodway stations were adjusted to match the floodways widths shown in the floodway data tables and to reduce or eliminate negative surcharges as much as possible. The HEC-RAS Version 5.0.7 was applied to Trail Creek to model the hydraulics (USACE 2018).

The alternative hydraulic model was developed using the surveyed cross-section data and modeled with the same Manning's roughness coefficients as used in the FIS (0.065 in channel, 0.20 in overbank areas) to try to reproduce the FIS profiles. Bank stations were simulated at or inside the published floodway in attempted to develop a duplicate effective model (DEM). Data regarding floodplain modifications since the model was published in 1974 were not available. Floodway profile elevations between the alternative DEM model and the published floodway elevations from the FIS floodway data are shown in Table 2.

Floodway water surface elevations in the DEM generally compared to within 0.5 feet of the published elevations. At two cross-sections, the difference was larger than 0.5 feet. The City of Ketchum has indicated that it has had difficulties comparing water surface elevations from FIS to existing topography, and has indicted that the effective model is not appropriate for use in this analysis. The City agrees that discrepancies are beyond the area of hydraulic influence for this bridge and that the bridge construction does not warrant a conditional letter of map revision submittal. However, these discrepancies do indicate that a revised study of Trail Creek may be warranted to accurately represent flood hazards and the existing condition of Trail Creek. Figure 4 shows that the surveyed channel bottom upstream of the Leadville Ave Bridge is roughly 2 feet lower than the channel bottom surveyed in 1974, which further supports the fact the effective model does not represent the current geometry in this reach. Based on guidance from the City of Ketchum, no further changes were made in attempt to recreate the results in the FIS. The DEM was considered to be the new model and calibrated to reproduce the FIS profiles within 0.5 feet or as close as possible and with the available known information.




Figure 4. FIS and HEC-RAS DEM Thalweg and Water Surface Elevation Comparison

Table 2. Comparison of FIS WSE and Floodway Elevations Cross-Sections to HEC-RAS Model Results, without and with Floodway Encroachments

Lettered Cross-Sections from FIRM/FIS	FIS WSE without Floodway (ft, NAVD)	FIS WSE with Floodway (ft, NAVD)	DEM HEC-RAS model XS at the approximate location	DEM HEC-RAS WSE without Floodway (ft, NAVD)	DEM HEC-RAS WSE with Floodway (ft, NAVD)	Difference in 100—WSE (ft)	Difference in Floodway WSE (ft)
D	5782.3	5782.8	-53	5782.5	5782.5	0.1	-0.3
E	5784.6	5784.7	162	5784.2	5784.2	-0.4	-0.5
F	5788.7	5789.7	958	5790.0	5790.2	1.3	0.5
G	5798.5	5798.5	1719	5797.9	5798.0	-0.6	-0.5
H	5804.1	5804.1	2247	5804.1	5804.1	0.0	-0.1
I	5805.1	5806.1	2415	5805.2	5805.3	0.1	-0.8
J	5810.8	5810.8	2881	5809.9	5809.9	-0.9	-0.9
K	5816.8	5817.1	3694	5816.6	5816.6	-0.3	-0.5

FIRM = Flood Insurance Rate Map; FIS = Flood Insurance Study; ft = feet; NAVD = North American Vertical Datum of 1988; WSE = water surface elevation; DEM = duplicate effective model; HEC-RAS = Hydrologic Engineering Center River Analysis System

4.2.2.2 EXISTING CONDITIONS (PRE-PROJECT) MODEL

The DEM model was revised to reflect modifications that have occurred within the floodplain since the date of the effective model. Changes from the DEM include Manning’s roughness coefficients and bank stations that better represent the observed stream conditions based on



field observations and field survey data. The existing condition model serves as the baseline condition for determining the hydraulic effects of the proposed condition design.

4.2.2.3 PROPOSED CONDITION (POST-PROJECT) MODEL

A proposed conditions model was created based on existing conditions model and the proposed SH-75 Bridge. The results of the proposed conditions model are compared to the existing conditions model to determine the impact of the project.

The model downstream boundary condition for the existing and proposed models is normal depth. Manning’s n values for both the main channel and culvert/bridge locations are based on the guidance in Chapters 3 and 6 of the HEC-RAS manual (USACE 2016). Selected hydraulic model conditions are summarized in Table 3.

Table 3. Summary of Selected Hydraulic Model Input Parameters

Hydraulic Model Parameter	Value Used in Model
Number of cross-sections	48
Channel roughness values (Manning’s n)	0.070 (left overbank) 0.045 (channel) 0.070 (right overbank)
Contraction coefficient	0.1, except at bridges 0.3, 0.6 for SH-75 existing
Expansion coefficient	0.3, except at bridges 0.5, 0.8 for SH-75 existing
Boundary condition	Normal depth Slope = 0.01
Flow profiles	See Table 1

4.2.2.4 HYDRAULIC ANALYSIS DOWNSTREAM BOUNDARY CONDITION SENSITIVITY

The sensitivity of the results to the downstream boundary condition was assessed. The selected hydraulic model input parameters are shown in Table 3. The boundary condition was changed and simulated for two conditions, a multiplier of a 10 (slope = 0.1) and a divisor of 10 (slope = 0.001). These changes in the boundary condition resulted in changes to the predicted water surface at distance upstream from the downstream boundary condition of up to 1,167 feet. The SH-75 Bridge is located at 2,188 feet from the downstream boundary condition. This sensitivity analysis demonstrates the SH-75 is upstream of the influence of the downstream boundary condition.

4.2.2.5 HYDRAULIC ANALYSIS MANNING’S N SENSITIVITY

The sensitivity of the results to Manning’s n was assessed. The selected hydraulic model input parameters are shown in Table 3. The Manning’s n was changed and simulated for two conditions, an addition of 0.02 (Manning’s n channel = 0.065) and a subtraction of 0.02 (Manning’s n channel = 0.025). These changes were made to bound the range of reasonable roughness coefficients for the studied stream reach. Results show that modifying the Manning’s n coefficient changed the predicted water surface of approximately 0.75 feet. This demonstrates the model sensitivity to the selection of Manning’s n is less than 1.0 feet.

5 Existing Structure

The existing structure is a reinforced concrete stiffleg bridge built in 1929 and extended in 1980 to 48.2 feet wide in the direction of the channel with a clear span of 20 feet (ITD 1979). There are two travel lanes on the structure. The bridge is currently near the end of its design life. The HEC-RAS output for existing conditions is shown in Appendix C.

There are additional structures over Trail Creek near the SH-75 Bridge. The structures are a pedestrian bridge, S Leadville Avenue, and a second pedestrian bridge located upstream of the SH-75 Bridge and the crossing at 2nd Avenue S located downstream of the SH-75 Bridge (Appendix B). Parametrix surveyed these structures as part of the fall 2019 channel survey. The survey information was used to define these structures in the HEC-RAS model as shown in Table 4. The HEC-RAS model simulation predicted Q₅₀ and Q₁₀₀ water surface elevations of 5,802.14 feet and 5,802.64 feet. The existing SH-75 Bridge meets the 2-foot of clearance for the Q₅₀ flow.

Table 4. Summary of Structures in SH-75 Bridge HEC-RAS Model

Structure	Dimensions (Span x Rise x Length) (ft)	Channel Invert at Inlet (ft)	Low Chord Elevation (ft)
Pedestrian Bridge	49.5 x 7.5 x 9.5	5807.8	5815.33
S Leadville Ave Bridge	29.5 x 10.3 x 36	5800.9	5811.14
Pedestrian Bridge	30 x 7.0 x 8.7	5798.5	5805.49
SH-75 Bridge	20 x 9.3 x 48.5	5795.0	5804.31
2 nd Ave S Bridge	44 x 6.8 x 44	5777.4	5784.20

ft = feet

The FIS notes a potential for debris accumulation during high flows (FEMA 2010):

Flooding on Trail Creek would be aggravated by debris collecting behind the many small bridges crossing the channel. This debris would include cottonwood trees, sediment, and material washed away from the many homes located along the streambanks. Historically, all major floods in the Big Wood River basin have been aggravated by such debris accumulation at channel obstructions, resulting in significantly higher water-surface elevations just upstream.

The potential for debris to aggravate flooding on Trail Creek could justify additional clearance at the existing structure.

6 Proposed Structure

6.1 Structure Summary

The proposed structure is a prestressed, concrete-voided, slab bridge that is 62 feet wide measured normal to the roadway centerline with a span of 57.5 feet for a clear opening of 54 feet. A structure summary is provided in Table 5. The cross-section provides a 3-foot horizontal



bench under the bridge abutment, with a 2 to 1 slope to a 3-foot horizontal wildlife bench at an elevation above ordinary high water and 2 to 1 slope that intersects with the existing channel bed cross-section. There is 5.4 feet of clearance from ordinary high water to the low chord that provides the wildlife crossing requirement of 5 feet of clearance.

6.2 Hydraulic Performance

Table 6 summarizes the changes in water surface elevations and velocities for the design flow. Table 7 summarizes these changes considering published floodway encroachments. The HEC-RAS output for proposed conditions is shown in Appendix D. A comparison of the existing and proposed condition results is shown in Appendix E.

Table 5. Summary of Existing and Proposed Structures and Water Surface Elevations Modeled

Structure	Dimensions (Clear Span) (ft)	Channel Invert at Inlet (ft)	Low Chord Elevation (ft)	Headwater Elevation at Q50 of 900 cfs (ft)	Clearance at Q50 of 900 cfs (ft)	Headwater Elevation at Q100 of 1,020 cfs (ft)	Clearance at Q100 of 1,020 cfs (ft)
Existing	20	5795.03	5804.31	5802.14	2.17	5802.64	1.67
Proposed	54	5795.03	5804.91	5801.63	3.28	5801.95	2.96

ft = feet; Q50 = 50-year flow; Q100 = 100-year flow; cfs = cubic feet per second
Ordinary High Water (OHW) Elevation is approximately 5799.6 ft



Table 6. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures

River Station	Flow	WSEs (ft)			Average Velocities (fps)		
		Existing	Proposed	Change	Existing	Proposed	Change
3694	1,020	5815.72	5815.72	0.00	7.27	7.27	0.00
3532	1,020	5814.54	5814.54	0.00	5.42	5.42	0.00
3422	1,020	5813.36	5813.36	0.00	6.89	6.89	0.00
3418	1,020	Existing Structure Pedestrian Bridge					
3404	1,020	5813.15	5813.15	0.00	6.95	6.95	0.00
3304	1,020	5812.87	5812.87	0.00	4.30	4.30	0.00
3252	1,020	5812.07	5812.07	0.00	7.01	7.01	0.00
3189	1,020	5811.66	5811.66	0.00	6.12	6.12	0.00
3140	1,020	5811.23	5811.23	0.00	6.28	6.28	0.00
3008	1,020	5810.05	5810.05	0.00	6.42	6.42	0.00
2881	1,020	5808.95	5808.94	-0.01	6.71	6.72	0.01
2815	1,020	5808.78	5808.77	-0.01	5.56	5.57	0.01
2810	1,020	Existing Structure Leadville Ave Bridge					
2769	1,020	5807.89	5807.86	-0.03	7.22	7.27	0.05
2680	1,020	5807.37	5807.32	-0.05	6.20	6.27	0.07
2550	1,020	5806.48	5806.43	-0.05	6.04	6.19	0.15
2439	1,020	5804.06	5803.97	-0.09	10.07	10.3	0.23
2415	1,020	5804.26	5804.18	-0.08	7.35	7.51	0.16
2407	1,020	Existing Structure Pedestrian Bridge					
2389	1,020	5803.73	5803.54	-0.19	8.06	8.52	0.46
2300	1,020	5803.51	5803.19	-0.32	5.30	5.79	0.49
2247	1,020	5803.39	5802.99	-0.40	4.48	5.02	0.54
2205	1,020	5802.91	5802.14	-0.77	6.07	7.59	1.52
2147	1,020	5802.64	5801.95	-0.69	5.67	5.88	0.21
2135	1,020	Existing/Proposed Structure SH-75 over Trail Creek					
2075	1,020	5800.47	5800.40	-0.07	8.74	9.37	0.63
1984	1,020	5799.71	5799.71	0.00	6.38	6.38	0.00
1824	1,020	5798.03	5798.03	0.00	6.92	6.92	0.00
1769	1,020	5797.63	5797.63	0.00	6.39	6.39	0.00
1719	1,020	5796.96	5796.96	0.00	7.38	7.38	0.00
1524	1,020	5795.31	5795.31	0.00	6.71	6.71	0.00
1463	1,020	5794.53	5794.53	0.00	7.73	7.73	0.00
1414	1,020	5794.07	5794.07	0.00	7.69	7.69	0.00
1349	1,020	5792.89	5792.89	0.00	9.13	9.13	0.00
1239	1,020	5792.24	5792.24	0.00	6.43	6.43	0.00
1200	1,020	5791.73	5791.73	0.00	7.19	7.19	0.00
1114	1,020	5790.81	5790.81	0.00	6.39	6.39	0.00
1050	1,020	5790.02	5790.02	0.00	6.08	6.08	0.00



Table 6. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures

River Station	Flow	WSEs (ft)			Average Velocities (fps)		
		Existing	Proposed	Change	Existing	Proposed	Change
958	1,020	5789.28	5789.28	0.00	5.07	5.07	0.00
936	1,020	5788.92	5788.92	0.00	5.99	5.99	0.00
842	1,020	5788.30	5788.30	0.00	5.63	5.63	0.00
784	1,020	5788.03	5788.03	0.00	5.40	5.40	0.00
643	1,020	5786.82	5786.82	0.00	7.35	7.35	0.00
587	1,020	5786.45	5786.45	0.00	6.87	6.87	0.00
549	1,020	5785.94	5785.94	0.00	7.48	7.48	0.00
482	1,020	5785.46	5785.46	0.00	6.76	6.76	0.00
376	1,020	5784.65	5784.65	0.00	6.81	6.81	0.00
241	1,020	5783.87	5783.87	0.00	5.87	5.87	0.00
162	1,020	5783.33	5783.33	0.00	6.03	6.03	0.00
93	1,020	5783.08	5783.08	0.00	5.07	5.07	0.00
66	1,020	Existing Structure Second Ave Bridge					
-5	1,020	5781.97	5781.97	0.00	7.06	7.06	0.00
-53	1,020	5781.51	5781.51	0.00	6.79	6.79	0.00

WSE = water surface elevation; ft = feet; fps = feet per second



Table 7. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures Considering Floodway Encroachments

River Station	Flow	WSEs (ft)			Average Velocities (fps)		
		Existing	Proposed	Change	Existing	Proposed	Change
3694	1,020	5815.64	5815.64	0.00	7.59	7.59	0.00
3532	1,020	5814.48	5814.48	0.00	5.58	5.58	0.00
3422	1,020	5813.34	5813.34	0.00	6.92	6.92	0.00
3418	1,020	<i>Existing Structure Pedestrian Bridge</i>					
3404	1,020	5813.13	5813.13	0.00	6.98	6.98	0.00
3304	1,020	5812.86	5812.86	0.00	4.38	4.38	0.00
3252	1,020	5812.07	5812.07	0.00	7.01	7.01	0.00
3189	1,020	5811.65	5811.65	0.00	6.18	6.18	0.00
3140	1,020	5811.23	5811.23	0.00	6.28	6.28	0.00
3008	1,020	5810.06	5810.05	-0.01	6.41	6.42	0.01
2881	1,020	5808.96	5808.95	-0.01	6.70	6.71	0.01
2815	1,020	5808.78	5808.78	0.00	5.55	5.56	0.01
2810	1,020	<i>Existing Structure Leadville Ave Bridge</i>					
2769	1,020	5807.90	5807.88	-0.02	7.24	7.28	0.04
2680	1,020	5807.36	5807.32	-0.04	6.21	6.28	0.07
2550	1,020	5806.47	5806.42	-0.05	6.09	6.24	0.15
2439	1,020	5804.04	5803.96	-0.08	10.10	10.33	0.23
2415	1,020	5804.25	5804.17	-0.08	7.37	7.52	0.15
2407	1,020	<i>Existing Structure Pedestrian Bridge</i>					
2389	1,020	5803.71	5803.51	-0.20	8.10	8.57	0.47
2300	1,020	5803.50	5803.16	-0.34	5.38	5.87	0.49
2247	1,020	5803.30	5802.89	-0.41	5.14	5.67	0.53
2205	1,020	5802.91	5802.13	-0.78	6.07	7.63	1.56
2147	1,020	5802.64	5801.90	-0.74	5.67	6.04	0.37
2135	1,020	<i>Existing/Proposed Structure SH-75 over Trail Creek</i>					
2075	1,020	5800.50	5800.48	-0.02	8.68	9.14	0.46
1984	1,020	5799.74	5799.74	0.00	6.67	6.67	0.00
1824	1,020	5798.03	5798.03	0.00	7.35	7.35	0.00
1769	1,020	5797.60	5797.60	0.00	6.80	6.80	0.00
1719	1,020	5796.99	5796.99	0.00	7.41	7.41	0.00
1524	1,020	5795.29	5795.29	0.00	6.94	6.94	0.00
1463	1,020	5794.53	5794.53	0.00	7.80	7.80	0.00
1414	1,020	5794.08	5794.08	0.00	7.67	7.67	0.00
1349	1,020	5793.06	5793.06	0.00	8.73	8.73	0.00
1239	1,020	5792.64	5792.64	0.00	5.83	5.83	0.00
1200	1,020	5792.37	5792.37	0.00	6.01	6.01	0.00
1114	1,020	5791.84	5791.84	0.00	5.83	5.83	0.00
1050	1,020	5790.32	5790.32	0.00	8.93	8.93	0.00



Table 7. Summary of Reach Water Surface Elevations and Velocities with Existing and Proposed Structures Considering Floodway Encroachments

River Station	Flow	WSEs (ft)			Average Velocities (fps)		
		Existing	Proposed	Change	Existing	Proposed	Change
958	1,020	5789.26	5789.26	0.00	5.66	5.66	0.00
936	1,020	5789.08	5789.08	0.00	5.68	5.68	0.00
842	1,020	5788.35	5788.35	0.00	6.00	6.00	0.00
784	1,020	5788.04	5788.04	0.00	5.85	5.85	0.00
643	1,020	5786.82	5786.82	0.00	7.34	7.34	0.00
587	1,020	5786.45	5786.45	0.00	6.86	6.86	0.00
549	1,020	5785.93	5785.93	0.00	7.54	7.54	0.00
482	1,020	5785.46	5785.46	0.00	6.77	6.77	0.00
376	1,020	5784.65	5784.65	0.00	6.82	6.82	0.00
241	1,020	5783.86	5783.86	0.00	5.88	5.88	0.00
162	1,020	5783.32	5783.32	0.00	6.05	6.05	0.00
93	1,020	5783.07	5783.07	0.00	5.11	5.11	0.00
66	1,020	<i>Existing Structure Second Ave Bridge</i>					
-5	1,020	5781.96	5781.96	0.00	7.08	7.08	0.00
-53	1,020	5781.51	5781.51	0.00	6.79	6.79	0.00

WSE = water surface elevation; ft = feet; fps = feet per second

The proposed structure increases the available conveyance area for Trail Creek under SH-75 dramatically. The proposed structure reduces the base flood elevation immediately upstream of SH-75 by almost 0.8 feet with and without floodway encroachments considered. Model results demonstrate that there is not an increase in upstream and downstream flood elevations for the base flood as a result of this project, and that the project meets no-rise criteria.

6.3 Channel Stability Considerations

The existing channel profile was compared to the channel profile documented in the FIS, as shown in Figure 4. There are reaches, notably between model station 2800 and the upstream end of the study reach, where cross-section data from the effective FIS study, dated 1974, indicate the channel thalweg may be up to 2.0 feet lower now than it was in 1974. There is also a reach downstream of the bridge, from model cross-sections 958 and 1114, where the low-flow channel bifurcates and is wider than the floodway. This indicates an area where sedimentation may have occurred since 1974. However, surveyed cross-section inverts at and within 500 feet of the bridge are within 1 foot of the cross-section data from the 1974 hydraulic study. This suggests that the channel is not actively degrading at the existing structure. For this reason, long-term degradation will not be considered in the scour evaluation for the bridge.

The proposed channel modification is only under the bridge and transitions upstream and downstream at elevations to accommodate higher flows. The proposed bridge is designed to accommodate these modifications. This short reach of modifications increases the conveyance capacity of Trail Creek at the bridge, which results in some increases to channel-average

velocity upstream of the bridge. The City of Ketchum requested ITD evaluate the implications on increasing velocity in this reach on channel stability.

The 2-year or ordinary high water event is used to approximate channel-forming event. The existing and proposed velocity for the 2-year event upstream and downstream of the bridge are shown in Table 8.

Table 8. Summary of 2-year Velocity and Top Width Upstream and Downstream of the SH-75 Crossing for Existing and Proposed Conditions

Cross-Section	Existing		Proposed	
	Velocity (fps)	Top Width (ft)	Velocity (fps)	Top Width (ft)
2389	5.97	28.20	5.97	28.20
2300	4.44	37.45	4.45	37.40
2247	4.60	40.91	4.64	40.63
2205	6.10	27.68	6.58	26.66
2147	4.35	27.45	4.32	27.70
SH-75 Bridge				
2075	5.07	31.48	5.94	24.46
1984	4.74	42.61	4.74	42.61
1824	5.56	36.50	5.56	36.50

fps = feet per second; ft = feet

Model results indicate increased channel average velocities of greater than 0.5 feet per second (fps) at one cross-section, 2075. Cross-section 2075 is located 7 feet downstream of the bridge. Bridge construction will include riprap stabilization at this cross-section, placed above OHW. Model results indicate that the section of the river immediately upstream of the bridge may experience increases in velocity up to about 0.5 fps. The section has a cobble bed with banks that have been stabilized by both large rock placed on the banks and by large tree roots (see Photo 6 through Photo 8). There are also areas that appear to have been cleared manually, as is evident by the lack of gravel, tree materials, and plants near the channel.

The rock on the bank in this reach appears to have a D50 between 0.5 feet and 1.0 feet. The Stream Restoration Design National Engineering Handbook Threshold Channel Design (NRCS 2007) estimates sediment sizes between a D50 of 0.5 feet and 1.0 feet would have an allowable velocity (for stability) of 10 to 12 fps, and cobbles to have a permissible velocity (for stability) of 6.5 fps.

To evaluate the safety factor for channel materials, the Colorado State University (CSU) method for evaluating safety factor for various riprap sizes (Simons and Sentunk 1992) was completed for all flows between the 2-year and 500-year. This method evaluates a safety factor for bed and bank materials based on channel geometry as a function of channel geometry, stream slope, and riprap sizing. These evaluations are summarized in Appendix F. This evaluation method indicates that for the 2-year flow, a stream bed with a D50 of about 0.2 feet has a safety factor just under 1.0, and 0.3 feet has a safety factor of 1.4. These grain sizes are consistent with the D50 collected for the project (see Appendix F). A safety factor of 1.0 suggests that bed material



may start to mobilize just above the 2-year flow, which is consistent with expectations for a stable channel. The evaluation also shows that for the 100- and 500-year flows, side slopes protected with rock with a D50 of 0.5 feet has a safety factor of 1.2-1.3, indicating that this material is not likely to mobilize during high flows.

Throughout the entire modeled study reach, 2-year channel average velocities range from 3.75 fps to 6.75 fps and the follow a typical pool-riffle pattern. The channel top width ranges from 23 to 70 feet, with most cross-sections having top widths between 25 and 40 feet.

Based on an evaluation of the site conditions, the CSU stability evaluation, and model results, the channel bed material is not likely to mobilize and degrade during the 2-year event. If bed material were to mobilize and degrade the channel (which is unlikely), the riprap and other large material on the banks would drop into the scour hole, thus maintaining lateral channel stability. Therefore, the lateral stability of the channel is considered high, and the channel is not likely to move laterally as a result of this project.

As stated above, a comparison of channel bottom data from 1974 to 2019 survey data indicates that the channel has not changed more than a foot over the last 50 years. This suggests that the existing channel is stable. The hydraulic model results show a small increase in velocity upstream and downstream of the bridge, but do not indicate the project will significantly alter the hydraulics for the 2-year event in the vicinity of the crossing. Proposed conditions velocities do increase slightly, but are under or roughly equal to the published permissible velocities that minimize sediment movement for the size of materials present in Trail Creek. Historical data and hydraulic results indicate that the vertical channel stability will not be altered by this project.



Photo 6. Reach of Trail Creek Upstream of SH-75 Crossing



Photo 7. Stable natural stream bed and bank rock along the right (north) bank of Trail Creek upstream of the SH-75 Crossing



Photo 8. Bank Protection and Tree Roots along the left (south) bank of Trail Creek Upstream of SH-75 Bridge

6.4 Review of additional conditions

No design constraints, issues, problems, or adverse conditions were identified relating to the need and provisions for fish passage, navigation requirements, need for stream controls to protect highway, effects on stream ecology, and need for emergency supply and evacuation routes.



7 Outlet Protection and Riprap Recommendations

The proposed condition was evaluated to design the necessary scour protection measures. The proposed condition model was used to estimate potential contraction scour depth for the bridge design. Scour calculations were based on the design flow rate of 1,300 cfs as shown in Appendix F. A total contraction scour depth of 0.37 feet was calculated. This depth should be subtracted from the channel thalweg to estimate the design scour elevation of 5794.7 feet. The bridge substructure should be designed to sustain scour to this elevation. As described in Section 6.3, long term degradation is not observed and is not included in the scour analysis. Abutment scour was not considered, both because the abutments will be armored with multi-layer riprap and because the bridge abutments are above the 500-year water surface elevation.

7.1 Riprap Calculations

The abutment wing walls will be aligned with SH-75 due to the limited right-of-way. Riprap shall be applied to the abutment embankment for approximately 10 feet upstream and downstream of the SH-75 Bridge, which may require a permanent easement. Riprap shall have a gradation with the diameter of 50-percent of the particles (D_{50}) of 1.5 feet (18 inches) underlain with filter fabric (HEC-23 2009). Riprap shall extend down to 5794.0 feet, which is below the calculated contraction scour depth. The CSU riprap stability evaluation indicates that this riprap has a safety factor of about 2.0. Refer to Appendix A and Appendix F for the typical section for the riprap channel section. Any channel restoration in areas currently within the footprint of the reinforced concrete stiffleg shall use native material of a gradation similar to existing to reduce the potential for degradation.

The City of Ketchum requested the design team evaluate the feasibility of green or biotechnical alternatives to riprap. Biotechnical solutions are generally used in bank stabilization applications. The Federal Highway Administration's (FHWA) HEC-23 manual discusses biotechnical scour countermeasures:

Biotechnical engineering can be a useful and cost-effective tool in controlling bank or channel erosion, while increasing the aesthetics and habitat diversity of the site. However, where failure of the countermeasure could lead to failure of a bridge or highway structure, the only acceptable solution in the immediate vicinity of a structure is a traditional, "hard" engineering approach.

For this reason, biotechnical alternatives to riprap are not recommended at the bridge abutment. Biological aesthetic treatments, such as willow-plantings or vegetated riprap can be considered.

8 ITD Forms

ITD 210 Form for the hydraulic report is shown in Appendix G. The ITD Bridge Inspection Report is shown in Appendix H.

9 Consistency to Flood Insurance Requirements

The City of Ketchum floodplain administrator has reviewed this hydraulic report and provided a statement of concurrence that the structure, as shown, meets current hydraulic criteria. The City's statement of concurrence and supporting documents are shown in Appendix I. A final permit application should be submitted within 180 days prior to construction. The permit package has been provided to ITD as a separate deliverable.

10 References

- FEMA [Federal Emergency Management Agency]. 2010. Flood Insurance Study. Blaine County, Idaho and Incorporated Areas. Volumes 1 and 2 of 2. Flood Insurance Study Number 16013CV001A. November 26, 2010.
- FEMA [Federal Emergency Management Agency]. 2013. Procedures for "No-Rise" 'Certification For Proposed Developments in the Regulatory Floodway. October 2013.
- FHWA [Federal Highway Administration]. HEC-23 2009. Bridge Scour and Stream Instability Countermeasures: Experience, Selection, and Design Guidance-Third Edition Volume 2.
- Greene, Susan. (Michael Barker International). 2020. "RE: EXTERNAL: RE: FEMA DATA REQUEST". Message to Michael Schubert. March 9, 2020. Email.
- Hortness, J.E., and Berenbrock, Charles, 2001, Estimating Monthly and Annual Streamflow Statistics at Ungaged Sites in Idaho: U.S. Geological Survey Water Resources-Investigations Report 01-4093, 36 p.
- Hortness, J.E., and Berenbrock, Charles, 2004, Estimating the Magnitude of Bankfull Flows for Streams in Idaho: U.S. Geological Survey Water Resources-Investigations Report 03-4261, 37 p.
- Hortness, J.E., 2006, Estimating low-flow frequency statistics for unregulated streams in Idaho: U.S. Geological Survey Scientific Investigations Report 2006-5035, 31 p.
- ITD [Idaho Transportation Department]. 1979. Idaho Transportation Department. Situation and Layout Sheet.
- ITD 2008a. Timmerman to Ketch Environmental Analyses, Project No. STP-F-2392 (035), Key No. 3077, Agreement No. 4718, Concept Report.
- ITD 2008b. Article 2.3.3. Page 1 of 2. 2.3.3 Clearances. April, 2008.
- ITD 2016a. Bridge Inspection Report. Bridge Key 17675 Trail Creek.
- ITD 2016b. Design Manual, Hydraulics, Appendix B, Hydraulics.
- Ketchum [City of Ketchum]. 2014. Chapter 17 Floodplain Overlay District (FP) Ordinance 1120.



Natural Resources Conservation Service (NRCS). 2007. Part 654 Stream Restoration Design National Engineering Handbook. Chapter 8 Threshold Channel Design.

Rea, Alan, and Skinner, K.D., 2009, Estimated perennial streams of Idaho and related geospatial datasets: U.S. Geological Survey Data Series 412, 32 p.

Simons, D.B. and Senturk, F., 1992. "Sediment Transport Technology", Water Resources Publications, LLC.

USACE [U.S. Army Corps of Engineers]. 2016. Hydrologic Engineering Center River Analysis System (HEC-RAS). Institute for Water Resources Hydraulic Engineering Center. Available online: <http://www.hec.usace.army.mil/software/hecras/>

USACE [U.S. Army Corps of Engineers]. 2018. US Army Corps of Engineers Hydrologic Engineering Center, HEC-RAS, <https://www.hec.usace.army.mil/software/hecras/>

USGS [U.S. Geological Survey]. 2009. StreamStats in Idaho. About StreamStats v4.3.11. Additional references include:

Wood, M.S., Rea, Alan, Skinner, K.D., and Hortness, J.E. 2009. Estimating locations of perennial streams in Idaho using a generalized least-squares regression model of 7-day, 2-year low flows: U.S. Geological Survey Scientific Investigations Report 2009-5015, 26 p.

Wood, M.S., Fosness, R.L., Skinner, K.D., and Veilleux, A.G. 2016. Estimating peak-flow frequency statistics for selected gaged and ungaged sites in naturally flowing streams and rivers in Idaho: U.S. Geological Survey Scientific Investigations Report 2016-5083, 56 p.

Zung, Jen. 2020. (Harmony Design & Engineering). "Contact Info". Message to Michael Schubert. February 19, 2020. Email.

Appendix A Site Map with Contours, Type Size and Location

Appendix B. HEC-RAS Model Inputs including Cross-Sections






HEC-RAS plan view of geometric data. Cross-sections shown in existing and proposed appendices. Stream is blue line flowing approximately from north to south. Cross-section locations shown as green lines. Left and right bank shown as red dots. Structures shown as grey rectangles.



Appendix C. HEC-RAS Output: Existing Conditions



Trail_Creek Plan: 1) Existing 7/8/2020



Trail Creek Channel





















































































Trail_Creek Plan: Existing 7/8/2020
 River = Trail Creek Reach = Channel RS = 643







Legend	
EG 500-yr	Green square
EG 100-yr Floodway	Green circle
EG 100-yr	Green 'x'
WS 500-yr	Blue square
EG 50-yr	Green inverted triangle
WS 100-yr Floodway	Blue inverted triangle
WS 100-yr	Blue 'x'
WS 50-yr	Blue inverted triangle
EG 10-yr	Green triangle
WS 10-yr	Blue triangle
EG 2-yr	Green line
WS 2-yr	Blue line
Ground	Black square
Bank Sta	Red circle



Trail_Creek Plan: Existing 7/8/2020
 River = Trail Creek Reach = Channel RS = 587







Legend	
EG 500-yr	Green square
EG 100-yr Floodway	Green circle
EG 100-yr	Green 'x'
WS 500-yr	Blue square
EG 50-yr	Green inverted triangle
WS 100-yr Floodway	Blue inverted triangle
WS 100-yr	Blue 'x'
WS 50-yr	Blue inverted triangle
EG 10-yr	Green triangle
WS 10-yr	Blue triangle
EG 2-yr	Green line
WS 2-yr	Blue line
Ground	Black square
Bank Sta	Red circle











HEC-RAS Plan: Existing River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	2769	2-yr	360.00	5802.88	5805.53	5805.15	5806.08	0.014032	5.99	60.11	30.79	0.76
Channel	2769	10-yr	600.00	5802.88	5806.53	5805.89	5807.17	0.010538	6.40	93.78	37.69	0.69
Channel	2769	50-yr	900.00	5802.88	5807.56	5806.59	5808.31	0.008062	6.94	129.62	42.40	0.64
Channel	2769	100-yr	1020.00	5802.88	5807.89	5806.84	5808.70	0.007781	7.22	141.22	43.88	0.63
Channel	2769	500-yr	1300.00	5802.88	5808.53	5807.35	5809.51	0.007728	7.94	163.68	46.23	0.65
Channel	2769	100-yr Floodway	1020.00	5802.88	5807.90	5806.85	5808.71	0.008241	7.24	140.91	36.10	0.63
Channel	2680	2-yr	360.00	5801.68	5804.75	5803.83	5805.12	0.007042	4.90	73.51	29.71	0.55
Channel	2680	10-yr	600.00	5801.68	5805.92	5804.61	5806.37	0.006045	5.42	110.62	33.81	0.53
Channel	2680	50-yr	900.00	5801.68	5807.03	5805.39	5807.58	0.006047	5.97	150.69	39.92	0.54
Channel	2680	100-yr	1020.00	5801.68	5807.37	5805.69	5807.97	0.006248	6.20	164.57	47.86	0.55
Channel	2680	500-yr	1300.00	5801.68	5808.07	5806.25	5808.77	0.005857	6.70	194.08	67.40	0.55
Channel	2680	100-yr Floodway	1020.00	5801.68	5807.36	5805.69	5807.96	0.006280	6.21	164.32	46.65	0.55
Channel	2550	2-yr	360.00	5798.62	5803.62	5802.49	5804.10	0.008794	5.58	64.53	23.48	0.59
Channel	2550	10-yr	600.00	5798.62	5804.83	5803.60	5805.41	0.009282	6.09	98.47	33.54	0.63
Channel	2550	50-yr	900.00	5798.62	5806.08	5804.66	5806.65	0.008674	6.07	148.37	49.56	0.62
Channel	2550	100-yr	1020.00	5798.62	5806.48	5805.03	5807.05	0.008035	6.04	168.96	53.91	0.60
Channel	2550	500-yr	1300.00	5798.62	5807.41	5805.67	5807.93	0.006249	5.78	225.82	68.84	0.54
Channel	2550	100-yr Floodway	1020.00	5798.62	5806.47	5805.02	5807.04	0.007994	6.09	167.57	51.83	0.60
Channel	2439	2-yr	360.00	5797.78	5802.20	5801.64	5802.87	0.013964	6.54	55.05	22.66	0.74
Channel	2439	10-yr	600.00	5797.78	5803.01	5802.62	5804.02	0.016429	8.08	74.26	24.80	0.82
Channel	2439	50-yr	900.00	5797.78	5803.76	5803.51	5805.20	0.018794	9.63	93.47	26.06	0.90
Channel	2439	100-yr	1020.00	5797.78	5804.06	5803.82	5805.63	0.019105	10.07	101.24	26.51	0.91
Channel	2439	500-yr	1300.00	5797.78	5805.83	5804.50	5806.98	0.010722	8.58	151.49	37.17	0.70
Channel	2439	100-yr Floodway	1020.00	5797.78	5804.04	5803.82	5805.63	0.019269	10.10	100.95	26.50	0.91
Channel	2415	2-yr	360.00	5798.48	5802.06	5801.38	5802.52	0.009819	5.46	65.95	29.23	0.64
Channel	2415	10-yr	600.00	5798.48	5802.97	5802.17	5803.60	0.009849	6.36	94.35	32.80	0.66
Channel	2415	50-yr	900.00	5798.48	5803.90	5802.98	5804.69	0.009485	7.15	125.83	35.11	0.67
Channel	2415	100-yr	1020.00	5798.48	5804.26	5803.25	5805.10	0.009145	7.35	138.80	35.97	0.66
Channel	2415	500-yr	1300.00	5798.48	5806.04	5803.82	5806.65	0.004605	6.31	206.15	40.54	0.49
Channel	2415	100-yr Floodway	1020.00	5798.48	5804.25	5803.21	5805.10	0.009184	7.37	138.43	35.77	0.66
Channel	2407		Bridge									
Channel	2389	2-yr	360.00	5798.91	5801.64	5801.19	5802.20	0.012621	5.97	60.28	28.20	0.72
Channel	2389	10-yr	600.00	5798.91	5802.51	5801.97	5803.26	0.012498	6.98	85.90	31.22	0.74
Channel	2389	50-yr	900.00	5798.91	5803.38	5802.76	5804.34	0.012320	7.86	114.54	34.20	0.76
Channel	2389	100-yr	1020.00	5798.91	5803.73	5803.03	5804.74	0.011597	8.06	126.56	35.49	0.74
Channel	2389	500-yr	1300.00	5798.91	5805.76	5803.62	5806.43	0.004356	6.55	198.49	46.70	0.49
Channel	2389	100-yr Floodway	1020.00	5798.91	5803.71	5803.04	5804.73	0.011777	8.10	125.94	35.43	0.75
Channel	2300	2-yr	360.00	5797.77	5801.02	5800.14	5801.33	0.006695	4.44	81.14	37.45	0.53
Channel	2300	10-yr	600.00	5797.77	5802.05	5800.82	5802.42	0.005739	4.86	123.46	44.08	0.51
Channel	2300	50-yr	900.00	5797.77	5803.09	5801.53	5803.52	0.004989	5.25	171.34	48.69	0.49
Channel	2300	100-yr	1020.00	5797.77	5803.51	5801.80	5803.95	0.004644	5.30	192.36	51.02	0.48
Channel	2300	500-yr	1300.00	5797.77	5805.84	5802.30	5806.08	0.001604	3.99	328.18	96.39	0.30
Channel	2300	100-yr Floodway	1020.00	5797.77	5803.50	5801.77	5803.95	0.004514	5.38	189.42	46.47	0.47
Channel	2247	2-yr	360.00	5797.23	5800.60	5799.90	5800.92	0.008403	4.60	78.26	40.91	0.59
Channel	2247	10-yr	600.00	5797.23	5801.80	5800.58	5802.11	0.005405	4.47	134.36	52.62	0.49
Channel	2247	50-yr	900.00	5797.23	5802.93	5801.23	5803.25	0.003975	4.51	199.36	61.49	0.44
Channel	2247	100-yr	1020.00	5797.23	5803.39	5801.45	5803.70	0.003352	4.48	230.09	71.00	0.41
Channel	2247	500-yr	1300.00	5797.23	5805.84	5801.92	5805.99	0.000920	3.24	449.27	114.45	0.23
Channel	2247	100-yr Floodway	1020.00	5797.23	5803.30	5801.43	5803.71	0.003937	5.14	198.56	45.00	0.43
Channel	2205	2-yr	360.00	5796.09	5799.89	5799.37	5800.46	0.013168	6.10	59.00	27.68	0.74
Channel	2205	10-yr	600.00	5796.09	5801.27	5800.24	5801.81	0.008114	5.91	101.55	34.44	0.61
Channel	2205	50-yr	900.00	5796.09	5802.40	5801.07	5803.00	0.007310	6.21	145.00	42.29	0.59
Channel	2205	100-yr	1020.00	5796.09	5802.91	5801.35	5803.48	0.006872	6.07	168.14	48.65	0.58
Channel	2205	500-yr	1300.00	5796.09	5805.65	5801.98	5805.93	0.001595	4.29	303.00	114.24	0.31
Channel	2205	100-yr Floodway	1020.00	5796.09	5802.91	5801.36	5803.48	0.006872	6.07	168.14	48.65	0.58
Channel	2147	2-yr	360.00	5795.03	5799.61	5798.15	5799.91	0.004495	4.35	82.74	27.45	0.44
Channel	2147	10-yr	600.00	5795.03	5801.04	5799.01	5801.40	0.003902	4.80	124.95	31.61	0.43
Channel	2147	50-yr	900.00	5795.03	5802.14	5799.85	5802.62	0.004385	5.57	161.55	35.55	0.46
Channel	2147	100-yr	1020.00	5795.03	5802.64	5800.17	5803.14	0.004219	5.67	179.91	37.44	0.46
Channel	2147	500-yr	1300.00	5795.03	5805.54	5800.81	5805.84	0.001563	4.38	296.88	76.89	0.29
Channel	2147	100-yr Floodway	1020.00	5795.03	5802.64	5800.13	5803.14	0.004219	5.67	179.91	37.44	0.46
Channel	2135		Bridge									
Channel	2075	2-yr	360.00	5795.28	5798.71	5797.81	5799.11	0.006460	5.07	71.06	31.48	0.54
Channel	2075	10-yr	600.00	5795.28	5799.48	5798.53	5800.16	0.007856	6.59	91.04	40.44	0.62
Channel	2075	50-yr	900.00	5795.28	5800.21	5799.34	5801.25	0.009417	8.18	109.97	45.85	0.70
Channel	2075	100-yr	1020.00	5795.28	5800.47	5799.64	5801.66	0.009938	8.74	116.64	47.80	0.73
Channel	2075	500-yr	1300.00	5795.28	5800.99	5800.27	5802.54	0.011163	9.98	130.29	53.40	0.79
Channel	2075	100-yr Floodway	1020.00	5795.28	5800.50	5799.64	5801.67	0.009696	8.68	117.51	41.53	0.72

HEC-RAS Plan: Existing River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	1984	2-yr	360.00	5794.97	5798.01	5797.48	5798.36	0.009728	4.74	75.92	42.61	0.63
Channel	1984	10-yr	600.00	5794.97	5798.73	5798.09	5799.20	0.009920	5.53	108.57	49.03	0.65
Channel	1984	50-yr	900.00	5794.97	5799.45	5798.71	5800.04	0.009491	6.18	145.70	53.71	0.66
Channel	1984	100-yr	1020.00	5794.97	5799.71	5798.88	5800.34	0.009351	6.38	159.98	55.58	0.66
Channel	1984	500-yr	1300.00	5794.97	5800.29	5799.35	5800.99	0.008476	6.73	195.94	88.60	0.65
Channel	1984	100-yr Floodway	1020.00	5794.97	5799.74	5798.87	5800.44	0.009154	6.67	153.01	47.23	0.65
Channel	1824	2-yr	360.00	5793.50	5796.05	5795.70	5796.53	0.013546	5.56	64.71	36.50	0.74
Channel	1824	10-yr	600.00	5793.50	5796.88	5796.35	5797.48	0.011576	6.22	96.48	40.69	0.71
Channel	1824	50-yr	900.00	5793.50	5797.73	5797.02	5798.44	0.010400	6.75	133.38	45.75	0.70
Channel	1824	100-yr	1020.00	5793.50	5798.03	5797.22	5798.77	0.010091	6.92	147.31	47.46	0.69
Channel	1824	500-yr	1300.00	5793.50	5798.72	5797.76	5799.50	0.010098	7.09	183.44	57.23	0.70
Channel	1824	100-yr Floodway	1020.00	5793.50	5798.03	5797.24	5798.87	0.010253	7.35	138.83	39.02	0.69
Channel	1769	2-yr	360.00	5792.44	5795.57	5794.85	5795.93	0.008224	4.82	74.76	35.62	0.59
Channel	1769	10-yr	600.00	5792.44	5796.43	5795.54	5796.92	0.008118	5.57	107.65	40.60	0.60
Channel	1769	50-yr	900.00	5792.44	5797.32	5796.26	5797.92	0.007630	6.17	145.81	44.56	0.60
Channel	1769	100-yr	1020.00	5792.44	5797.63	5796.49	5798.26	0.007557	6.39	159.57	45.75	0.60
Channel	1769	500-yr	1300.00	5792.44	5798.29	5796.97	5799.01	0.007395	6.82	190.75	70.89	0.61
Channel	1769	100-yr Floodway	1020.00	5792.44	5797.60	5796.52	5798.32	0.008565	6.80	149.91	41.07	0.63
Channel	1719	2-yr	360.00	5791.53	5795.02	5794.45	5795.45	0.010488	5.31	67.82	32.89	0.65
Channel	1719	10-yr	600.00	5791.53	5795.83	5795.15	5796.44	0.010353	6.24	96.09	35.90	0.67
Channel	1719	50-yr	900.00	5791.53	5796.69	5795.87	5797.46	0.010004	7.04	127.83	38.53	0.68
Channel	1719	100-yr	1020.00	5791.53	5796.96	5796.13	5797.80	0.010154	7.38	138.26	39.12	0.69
Channel	1719	500-yr	1300.00	5791.53	5797.53	5796.68	5798.54	0.010486	8.07	161.04	56.75	0.71
Channel	1719	100-yr Floodway	1020.00	5791.53	5796.99	5796.06	5797.84	0.009994	7.41	137.57	37.05	0.68
Channel	1524	2-yr	360.00	5789.62	5792.78	5792.16	5793.30	0.011546	5.78	62.33	28.35	0.69
Channel	1524	10-yr	600.00	5789.62	5793.82	5793.04	5794.44	0.010103	6.33	94.75	33.90	0.67
Channel	1524	50-yr	900.00	5789.62	5794.94	5793.81	5795.61	0.008634	6.58	136.72	178.40	0.64
Channel	1524	100-yr	1020.00	5789.62	5795.31	5794.14	5796.01	0.007980	6.71	152.54	202.29	0.62
Channel	1524	500-yr	1300.00	5789.62	5796.10	5794.71	5796.86	0.006630	6.98	189.67	259.64	0.59
Channel	1524	100-yr Floodway	1020.00	5789.62	5795.29	5794.10	5796.04	0.008238	6.94	147.30	44.30	0.62
Channel	1463	2-yr	360.00	5787.08	5792.32	5791.04	5792.73	0.006894	5.13	70.22	24.26	0.53
Channel	1463	10-yr	600.00	5787.08	5793.25	5792.07	5793.88	0.008508	6.38	94.11	31.16	0.61
Channel	1463	50-yr	900.00	5787.08	5794.19	5793.02	5795.05	0.009475	7.41	121.48	103.48	0.65
Channel	1463	100-yr	1020.00	5787.08	5794.53	5793.35	5795.46	0.009434	7.73	132.71	160.20	0.66
Channel	1463	500-yr	1300.00	5787.08	5795.29	5794.06	5796.36	0.008762	8.32	158.94	253.01	0.65
Channel	1463	100-yr Floodway	1020.00	5787.08	5794.53	5793.27	5795.48	0.009793	7.80	131.39	39.47	0.66
Channel	1414	2-yr	360.00	5788.70	5791.79	5791.22	5792.30	0.011112	5.75	62.56	27.95	0.68
Channel	1414	10-yr	600.00	5788.70	5792.73	5792.01	5793.42	0.010441	6.66	90.03	30.26	0.68
Channel	1414	50-yr	900.00	5788.70	5793.72	5792.80	5794.58	0.009811	7.43	121.07	32.37	0.68
Channel	1414	100-yr	1020.00	5788.70	5794.07	5793.03	5794.99	0.009662	7.69	132.72	33.20	0.68
Channel	1414	500-yr	1300.00	5788.70	5794.90	5793.68	5795.90	0.009491	8.05	161.45	106.32	0.68
Channel	1414	100-yr Floodway	1020.00	5788.70	5794.08	5793.08	5795.00	0.009554	7.67	132.95	32.78	0.67
Channel	1349	2-yr	360.00	5787.23	5791.29	5790.10	5791.71	0.007022	5.23	68.90	24.05	0.54
Channel	1349	10-yr	600.00	5787.23	5792.01	5791.11	5792.75	0.010189	6.88	87.20	26.46	0.67
Channel	1349	50-yr	900.00	5787.23	5792.67	5792.03	5793.80	0.013690	8.54	105.35	28.71	0.79
Channel	1349	100-yr	1020.00	5787.23	5792.89	5792.26	5794.18	0.014981	9.13	111.70	29.43	0.83
Channel	1349	500-yr	1300.00	5787.23	5793.38	5793.03	5795.01	0.018229	10.26	126.76	48.34	0.92
Channel	1349	100-yr Floodway	1020.00	5787.23	5793.06	5792.38	5794.24	0.013315	8.73	116.82	30.12	0.78
Channel	1239	2-yr	360.00	5787.81	5790.77	5789.80	5791.00	0.004915	3.87	93.80	59.26	0.46
Channel	1239	10-yr	600.00	5787.81	5791.42	5790.42	5791.79	0.005829	4.94	122.88	67.63	0.52
Channel	1239	50-yr	900.00	5787.81	5792.04	5791.02	5792.60	0.006654	6.03	151.93	73.15	0.58
Channel	1239	100-yr	1020.00	5787.81	5792.24	5791.23	5792.88	0.006993	6.43	161.87	74.32	0.60
Channel	1239	500-yr	1300.00	5787.81	5792.68	5791.68	5793.50	0.007703	7.29	183.15	76.74	0.64
Channel	1239	100-yr Floodway	1020.00	5787.81	5792.64	5791.23	5793.16	0.005226	5.83	176.72	66.24	0.51
Channel	1200	2-yr	360.00	5786.77	5790.46		5790.76	0.007767	4.34	82.95	44.52	0.56
Channel	1200	10-yr	600.00	5786.77	5791.02		5791.50	0.009151	5.54	109.29	49.70	0.63
Channel	1200	50-yr	900.00	5786.77	5791.56		5792.26	0.010493	6.74	137.21	54.88	0.70
Channel	1200	100-yr	1020.00	5786.77	5791.73		5792.53	0.011081	7.19	146.67	56.35	0.72
Channel	1200	500-yr	1300.00	5786.77	5792.08		5793.10	0.012359	8.17	166.88	58.47	0.78
Channel	1200	100-yr Floodway	1020.00	5786.77	5792.37		5792.93	0.006507	6.01	169.68	45.71	0.55
Channel	1114	2-yr	360.00	5786.95	5789.69		5789.97	0.010840	4.23	85.01	61.31	0.63
Channel	1114	10-yr	600.00	5786.95	5790.16		5790.59	0.012193	5.23	114.73	65.76	0.70
Channel	1114	50-yr	900.00	5786.95	5790.64		5791.22	0.013222	6.08	148.01	71.80	0.75
Channel	1114	100-yr	1020.00	5786.95	5790.81		5791.44	0.013348	6.39	159.69	72.40	0.76
Channel	1114	500-yr	1300.00	5786.95	5791.18		5791.93	0.013236	6.97	186.61	73.58	0.77
Channel	1114	100-yr Floodway	1020.00	5786.95	5791.84		5792.37	0.006416	5.83	174.97	47.00	0.53
Channel	1050	2-yr	360.00	5786.60	5788.88		5789.18	0.014416	4.34	83.02	71.48	0.71
Channel	1050	10-yr	600.00	5786.60	5789.34		5789.76	0.013725	5.16	116.35	74.30	0.73
Channel	1050	50-yr	900.00	5786.60	5789.83		5790.36	0.013086	5.87	153.24	77.49	0.74
Channel	1050	100-yr	1020.00	5786.60	5790.02		5790.59	0.012652	6.08	167.90	78.60	0.73

HEC-RAS Plan: Existing River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	1050	500-yr	1300.00	5786.60	5790.46		5791.09	0.011731	6.37	204.03	83.91	0.72
Channel	1050	100-yr Floodway	1020.00	5786.62	5790.32	5790.32	5791.56	0.026717	8.93	114.21	46.82	1.01
Channel	958	2-yr	360.00	5785.00	5787.74	5787.20	5788.01	0.011265	4.14	86.85	66.27	0.64
Channel	958	10-yr	600.00	5785.00	5788.32	5787.80	5788.67	0.009996	4.72	127.22	73.03	0.63
Channel	958	50-yr	900.00	5785.00	5789.02	5788.26	5789.40	0.007850	4.99	180.33	79.11	0.58
Channel	958	100-yr	1020.00	5785.00	5789.28	5788.42	5789.68	0.007242	5.07	201.09	80.86	0.57
Channel	958	500-yr	1300.00	5785.00	5789.87	5788.77	5790.29	0.005919	5.20	249.81	84.46	0.53
Channel	958	100-yr Floodway	1020.00	5785.00	5789.26	5788.43	5789.75	0.008120	5.66	180.19	63.21	0.59
Channel	936	2-yr	360.00	5785.06	5787.52		5787.78	0.008223	4.09	88.09	54.58	0.57
Channel	936	10-yr	600.00	5785.06	5788.01		5788.43	0.010089	5.20	115.30	57.80	0.65
Channel	936	50-yr	900.00	5785.06	5788.67		5789.20	0.009079	5.81	155.46	65.29	0.64
Channel	936	100-yr	1020.00	5785.06	5788.92		5789.48	0.008505	5.99	172.49	70.56	0.63
Channel	936	500-yr	1300.00	5785.06	5789.52		5790.12	0.007146	6.24	215.64	73.72	0.60
Channel	936	100-yr Floodway	1020.00	5785.06	5789.08		5789.58	0.007136	5.68	179.78	61.21	0.58
Channel	842	2-yr	360.00	5783.60	5785.74	5785.74	5786.45	0.027415	6.75	53.34	38.47	1.01
Channel	842	10-yr	600.00	5783.60	5786.88		5787.41	0.011679	5.84	102.66	47.99	0.70
Channel	842	50-yr	900.00	5783.60	5787.94		5788.43	0.007246	5.61	164.72	66.28	0.58
Channel	842	100-yr	1020.00	5783.60	5788.30		5788.78	0.006244	5.63	188.64	68.25	0.55
Channel	842	500-yr	1300.00	5783.60	5789.04		5789.54	0.004960	5.76	240.50	71.66	0.51
Channel	842	100-yr Floodway	1020.00	5783.60	5788.35		5788.91	0.007034	6.00	170.07	48.82	0.57
Channel	784	2-yr	360.00	5780.62	5785.49		5785.75	0.004572	4.10	87.87	33.14	0.44
Channel	784	10-yr	600.00	5780.62	5786.61		5786.95	0.004504	4.68	128.10	39.04	0.46
Channel	784	50-yr	900.00	5780.62	5787.68		5788.09	0.004165	5.20	175.46	50.35	0.45
Channel	784	100-yr	1020.00	5780.62	5788.03		5788.49	0.004007	5.40	194.54	56.33	0.45
Channel	784	500-yr	1300.00	5780.62	5788.78		5789.29	0.003754	5.79	244.50	76.20	0.45
Channel	784	100-yr Floodway	1020.00	5780.62	5788.04		5788.57	0.004829	5.85	174.26	36.08	0.47
Channel	643	2-yr	360.00	5780.66	5784.52		5784.93	0.007304	5.16	69.71	26.50	0.56
Channel	643	10-yr	600.00	5780.66	5785.53		5786.11	0.007706	6.12	97.97	29.62	0.59
Channel	643	50-yr	900.00	5780.66	5786.49		5787.26	0.008195	7.03	128.04	32.66	0.63
Channel	643	100-yr	1020.00	5780.66	5786.82		5787.66	0.008407	7.35	138.85	33.70	0.64
Channel	643	500-yr	1300.00	5780.66	5787.46		5788.47	0.008656	8.06	163.38	41.90	0.66
Channel	643	100-yr Floodway	1020.00	5780.66	5786.82		5787.66	0.008377	7.34	139.03	33.72	0.64
Channel	587	2-yr	360.00	5780.43	5784.10		5784.51	0.007882	5.11	70.49	29.14	0.58
Channel	587	10-yr	600.00	5780.43	5785.14		5785.67	0.007435	5.84	102.67	32.86	0.58
Channel	587	50-yr	900.00	5780.43	5786.12		5786.80	0.007443	6.59	136.58	36.23	0.60
Channel	587	100-yr	1020.00	5780.43	5786.45		5787.18	0.007595	6.87	148.56	37.55	0.61
Channel	587	500-yr	1300.00	5780.43	5787.08		5787.95	0.008549	7.48	173.91	42.39	0.65
Channel	587	100-yr Floodway	1020.00	5780.43	5786.45		5787.18	0.007564	6.86	148.80	37.59	0.61
Channel	549	2-yr	360.00	5779.68	5783.49		5784.10	0.013092	6.27	57.40	25.10	0.73
Channel	549	10-yr	600.00	5779.68	5784.57		5785.29	0.011845	6.83	87.82	31.31	0.72
Channel	549	50-yr	900.00	5779.68	5785.62		5786.44	0.010708	7.28	123.65	37.14	0.70
Channel	549	100-yr	1020.00	5779.68	5785.94		5786.81	0.011229	7.48	136.35	40.87	0.72
Channel	549	500-yr	1300.00	5779.68	5786.59		5787.56	0.011411	7.90	164.64	46.15	0.74
Channel	549	100-yr Floodway	1020.00	5779.68	5785.93		5786.82	0.011196	7.54	135.31	39.33	0.72
Channel	482	2-yr	360.00	5778.50	5783.16	5781.61	5783.50	0.005248	4.66	77.18	26.04	0.48
Channel	482	10-yr	600.00	5778.50	5784.17	5782.65	5784.67	0.006331	5.69	105.46	30.28	0.54
Channel	482	50-yr	900.00	5778.50	5785.16	5783.60	5785.81	0.007297	6.46	140.01	63.06	0.59
Channel	482	100-yr	1020.00	5778.50	5785.46	5783.92	5786.17	0.007339	6.76	152.46	104.12	0.59
Channel	482	500-yr	1300.00	5778.50	5786.07	5784.69	5786.93	0.007410	7.46	177.89	119.01	0.61
Channel	482	100-yr Floodway	1020.00	5778.50	5785.46	5783.93	5786.17	0.007342	6.77	152.44	49.76	0.59
Channel	376	2-yr	360.00	5778.47	5782.49	5781.51	5782.86	0.006906	4.84	74.43	30.08	0.54
Channel	376	10-yr	600.00	5778.47	5783.42	5782.33	5783.94	0.007466	5.76	104.22	34.23	0.58
Channel	376	50-yr	900.00	5778.47	5784.35	5783.11	5785.01	0.007730	6.53	137.94	39.88	0.61
Channel	376	100-yr	1020.00	5778.47	5784.65	5783.41	5785.37	0.007704	6.81	150.75	44.52	0.61
Channel	376	500-yr	1300.00	5778.47	5785.28	5784.03	5786.13	0.007511	7.41	178.79	119.76	0.62
Channel	376	100-yr Floodway	1020.00	5778.47	5784.65	5783.41	5785.37	0.007716	6.82	150.66	44.48	0.61
Channel	241	2-yr	360.00	5778.25	5781.58	5780.73	5781.91	0.007004	4.58	78.56	35.80	0.55
Channel	241	10-yr	600.00	5778.25	5782.57	5781.45	5782.98	0.006315	5.15	116.48	40.80	0.54
Channel	241	50-yr	900.00	5778.25	5783.55	5782.15	5784.05	0.005967	5.67	158.81	45.83	0.54
Channel	241	100-yr	1020.00	5778.25	5783.87	5782.39	5784.40	0.006008	5.87	173.63	47.63	0.54
Channel	241	500-yr	1300.00	5778.25	5784.55	5782.93	5785.16	0.005952	6.26	207.70	51.18	0.55
Channel	241	100-yr Floodway	1020.00	5778.25	5783.86	5782.40	5784.40	0.006037	5.88	173.33	47.59	0.54
Channel	162	2-yr	360.00	5777.50	5781.09	5779.97	5781.40	0.005703	4.47	80.49	32.20	0.50
Channel	162	10-yr	600.00	5777.50	5782.06	5780.76	5782.49	0.006009	5.26	114.01	36.98	0.53
Channel	162	50-yr	900.00	5777.50	5783.01	5781.56	5783.54	0.006638	5.84	154.05	46.14	0.56
Channel	162	100-yr	1020.00	5777.50	5783.33	5781.83	5783.90	0.006591	6.03	169.17	48.04	0.57
Channel	162	500-yr	1300.00	5777.50	5784.03	5782.48	5784.66	0.006682	6.34	205.04	54.63	0.58
Channel	162	100-yr Floodway	1020.00	5777.50	5783.32	5781.83	5783.89	0.006657	6.05	168.58	47.98	0.57
Channel	93	2-yr	360.00	5777.38	5780.77	5779.63	5781.02	0.005024	4.01	89.71	38.74	0.46

HEC-RAS Plan: Existing River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	93	10-yr	600.00	5777.38	5781.76	5780.36	5782.08	0.005084	4.55	131.95	47.46	0.48
Channel	93	50-yr	900.00	5777.38	5782.74	5781.02	5783.12	0.004658	4.93	182.54	62.74	0.47
Channel	93	100-yr	1020.00	5777.38	5783.08	5781.29	5783.48	0.004532	5.07	201.04	78.00	0.47
Channel	93	500-yr	1300.00	5777.38	5783.79	5781.89	5784.24	0.004365	5.36	242.57	222.15	0.47
Channel	93	100-yr Floodway	1020.00	5777.38	5783.07	5781.32	5783.47	0.004417	5.11	199.59	53.21	0.47
Channel	66	Bridge										
Channel	-5	2-yr	360.00	5776.76	5779.82	5779.26	5780.29	0.010643	5.49	65.52	30.86	0.66
Channel	-5	10-yr	600.00	5776.76	5780.68	5779.98	5781.31	0.010770	6.42	93.53	56.63	0.69
Channel	-5	50-yr	900.00	5776.76	5781.62	5780.76	5782.37	0.010397	6.94	129.59	121.01	0.70
Channel	-5	100-yr	1020.00	5776.76	5781.97	5781.05	5782.74	0.010161	7.06	144.50	139.41	0.69
Channel	-5	500-yr	1300.00	5776.76	5782.68	5781.67	5783.51	0.009351	7.27	178.74	176.16	0.68
Channel	-5	100-yr Floodway	1020.00	5776.76	5781.96	5781.05	5782.74	0.010034	7.08	144.11	43.83	0.69
Channel	-53	2-yr	360.00	5776.13	5779.33	5778.70	5779.78	0.010002	5.36	67.22	31.56	0.65
Channel	-53	10-yr	600.00	5776.13	5780.19	5779.45	5780.80	0.010015	6.24	96.15	35.72	0.67
Channel	-53	50-yr	900.00	5776.13	5781.15	5780.20	5781.86	0.010010	6.74	133.45	51.64	0.68
Channel	-53	100-yr	1020.00	5776.13	5781.51	5780.46	5782.23	0.010001	6.79	150.20	78.26	0.69
Channel	-53	500-yr	1300.00	5776.13	5782.27	5781.12	5782.98	0.010002	6.75	192.97	171.21	0.69
Channel	-53	100-yr Floodway	1020.00	5776.13	5781.51	5780.46	5782.23	0.010001	6.79	150.20	49.22	0.69


HEC-RAS Plan: Existing River: Trail Creek Reach: Channel

Reach	River Sta	Profile	E.G. US. (ft)	Min El Prs (ft)	BR Open Area (sq ft)	Prs O WS (ft)	Q Total (cfs)	Min El Weir Flow (ft)	Q Weir (cfs)	Delta EG (ft)	BR Sluice Coef
Channel	3418	2-yr	5811.55	5816.70	275.60		360.00	5816.67		0.19	
Channel	3418	10-yr	5812.60	5816.70	275.60		600.00	5816.67		0.20	
Channel	3418	50-yr	5813.70	5816.70	275.60		900.00	5816.67		0.19	
Channel	3418	100-yr	5814.09	5816.70	275.60		1020.00	5816.67		0.20	
Channel	3418	500-yr	5814.86	5816.70	275.60		1300.00	5816.67		0.21	
Channel	3418	100-yr Floodway	5814.09	5816.70	267.28		1020.00	5816.90		0.20	
Channel	2810	2-yr	5806.47	5811.81	221.26		360.00	5812.13		0.38	
Channel	2810	10-yr	5807.60	5811.81	221.26		600.00	5812.13		0.43	
Channel	2810	50-yr	5808.82	5811.81	221.26		900.00	5812.13		0.52	
Channel	2810	100-yr	5809.26	5811.81	221.26		1020.00	5812.13		0.56	
Channel	2810	500-yr	5810.18	5811.81	221.26		1300.00	5812.13		0.67	
Channel	2810	100-yr Floodway	5809.26	5811.81	221.26		1020.00	5812.13		0.55	
Channel	2407	2-yr	5802.52	5808.51	213.90		360.00	5807.91		0.33	
Channel	2407	10-yr	5803.60	5808.51	213.90		600.00	5807.91		0.33	
Channel	2407	50-yr	5804.69	5808.51	213.90		900.00	5807.91		0.35	
Channel	2407	100-yr	5805.10	5808.51	213.90		1020.00	5807.91		0.36	
Channel	2407	500-yr	5806.65	5808.51	213.90		1300.00	5807.91		0.22	
Channel	2407	100-yr Floodway	5805.10	5808.51	213.90		1020.00	5807.91		0.36	
Channel	2135	2-yr	5799.91	5804.50	166.28		360.00	5808.42		0.79	
Channel	2135	10-yr	5801.40	5804.50	166.28		600.00	5808.42		1.24	
Channel	2135	50-yr	5802.62	5804.50	166.28		900.00	5808.42		1.37	
Channel	2135	100-yr	5803.14	5804.50	166.28		1020.00	5808.42		1.48	
Channel	2135	500-yr	5805.84	5804.50	166.28	5805.54	1300.00	5808.42		3.30	0.41
Channel	2135	100-yr Floodway	5803.14	5804.50	166.28		1020.00	5808.42		1.47	
Channel	66	2-yr	5781.02	5784.28	240.55		360.00	5787.62		0.73	
Channel	66	10-yr	5782.08	5784.28	240.55		600.00	5787.62		0.76	
Channel	66	50-yr	5783.12	5784.28	240.55		900.00	5787.62		0.74	
Channel	66	100-yr	5783.48	5784.28	240.55		1020.00	5787.62		0.73	
Channel	66	500-yr	5784.24	5784.28	240.55		1300.00	5787.62		0.73	
Channel	66	100-yr Floodway	5783.47	5784.28	240.55		1020.00	5787.62		0.73	



Appendix D. HEC-RAS Output: Proposed Conditions



Trail_Creek Plan: Proposed 7/8/2020



Trail Creek Channel







Legend	
EG 500-yr	(Green dashed line with square markers)
WS 500-yr	(Blue solid line with square markers)
EG 100-yr	(Green dashed line with triangle markers)
EG 100-yr Floodway	(Green dashed line with inverted triangle markers)
EG 50-yr	(Green dashed line with inverted triangle markers)
WS 100-yr	(Blue solid line with cross markers)
WS 100-yr Floodway	(Blue solid line with inverted triangle markers)
WS 50-yr	(Blue solid line with inverted triangle markers)
Crit 500-yr	(Red dotted line with square markers)
EG 10-yr	(Green dashed line with triangle markers)
Crit 100-yr	(Red dotted line with cross markers)
Crit 100-yr Floodway	(Red dotted line with inverted triangle markers)
Crit 50-yr	(Red dotted line with inverted triangle markers)
WS 10-yr	(Blue solid line with triangle markers)
EG 2-yr	(Green dashed line with triangle markers)
Crit 10-yr	(Red dotted line with triangle markers)
WS 2-yr	(Blue solid line with triangle markers)
Crit 2-yr	(Red dotted line with cross markers)
Ground	(Black solid line with square markers)

















Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 3008







Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 2881























































Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 1114




Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 1050






Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 643







Legend	
EG 500-yr	Green square
EG 100-yr Floodway	Green circle
EG 100-yr	Green 'x'
WS 500-yr	Blue square
EG 50-yr	Green inverted triangle
WS 100-yr Floodway	Blue inverted triangle
WS 100-yr	Blue 'x'
WS 50-yr	Blue inverted triangle
EG 10-yr	Green triangle
WS 10-yr	Blue triangle
EG 2-yr	Green 'x'
WS 2-yr	Blue line
Ground	Black square
Bank Sta	Red circle



Trail_Creek Plan: Proposed 7/8/2020
 River = Trail Creek Reach = Channel RS = 587







Legend	
EG 500-yr	Green square
EG 100-yr Floodway	Green circle
EG 100-yr	Green 'x'
WS 500-yr	Blue square
EG 50-yr	Green inverted triangle
WS 100-yr Floodway	Blue inverted triangle
WS 100-yr	Blue 'x'
WS 50-yr	Blue inverted triangle
EG 10-yr	Green triangle
WS 10-yr	Blue triangle
EG 2-yr	Green 'x'
WS 2-yr	Blue line
Ground	Black square
Bank Sta	Red circle











HEC-RAS Plan: PRP River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	2769	2-yr	360.00	5802.88	5805.53	5805.15	5806.08	0.014032	5.99	60.11	30.79	0.76
Channel	2769	10-yr	600.00	5802.88	5806.53	5805.89	5807.17	0.010531	6.40	93.80	37.70	0.69
Channel	2769	50-yr	900.00	5802.88	5807.54	5806.59	5808.30	0.008165	6.97	129.12	42.32	0.64
Channel	2769	100-yr	1020.00	5802.88	5807.86	5806.84	5808.68	0.007940	7.27	140.37	43.76	0.64
Channel	2769	500-yr	1300.00	5802.88	5808.47	5807.35	5809.47	0.008080	8.05	161.51	45.87	0.66
Channel	2769	100-yr Floodway	1020.00	5802.88	5807.88	5806.85	5808.70	0.008398	7.28	140.08	36.09	0.64
Channel	2680	2-yr	360.00	5801.68	5804.75	5803.83	5805.12	0.007042	4.90	73.51	29.71	0.55
Channel	2680	10-yr	600.00	5801.68	5805.92	5804.61	5806.37	0.006042	5.42	110.64	33.81	0.53
Channel	2680	50-yr	900.00	5801.68	5807.00	5805.39	5807.57	0.006160	6.01	149.68	39.62	0.55
Channel	2680	100-yr	1020.00	5801.68	5807.32	5805.69	5807.94	0.006497	6.27	162.65	45.80	0.56
Channel	2680	500-yr	1300.00	5801.68	5807.97	5806.25	5808.70	0.006310	6.85	189.79	62.88	0.57
Channel	2680	100-yr Floodway	1020.00	5801.68	5807.32	5805.69	5807.93	0.006533	6.28	162.38	44.83	0.56
Channel	2550	2-yr	360.00	5798.62	5803.62	5802.49	5804.10	0.008794	5.58	64.53	23.48	0.59
Channel	2550	10-yr	600.00	5798.62	5804.83	5803.60	5805.41	0.009264	6.09	98.57	33.57	0.63
Channel	2550	50-yr	900.00	5798.62	5806.06	5804.66	5806.64	0.008404	6.12	147.00	49.24	0.61
Channel	2550	100-yr	1020.00	5798.62	5806.43	5805.03	5807.03	0.007581	6.19	164.76	53.18	0.59
Channel	2550	500-yr	1300.00	5798.62	5807.23	5805.67	5807.86	0.006195	6.39	204.11	64.19	0.55
Channel	2550	100-yr Floodway	1020.00	5798.62	5806.42	5805.02	5807.02	0.007540	6.24	163.51	51.23	0.58
Channel	2439	2-yr	360.00	5797.78	5802.20	5801.64	5802.87	0.013964	6.54	55.05	22.66	0.74
Channel	2439	10-yr	600.00	5797.78	5803.00	5802.62	5804.02	0.016603	8.11	73.99	24.78	0.83
Channel	2439	50-yr	900.00	5797.78	5803.72	5803.51	5805.19	0.019369	9.73	92.51	26.01	0.91
Channel	2439	100-yr	1020.00	5797.78	5803.97	5803.82	5805.62	0.020405	10.30	98.98	26.38	0.94
Channel	2439	500-yr	1300.00	5797.78	5804.55	5804.50	5806.55	0.021769	11.35	114.51	27.33	0.98
Channel	2439	100-yr Floodway	1020.00	5797.78	5803.96	5803.82	5805.62	0.020552	10.33	98.74	26.36	0.94
Channel	2415	2-yr	360.00	5798.48	5802.06	5801.38	5802.52	0.009819	5.46	65.95	29.23	0.64
Channel	2415	10-yr	600.00	5798.48	5802.96	5802.17	5803.59	0.009989	6.39	93.90	32.76	0.67
Channel	2415	50-yr	900.00	5798.48	5803.86	5802.98	5804.67	0.009779	7.23	124.53	35.02	0.68
Channel	2415	100-yr	1020.00	5798.48	5804.18	5803.25	5805.06	0.009727	7.51	135.90	35.79	0.68
Channel	2415	500-yr	1300.00	5798.48	5804.93	5803.82	5805.91	0.009286	7.96	163.33	37.61	0.67
Channel	2415	100-yr Floodway	1020.00	5798.48	5804.17	5803.21	5805.05	0.009776	7.52	135.62	35.72	0.68
Channel	2407		Bridge									
Channel	2389	2-yr	360.00	5798.91	5801.64	5801.19	5802.20	0.012638	5.97	60.25	28.20	0.72
Channel	2389	10-yr	600.00	5798.91	5802.47	5801.97	5803.25	0.013020	7.08	84.70	31.09	0.76
Channel	2389	50-yr	900.00	5798.91	5803.26	5802.76	5804.29	0.013686	8.16	110.36	33.75	0.80
Channel	2389	100-yr	1020.00	5798.91	5803.54	5803.03	5804.66	0.013769	8.52	119.76	34.77	0.80
Channel	2389	500-yr	1300.00	5798.91	5804.10	5803.62	5805.45	0.013942	9.32	139.46	36.86	0.83
Channel	2389	100-yr Floodway	1020.00	5798.91	5803.51	5803.04	5804.65	0.014055	8.57	118.97	34.68	0.81
Channel	2300	2-yr	360.00	5797.77	5801.01	5800.14	5801.32	0.006753	4.45	80.89	37.40	0.53
Channel	2300	10-yr	600.00	5797.77	5801.94	5800.82	5802.34	0.006505	5.07	118.39	43.64	0.54
Channel	2300	50-yr	900.00	5797.77	5802.87	5801.53	5803.36	0.005958	5.60	160.80	47.51	0.54
Channel	2300	100-yr	1020.00	5797.77	5803.19	5801.80	5803.71	0.005943	5.79	176.10	49.27	0.54
Channel	2300	500-yr	1300.00	5797.77	5803.86	5802.30	5804.45	0.005923	6.18	210.30	55.14	0.55
Channel	2300	100-yr Floodway	1020.00	5797.77	5803.16	5801.77	5803.70	0.005903	5.87	173.83	46.47	0.53
Channel	2247	2-yr	360.00	5797.23	5800.58	5799.90	5800.91	0.008570	4.64	77.59	40.63	0.59
Channel	2247	10-yr	600.00	5797.23	5801.62	5800.58	5801.98	0.006527	4.79	125.26	50.87	0.54
Channel	2247	50-yr	900.00	5797.23	5802.65	5801.23	5803.03	0.005208	4.93	182.39	59.67	0.50
Channel	2247	100-yr	1020.00	5797.23	5802.99	5801.45	5803.39	0.004814	5.02	203.20	63.45	0.48
Channel	2247	500-yr	1300.00	5797.23	5803.71	5801.92	5804.14	0.004154	5.23	253.59	74.80	0.46
Channel	2247	100-yr Floodway	1020.00	5797.23	5802.89	5801.43	5803.39	0.005345	5.67	179.98	45.00	0.50
Channel	2205	2-yr	360.00	5796.09	5799.73	5799.37	5800.40	0.016113	6.58	54.70	26.66	0.81
Channel	2205	10-yr	600.00	5796.09	5800.86	5800.24	5801.58	0.011924	6.82	87.94	32.10	0.73
Channel	2205	50-yr	900.00	5796.09	5801.82	5801.07	5802.67	0.011432	7.39	121.71	38.15	0.73
Channel	2205	100-yr	1020.00	5796.09	5802.14	5801.35	5803.04	0.011401	7.59	134.41	40.47	0.73
Channel	2205	500-yr	1300.00	5796.09	5802.85	5801.98	5803.81	0.011616	7.87	165.19	47.94	0.75
Channel	2205	100-yr Floodway	1020.00	5796.09	5802.13	5801.36	5803.03	0.011577	7.63	133.64	40.35	0.74
Channel	2147	2-yr	360.00	5795.03	5799.55	5798.08	5799.84	0.004494	4.32	83.42	27.70	0.44
Channel	2147	10-yr	600.00	5795.03	5800.65	5798.89	5801.03	0.005365	4.95	121.13	37.80	0.49
Channel	2147	50-yr	900.00	5795.03	5801.63	5799.97	5802.12	0.005448	5.62	160.11	41.72	0.51
Channel	2147	100-yr	1020.00	5795.03	5801.95	5800.24	5802.48	0.005571	5.88	173.55	42.99	0.52
Channel	2147	500-yr	1300.00	5795.03	5802.62	5800.77	5803.25	0.005812	6.40	203.14	45.66	0.53
Channel	2147	100-yr Floodway	1020.00	5795.03	5801.90	5800.24	5802.47	0.005717	6.04	168.80	39.41	0.51
Channel	2135		Bridge									
Channel	2075	2-yr	360.00	5795.28	5798.79		5799.34	0.010517	5.94	60.64	24.46	0.66
Channel	2075	10-yr	600.00	5795.28	5799.49		5800.39	0.014177	7.62	78.73	27.17	0.79
Channel	2075	50-yr	900.00	5795.28	5800.20	5800.08	5801.42	0.019737	8.87	101.43	36.00	0.93
Channel	2075	100-yr	1020.00	5795.28	5800.40	5800.30	5801.77	0.020696	9.37	108.81	36.81	0.96
Channel	2075	500-yr	1300.00	5795.28	5800.90	5800.90	5802.51	0.021319	10.20	127.51	38.79	0.99
Channel	2075	100-yr Floodway	1020.00	5795.28	5800.48	5800.33	5801.78	0.019245	9.14	111.59	37.11	0.93

HEC-RAS Plan: PRP River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	1984	2-yr	360.00	5794.97	5798.01	5797.48	5798.36	0.009728	4.74	75.92	42.61	0.63
Channel	1984	10-yr	600.00	5794.97	5798.73	5798.09	5799.20	0.009920	5.53	108.57	49.03	0.65
Channel	1984	50-yr	900.00	5794.97	5799.45	5798.71	5800.04	0.009491	6.18	145.70	53.71	0.66
Channel	1984	100-yr	1020.00	5794.97	5799.71	5798.88	5800.34	0.009351	6.38	159.98	55.58	0.66
Channel	1984	500-yr	1300.00	5794.97	5800.29	5799.35	5800.99	0.008476	6.73	195.94	88.60	0.65
Channel	1984	100-yr Floodway	1020.00	5794.97	5799.74	5798.87	5800.44	0.009154	6.67	153.01	47.23	0.65
Channel	1824	2-yr	360.00	5793.50	5796.05	5795.70	5796.53	0.013546	5.56	64.71	36.50	0.74
Channel	1824	10-yr	600.00	5793.50	5796.88	5796.35	5797.48	0.011576	6.22	96.48	40.69	0.71
Channel	1824	50-yr	900.00	5793.50	5797.73	5797.02	5798.44	0.010400	6.75	133.38	45.75	0.70
Channel	1824	100-yr	1020.00	5793.50	5798.03	5797.22	5798.77	0.010091	6.92	147.31	47.46	0.69
Channel	1824	500-yr	1300.00	5793.50	5798.72	5797.76	5799.50	0.010098	7.09	183.44	57.23	0.70
Channel	1824	100-yr Floodway	1020.00	5793.50	5798.03	5797.24	5798.87	0.010253	7.35	138.83	39.02	0.69
Channel	1769	2-yr	360.00	5792.44	5795.57	5794.85	5795.93	0.008224	4.82	74.76	35.62	0.59
Channel	1769	10-yr	600.00	5792.44	5796.43	5795.54	5796.92	0.008118	5.57	107.65	40.60	0.60
Channel	1769	50-yr	900.00	5792.44	5797.32	5796.26	5797.92	0.007630	6.17	145.81	44.56	0.60
Channel	1769	100-yr	1020.00	5792.44	5797.63	5796.49	5798.26	0.007557	6.39	159.57	45.75	0.60
Channel	1769	500-yr	1300.00	5792.44	5798.29	5796.97	5799.01	0.007395	6.82	190.75	70.89	0.61
Channel	1769	100-yr Floodway	1020.00	5792.44	5797.60	5796.52	5798.32	0.008565	6.80	149.91	41.07	0.63
Channel	1719	2-yr	360.00	5791.53	5795.02	5794.45	5795.45	0.010488	5.31	67.82	32.89	0.65
Channel	1719	10-yr	600.00	5791.53	5795.83	5795.15	5796.44	0.010353	6.24	96.09	35.90	0.67
Channel	1719	50-yr	900.00	5791.53	5796.69	5795.87	5797.46	0.010004	7.04	127.83	38.53	0.68
Channel	1719	100-yr	1020.00	5791.53	5796.96	5796.13	5797.80	0.010154	7.38	138.26	39.12	0.69
Channel	1719	500-yr	1300.00	5791.53	5797.53	5796.68	5798.54	0.010486	8.07	161.04	56.75	0.71
Channel	1719	100-yr Floodway	1020.00	5791.53	5796.99	5796.06	5797.84	0.009994	7.41	137.57	37.05	0.68
Channel	1524	2-yr	360.00	5789.62	5792.78	5792.16	5793.30	0.011546	5.78	62.33	28.35	0.69
Channel	1524	10-yr	600.00	5789.62	5793.82	5793.04	5794.44	0.010103	6.33	94.75	33.90	0.67
Channel	1524	50-yr	900.00	5789.62	5794.94	5793.81	5795.61	0.008634	6.58	136.72	178.40	0.64
Channel	1524	100-yr	1020.00	5789.62	5795.31	5794.14	5796.01	0.007980	6.71	152.54	202.29	0.62
Channel	1524	500-yr	1300.00	5789.62	5796.10	5794.71	5796.86	0.006630	6.98	189.67	259.64	0.59
Channel	1524	100-yr Floodway	1020.00	5789.62	5795.29	5794.10	5796.04	0.008238	6.94	147.30	44.30	0.62
Channel	1463	2-yr	360.00	5787.08	5792.32	5791.04	5792.73	0.006894	5.13	70.22	24.26	0.53
Channel	1463	10-yr	600.00	5787.08	5793.25	5792.07	5793.88	0.008508	6.38	94.11	31.16	0.61
Channel	1463	50-yr	900.00	5787.08	5794.19	5793.02	5795.05	0.009475	7.41	121.48	103.48	0.65
Channel	1463	100-yr	1020.00	5787.08	5794.53	5793.35	5795.46	0.009434	7.73	132.71	160.20	0.66
Channel	1463	500-yr	1300.00	5787.08	5795.29	5794.06	5796.36	0.008762	8.32	158.94	253.01	0.65
Channel	1463	100-yr Floodway	1020.00	5787.08	5794.53	5793.27	5795.48	0.009793	7.80	131.39	39.47	0.66
Channel	1414	2-yr	360.00	5788.70	5791.79	5791.22	5792.30	0.011112	5.75	62.56	27.95	0.68
Channel	1414	10-yr	600.00	5788.70	5792.73	5792.01	5793.42	0.010441	6.66	90.03	30.26	0.68
Channel	1414	50-yr	900.00	5788.70	5793.72	5792.80	5794.58	0.009811	7.43	121.07	32.37	0.68
Channel	1414	100-yr	1020.00	5788.70	5794.07	5793.03	5794.99	0.009662	7.69	132.72	33.20	0.68
Channel	1414	500-yr	1300.00	5788.70	5794.90	5793.68	5795.90	0.009491	8.05	161.45	106.32	0.68
Channel	1414	100-yr Floodway	1020.00	5788.70	5794.08	5793.08	5795.00	0.009554	7.67	132.95	32.78	0.67
Channel	1349	2-yr	360.00	5787.23	5791.29	5790.10	5791.71	0.007022	5.23	68.90	24.05	0.54
Channel	1349	10-yr	600.00	5787.23	5792.01	5791.11	5792.75	0.010189	6.88	87.20	26.46	0.67
Channel	1349	50-yr	900.00	5787.23	5792.67	5792.03	5793.80	0.013690	8.54	105.35	28.71	0.79
Channel	1349	100-yr	1020.00	5787.23	5792.89	5792.26	5794.18	0.014981	9.13	111.70	29.43	0.83
Channel	1349	500-yr	1300.00	5787.23	5793.38	5793.03	5795.01	0.018229	10.26	126.76	48.34	0.92
Channel	1349	100-yr Floodway	1020.00	5787.23	5793.06	5792.38	5794.24	0.013315	8.73	116.82	30.12	0.78
Channel	1239	2-yr	360.00	5787.81	5790.77	5789.80	5791.00	0.004915	3.87	93.80	59.26	0.46
Channel	1239	10-yr	600.00	5787.81	5791.42	5790.42	5791.79	0.005829	4.94	122.88	67.63	0.52
Channel	1239	50-yr	900.00	5787.81	5792.04	5791.02	5792.60	0.006654	6.03	151.93	73.15	0.58
Channel	1239	100-yr	1020.00	5787.81	5792.24	5791.23	5792.88	0.006993	6.43	161.87	74.32	0.60
Channel	1239	500-yr	1300.00	5787.81	5792.68	5791.68	5793.50	0.007703	7.29	183.15	76.74	0.64
Channel	1239	100-yr Floodway	1020.00	5787.81	5792.64	5791.23	5793.16	0.005226	5.83	176.72	66.24	0.51
Channel	1200	2-yr	360.00	5786.77	5790.46		5790.76	0.007767	4.34	82.95	44.52	0.56
Channel	1200	10-yr	600.00	5786.77	5791.02		5791.50	0.009151	5.54	109.29	49.70	0.63
Channel	1200	50-yr	900.00	5786.77	5791.56		5792.26	0.010493	6.74	137.21	54.88	0.70
Channel	1200	100-yr	1020.00	5786.77	5791.73		5792.53	0.011081	7.19	146.67	56.35	0.72
Channel	1200	500-yr	1300.00	5786.77	5792.08		5793.10	0.012359	8.17	166.88	58.47	0.78
Channel	1200	100-yr Floodway	1020.00	5786.77	5792.37		5792.93	0.006507	6.01	169.68	45.71	0.55
Channel	1114	2-yr	360.00	5786.95	5789.69		5789.97	0.010840	4.23	85.01	61.31	0.63
Channel	1114	10-yr	600.00	5786.95	5790.16		5790.59	0.012193	5.23	114.73	65.76	0.70
Channel	1114	50-yr	900.00	5786.95	5790.64		5791.22	0.013222	6.08	148.01	71.80	0.75
Channel	1114	100-yr	1020.00	5786.95	5790.81		5791.44	0.013348	6.39	159.69	72.40	0.76
Channel	1114	500-yr	1300.00	5786.95	5791.18		5791.93	0.013236	6.97	186.61	73.58	0.77
Channel	1114	100-yr Floodway	1020.00	5786.95	5791.84		5792.37	0.006416	5.83	174.97	47.00	0.53
Channel	1050	2-yr	360.00	5786.60	5788.88		5789.18	0.014416	4.34	83.02	71.48	0.71
Channel	1050	10-yr	600.00	5786.60	5789.34		5789.76	0.013725	5.16	116.35	74.30	0.73
Channel	1050	50-yr	900.00	5786.60	5789.83		5790.36	0.013086	5.87	153.24	77.49	0.74
Channel	1050	100-yr	1020.00	5786.60	5790.02		5790.59	0.012652	6.08	167.90	78.60	0.73

HEC-RAS Plan: PRP River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	1050	500-yr	1300.00	5786.60	5790.46		5791.09	0.011731	6.37	204.03	83.91	0.72
Channel	1050	100-yr Floodway	1020.00	5786.62	5790.32	5790.32	5791.56	0.026717	8.93	114.21	46.82	1.01
Channel	958	2-yr	360.00	5785.00	5787.74	5787.20	5788.01	0.011265	4.14	86.85	66.27	0.64
Channel	958	10-yr	600.00	5785.00	5788.32	5787.80	5788.67	0.009996	4.72	127.22	73.03	0.63
Channel	958	50-yr	900.00	5785.00	5789.02	5788.26	5789.40	0.007850	4.99	180.33	79.11	0.58
Channel	958	100-yr	1020.00	5785.00	5789.28	5788.42	5789.68	0.007242	5.07	201.09	80.86	0.57
Channel	958	500-yr	1300.00	5785.00	5789.87	5788.77	5790.29	0.005919	5.20	249.81	84.46	0.53
Channel	958	100-yr Floodway	1020.00	5785.00	5789.26	5788.43	5789.75	0.008120	5.66	180.19	63.21	0.59
Channel	936	2-yr	360.00	5785.06	5787.52		5787.78	0.008223	4.09	88.09	54.58	0.57
Channel	936	10-yr	600.00	5785.06	5788.01		5788.43	0.010089	5.20	115.30	57.80	0.65
Channel	936	50-yr	900.00	5785.06	5788.67		5789.20	0.009079	5.81	155.46	65.29	0.64
Channel	936	100-yr	1020.00	5785.06	5788.92		5789.48	0.008505	5.99	172.49	70.56	0.63
Channel	936	500-yr	1300.00	5785.06	5789.52		5790.12	0.007146	6.24	215.64	73.72	0.60
Channel	936	100-yr Floodway	1020.00	5785.06	5789.08		5789.58	0.007136	5.68	179.78	61.21	0.58
Channel	842	2-yr	360.00	5783.60	5785.74	5785.74	5786.45	0.027415	6.75	53.34	38.47	1.01
Channel	842	10-yr	600.00	5783.60	5786.88		5787.41	0.011679	5.84	102.66	47.99	0.70
Channel	842	50-yr	900.00	5783.60	5787.94		5788.43	0.007246	5.61	164.72	66.28	0.58
Channel	842	100-yr	1020.00	5783.60	5788.30		5788.78	0.006244	5.63	188.64	68.25	0.55
Channel	842	500-yr	1300.00	5783.60	5789.04		5789.54	0.004960	5.76	240.50	71.66	0.51
Channel	842	100-yr Floodway	1020.00	5783.60	5788.35		5788.91	0.007034	6.00	170.07	48.82	0.57
Channel	784	2-yr	360.00	5780.62	5785.49		5785.75	0.004572	4.10	87.87	33.14	0.44
Channel	784	10-yr	600.00	5780.62	5786.61		5786.95	0.004504	4.68	128.10	39.04	0.46
Channel	784	50-yr	900.00	5780.62	5787.68		5788.09	0.004165	5.20	175.46	50.35	0.45
Channel	784	100-yr	1020.00	5780.62	5788.03		5788.49	0.004007	5.40	194.54	56.33	0.45
Channel	784	500-yr	1300.00	5780.62	5788.78		5789.29	0.003754	5.79	244.50	76.20	0.45
Channel	784	100-yr Floodway	1020.00	5780.62	5788.04		5788.57	0.004829	5.85	174.26	36.08	0.47
Channel	643	2-yr	360.00	5780.66	5784.52		5784.93	0.007304	5.16	69.71	26.50	0.56
Channel	643	10-yr	600.00	5780.66	5785.53		5786.11	0.007706	6.12	97.97	29.62	0.59
Channel	643	50-yr	900.00	5780.66	5786.49		5787.26	0.008195	7.03	128.04	32.66	0.63
Channel	643	100-yr	1020.00	5780.66	5786.82		5787.66	0.008407	7.35	138.85	33.70	0.64
Channel	643	500-yr	1300.00	5780.66	5787.46		5788.47	0.008656	8.06	163.38	41.90	0.66
Channel	643	100-yr Floodway	1020.00	5780.66	5786.82		5787.66	0.008377	7.34	139.03	33.72	0.64
Channel	587	2-yr	360.00	5780.43	5784.10		5784.51	0.007882	5.11	70.49	29.14	0.58
Channel	587	10-yr	600.00	5780.43	5785.14		5785.67	0.007435	5.84	102.67	32.86	0.58
Channel	587	50-yr	900.00	5780.43	5786.12		5786.80	0.007443	6.59	136.58	36.23	0.60
Channel	587	100-yr	1020.00	5780.43	5786.45		5787.18	0.007595	6.87	148.56	37.55	0.61
Channel	587	500-yr	1300.00	5780.43	5787.08		5787.95	0.008549	7.48	173.91	42.39	0.65
Channel	587	100-yr Floodway	1020.00	5780.43	5786.45		5787.18	0.007564	6.86	148.80	37.59	0.61
Channel	549	2-yr	360.00	5779.68	5783.49		5784.10	0.013092	6.27	57.40	25.10	0.73
Channel	549	10-yr	600.00	5779.68	5784.57		5785.29	0.011845	6.83	87.82	31.31	0.72
Channel	549	50-yr	900.00	5779.68	5785.62		5786.44	0.010708	7.28	123.65	37.14	0.70
Channel	549	100-yr	1020.00	5779.68	5785.94		5786.81	0.011229	7.48	136.35	40.87	0.72
Channel	549	500-yr	1300.00	5779.68	5786.59		5787.56	0.011411	7.90	164.64	46.15	0.74
Channel	549	100-yr Floodway	1020.00	5779.68	5785.93		5786.82	0.011196	7.54	135.31	39.33	0.72
Channel	482	2-yr	360.00	5778.50	5783.16	5781.61	5783.50	0.005248	4.66	77.18	26.04	0.48
Channel	482	10-yr	600.00	5778.50	5784.17	5782.65	5784.67	0.006331	5.69	105.46	30.28	0.54
Channel	482	50-yr	900.00	5778.50	5785.16	5783.60	5785.81	0.007297	6.46	140.01	63.06	0.59
Channel	482	100-yr	1020.00	5778.50	5785.46	5783.92	5786.17	0.007339	6.76	152.46	104.12	0.59
Channel	482	500-yr	1300.00	5778.50	5786.07	5784.69	5786.93	0.007410	7.46	177.89	119.01	0.61
Channel	482	100-yr Floodway	1020.00	5778.50	5785.46	5783.93	5786.17	0.007342	6.77	152.44	49.76	0.59
Channel	376	2-yr	360.00	5778.47	5782.49	5781.51	5782.86	0.006906	4.84	74.43	30.08	0.54
Channel	376	10-yr	600.00	5778.47	5783.42	5782.33	5783.94	0.007466	5.76	104.22	34.23	0.58
Channel	376	50-yr	900.00	5778.47	5784.35	5783.11	5785.01	0.007730	6.53	137.94	39.88	0.61
Channel	376	100-yr	1020.00	5778.47	5784.65	5783.41	5785.37	0.007704	6.81	150.75	44.52	0.61
Channel	376	500-yr	1300.00	5778.47	5785.28	5784.03	5786.13	0.007511	7.41	178.79	119.76	0.62
Channel	376	100-yr Floodway	1020.00	5778.47	5784.65	5783.41	5785.37	0.007716	6.82	150.66	44.48	0.61
Channel	241	2-yr	360.00	5778.25	5781.58	5780.73	5781.91	0.007004	4.58	78.56	35.80	0.55
Channel	241	10-yr	600.00	5778.25	5782.57	5781.45	5782.98	0.006315	5.15	116.48	40.80	0.54
Channel	241	50-yr	900.00	5778.25	5783.55	5782.15	5784.05	0.005967	5.67	158.81	45.83	0.54
Channel	241	100-yr	1020.00	5778.25	5783.87	5782.39	5784.40	0.006008	5.87	173.63	47.63	0.54
Channel	241	500-yr	1300.00	5778.25	5784.55	5782.93	5785.16	0.005952	6.26	207.70	51.18	0.55
Channel	241	100-yr Floodway	1020.00	5778.25	5783.86	5782.40	5784.40	0.006037	5.88	173.33	47.59	0.54
Channel	162	2-yr	360.00	5777.50	5781.09	5779.97	5781.40	0.005703	4.47	80.49	32.20	0.50
Channel	162	10-yr	600.00	5777.50	5782.06	5780.76	5782.49	0.006009	5.26	114.01	36.98	0.53
Channel	162	50-yr	900.00	5777.50	5783.01	5781.56	5783.54	0.006638	5.84	154.05	46.14	0.56
Channel	162	100-yr	1020.00	5777.50	5783.33	5781.83	5783.90	0.006591	6.03	169.17	48.04	0.57
Channel	162	500-yr	1300.00	5777.50	5784.03	5782.48	5784.66	0.006682	6.34	205.04	54.63	0.58
Channel	162	100-yr Floodway	1020.00	5777.50	5783.32	5781.83	5783.89	0.006657	6.05	168.58	47.98	0.57
Channel	93	2-yr	360.00	5777.38	5780.77	5779.63	5781.02	0.005024	4.01	89.71	38.74	0.46

HEC-RAS Plan: PRP River: Trail Creek Reach: Channel (Continued)

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Channel	93	10-yr	600.00	5777.38	5781.76	5780.36	5782.08	0.005084	4.55	131.95	47.46	0.48
Channel	93	50-yr	900.00	5777.38	5782.74	5781.02	5783.12	0.004658	4.93	182.54	62.74	0.47
Channel	93	100-yr	1020.00	5777.38	5783.08	5781.29	5783.48	0.004532	5.07	201.04	78.00	0.47
Channel	93	500-yr	1300.00	5777.38	5783.79	5781.89	5784.24	0.004365	5.36	242.57	222.15	0.47
Channel	93	100-yr Floodway	1020.00	5777.38	5783.07	5781.32	5783.47	0.004417	5.11	199.59	53.21	0.47
Channel	66	Bridge										
Channel	-5	2-yr	360.00	5776.76	5779.82	5779.26	5780.29	0.010643	5.49	65.52	30.86	0.66
Channel	-5	10-yr	600.00	5776.76	5780.68	5779.98	5781.31	0.010770	6.42	93.53	56.63	0.69
Channel	-5	50-yr	900.00	5776.76	5781.62	5780.76	5782.37	0.010397	6.94	129.59	121.01	0.70
Channel	-5	100-yr	1020.00	5776.76	5781.97	5781.05	5782.74	0.010161	7.06	144.50	139.41	0.69
Channel	-5	500-yr	1300.00	5776.76	5782.68	5781.67	5783.51	0.009351	7.27	178.74	176.16	0.68
Channel	-5	100-yr Floodway	1020.00	5776.76	5781.96	5781.05	5782.74	0.010034	7.08	144.11	43.83	0.69
Channel	-53	2-yr	360.00	5776.13	5779.33	5778.70	5779.78	0.010002	5.36	67.22	31.56	0.65
Channel	-53	10-yr	600.00	5776.13	5780.19	5779.45	5780.80	0.010015	6.24	96.15	35.72	0.67
Channel	-53	50-yr	900.00	5776.13	5781.15	5780.20	5781.86	0.010010	6.74	133.45	51.64	0.68
Channel	-53	100-yr	1020.00	5776.13	5781.51	5780.46	5782.23	0.010001	6.79	150.20	78.26	0.69
Channel	-53	500-yr	1300.00	5776.13	5782.27	5781.12	5782.98	0.010002	6.75	192.97	171.21	0.69
Channel	-53	100-yr Floodway	1020.00	5776.13	5781.51	5780.46	5782.23	0.010001	6.79	150.20	49.22	0.69

HEC-RAS Plan: PRP River: Trail Creek Reach: Channel


Reach	River Sta	Profile	E.G. US. (ft)	Min El Prs (ft)	BR Open Area (sq ft)	Prs O WS (ft)	Q Total (cfs)	Min El Weir Flow (ft)	Q Weir (cfs)	Delta EG (ft)	BR Sluice Coef
Channel	3418	2-yr	5811.55	5816.70	275.60		360.00	5816.67		0.19	
Channel	3418	10-yr	5812.60	5816.70	275.60		600.00	5816.67		0.20	
Channel	3418	50-yr	5813.70	5816.70	275.60		900.00	5816.67		0.19	
Channel	3418	100-yr	5814.09	5816.70	275.60		1020.00	5816.67		0.20	
Channel	3418	500-yr	5814.86	5816.70	275.60		1300.00	5816.67		0.21	
Channel	3418	100-yr Floodway	5814.09	5816.70	267.28		1020.00	5816.90		0.20	
Channel	2810	2-yr	5806.47	5811.81	221.26		360.00	5812.13		0.38	
Channel	2810	10-yr	5807.60	5811.81	221.26		600.00	5812.13		0.43	
Channel	2810	50-yr	5808.82	5811.81	221.26		900.00	5812.13		0.52	
Channel	2810	100-yr	5809.25	5811.81	221.26		1020.00	5812.13		0.56	
Channel	2810	500-yr	5810.17	5811.81	221.26		1300.00	5812.13		0.69	
Channel	2810	100-yr Floodway	5809.26	5811.81	221.26		1020.00	5812.13		0.56	
Channel	2407	2-yr	5802.52	5808.51	213.90		360.00	5807.91		0.33	
Channel	2407	10-yr	5803.59	5808.51	213.90		600.00	5807.91		0.34	
Channel	2407	50-yr	5804.67	5808.51	213.90		900.00	5807.91		0.38	
Channel	2407	100-yr	5805.06	5808.51	213.90		1020.00	5807.91		0.39	
Channel	2407	500-yr	5805.91	5808.51	213.90		1300.00	5807.91		0.46	
Channel	2407	100-yr Floodway	5805.05	5808.51	213.90		1020.00	5807.91		0.40	
Channel	2135	2-yr	5799.84	5804.50	319.45		360.00	5809.37		0.50	
Channel	2135	10-yr	5801.03	5804.50	319.45		600.00	5809.37		0.64	
Channel	2135	50-yr	5802.12	5804.50	319.45		900.00	5809.37		0.70	
Channel	2135	100-yr	5802.48	5804.50	319.45		1020.00	5809.37		0.72	
Channel	2135	500-yr	5803.25	5804.50	319.45		1300.00	5809.37		0.74	
Channel	2135	100-yr Floodway	5802.47	5804.50	293.13		1020.00	5811.42		0.70	
Channel	66	2-yr	5781.02	5784.28	240.55		360.00	5787.62		0.73	
Channel	66	10-yr	5782.08	5784.28	240.55		600.00	5787.62		0.76	
Channel	66	50-yr	5783.12	5784.28	240.55		900.00	5787.62		0.74	
Channel	66	100-yr	5783.48	5784.28	240.55		1020.00	5787.62		0.73	
Channel	66	500-yr	5784.24	5784.28	240.55		1300.00	5787.62		0.73	
Channel	66	100-yr Floodway	5783.47	5784.28	240.55		1020.00	5787.62		0.73	

Appendix E. HEC-RAS Output: Existing vs. Proposed Conditions

Trail_Creek Plan: 1) Existing 7/8/2020 2) PRP 7/8/2020

Trail Creek Channel

Elevation (ft)



Legend

EG 100-yr - Existing

EG 100-yr - PRP

WS 100-yr - PRP

WS 100-yr - Existing


Crit 100-yr - Existing

Crit 100-yr - PRP

Ground

Appendix F Scour and Riprap

4420-150-00 Date Exported: 12/10/2019



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

Symbol	Stream Bed Samples	Depth (feet)	Moisture (%)	Soil Description
◆	S-1 & S2 (Blend)	Surface	N/A	Gravel with Cobbles (GP)
■	S-3 & S-4 (Blend)	Surface	N/A	Gravel with Cobbles (GP)

Note: This report may not be reproduced, except in full, without written approval of GeoEngineers, Inc. Test results are applicable only to the specific sample on which they were performed, and should not be interpreted as representative of any other samples obtained at other times, depths or locations, or generated by separate operations or processes.

The grain size analysis results were obtained in general accordance with ASTM D 6913. Test completed by Strata located in Boise, Idaho.



Figure D-8

Steve Analysis Results
 SH-75, Elkhorn Road to River Street, Ketchum
 ITD Project No. A020(033); Key No. 20033
 Blaine County, Idaho



Project: SH-75 Trail Creek
Subject: Scour
Task: Calculations
Job #:

Computed: MK
Checked: MS
Page: 1
No:

Date: 7/8/2020
Date: 7/8/2020
of: 5

Scour Calculation Results

Reference HEC 18, 5th Edition

Design Year: **500**

Clear-Water contraction scour will exist. Use the Clear-Water analysis.

Do Coarse Bed Conditions Exist? **NO** ("YES" or "NO")

Contractions Scour Results:

If Clear-Water Governs 0.37 ft

If Live-Bed Governs, Minimum of ysLB and ysCW 1.61 ft

500-yr Contraction Scour: 0.37 feet

Does Vertical Contractions Scour Occur? **No** ("YES" or "NO")

--

-- --

-- --

-- --

Are there piers within the 500-year floodplain? **No** ("YES" or "NO")

-- --

Riprap Size at Abutments: D50 = 1.5 Ft

-- --

500-yr Scour Results (ft)			
Scour Type	Abutment 1	Abutment 2	Pier
Contraction Scour	0.37	0.37	--
Vertical Contraction Scour	--	--	--
Local Scour	--	--	--
Total Scour	0.37	0.37	0.00

Notes: (1) Local abutment scour calculations are not required when the substructure is protected with multi-layered riprap protection. (2) If multi-layered riprap protection is proposed at the piers the local pier scour depth may be reduced by 50%.



Project: SH-75 Trail Creek
 Subject: Scour
 Task: Calculations
 Job #: 0

Computed: MK
 Checked: MS
 Page: 3
 No:


Date: 7/8/20
 Date: 7/8/20
 of: 5

Scour 500-yr

Streambed Particle Size (D_{50}): 1.500 in.
 38.100 mm
 0.1250 ft.

Determined by: Visual Inspection
 Note: Set minimum D_{50} to 0.2mm (0.008-inch) for low flow

Upstream Uncontracted Cross Section (XS1):	2247	Length to XS1:	41.80 ft.
Internal Upstream Cross Section (XS2):	2135	Length to XS3:	57.90 ft.
Upstream Bounding Cross Section (XS3):	2205	Low Chord Elevation:	5804.91 ft.
Long-term aggradation / degradation:	0.0 ft.	Water Surface Elevation:	5802.60 ft.
		Streambed Elevation:	5795.03 ft.



Key	
1.	Upstream uncontracted cross section (XS output)
2.	Internal bridge cross section (BR U or BR D in HEC-RAS output)
3.	Upstream bounding cross section (XS output)

Determine Clear-Water or Live-Bed Flow Conditions

K_u coefficient (Enter 6.19 for SI units or 11.17 for English Units): 11.17
 Channel Hydraulic Depth Variable (from XS1), y : 3.97 ft.
 Channel Velocity (from XS1), V : 5.230 ft./s

V_c is the critical velocity. Speeds at or above this level will transport bed material of D_{50} and smaller. Use Equation 6.1 (HEC-18):

$$V_c = K_u y^{1/6} (D_{50})^{1/3} \quad V_c = 7.028 \text{ ft./s}$$

If $V_c < V$ Live-Bed Scour Occurs
 If $V_c > V$ Clear-Water Scour Occurs

Clear-Water contraction scour will exist. Use the Clear-Water analysis.

K_u Coefficient (Enter 0.25 for SI units or 0.0077 for English Units): 0.0077
 W, W_1, W_2 values are taken at: at top of channel
 For Vertical Contraction Scour:
 Does overtopping of the bridge or approach roadway occur? No
 T Superstructure Depth (including girders, deck and parapet): 2.50 ft.



Project: SH-75 Trail Creek
Subject: Scour
Task: Calculations
Job #: 0

Computed: MK
Checked: MS
Page: 4
No:

Date: 7/8/20
Date: 7/8/20
of: 5

Contraction Scour 500-yr

Clear-Water Scour (GOVERNS)

K_u	Coefficient (Enter 0.25 for SI units or 0.0077 for English Units):	0.0077	
y₀	Hydraulic Depth Variable (from XS2):	3.69	ft
W	Estimated bottom or top channel width, less pier widths (XS2):	41.25	ft at top of channel
Q	Flow through the bridge opening, or on the set-back over bank area at the bridge associated with the width, W (from XS2):	1300	cfs
D_m	Diameter of the smallest nontransportable particle in the bed material, 1.25 * D ₅₀ :	0.15625	ft
y₂	Average depth in the contracted section: Equation 6.4 (HEC-18)	$y_2 = \left[\frac{0.0077Q^2}{D_m^{2/3} W^2} \right]^{3/7}$	4.06 ft
y_s	Average contraction scour depth: Equation 6.5 (HEC-18)	$y_s = y_2 - y_0$	0.37 ft



Project: SH-75 Trail Creek
Subject: Scour
Task: Calculations
Job #: 0

Computed: MK
Checked: MS
Page: 5
No:

Date: 7/8/20
Date: 7/8/20
of: 5

Riprap Sizing 100 year

Type of Abutment:

Vertical

HEC-23 Rip Rap Sizing for Vertical or Spill Through Abutments

fr $V/(gy)^{1/2} \leq 0.80$ $D_{50} = y*(K/(S_s-1))*(V^2/gy)$

K spill through abutment = 0.89
vertical wall abutment = 1.02

fr $V/(gy)^{1/2} > 0.80$ $D_{50} = y*(K/(S_s-1))*(V^2/gy)^{0.14}$

K spill through abutment = 0.61
vertical wall abutment = 0.69

Where:

fr (froude number at XS2) 0.78

Abutment type (spill through or vertical wall) Vertical

K 1.02

y Depth of flow in the contracted bridge opening (depth from XS2) 4.01 ft

V As described above for Abutments or Piers: 7.97 ft/s

S Specific Gravity: 2.65

g Gravity Constant (Enter 9.81 m/s² for SI or 32.2 ft/s² for English): 32.2 ft/s²

D₅₀ 1.22 ft

D₅₀ 15 in

Recommended Riprap Abutment Size per ITD Riprap Table: D50 = 18 inches



Determine Safety Factor of Riprap Design using CSU Method (Safety Factor vs Riprap Size)
 (Simons, D.B. and Senturk, F., "Sediment Transport Technology", Water Resources Publications, LLC, 1992)

Project: SH-75 Bridge over Trail Creek
Project No.: 20033
Location: Ketchum, ID
Designer: Mike Schubert, PE
 HDR Engineering, Inc.

Given:

Flow in Channel:	360	cfs
Channel Slope, S:	0.01	ft/ft
Bed slope angle, q:	0.572939	degrees
Unit Weight of Water (γ_w):	62.4	lb/ft ³
Channel Bottom, b:	26	ft
Channel Side Slopes, zH:1V	3	
Riprap Angle of repose:	37	degrees
Riprap Angle of repose:	0.646	radians
Specific Gravity of Riprap:	2.65	
$\alpha = \text{atan}(1/z)$	0.321751	radians
α :	18.435	degrees
Φ , material angle of repose, degrees	41.000	degrees


-----> θ : 0.0100 radians

-----> Φ : 0.7156 radians

Determine safety factor for riprap on channel bed:

Iterate depth until Calculated Q matches Actual Q

	(EQN)	Calculated	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	
Depth	D_{50}	Q	$n(D_{50})$	$C(D_{50})$	$d_n(D_{50})$	$A(D_{50})$	$V(D_{50})$	$P(D_{50})$	$R(D_{50})$	$\tau(D_{50})$	$\eta_b(D_{50})$	$SF_b(D_{50})$	
0	1.4977	0.100	360.000	0.027	65.195	1.4977	45.669	7.883	26.000	1.756	0.935	1.906	0.521
1	1.5820	0.200	360.000	0.030	73.179	1.5820	48.639	7.402	26.000	1.871	0.987	1.007	0.982
2	1.6333	0.300	360.000	0.032	78.295	1.6333	50.470	7.133	26.000	1.941	1.019	0.693	1.420
3	1.6707	0.400	360.000	0.034	82.141	1.6707	51.813	6.948	26.000	1.993	1.043	0.532	1.841
4	1.7003	0.500	360.000	0.035	85.253	1.7003	52.881	6.808	26.000	2.034	1.061	0.433	2.251
5	1.7248	0.600	360.000	0.036	87.883	1.7248	53.771	6.695	26.000	2.068	1.076	0.366	2.650
6	1.7642	0.800	360.000	0.038	92.200	1.7642	55.207	6.521	26.000	2.123	1.101	0.281	3.422
7	1.7954	1.000	360.000	0.040	95.693	1.7954	56.349	6.389	26.000	2.167	1.120	0.229	4.166
8	1.8212	1.200	360.000	0.041	98.646	1.8212	57.301	6.283	26.000	2.204	1.136	0.193	4.886
9	1.8433	1.400	360.000	0.042	101.213	1.8433	58.119	6.194	26.000	2.235	1.150	0.168	5.584
10	1.8626	1.600	360.000	0.043	103.491	1.8626	58.837	6.119	26.000	2.263	1.162	0.148	6.263
11	1.8799	1.800	360.000	0.044	105.542	1.8799	59.479	6.053	26.000	2.288	1.173	0.133	6.924
12	1.8878	1.900	360.000	0.044	106.498	1.8878	59.776	6.023	26.000	2.299	1.178	0.126	7.248
13	1.8954	2.000	360.000	0.044	107.412	1.8954	60.059	5.994	26.000	2.310	1.183	0.121	7.568
14	1.9096	2.200	360.000	0.045	109.132	1.9096	60.589	5.942	26.000	2.330	1.192	0.110	8.198



$\sin(\theta)$	0.010
$\cos(\theta)$	1.000
$\tan(\Phi)$	0.869




Assume a normal depth, d:	2.900	ft
b/d:	8.966	
K:	0.750	
$\lambda = \theta$:	0.573	degrees
$\alpha = \text{atan}(1/z)$:	0.322	radians
α :	18.435	degrees

$\sin(\lambda)$	0.010
$\cos(\lambda)$	1.000
$\sin(\alpha)$	0.316
$\cos(\alpha)$	0.949
$\tan(\Phi)$	0.869

Assume riprap trial size

(EQN)	(11)	(12)	(13)	(14)	(15)	
D_{50}	$\eta_{\text{side}}(D_{50})$	$\eta_{\text{side}}(D_{50})$	$\beta(D_{50})$	$\eta_{\text{sp}}(D_{50})$	$SF_{\text{side}}(D_{50})$	
0	0.100	0.70	1.430	62.573	1.357	0.622
1	0.200	0.74	0.755	45.764	0.651	1.048
2	0.300	0.76	0.520	35.344	0.412	1.338
3	0.400	0.78	0.399	28.590	0.296	1.542
4	0.500	0.80	0.325	23.948	0.229	1.690
5	0.600	0.81	0.274	20.592	0.186	1.801
6	0.800	0.83	0.211	16.092	0.135	1.959
7	1.000	0.84	0.171	13.224	0.106	2.064
8	1.200	0.85	0.145	11.239	0.087	2.139
9	1.400	0.86	0.126	9.784	0.074	2.195
10	1.600	0.87	0.111	8.671	0.064	2.239
11	1.800	0.88	0.100	7.791	0.057	2.274
12	1.900	0.88	0.095	7.417	0.054	2.290
13	2.000	0.89	0.090	7.079	0.051	2.303
14	2.200	0.89	0.083	6.489	0.046	2.327





(1) Strickler relationship between riprap size and flow resistance: $n(D_{50}) := 0.0395 \cdot D_{50}^{\frac{1}{6}} \cdot \frac{\text{sec}}{\text{ft}^2}$

Manning's equation, assuming a trapezoidal or rectangular channel:

$$\frac{Q \cdot n}{1.486 \cdot \sqrt{S}} = A \cdot R^{\frac{2}{3}} \quad Q = \frac{1.486}{n} \cdot (b \cdot d + z \cdot d^2) \cdot \left[\frac{b \cdot d + z \cdot d^2}{b \cdot 2 \cdot d \cdot \sqrt{1 + z^2}} \right]^{\frac{2}{3}} \cdot \sqrt{S}$$

Solve Manning's equation for d:

(2) $C(D_{50}) := \frac{Q \cdot n(D_{50})}{1.486 \cdot \sqrt{S}}$ Channel conveyance

d := 5 ft Guess value for normal depth

(3) $d_n(D_{50}) := \text{root} \left[\frac{[(b + z \cdot d) \cdot d]^{\frac{5}{3}}}{(b + 2 \cdot d \cdot \sqrt{1 + z^2})^3} - C(D_{50}), d \right]$ Normal Flow Depth

Iterate Depth until Calculated Flow matches Actual Flow

(4) $A(D_{50}) := (b + z \cdot d_n(D_{50})) \cdot d_n(D_{50})$ Flow Area

(5) $V(D_{50}) := \frac{Q}{A(D_{50})}$ Flow Velocity

(6) Determine hydraulic radius, R: $P(D_{50}) := b + 2 \cdot d_n(D_{50}) \cdot \sqrt{1 + z^2}$ Wetted Perim

(7) $R(D_{50}) := \frac{A(D_{50})}{P(D_{50})}$ Hydraulic radius, based on normal depth

Check for riprap stability, based on Shields initiation of motion criterion:

(8) $\tau(D_{50}) := \gamma_w \cdot d_n(D_{50}) \cdot S$ Average shear stress on bed

(9) $\eta_b(D_{50}) := \frac{21 \cdot \tau(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Riprap stability factor

(10) $SF_b(D_{50}) := \frac{\cos(\theta) \cdot \tan(\phi)}{\sin(\theta) + \eta_b(D_{50}) \cdot \tan(\phi)}$ Safety factor for selected riprap size on channel bed



Determine Safety Factor for riprap on channel bank sideslopes:

$K = 0.75$ **Maximum shear stress coefficient on channel sides, K [From "Sediment Transport: Theory and Practice", Yang, p.44, Fig. 2.14 (Lane, 1953) or SCS Standard Dwg. No. 140, Sheet 6 of 8].**

(11) $\tau_{\text{side}}(D_{50}) := K \cdot \tau(D_{50})$ Shear stress on channel sideslope

(12) $\eta_{\text{side}}(D_{50}) := \frac{2 \cdot \tau_{\text{side}}(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Stability factor for channel sideslope

$\lambda := \theta$ ion for uniform flow

$\alpha := \text{atan}\left(\frac{1}{z}\right)$ deslope angle

(13) $\beta(D_{50}) := \text{atan}\left[\frac{\cos(\lambda)}{\left(\frac{2 \cdot \sin(\alpha)}{\eta_{\text{side}}(D_{50}) \cdot \tan(\phi)}\right) + \sin(\lambda)}\right]$

(14) $\eta_{\text{sp}}(D_{50}) := \eta_{\text{side}}(D_{50}) \cdot \left(\frac{1 + \sin(\lambda + \beta(D_{50}))}{2}\right)$ Stability factor for sideslopes

(15) $\text{SF}_{\text{side}}(D_{50}) := \frac{\cos(\alpha) \cdot \tan(\phi)}{\eta_{\text{sp}}(D_{50}) \cdot \tan(\phi) + \sin(\alpha) \cdot \cos(\beta(D_{50}))}$ Safety factor for riprap on sideslopes



Determine Safety Factor of Riprap Design using CSU Method (Safety Factor vs Riprap Size)
 (Simons, D.B. and Senturk, F., "Sediment Transport Technology", Water Resources Publications, LLC, 1992)

Project: SH-75 Bridge over Trail Creek
Project No.: 20033
Location: Ketchum, ID
Designer: Mike Schubert, PE
 HDR Engineering, Inc.

Given:

Flow in Channel:	600	cfs
Channel Slope, S:	0.01	ft/ft
Bed slope angle, q:	0.572939	degrees
Unit Weight of Water (γ_w):	62.4	lb/ft ³
Channel Bottom, b:	26	ft
Channel Side Slopes, zH:1V	3	
Riprap Angle of repose:	37	degrees
Riprap Angle of repose:	0.646	radians
Specific Gravity of Riprap:	2.65	
$\alpha = \text{atan}(1/z)$	0.321751	radians
α :	18.435	degrees
Φ , material angle of repose, degrees	41.000	degrees


-----> θ : 0.0100 radians

-----> Φ : 0.7156 radians

Determine safety factor for riprap on channel bed:

Iterate depth until Calculated Q matches Actual Q

	(EQN)	Calculated	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	
Depth	D_{50}	Q	$n(D_{50})$	$C(D_{50})$	$d_n(D_{50})$	$A(D_{50})$	$V(D_{50})$	$P(D_{50})$	$R(D_{50})$	$\tau(D_{50})$	$\eta_b(D_{50})$	$SF_b(D_{50})$	
0	1.9057	0.100	600.000	0.027	108.658	1.9057	60.443	9.927	26.000	2.325	1.189	2.425	0.410
1	2.0116	0.200	600.000	0.030	121.965	2.0116	64.439	9.311	26.000	2.478	1.255	1.280	0.774
2	2.0760	0.300	599.995	0.032	130.492	2.0760	66.906	8.968	26.000	2.573	1.295	0.881	1.121
3	2.1229	0.400	604.304	0.034	136.901	2.1229	68.716	8.732	26.000	2.643	1.325	0.675	1.456
4	2.1600	0.500	600.000	0.035	142.088	2.1600	70.156	8.552	26.000	2.698	1.348	0.550	1.781
5	2.1907	0.600	600.000	0.036	146.472	2.1907	71.357	8.408	26.000	2.744	1.367	0.465	2.100
6	2.2401	0.800	599.999	0.038	153.666	2.2401	73.295	8.186	26.000	2.819	1.398	0.356	2.718
7	2.2790	1.000	600.000	0.040	159.489	2.2790	74.837	8.017	26.000	2.878	1.422	0.290	3.316
8	2.3114	1.200	600.000	0.041	164.409	2.3114	76.123	7.882	26.000	2.928	1.442	0.245	3.896
9	2.3390	1.400	600.000	0.042	168.688	2.3390	77.228	7.769	26.000	2.970	1.460	0.213	4.461
10	2.3632	1.600	600.000	0.043	172.484	2.3632	78.199	7.673	26.000	3.008	1.475	0.188	5.013
11	2.3848	1.800	600.000	0.044	175.904	2.3848	79.066	7.589	26.000	3.041	1.488	0.169	5.551
12	2.3947	1.900	600.000	0.044	177.496	2.3947	79.468	7.550	26.000	3.056	1.494	0.160	5.816
13	2.4042	2.000	600.000	0.044	179.020	2.4042	79.851	7.514	26.000	3.071	1.500	0.153	6.079
14	2.4219	2.200	600.000	0.045	181.886	2.4219	80.567	7.447	26.000	3.099	1.511	0.140	6.595



sin(θ)	0.010
cos(θ)	1.000
tan(Φ)	0.869




Assume a normal depth, d:	2.900	ft
b/d:	8.966	
K:	0.750	
$\lambda = \theta$:	0.573	degrees
$\alpha = \text{atan}(1/z)$:	0.322	radians
α :	18.435	degrees

$\sin(\lambda)$	0.010
$\cos(\lambda)$	1.000
$\sin(\alpha)$	0.316
$\cos(\alpha)$	0.949
$\tan(\Phi)$	0.869

Assume riprap trial size

(EQN)	(11)	(12)	(13)	(14)	(15)	
D_{50}	$\eta_{\text{side}}(D_{50})$	$\eta_{\text{side}}(D_{50})$	$\beta(D_{50})$	$\eta_{\text{sp}}(D_{50})$	$SF_{\text{side}}(D_{50})$	
0	0.100	0.89	1.819	67.707	1.762	0.499
1	0.200	0.94	0.960	52.481	0.866	0.873
2	0.300	0.97	0.661	41.977	0.554	1.151
3	0.400	0.99	0.507	34.662	0.399	1.358
4	0.500	1.01	0.412	29.404	0.309	1.516
5	0.600	1.03	0.349	25.488	0.250	1.640
6	0.800	1.05	0.267	20.103	0.180	1.818
7	1.000	1.07	0.218	16.599	0.140	1.941
8	1.200	1.08	0.184	14.147	0.115	2.030
9	1.400	1.09	0.159	12.337	0.097	2.097
10	1.600	1.11	0.141	10.946	0.084	2.150
11	1.800	1.12	0.126	9.844	0.074	2.193
12	1.900	1.12	0.120	9.374	0.070	2.211
13	2.000	1.13	0.115	8.948	0.066	2.228
14	2.200	1.13	0.105	8.207	0.060	2.258





(1) Strickler relationship between riprap size and flow resistance: $n(D_{50}) := 0.0395 \cdot D_{50}^{\frac{1}{6}} \cdot \frac{\text{sec}}{\text{ft}^2}$

Manning's equation, assuming a trapezoidal or rectangular channel:

$$\frac{Q \cdot n}{1.486 \cdot \sqrt{S}} = A \cdot R^{\frac{2}{3}} \quad Q = \frac{1.486}{n} \cdot (b \cdot d + z \cdot d^2) \cdot \left[\frac{b \cdot d + z \cdot d^2}{b \cdot 2 \cdot d \cdot \sqrt{1 + z^2}} \right]^{\frac{2}{3}} \cdot \sqrt{S}$$

Solve Manning's equation for d:

(2) $C(D_{50}) := \frac{Q \cdot n(D_{50})}{1.486 \cdot \sqrt{S}}$ Channel conveyance

d := 5 ft Guess value for normal depth

(3) $d_n(D_{50}) := \text{root} \left[\frac{[(b + z \cdot d) \cdot d]^{\frac{5}{3}}}{(b + 2 \cdot d \cdot \sqrt{1 + z^2})^3} - C(D_{50}), d \right]$ Normal Flow Depth

Iterate Depth until Calculated Flow matches Actual Flow

(4) $A(D_{50}) := (b + z \cdot d_n(D_{50})) \cdot d_n(D_{50})$ Flow Area

(5) $V(D_{50}) := \frac{Q}{A(D_{50})}$ Flow Velocity

(6) Determine hydraulic radius, R: $P(D_{50}) := b + 2 \cdot d_n(D_{50}) \cdot \sqrt{1 + z^2}$ Wetted Perim

(7) $R(D_{50}) := \frac{A(D_{50})}{P(D_{50})}$ Hydraulic radius, based on normal depth

Check for riprap stability, based on Shields initiation of motion criterion:

(8) $\tau(D_{50}) := \gamma_w \cdot d_n(D_{50}) \cdot S$ Average shear stress on bed

(9) $\eta_b(D_{50}) := \frac{21 \cdot \tau(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Riprap stability factor

(10) $SF_b(D_{50}) := \frac{\cos(\theta) \cdot \tan(\phi)}{\sin(\theta) + \eta_b(D_{50}) \cdot \tan(\phi)}$ Safety factor for selected riprap size on channel bed



Determine Safety Factor for riprap on channel bank sideslopes:

$K = 0.75$ **Maximum shear stress coefficient on channel sides, K [From "Sediment Transport: Theory and Practice", Yang, p.44, Fig. 2.14 (Lane, 1953) or SCS Standard Dwg. No. 140, Sheet 6 of 8].**

(11) $\tau_{\text{side}}(D_{50}) := K \cdot \tau(D_{50})$ Shear stress on channel sideslope

(12) $\eta_{\text{side}}(D_{50}) := \frac{2 \cdot \tau_{\text{side}}(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Stability factor for channel sideslope

$\lambda := \theta$ ion for uniform flow

$\alpha := \text{atan}\left(\frac{1}{z}\right)$ deslope angle

(13) $\beta(D_{50}) := \text{atan}\left[\frac{\cos(\lambda)}{\left(\frac{2 \cdot \sin(\alpha)}{\eta_{\text{side}}(D_{50}) \cdot \tan(\phi)}\right) + \sin(\lambda)}\right]$

(14) $\eta_{\text{sp}}(D_{50}) := \eta_{\text{side}}(D_{50}) \cdot \left(\frac{1 + \sin(\lambda + \beta(D_{50}))}{2}\right)$ Stability factor for sideslopes

(15) $\text{SF}_{\text{side}}(D_{50}) := \frac{\cos(\alpha) \cdot \tan(\phi)}{\eta_{\text{sp}}(D_{50}) \cdot \tan(\phi) + \sin(\alpha) \cdot \cos(\beta(D_{50}))}$ Safety factor for riprap on sideslopes



Determine Safety Factor of Riprap Design using CSU Method (Safety Factor vs Riprap Size)
 (Simons, D.B. and Senturk, F., "Sediment Transport Technology", Water Resources Publications, LLC, 1992)

Project: SH-75 Bridge over Trail Creek
Project No.: 20033
Location: Ketchum, ID
Designer: Mike Schubert, PE
 HDR Engineering, Inc.

Given:

Flow in Channel:	900	cfs
Channel Slope, S:	0.01	ft/ft
Bed slope angle, q:	0.572939	degrees
Unit Weight of Water (γ_w):	62.4	lb/ft ³
Channel Bottom, b:	26	ft
Channel Side Slopes, zH:1V	3	
Riprap Angle of repose:	37	degrees
Riprap Angle of repose:	0.646	radians
Specific Gravity of Riprap:	2.65	
$\alpha = \text{atan}(1/z)$	0.321751	radians
α :	18.435	degrees
Φ , material angle of repose, degrees	41.000	degrees


-----> θ : 0.0100 radians

-----> Φ : 0.7156 radians

Determine safety factor for riprap on channel bed:

Iterate depth until Calculated Q matches Actual Q

	(EQN)	Calculated	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	
Depth	D_{50}	Q	$n(D_{50})$	$C(D_{50})$	$d_n(D_{50})$	$A(D_{50})$	$V(D_{50})$	$P(D_{50})$	$R(D_{50})$	$\tau(D_{50})$	$\eta_b(D_{50})$	$SF_b(D_{50})$	
0	2.3021	0.100	900.000	0.027	162.987	2.3021	75.753	11.881	26.000	2.914	1.437	2.930	0.340
1	2.4284	0.200	900.000	0.030	182.947	2.4284	80.832	11.134	26.000	3.109	1.515	1.545	0.642
2	2.5053	0.300	900.000	0.032	195.738	2.5053	83.969	10.718	26.000	3.230	1.563	1.063	0.931
3	2.5613	0.400	900.000	0.034	205.351	2.5613	86.273	10.432	26.000	3.318	1.598	0.815	1.210
4	2.6054	0.500	900.000	0.035	213.132	2.6054	88.106	10.215	26.000	3.389	1.626	0.663	1.482
5	2.6420	0.600	900.000	0.036	219.708	2.6420	89.634	10.041	26.000	3.447	1.649	0.560	1.748
6	2.7008	0.800	900.000	0.038	230.499	2.7008	92.104	9.772	26.000	3.542	1.685	0.430	2.267
7	2.7472	1.000	900.000	0.040	239.233	2.7472	94.069	9.567	26.000	3.618	1.714	0.350	2.769
8	2.7857	1.200	900.000	0.041	246.614	2.7857	95.707	9.404	26.000	3.681	1.738	0.295	3.258
9	2.8186	1.400	900.000	0.042	253.032	2.8186	97.116	9.267	26.000	3.735	1.759	0.256	3.735
10	2.8474	1.600	900.000	0.043	258.726	2.8474	98.355	9.151	26.000	3.783	1.777	0.226	4.201
11	2.8730	1.800	900.000	0.044	263.856	2.8730	99.461	9.049	26.000	3.825	1.793	0.203	4.659
12	2.8849	1.900	900.000	0.044	266.244	2.8849	99.973	9.002	26.000	3.845	1.800	0.193	4.884
13	2.8961	2.000	900.000	0.044	268.530	2.8961	100.462	8.959	26.000	3.864	1.807	0.184	5.107
14	2.9172	2.200	900.000	0.045	272.829	2.9172	101.376	8.878	26.000	3.899	1.820	0.169	5.547






Assume a normal depth, d:	2.900	ft
b/d:	8.966	
K:	0.750	
$\lambda = \theta$:	0.573	degrees
$\alpha = \text{atan}(1/z)$:	0.322	radians
α :	18.435	degrees

$\sin(\lambda)$	0.010
$\cos(\lambda)$	1.000
$\sin(\alpha)$	0.316
$\cos(\alpha)$	0.949
$\tan(\Phi)$	0.869

Assume riprap trial size

(EQN)	(11)	(12)	(13)	(14)	(15)	
D_{50}	$\eta_{\text{side}}(D_{50})$	$\eta_{\text{side}}(D_{50})$	$\beta(D_{50})$	$\eta_{\text{sp}}(D_{50})$	$SF_{\text{side}}(D_{50})$	
0	0.100	1.08	2.197	71.165	2.151	0.418
1	0.200	1.14	1.159	57.472	1.074	0.747
2	0.300	1.17	0.797	47.301	0.695	1.007
3	0.400	1.20	0.611	39.796	0.504	1.211
4	0.500	1.22	0.497	34.176	0.390	1.373
5	0.600	1.24	0.420	29.872	0.316	1.502
6	0.800	1.26	0.322	23.795	0.227	1.695
7	1.000	1.29	0.262	19.754	0.176	1.830
8	1.200	1.30	0.222	16.890	0.143	1.930
9	1.400	1.32	0.192	14.758	0.121	2.007
10	1.600	1.33	0.170	13.112	0.104	2.068
11	1.800	1.34	0.152	11.803	0.092	2.117
12	1.900	1.35	0.145	11.244	0.087	2.139
13	2.000	1.36	0.138	10.737	0.082	2.158
14	2.200	1.37	0.127	9.852	0.074	2.193





(1) Strickler relationship between riprap size and flow resistance: $n(D_{50}) := 0.0395 \cdot D_{50}^{\frac{1}{6}} \cdot \frac{\text{sec}}{\text{ft}^2}$

Manning's equation, assuming a trapezoidal or rectangular channel:

$$\frac{Q \cdot n}{1.486 \cdot \sqrt{S}} = A \cdot R^{\frac{2}{3}} \quad Q = \frac{1.486}{n} \cdot (b \cdot d + z \cdot d^2) \cdot \left[\frac{b \cdot d + z \cdot d^2}{b \cdot 2 \cdot d \cdot \sqrt{1 + z^2}} \right]^{\frac{2}{3}} \cdot \sqrt{S}$$

Solve Manning's equation for d:

(2) $C(D_{50}) := \frac{Q \cdot n(D_{50})}{1.486 \cdot \sqrt{S}}$ Channel conveyance

d := 5 ft Guess value for normal depth

(3) $d_n(D_{50}) := \text{root} \left[\frac{[(b + z \cdot d) \cdot d]^{\frac{5}{3}}}{(b + 2 \cdot d \cdot \sqrt{1 + z^2})^3} - C(D_{50}), d \right]$ Normal Flow Depth

Iterate Depth until Calculated Flow matches Actual Flow

(4) $A(D_{50}) := (b + z \cdot d_n(D_{50})) \cdot d_n(D_{50})$ Flow Area

(5) $V(D_{50}) := \frac{Q}{A(D_{50})}$ Flow Velocity

(6) Determine hydraulic radius, R: $P(D_{50}) := b + 2 \cdot d_n(D_{50}) \cdot \sqrt{1 + z^2}$ Wetted Perim

(7) $R(D_{50}) := \frac{A(D_{50})}{P(D_{50})}$ Hydraulic radius, based on normal depth

Check for riprap stability, based on Shields initiation of motion criterion:

(8) $\tau(D_{50}) := \gamma_w \cdot d_n(D_{50}) \cdot S$ Average shear stress on bed

(9) $\eta_b(D_{50}) := \frac{21 \cdot \tau(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Riprap stability factor

(10) $SF_b(D_{50}) := \frac{\cos(\theta) \cdot \tan(\phi)}{\sin(\theta) + \eta_b(D_{50}) \cdot \tan(\phi)}$ Safety factor for selected riprap size on channel bed

Determine Safety Factor for riprap on channel bank sideslopes:

$K = 0.75$ **Maximum shear stress coefficient on channel sides, K [From "Sediment Transport: Theory and Practice", Yang, p.44, Fig. 2.14 (Lane, 1953) or SCS Standard Dwg. No. 140, Sheet 6 of 8].**

(11) $\tau_{\text{side}}(D_{50}) := K \cdot \tau(D_{50})$ Shear stress on channel sideslope

(12) $\eta_{\text{side}}(D_{50}) := \frac{2 \cdot \tau_{\text{side}}(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Stability factor for channel sideslope

$\lambda := \theta$ ion for uniform flow

$\alpha := \text{atan}\left(\frac{1}{z}\right)$ deslope angle

(13) $\beta(D_{50}) := \text{atan}\left[\frac{\cos(\lambda)}{\left(\frac{2 \cdot \sin(\alpha)}{\eta_{\text{side}}(D_{50}) \cdot \tan(\phi)}\right) + \sin(\lambda)}\right]$

(14) $\eta_{\text{sp}}(D_{50}) := \eta_{\text{side}}(D_{50}) \cdot \left(\frac{1 + \sin(\lambda + \beta(D_{50}))}{2}\right)$ Stability factor for sideslopes

(15) $\text{SF}_{\text{side}}(D_{50}) := \frac{\cos(\alpha) \cdot \tan(\phi)}{\eta_{\text{sp}}(D_{50}) \cdot \tan(\phi) + \sin(\alpha) \cdot \cos(\beta(D_{50}))}$ Safety factor for riprap on sideslopes



Determine Safety Factor of Riprap Design using CSU Method (Safety Factor vs Riprap Size)
 (Simons, D.B. and Senturk, F., "Sediment Transport Technology", Water Resources Publications, LLC, 1992)

Project: SH-75 Bridge over Trail Creek
Project No.: 20033
Location: Ketchum, ID
Designer: Mike Schubert, PE
 HDR Engineering, Inc.

Given:

Flow in Channel:	1020	cfs
Channel Slope, S:	0.01	ft/ft
Bed slope angle, q:	0.572939	degrees
Unit Weight of Water (γ_w):	62.4	lb/ft ³
Channel Bottom, b:	26	ft
Channel Side Slopes, zH:1V	3	
Riprap Angle of repose:	37	degrees
Riprap Angle of repose:	0.646	radians
Specific Gravity of Riprap:	2.65	
$\alpha = \text{atan}(1/z)$	0.321751	radians
α :	18.435	degrees
Φ , material angle of repose, degrees	41.000	degrees


-----> θ : 0.0100 radians

-----> Φ : 0.7156 radians

Determine safety factor for riprap on channel bed:

Iterate depth until Calculated Q matches Actual Q

	(EQN)	Calculated	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	
Depth	D_{50}	Q	$n(D_{50})$	$C(D_{50})$	$d_n(D_{50})$	$A(D_{50})$	$V(D_{50})$	$P(D_{50})$	$R(D_{50})$	$\tau(D_{50})$	$\eta_b(D_{50})$	$SF_b(D_{50})$	
0	2.4393	0.100	1020.000	0.027	184.719	2.4393	81.271	12.551	26.000	3.126	1.522	3.105	0.321
1	2.5726	0.200	1020.000	0.030	207.340	2.5726	86.744	11.759	26.000	3.336	1.605	1.637	0.607
2	2.6538	0.300	1020.000	0.032	221.836	2.6538	90.125	11.318	26.000	3.466	1.656	1.126	0.879
3	2.7128	0.400	1020.000	0.034	232.731	2.7128	92.609	11.014	26.000	3.562	1.693	0.863	1.143
4	2.7594	0.500	1020.000	0.035	241.550	2.7594	94.585	10.784	26.000	3.638	1.722	0.702	1.401
5	2.7980	0.600	1020.000	0.036	249.002	2.7980	96.233	10.599	26.000	3.701	1.746	0.594	1.653
6	2.8599	0.800	1020.000	0.038	261.232	2.8599	98.896	10.314	26.000	3.804	1.785	0.455	2.144
7	2.9089	1.000	1020.000	0.040	271.131	2.9089	101.016	10.097	26.000	3.885	1.815	0.370	2.620
8	2.9494	1.200	1020.000	0.041	279.496	2.9494	102.783	9.924	26.000	3.953	1.840	0.313	3.083
9	2.9841	1.400	1020.000	0.042	286.770	2.9841	104.303	9.779	26.000	4.012	1.862	0.271	3.536
10	3.0145	1.600	1020.000	0.043	293.223	3.0145	105.638	9.656	26.000	4.063	1.881	0.240	3.979
11	3.0415	1.800	1020.000	0.044	299.036	3.0415	106.832	9.548	26.000	4.109	1.898	0.215	4.414
12	3.0540	1.900	1020.000	0.044	301.743	3.0540	107.384	9.499	26.000	4.130	1.906	0.205	4.628
13	3.0659	2.000	1020.000	0.044	304.334	3.0659	107.911	9.452	26.000	4.150	1.913	0.195	4.840
14	3.0881	2.200	1020.000	0.045	309.207	3.0881	108.898	9.367	26.000	4.188	1.927	0.179	5.259



sin(θ)	0.010
cos(θ)	1.000
tan(Φ)	0.869




Assume a normal depth, d:	2.900	ft
b/d:	8.966	
K:	0.750	
$\lambda = \theta$:	0.573	degrees
$\alpha = \text{atan}(1/z)$:	0.322	radians
α :	18.435	degrees

$\sin(\lambda)$	0.010
$\cos(\lambda)$	1.000
$\sin(\alpha)$	0.316
$\cos(\alpha)$	0.949
$\tan(\Phi)$	0.869

Assume riprap trial size

(EQN)	(11)	(12)	(13)	(14)	(15)	
D_{50}	$\eta_{\text{side}}(D_{50})$	$\eta_{\text{side}}(D_{50})$	$\beta(D_{50})$	$\eta_{\text{sp}}(D_{50})$	$SF_{\text{side}}(D_{50})$	
0	0.100	1.14	2.328	72.126	2.286	0.396
1	0.200	1.20	1.228	58.928	1.146	0.711
2	0.300	1.24	0.844	48.922	0.744	0.965
3	0.400	1.27	0.647	41.409	0.541	1.166
4	0.500	1.29	0.527	35.709	0.419	1.328
5	0.600	1.31	0.445	31.302	0.340	1.458
6	0.800	1.34	0.341	25.024	0.244	1.655
7	1.000	1.36	0.278	20.815	0.189	1.794
8	1.200	1.38	0.235	17.818	0.154	1.897
9	1.400	1.40	0.203	15.582	0.129	1.977
10	1.600	1.41	0.180	13.851	0.112	2.041
11	1.800	1.42	0.161	12.472	0.098	2.092
12	1.900	1.43	0.153	11.883	0.093	2.114
13	2.000	1.43	0.146	11.349	0.088	2.135
14	2.200	1.45	0.134	10.415	0.079	2.171



(1) Strickler relationship between riprap size and flow resistance: $n(D_{50}) := 0.0395 \cdot D_{50}^{\frac{1}{6}} \cdot \frac{\text{sec}}{\text{ft}^2}$

Manning's equation, assuming a trapezoidal or rectangular channel:

$$\frac{Q \cdot n}{1.486 \cdot \sqrt{S}} = A \cdot R^{\frac{2}{3}} \quad Q = \frac{1.486}{n} \cdot (b \cdot d + z \cdot d^2) \cdot \left[\frac{b \cdot d + z \cdot d^2}{b \cdot 2 \cdot d \cdot \sqrt{1 + z^2}} \right]^{\frac{2}{3}} \cdot \sqrt{S}$$

Solve Manning's equation for d:

(2) $C(D_{50}) := \frac{Q \cdot n(D_{50})}{1.486 \cdot \sqrt{S}}$ Channel conveyance

d := 5 ft Guess value for normal depth

(3) $d_n(D_{50}) := \text{root} \left[\frac{[(b + z \cdot d) \cdot d]^{\frac{5}{3}}}{(b + 2 \cdot d \cdot \sqrt{1 + z^2})^3} - C(D_{50}), d \right]$ Normal Flow Depth

Iterate Depth until Calculated Flow matches Actual Flow

(4) $A(D_{50}) := (b + z \cdot d_n(D_{50})) \cdot d_n(D_{50})$ Flow Area

(5) $V(D_{50}) := \frac{Q}{A(D_{50})}$ Flow Velocity

(6) Determine hydraulic radius, R: $P(D_{50}) := b + 2 \cdot d_n(D_{50}) \cdot \sqrt{1 + z^2}$ Wetted Perim

(7) $R(D_{50}) := \frac{A(D_{50})}{P(D_{50})}$ Hydraulic radius, based on normal depth

Check for riprap stability, based on Shields initiation of motion criterion:

(8) $\tau(D_{50}) := \gamma_w \cdot d_n(D_{50}) \cdot S$ Average shear stress on bed

(9) $\eta_b(D_{50}) := \frac{21 \cdot \tau(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Riprap stability factor

(10) $SF_b(D_{50}) := \frac{\cos(\theta) \cdot \tan(\phi)}{\sin(\theta) + \eta_b(D_{50}) \cdot \tan(\phi)}$ Safety factor for selected riprap size on channel bed



Determine Safety Factor for riprap on channel bank sideslopes:

$K = 0.75$ **Maximum shear stress coefficient on channel sides, K [From "Sediment Transport: Theory and Practice", Yang, p.44, Fig. 2.14 (Lane, 1953) or SCS Standard Dwg. No. 140, Sheet 6 of 8].**

(11) $\tau_{\text{side}}(D_{50}) := K \cdot \tau(D_{50})$ Shear stress on channel sideslope

(12) $\eta_{\text{side}}(D_{50}) := \frac{2 \cdot \tau_{\text{side}}(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Stability factor for channel sideslope

$\lambda := \theta$ ion for uniform flow

$\alpha := \text{atan}\left(\frac{1}{z}\right)$ deslope angle

(13) $\beta(D_{50}) := \text{atan}\left[\frac{\cos(\lambda)}{\left(\frac{2 \cdot \sin(\alpha)}{\eta_{\text{side}}(D_{50}) \cdot \tan(\phi)}\right) + \sin(\lambda)}\right]$

(14) $\eta_{\text{sp}}(D_{50}) := \eta_{\text{side}}(D_{50}) \cdot \left(\frac{1 + \sin(\lambda + \beta(D_{50}))}{2}\right)$ Stability factor for sideslopes

(15) $\text{SF}_{\text{side}}(D_{50}) := \frac{\cos(\alpha) \cdot \tan(\phi)}{\eta_{\text{sp}}(D_{50}) \cdot \tan(\phi) + \sin(\alpha) \cdot \cos(\beta(D_{50}))}$ Safety factor for riprap on sideslopes



Determine Safety Factor of Riprap Design using CSU Method (Safety Factor vs Riprap Size)
 (Simons, D.B. and Senturk, F., "Sediment Transport Technology", Water Resources Publications, LLC, 1992)

Project: Si
Project No.: 20033
Location: Ketchum, ID
Designer: Mike Schubert, PE
 HDR Engineering, Inc.

Given:

Flow in Channel:	1300	cfs
Channel Slope, S:	0.01	ft/ft
Bed slope angle, q:	0.572939	degrees
Unit Weight of Water (γ_w):	62.4	lb/ft ³
Channel Bottom, b:	26	ft
Channel Side Slopes, zH:1V	3	
Riprap Angle of repose:	37	degrees
Riprap Angle of repose:	0.646	radians
Specific Gravity of Riprap:	2.65	
$\alpha = \text{atan}(1/z)$	0.321751	radians
α :	18.435	degrees
Φ , material angle of repose, degrees	41.000	degrees


-----> θ : 0.0100 radians

-----> Φ : 0.7156 radians

Determine safety factor for riprap on channel bed:

Iterate depth until Calculated Q matches Actual Q

	(EQN)	Calculated	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	
Depth	D_{50}	Q	$n(D_{50})$	$C(D_{50})$	$d_n(D_{50})$	$A(D_{50})$	$V(D_{50})$	$P(D_{50})$	$R(D_{50})$	$\tau(D_{50})$	$\eta_b(D_{50})$	$SF_b(D_{50})$	
0	2.7271	0.100	1300.000	0.027	235.426	2.7271	93.216	13.946	26.000	3.585	1.702	3.471	0.287
1	2.8750	0.200	1300.000	0.030	264.257	2.8750	99.547	13.059	26.000	3.829	1.794	1.830	0.543
2	2.9649	0.300	1299.999	0.032	282.732	2.9649	103.461	12.565	26.000	3.979	1.850	1.258	0.788
3	3.0303	0.400	1300.000	0.034	296.619	3.0303	106.337	12.225	26.000	4.090	1.891	0.964	1.025
4	3.0819	0.500	1300.000	0.035	307.858	3.0819	108.625	11.968	26.000	4.178	1.923	0.784	1.256
5	3.1247	0.600	1300.000	0.036	317.356	3.1247	110.534	11.761	26.000	4.251	1.950	0.663	1.483
6	3.1933	0.800	1300.000	0.038	332.943	3.1933	113.619	11.442	26.000	4.370	1.993	0.508	1.925
7	3.2475	1.000	1300.000	0.040	345.559	3.2475	116.075	11.200	26.000	4.464	2.026	0.413	2.354
8	3.2924	1.200	1300.000	0.041	356.220	3.2924	118.123	11.005	26.000	4.543	2.054	0.349	2.772
9	3.3308	1.400	1300.000	0.042	365.491	3.3308	119.884	10.844	26.000	4.611	2.078	0.303	3.181
10	3.3644	1.600	1300.000	0.043	373.716	3.3644	121.433	10.705	26.000	4.670	2.099	0.268	3.582
11	3.3943	1.800	1300.000	0.044	381.125	3.3943	122.816	10.585	26.000	4.724	2.118	0.240	3.976
12	3.4081	1.900	1300.000	0.044	384.575	3.4081	123.457	10.530	26.000	4.748	2.127	0.228	4.170
13	3.4213	2.000	1300.000	0.044	387.876	3.4213	124.068	10.478	26.000	4.772	2.135	0.218	4.362
14	3.4458	2.200	1300.000	0.045	394.087	3.4458	125.212	10.382	26.000	4.816	2.150	0.199	4.743



$\sin(\theta)$	0.010
$\cos(\theta)$	1.000
$\tan(\Phi)$	0.869




Assume a normal depth, d:	2.900	ft
b/d:	8.966	
K:	0.750	
$\lambda = \theta$:	0.573	degrees
$\alpha = \text{atan}(1/z)$:	0.322	radians
α :	18.435	degrees

$\sin(\lambda)$	0.010
$\cos(\lambda)$	1.000
$\sin(\alpha)$	0.316
$\cos(\alpha)$	0.949
$\tan(\Phi)$	0.869

Assume riprap trial size

(EQN)	(11)	(12)	(13)	(14)	(15)	
D_{50}	$\eta_{\text{side}}(D_{50})$	$\eta_{\text{side}}(D_{50})$	$\beta(D_{50})$	$\eta_{\text{sp}}(D_{50})$	$SF_{\text{side}}(D_{50})$	
0	0.100	1.28	2.603	73.854	2.567	0.356
1	0.200	1.35	1.372	61.620	1.297	0.645
2	0.300	1.39	0.943	52.001	0.848	0.885
3	0.400	1.42	0.723	44.541	0.618	1.081
4	0.500	1.44	0.588	38.735	0.481	1.241
5	0.600	1.46	0.497	34.161	0.390	1.373
6	0.800	1.49	0.381	27.517	0.280	1.575
7	1.000	1.52	0.310	22.989	0.216	1.721
8	1.200	1.54	0.262	19.731	0.176	1.831
9	1.400	1.56	0.227	17.284	0.148	1.916
10	1.600	1.57	0.201	15.382	0.127	1.984
11	1.800	1.59	0.180	13.863	0.112	2.040
12	1.900	1.60	0.171	13.212	0.105	2.064
13	2.000	1.60	0.163	12.621	0.100	2.086
14	2.200	1.61	0.150	11.589	0.090	2.126



(1) Strickler relationship between riprap size and flow resistance:
$$n(D_{50}) := 0.0395 \cdot D_{50}^{\frac{1}{6}} \cdot \frac{\text{sec}}{\text{ft}^2}$$

Manning's equation, assuming a trapezoidal or rectangular channel:

$$\frac{Q \cdot n}{1.486 \cdot \sqrt{S}} = A \cdot R^{\frac{2}{3}} \quad Q = \frac{1.486}{n} \cdot (b \cdot d + z \cdot d^2) \cdot \left[\frac{b \cdot d + z \cdot d^2}{b \cdot 2 \cdot d \cdot \sqrt{1 + z^2}} \right]^{\frac{2}{3}} \cdot \sqrt{S}$$

Solve Manning's equation for d:

(2) $C(D_{50}) := \frac{Q \cdot n(D_{50})}{1.486 \cdot \sqrt{S}}$ Channel conveyance

d := 5 ft Guess value for normal depth

(3) $d_n(D_{50}) := \text{root} \left[\frac{[(b + z \cdot d) \cdot d]^{\frac{5}{3}}}{(b + 2 \cdot d \cdot \sqrt{1 + z^2})^3} - C(D_{50}), d \right]$ Normal Flow Depth

Iterate Depth until Calculated Flow matches Actual Flow

(4) $A(D_{50}) := (b + z \cdot d_n(D_{50})) \cdot d_n(D_{50})$ Flow Area

(5) $V(D_{50}) := \frac{Q}{A(D_{50})}$ Flow Velocity

(6) Determine hydraulic radius, R: $P(D_{50}) := b + 2 \cdot d_n(D_{50}) \cdot \sqrt{1 + z^2}$ Wetted Perim

(7) $R(D_{50}) := \frac{A(D_{50})}{P(D_{50})}$ Hydraulic radius, based on normal depth

Check for riprap stability, based on Shields initiation of motion criterion:

(8) $\tau(D_{50}) := \gamma_w \cdot d_n(D_{50}) \cdot S$ Average shear stress on bed

(9) $\eta_b(D_{50}) := \frac{21 \cdot \tau(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Riprap stability factor

(10) $SF_b(D_{50}) := \frac{\cos(\theta) \cdot \tan(\phi)}{\sin(\theta) + \eta_b(D_{50}) \cdot \tan(\phi)}$ Safety factor for selected riprap size on channel bed

Determine Safety Factor for riprap on channel bank sideslopes:

$K = 0.75$ **Maximum shear stress coefficient on channel sides, K [From "Sediment Transport: Theory and Practice", Yang, p.44, Fig. 2.14 (Lane, 1953) or SCS Standard Dwg. No. 140, Sheet 6 of 8].**

(11) $\tau_{\text{side}}(D_{50}) := K \cdot \tau(D_{50})$ Shear stress on channel sideslope

(12) $\eta_{\text{side}}(D_{50}) := \frac{2 \cdot \tau_{\text{side}}(D_{50})}{\gamma_w \cdot (G_s - 1) \cdot D_{50}}$ Stability factor for channel sideslope

$\lambda := \theta$ ion for uniform flow

$\alpha := \text{atan}\left(\frac{1}{z}\right)$ deslope angle

(13) $\beta(D_{50}) := \text{atan}\left[\frac{\cos(\lambda)}{\left(\frac{2 \cdot \sin(\alpha)}{\eta_{\text{side}}(D_{50}) \cdot \tan(\phi)}\right) + \sin(\lambda)}\right]$

(14) $\eta_{\text{sp}}(D_{50}) := \eta_{\text{side}}(D_{50}) \cdot \left(\frac{1 + \sin(\lambda + \beta(D_{50}))}{2}\right)$ Stability factor for sideslopes

(15) $\text{SF}_{\text{side}}(D_{50}) := \frac{\cos(\alpha) \cdot \tan(\phi)}{\eta_{\text{sp}}(D_{50}) \cdot \tan(\phi) + \sin(\alpha) \cdot \cos(\beta(D_{50}))}$ Safety factor for riprap on sideslopes

Appendix G ITD 210 Form



Hydraulics Structures Survey

ITD 0210 (Rev. 05-17)
itd.idaho.gov

A hydraulic report should accompany this form for natural streams with Q₅₀ of 500cfs or more and canals.

Key Number 20033	Project Number A020(033)	Station Sta. 1474+63.10, MP 128.109	Date 7/24/20
Project Title SH-75, Elkhorn Rd to River St., Ketchum		Local Name SH-75 Trail Creek Bridge	
Location Ketchum, ID		County Blaine	
Roadway Identification SH-75, Segment Code 002230			
Crossing <input checked="" type="checkbox"/> Creek <input type="checkbox"/> River <input type="checkbox"/> Canal		A Tributary Of Big Wood River	

Hydrologic Data

Hydrology Methods Used to Determine Design Flows <input type="checkbox"/> USGS Website <input checked="" type="checkbox"/> Flood Insurance Study <input type="checkbox"/> USGS Regression Equations <input type="checkbox"/> Other (Describe)		
Description of Watershed The Trail Creek floodplain is extensively developed, with dwellings lining the stream from one end of the city to the other.		
Drainage Basin Area <input checked="" type="checkbox"/> mi ² <input type="checkbox"/> acres 69	Community Name Blaine County, Idaho and Incorporated Area	
Flood Insurance Rate Map (FIRM) Panel Number* 16013C0461E	Regulatory Floodway <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	If Yes, Floodway Map Panel Number* 16013C0461E

*Attach 8 1/2" x 11" copy of map panel at the structure location.

Stream Data

<input checked="" type="checkbox"/> Natural Stream <input type="checkbox"/> Canal	Months Dry, If Any	Streambed Elevation of Structure 5795.0	Streambed Slope 0.015	ft
Stream Carries an Appreciable Amount of Ice <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Ice Thickness in	Stream Carries an Appreciable Amount of Driftwood <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Character of Streambed <input checked="" type="checkbox"/> Stable <input type="checkbox"/> Agrading <input type="checkbox"/> Degrading <input type="checkbox"/> Headcutting	Describe Streambed Gravel with cobbles			
Flow Controlled <input checked="" type="checkbox"/> Upstream <input type="checkbox"/> Downstream	If Controlled, Explain Sun Valley Lake			

Existing Structure

<input checked="" type="checkbox"/> Bridge <input type="checkbox"/> Culvert (Describe the Bridge or Culvert) reinforced concrete stiffleg				
General Condition Satisfactory				Year Constructed 1980
Describe Any Existing Adverse Conditions				
Type of Bridge Piers <input type="checkbox"/> Spread Footings <input checked="" type="checkbox"/> Piles	Number of Piers 0	Bridge or Culvert Type Bridge	Structure Dimensions, Diameter, Etc. Span 20 x Rise 9.3 x Length 48.5	
Total Bridge Opening Area Normal to Channel 152	ft ²	Bridge Clearance Above Q ₅₀ High Water 2.17	ft	Velocity Through Structure 11.30 @ Inside BR DS
Existing Culvert Carried Flow Adequately <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		If No, Explain		

Distribution: **Consultant** – Signed Original to District/LHTAC Project Manager
District/LHTAC – Signed Original to Project File

No additional copies required



Hydraulics Structures Survey

ITD 0210 (Rev. 05-17)
itd.idaho.gov

Design Flow Data

Flood	Discharge		Water Surface Elevation		Velocity	
Design [Q ₅₀]*	900	cfs	5801.63 @XS2147	ft	5.62 @XS2147	fps
Base [Q ₁₀₀]	1,020	cfs	5801.95 @XS2147	ft	5.88 @XS2147	fps
Scour [Q ₅₀₀]	1,300	cfs	5802.62 @XS2147	ft	6.40 @XS2147	fps
Canal Flow		cfs		ft		fps

*Use Q₅₀ for bridges and culverts 12 ft or more in width/diameter and for open bottom culverts. Use Q₂₅ for all other culverts.

Proposed Bridge

Type prestressed concrete voided slab bridge	Ordinary High Water Elevation 5799.55	ft	Number and Length of Spans 1 @ 57.5 ft
Skew Angle 0	Calculated Riprap Size, D ₅₀ 1.5	ft	Bottom of Girder Elevation 5804.91
Flow Angle to Pier	Calculated Contraction Scour Depth 0.36	ft	Q ₅₀ Water Surface Elevation 5801.63
Streambed Material Size, D ₅₀ 38	Calculated Pier Scour Depth	ft	Q ₅₀ Freeboard 3.28

Proposed Culvert

Type	Dimensions	Inlet Type
Culvert Flowing Under <input type="checkbox"/> Inlet Control <input type="checkbox"/> Outlet Control	Invert Inlet Elevation	Outlet Elevation
Outlet Protection Required <input type="checkbox"/> No <input type="checkbox"/> Yes	Tailwater Elevation	Bottom of Gravel Course Elevation
Channel Change <input type="checkbox"/> No <input type="checkbox"/> Yes	Tailwater Depth	Calculated Headwater Elevation (HW)
Energy Dissipater (If Yes, Describe) <input type="checkbox"/> No <input type="checkbox"/> Yes	Culvert Slope	Bottom of Gravel Course Freeboard
Riprap Required (If Yes, D ₅₀) <input type="checkbox"/> No <input type="checkbox"/> Yes	Finished Grade Elevation Centerline Roadway	HW/D Ratio
Proposed Culvert Will Carry the Base Flood (Q ₁₀₀) Without Overtopping the Roadway <input type="checkbox"/> No <input type="checkbox"/> Yes		

In addition to the above information, submit and check each of the following that apply.

- A typical proposed roadway section at the structure.
- A 11" x 17" contour map of the structure site showing 1 foot contours.
- A centerline profile to the same scale as the contour map.
- A vicinity map, such as a county map, with the location of the structure clearly indicated.
- A streambed profile 500 to 1,000 feet above and below the structure.
- Riprap details (typical section, limits, size, toe embedment, etc.) for proposed locations.
- Photographs of the existing structure and channel upstream and downstream from the site.
- Channel change or canal lining details (typical section, plan and profile, and limits).
- Computations for scour based on Q₅₀₀ or canal flow. (Attach HEC-RAS contraction scour and if applicable, pier scour report.)
- Hydraulic report. (See Design Manual for format.)
- Letter of approval from canal company or irrigation district.
- Floodplain Development Permit from the city/county if the structure is located in the 100-year floodplain.



Distribution: **Consultant** – Signed Original to District/LHTAC Project Manager
District/LHTAC – Signed Original to Project File

No additional
copies required



Hydraulics Structures Survey

ITD 0210 (Rev. 05-17)
itd.idaho.gov



Prepared By Michael Schubert, PE	Title Water Resources Engineer	Engineer's Signature and Seal 04/21/2021
Accepted by LHTAC Administrator, Bridge Engineer, or District Engineer	Signature/Date	

Distribution: **Consultant** – Signed Original to District/LHTAC Project Manager
District/LHTAC – Signed Original to Project File

No additional copies required

Appendix H ITD Pontis Field Inspection Report



Idaho Transportation Department Bridge Inspection Report

Bridge Key: 17675	Structure Name: S07500A 128.12
(6)Features Intersected: TRAIL CREEK	(9)Location: KETCHUM SCL
Xref Structure Name:	Admin Jurisdiction: 0004 District 4
	District: 04

Elem/Env	Element Description	Total Qty	Units	State 1	State 2	State 3	State 4
38/3	Reinforced Concrete Slab	1055	sq.ft	1045	10	0	0
	Asphalt roadway on a granular base in satisfactory condition. A few patches in the underside, right construction joint.						
1080/3	Delamination/Spall/Patched Area	10	sq.ft	0	10	0	0
	<i>A few patches in the underside, right construction joint.</i>						
215/3	Reinforced Concrete Abutment	152	ft	137	15	0	0
	Walls on the old center section have hairline random cracks. Wingwalls in good condition. Both abut walls have efflorescence staining at the construction joints.						
1120/3	Efflorescence/Rust Staining	15	ft	0	15	0	0
	<i>Efflorescence staining in the construction joints and a couple hairline cracks.</i>						
330/3	Metal Bridge Railing	20	ft	20	0	0	0
	Galvanized pedestrian fence along the left exterior, set on the concrete curb. Satisfactory condition.						
515/3	Steel Protective Coating	70	sq.ft	70	0	0	0
	<i>Galvanizing is in satisfactory condition.</i>						



**Idaho Transportation Department
Bridge Inspection Report**

Bridge Key:	17875	Structure Name:	S07500A 128.12
(8) Features Intersected:	TRAIL CREEK	(9) Location:	KETCHUM SCL
Xref Structure Name:		Admin Jurisdiction:	0004 District 4
		District:	04

Additional Information

ROADWAY APPROACHES: Asphalt roadway has several asphalt overlays with a chipseal in good condition.

SIDEWALKS/CURBS: Both concrete curbs have random hairline cracks, delamination and minor spalling. Asphalt sidewalk on the west side of the structure in satisfactory condition. Chain link fence on top of the curb, left side.

EMBANKMENT: Earth fill in good condition. Minor erosion under outside porta-rail, abutment 2 left side.

CHANNEL: Rock channel is in good condition. Inlet and outlet has rock rip-rap protection.

GUARDRAIL: Concrete porta-rail in fair condition on Lt. side with some moderate scaling on several of the sections. Not attached to the structure. Unpainted w-beam along right side. No post set in fill over structure.

SIGNS:

UTILITIES: Overhead utilities on the right side. Buried utilities along both shoulders.

NOTES: None.

INSPECTION FREQUENCY:

SCOUR:

WORK ACCOMPLISHED: Routine roadway maintenance.

Maintenance Recommendations

Recommendation	Priority	Suggested Work Assignment
Repair undermined porta rail.	Low	State Forces

Jim Holland

Digitally signed by Jim Holland
DN: cn=Jim Holland, o=ITD, ou=Bridge Asset Management,
email=jim.holland@itd.idaho.gov, c=US
Date: 2016.07.27 08:30:47 -06'00'

Inspector's Signature:

07/11/2016

Inspector Number and Name: 950 - Jim Holland, ITD Bridge Inspector



**Idaho Transportation Department
Bridge Inspection Report**

Bridge Key:	17875	Structure Name:	S07500A 128.12
(8)Features Intersected:	TRAIL CREEK	(9)Location:	KETCHUM SCL
Xref Structure Name:		Admin Jurisdiction:	0004 District 4
		District:	04

IDENTIFICATION	
(1)State:	16 Idaho
(2)District:	District 4
(3)County:	013 Blaine
(4)Place Code:	Ketchum
(5)Inventory Route:	131000750
(7)Facility Carried:	SH 75
(11)Milepoint:	128.109
(12)Base Hwy Network:	On Base Network
(13a)LRS Inventory Route:	
(13b)LRS Sub Route:	
(16)Latitude:	43° 40' 40"
(17)Longitude:	114° 21' 41"
(98)Border Bridge Code:	
(99)Border Bridge ID:	
Segment Code:	002230
Segment Under Rte:	
Segment Other Rte:	
Drawing Number:	847
Project Key Number:	276
Inspection Area:	4

Sufficiency Rating: **94.0**
Deficiency:

CLASSIFICATION	
(112)NBIS Length:	Too Short
(104)Highway System:	0 Not on NHS
(26)Functional Class:	06 Rural Minor Arterial
(100)Defense Highway:	0 Not a STRAHNET hwy
(101)Parallel Structure:	No bridge exists
(102)Direction of Traffic:	2 2-way traffic
(103)Temporary Structure:	
(105)Federal Lands Highway:	0 N/A (NBI)
(110)Design Natl Network:	1 Part of natl network
(20)Toll Facility:	3 On free road
(21)Custodian:	State Highway Agency
(22)Owner:	State Highway Agency
(37)Historical Significance:	3 Possibly eligible for

STRUCTURE TYPE AND MATERIALS	
(43a/b)Main Span Material/Design:	1 Concrete 7 Frame
(44a/b)Approach Span Material/Design:	
(45)No. of Spans Main Unit:	1
(46)No. of Approach Spans:	0
(107)Deck Type:	1 Concrete-Cast-in-Place
(108a)Wearing Surface:	6 Bituminous
(108b)Membrane:	0 None
(108c)Deck Protection:	None

GEOMETRIC DATA	
(48)Maximum Span Length:	20.0 ft
(49)Structure Length:	20 ft
Total Length:	20 ft
(50a)Curb/Sidewalk Width Lt:	8.0 ft
(50b)Curb/Sidewalk Width Rt:	1.3 ft
(51)Width Curb to Curb:	32.8 ft
(52)Width Out to Out:	48.1 ft
(32)App Roadway Width:	30 ft
(33)Median:	0 No median
(34)Skew:	0°
(35)Structure Flared:	0 No flare
(10)Vertical Clearance:	99.99 ft
(47)Total Horiz Clearance:	32.8 ft
(53)Min Vert Clr Over Deck:	99.99 ft
(54a)Min Vert Underclr Ref:	N Feature not hwy or RR
(54b)Min Vert Underclr:	0.0 ft
(55a)Min Lat Underclr Ref Rt:	N Feature not hwy or RR
(55b)Min Lat Underclr Rt:	0.0 ft
(56)Min Lat Underclr Lt:	0.0 ft

Deck Applications	

Environmental	
Environmental Concerns:	No



Idaho Transportation Department Bridge Inspection Report

Bridge Key: 17875	Structure Name: S07500A 128.12
(8) Features Intersected: TRAIL CREEK	(9) Location: KETCHUM SCL
Xref Structure Name:	Admin Jurisdiction: 0004 District 4
	District: 04

LOAD RATING	
(31) Design Load:	2 M 13.5 (H 15)
(64) Operating Rating:	61 tons / HS33.9
(66) Inventory Rating:	36 tons / HS20.0
(70) Posting:	5 A/Above Legal Loads
(41) Posting Status:	A Open, no restriction

CONDITION	
(58) Deck:	6 Satisfactory
(59) Superstructure:	6 Satisfactory
(60) Substructure:	6 Satisfactory
(61) Channel/Protection:	7 Minor Damage
(62) Culvert:	N N/A (NBI)

AGE AND SERVICE	
(27) Year Built:	1929
(106) Year Reconstructed:	1980
(42a) Type of Service On:	1 Highway
(42b) Type of Service Under:	5 Waterway
(28a) Lanes On: 2	(28b) Lanes Under: 0
(29) ADT:	12500
(30) Year of ADT:	2014
(109) Truck ADT:	4%
(19) Detour Length:	1 miles
Speed Limit:	25 MPH

APPRAISAL	
(67) Structure Condition:	6 Equal Min Criteria
(68) Deck Geometry:	4 Tolerable
(69) Undrclear, Vert and Horiz:	N Not applicable (NBI)
(71) Waterway Adequacy:	8 Equal Desirable
(72) Approach Alignment:	8 Equal Desirable Crit
(36) Traffic Safety Features:	
(a) Bridge Rail:	0 Substandard
(b) Transition:	0 Substandard
(c) Approach Rail:	0 Substandard
(d) Approach Rail Ends:	0 Substandard
(113) Scour Critical:	8 Stable Above Footing

PROPOSED IMPROVEMENTS	
(75a) Type of Work:	31 Repl-Load Capacity
(75b) Work Done By:	1 Contract
(76) Length of Improvement:	40 ft
(94) Bridge Improvement Cost:	\$290,000
(95) Rdwy Improvement Cost:	\$29,000
(96) Total Project Cost:	\$440,000
(97) Year of Cost Estimate:	2010
(114) Future ADT:	18750
(115) Year of Future ADT:	2034
YEAR PROGRAMMED:	

NAVIGATION DATA	
(38) Navigation Control:	Permit Not Required
(39) Vertical Clearance:	
(40) Horizontal Clearance:	
(111) Pier Protection:	
(116) Lift Bridge Vert Clr:	

INSPECTION			
(90) Inspection Date:	7/11/2016	(91) Inspection Frequency:	48 months
(92) Supplemental Inspections Frequency:		(93) Date of Inspections:	
(a) Fracture Critical Detail:	NA	(a) FC Inspection Date:	
(b) Underwater Inspection:	NA	(b) UW Inspection Date:	
(c) Fatigue Detail (OS) Inspection:	NA	(c) Fatigue Detail (OS) Date:	
(d) UBIT Inspection:	NA	(d) UBIT Date:	
(e) Confined Space Inspection:	NA	(e) Confined Space Date:	
Channel Cross Section Year:			
Equipment Needed for Regular Inspection?	None		



**Idaho Transportation Department
Bridge Inspection Report**

Bridge Key:	17875	Structure Name:	S07500A 128.12
(8) Features Intersected:	TRAIL CREEK	(9) Location:	KETCHUM SCL
Xref Structure Name:		Admin Jurisdiction:	0004 District 4
		District:	04

WEARING SURFACE and DEAD LOAD INFORMATION

Asphalt:	8.5 inches	Concrete:	0.0 inches
Granular:	11.0 inches	Timber:	0.0 inches

POSTING INFORMATION

WEIGHT

Load Analysis Date: 08/15/2014
 Load Analysis Required: N Analysis Complete

Load Rating Analysis

	IR (tons)	OR (tons)	Recommended Posting(tons)	Actual Posting(tons)
H Truck	20	34		
HS Truck	36	61		
Type3 (3 axle)	30	50	Type3 (3 axle)	
Type 3S2 (5 axle)	48	80	Type 3S2 (5 axle)	
Type 3-3 (6 axle)	60	100	Type 3-3 (6 axle)	
			Max Axle	

HEIGHT

	Recommended	Actual
Height Posting:		

ACTUAL WIDTH POSTING

Single Lane All Vehicles:	N
Single Lane Trucks/Buses:	N



Idaho Transportation Department Bridge Inspection Report

Bridge Key:	17675	Structure Name:	S07500A. 128.12
(6)Features Intersected:	TRAIL CREEK	(9)Location:	KETCHUM SCL
Xref Structure Name:		Admin Jurisdiction:	0004 District 4
		District:	04



Approach plus milepost



Right side



**Idaho Transportation Department
Bridge Inspection Report**

Bridge Key:	17675	Structure Name:	S07500A.128.12
(6)Features Intersected:	TRAIL CREEK	(9)Location:	KETCHUM SCL
Xref Structure Name:		Admin Jurisdiction:	0004 District 4
		District:	04



Erosion under rail at northwest corner

Appendix I. City of Ketchum Floodplain Permit Status



City of Ketchum
Planning & Building

MEMO

PROJECT: SH-75 Trail Creek Bridge Replacement

ADFP#: P20-037

OWNER: Bridge and Right-of-Way: Idaho Transportation Department (ITD)

REPRESENTATIVE: Nathan Jerke, Project Manager, ITD

ENGINEER: Mike Shubert, P.E., HDR

LOCATION: SH-75 Bridge spanning Trail Creek, ITD right-of-way, Ketchum City Limits

ZONING: Base Zone: N/A, right-of-way
Overlay: Floodplain, Floodway, and Riparian Zone

ATTACHMENTS: A. Hydraulics Report, SH-75 Trail Creek Bridge, HDR, November 15, 2020
B. Memo, Harmony Design & Engineering, December 6, 2020

DOCUMENTS REVIEWED:

1. Memo, Harmony Design & Engineering, December 6, 2020
2. Memo, HDR, November 17, 2020
3. Hydraulics Report, SH-75 Trail Creek Bridge, with Appendices A-I, HDR, November 15, 2020
4. Memo, HDR, July 24, 2020
5. Memo, HDR, July 9, 2020
6. Hydraulics Report, SH-75 Trail Creek Bridge, with Appendices A-I, HDR, July 9, 2020
 - a. Includes Engineering "No-Rise" Certificate, July 9, 2020
7. Site and vicinity photos, Brittany Skelton, June 18, 2020
8. Cross sections - locations for photos, Google Earth KMZ file, received June 4, 2020
9. Meeting notes summary, HDR, May 28, 2020
10. Memo, Harmony Design & Engineering, April 28, 2020
11. Memo, HDR, April 3, 2020

12. Application, March 30, 2020
13. Memo, HDR, March 30, 2020
14. Hydraulics Report, SH-75 Trail Creek Bridge, with Appendices A-I, HDR, April 1, 2020

BACKGROUND FACTS

1. The City of Ketchum is a municipal corporation organized under Article XII of the Idaho Constitution and the laws of the State of Idaho, Title 50, Idaho Code. Under Chapter 65, Title 67 of the Idaho Code, the City is required to pass certain ordinances regarding land use, including a zoning ordinance.
2. Pursuant to Zoning Code Title 17, Section 17.88.050(D)1, the administrator shall have the authority to consider and approve, approve with conditions, or deny applications for floodplain development permits and for waterways design review.
3. The Idaho Transportation (ITD) is developing design and construction documents for the SH-75 Bridge that spans Trail Creek in Ketchum city limits. The project is located in the floodplain and crosses the floodway. The project is anticipated to occur in FY2026.
4. HDR Engineering, on behalf of the Idaho Transportation Department (ITD) submitted documents for review in order to receive concurrence from the City of Ketchum regarding the hydraulics report in advance.
5. This memo serves to document concurrence with HDR's SH75 Trail Creek Bridge hydraulics report dated November 15, 2020.
6. ITD and their engineer, HDR, will coordinate with the City of Ketchum to obtain a permit prior to commencement of the project in FY206; a permit issued at this time would expire prior to the start of the project: City of Ketchum floodplain permits expire after one (1) year, allowed extensions may only extend a permit approval for up to an additional two (2) years.

DATED this 8th day of February, 2021



Brittany Skelton
Senior Planner, CFM

- ATTACHMENTS:**
- A. Hydraulics Report, SH-75 Trail Creek Bridge, HDR, November 15, 2020
 - B. Memo, Harmony Design & Engineering, December 6, 2020

ATTACHMENT A.

Hydraulics Report, SH-75 Trail Creek Bridge, HDR, November 15, 2020



July 24, 2020

Dear Brittany Skelton, City of Ketchum,

The Idaho Transportation Department (ITD) is developing design and construction documents for the SH-75 Bridge over Trail Creek in the City of Ketchum. The project is located in the floodplain and crosses the floodway. Therefore, a floodplain development permit and no-rise are required for the project. A brief memo is attached addressing this project and how it meet or exceeds permitting criteria set forth by the City of Ketchum. The draft ITD hydraulic report is also attached.

The purpose of this submittal address the City's comments on the hydraulic report and attain the City's concurrence that the hydraulic design meets or exceeds the City's criteria and needs for floodplain development. Since the project substantially increases flood conveyance, ITD believes that the design exceeds floodplain development criteria. The City also requested ITD evaluate changes to stream stability as a result of the project. This report concludes that the project is unlikely to impact the stable channel immediately upstream and downstream of the project. ITD understands that the City cannot require the state to pay a review fee, based on similar projects completed by ITD with other public permitting agencies.

The City's ordinance indicates that construction projects should be completed within 180 days of permit issuance. Since construction for this project is not planned until 2026, additional coordination or submittals may be needed at a later date. ITD requests a conditional permit or statement of concurrence related to the hydraulic design of the stream crossing. If you have any questions related to this submittal, please contact me at 208-387-7070 or Michael.Schubert@hdrinc.com.

Sincerely,

A handwritten signature in blue ink that reads "Michael Schubert".

Michael Schubert, PE
Water Resources Engineer



Memo

To: Brittany Skelton, City of Ketchum

From: Jennifer Zung, PE, CFM

Date: 12/6/2020

Re: SH-75 Trail Creek Bridge



I have reviewed the revised hydraulics report for the SH-75 Trail Creek Bridge Project by HDR dated November 15, 2020, and response memo dated November 17, 2020. The report and analysis were modified in response to comments made in a memo from Harmony Design & Engineering dated April 28, 2020, and a subsequent meeting held on May 28, 2020.

All comments in the April 28, 2020 memo have been addressed satisfactorily.

END OF DOCUMENT



Governor Brad Little

Director Mathew Weaver

July 19, 2024

Jesse Barrus
ITD Dist. 4
216 South Date Street
Shoshone, ID 83352

RE: Joint Application for Permit No. S37-20698
Trail Creek – Bridge Replacement

Dear ITD,

The Idaho Department of Water Resources (IDWR) has reviewed your above referenced application for a permit to alter Trail Creek and has prepared a decision as provided for in Section 42-3805, Idaho Code. The conditions set forth in this permit are intended to prevent degradation of water quality, protect fish and wildlife habitat, and protect the long-term stability of the stream channel. If you cannot meet the conditions set forth in the permit, please contact this office for further consideration.

Your project has been determined to meet the Stream Channel Alteration Rules, IDAPA 37.03.07 Minimum Standards (Rule 55). You may consider this letter a permit to construct your project according to your application, received May 31, 2024, including diagrams. The project location is within Township 04 North, Range 18 East, Section 18, Boise Meridian, Blaine County, Idaho.

Project activities include replacing a bridge over Trail Creek and stabilizing a streambank adjacent to the bridge. Once dewatering measures are in place, the old bridge will be removed, and new footings will be constructed above the Ordinary High Water Mark. Approximately 74-cubic yards of clean angular rock riprap, and natural streambed material, will be discharged to reconstruct the stream channel below the bridge and help protect the abutments from scour. A new bridge deck will be set on the abutments in a way that allows a minimum of one (1) foot of freeboard between the 1% flow elevation and the low chord of the bridge. Approximately 98-feet of streambank below the bridge will be stabilized using rock and soil lifts. Approximately 106-cubic yards of clean angular rock riprap and approximately 13-cubic yards of earthen fill will be discharged to help stabilize the streambank. The newly constructed streambank will be heavily planted with native woody vegetation.

Project activities also include replacing several culverts on unnamed ditches. It has been determined that an IDWR Stream Channel Alteration Permit will not be required for this work as provided for within Section 42-3802(d), Idaho Code.

Failure to adhere to the conditions as set forth herein can result in legal action as provided for in Section 42-3809, Idaho Code. This project is subject to the following Minimum Standards, Special and General Conditions.

MINIMUM STANDARDS:

These standards are established in the Administrative Rules of the Idaho Water Resources Board; Stream Channel Alteration Rules, IDAPA 37.03.07 dated July 1, 2021, and are enclosed with this permit.

Rule 56 – Construction Procedures
Rule 59 – Culverts and Bridges

SPECIAL CONDITIONS:

[1] All work shall be completed in accordance with the descriptions and methods on the application and diagrams, received May 31, 2024, attached herewith. This office must approve any changes prior to construction.

[2] All construction activities shall take place during low flow and in the dry to minimize turbidity, protect water quality, and comply with Idaho water quality standards.

[3] A minimum of 1-foot of freeboard shall be maintained between the low chord of the bridge and a 1% flow event, during installation.

[4] In water work shall only occur between July 15 and March 15.

[5] Along the stabilized streambank single cuttings shall be planted no greater than 2-foot intervals and bundles or rooted stock shall be planted no greater than 5-foot intervals. Vegetation shall be planted deep enough to reach low water and a native species to Idaho.

[6] Disturbed areas shall be reseeded with a native seed mix after construction to help reduce erosion.

[7] Cass Jones, IDWR Stream Protection Program 208-287-4897, shall be contacted within fourteen (14) business days after completion of in-water work.

[8] Silt fencing or other erosion/sediment control measures shall be installed between any area of earth disturbance and the water. Erosion and sediment control measures must be installed during construction, according to the manufacturer's specifications, and must be maintained until construction is completed and the disturbed ground is revegetated and stable.

[9] All temporary structures, excess excavated material, and vegetative or construction debris shall be disposed of out of the stream channel where it cannot reenter the channel. All construction debris shall be removed from the site and disposed of properly.

[10] All fuel, oil, and other hazardous materials shall be stored and equipment refueled away from the stream channel to ensure that a spill will not enter the waterway. Equipment must be free of fuel and lubricant leaks.

[11] Permittee is responsible for all work done by any contractor or sub-contractor and shall ensure any contractor who performs the work is informed of and follows all the terms and conditions of this authorization.

[12] This permit shall expire December 31, 2027.

GENERAL CONDITIONS:

1. This permit does not constitute any of the following:
 - a. An easement or right-of-way to trespass or work upon property belonging to others.
 - b. Other approval that may be required by Local, State or Federal Government, unless specifically stated in the special conditions above.
 - c. Responsibility of IDWR for damage to any properties due to work done.
 - d. Compliance with the Federal Flood Insurance Program, FEMA regulations, or approval of the local Planning and Zoning authority.
2. In accordance with Sections 55-2201 - 55-2210, Idaho Code, the applicant and/or contractors must contact Digline statewide phone number 1-800-342-1585 (Boise area 208-342-1585) not less than three working days prior to the start of any excavation for this project.
3. The permit holder or operator must have a copy of this permit at the alteration site, available for inspection at all times.
4. IDWR may cancel this permit at any time that it determines such action is necessary to minimize adverse impact on the stream channel.

Failure to adhere to conditions as set forth herein can result in legal action as provided for in Section 42-3809, Idaho Code.

If you object to the decision issuing this permit with the above conditions, you have 15 days in which to notify this office in writing that you request a formal hearing on the matter. If an objection has not been received within 15 days, the decision will be final under the provisions of IDAPA 37.03.07 (Rule 70).

Please contact Cass Jones 208-287-4897 or cass.jones@idwr.idaho.gov if you have any questions regarding this matter.

Sincerely,



Cass Jones
Stream Channel Protection
Idaho Department of Water Resources

cc: Rachel Martin, Blaine County
Sean Woodhead, Idaho Department of Environmental Quality, Twin Falls
Bradley Dawson, Idaho Department of Fish and Game, Jerome
Randal Brunmeier, Idaho Department of Lands, Jerome
U.S. Army Corps of Engineers, Boise
Aaron Golart, Idaho Department of Water Resources, Boise

056. CONSTRUCTION PROCEDURES (RULE 56).

01. Conformance to Procedures. Construction shall be done in accordance with the following procedures unless specific approval of other procedures has been given by the Director. When an applicant desires to proceed in a manner different from the following, such procedures should be described on the application. (3-18-22)

02. Operation of Construction Equipment. No construction equipment shall be operated below the existing water surface without specific approval from the Director except as follows: Forging the stream at one (1) location only will be permitted unless otherwise specified; however, vehicles and equipment will not be permitted to push or pull material along the streambed below the existing water level. Work below the water which is essential for preparation of culvert bedding or approved footing installations shall be permitted to the extent that it does not create unnecessary turbidity or stream channel disturbance. Frequent forging will not be permitted in areas where extensive turbidity will be created. (3-18-22)

03. Temporary Structures. Any temporary crossings, bridge supports, cofferdams, or other structures that will be needed during the period of construction shall be designed to handle high flows that could be anticipated during the construction period. All structures shall be completely removed from the stream channel at the conclusion of construction and the area shall be restored to a natural appearance. (3-18-22)

04. Minimizing Disturbance of Area. Care shall be taken to cause only the minimum necessary disturbance to the natural appearance of the area. Streambank vegetation shall be protected except where its removal is absolutely necessary for completion of the work adjacent to the stream channel. (3-18-22)

05. Disposal of Removed Materials. Any vegetation, debris, or other material removed during construction shall be disposed of at some location out of the stream channel where it cannot reenter the channel during high stream flows. (3-18-22)

06. New Cut of Fill Slopes. All new cut or fill slopes that will not be protected with some form of riprap shall be seeded with grass and planted with native vegetation to prevent erosion. (3-18-22)

07. Fill Material. All fill material shall be placed and compacted in horizontal lifts. Areas to be filled shall be cleared of all vegetation, debris and other materials that would be objectionable in the fill. (3-18-22)

08. Limitations on Construction Period. The Director may limit the period of construction as needed to minimize conflicts with fish migration and spawning, recreation use, and other uses. (3-18-22)

059. CULVERTS AND BRIDGES (RULE 59).

01. Culverts and Bridges. Culverts and bridges shall be capable of carrying streamflows and shall not significantly alter conditions upstream or downstream by causing flooding, turbidity, or other problems. The appearance of such installations shall not detract from the natural surroundings of the area. (3-18-22)

02. Location of Culverts and Bridges. Culverts and bridges should be located so that a direct line of approach exists at both the entrance and exit. Abrupt bends at the entrance or exit shall not exist unless suitable erosion protection is provided. (3-18-22)

03. Ideal Gradient. The ideal gradient (bottom slope) is one which is steep enough to prevent silting but flat enough to prevent scouring due to high velocity flows. It is often advisable to make the gradient of a culvert coincide with the average streambed gradient. (3-18-22)

a. Where a culvert is installed on a slope steeper than twenty percent (20%), provisions to anchor the culvert in position will be required. Such provisions shall be included in the application and may involve the use of collars, headwall structures, etc. Smooth concrete pipe having no protruding bell joints or other irregularities shall have such anchoring provisions if the gradient exceeds ten percent (10%). (3-18-22)

04. Size of Culvert or Bridge Opening. The size of the culvert or bridge opening shall be such that it is capable of passing design flows without overtopping the streambank or causing flooding or other damage. (3-18-22)

a. Design flows shall be based upon the following minimum criteria:

Drainage Area	Design Flow Frequency
Less than 50 sq. mi.	25 Years
Over 50 sq. mi. or more	50 years or greatest flow of record, whichever is more

(3-18-22)

b. For culverts and bridges located on U.S. Forest Service or other federal lands, the sizing should comply with the Forest Practices Act as adopted by the federal agencies or the Department of Lands. (3-18-22)

c. For culverts or bridges located in a community qualifying for the national flood issuance program, the minimum size culvert shall accommodate the one hundred (100) year design flow frequency. (3-18-22)

d. If the culvert or bridge design is impractical for the site, the crossing may be designed with additional flow capacity outside the actual crossing structure, provided there is no increase in the Base Flood Elevation.

(NOTE: When flow data on a particular stream is unavailable, it is almost always safe to maintain the existing gradient and cross-section area present in the existing stream channel. Comparing the proposed crossing size with others upstream or downstream is also a valuable means of obtaining information regarding the size needed for a proposed crossing.) (3-18-22)

e. Minimum clearance shall be at least one (1) foot at all bridges. This may need to be increased substantially in the areas where ice passage or debris may be a problem. Minimum culvert sizes required for stream crossings: (3-18-22)

i. Eighteen (18) inch diameter for culverts up to seventy (70) feet long; (3-18-22)

ii. Twenty-four (24) inch diameter for all culverts over seventy (70) feet long. (3-18-22)

f. In streams where fish passage is of concern as determined by the director, an applicant shall comply with the following provisions and/or other approved criteria to ensure that passage will not be prevented by a proposed crossing. (3-18-22)

g. Minimum water depth shall be approximately eight (8) inches for salmon and steelhead and at least three (3) inches in all other cases. (3-18-22)

h. Maximum flow velocities for streams shall not exceed those shown in Figure 17 in APPENDIX H, located at the end of this chapter, for more than a forty-eight (48) hour period. The curve used will depend on the type of fish to be passed. (3-18-22)

i. Where it is not feasible to adjust the size or slope to obtain permissible velocities, the following precautions may be utilized to achieve the desired situation. (3-18-22)

j. Baffles downstream or inside the culvert may be utilized to increase depth and reduce velocity. Design criteria may be obtained from the Idaho Fish and Game Department. (3-18-22)

k. Where multiple openings for flow are provided, baffles or other measures used in one (1) opening only shall be adequate provided that the opening is designed to carry the main flow during low-flow periods. (3-18-22)

05. Construction of Crossings. When crossings are constructed in erodible material, upstream and downstream ends shall be protected from erosive damage through the use of such methods as dumped rock riprap, headwall structures, etc., and such protection shall extend below the erodible streambed and into the banks at least two (2) feet unless some other provisions are made to prevent undermining. (3-18-22)

a. Where fish passage must be provided, upstream drops at the entrance to a culvert will not be permitted and a maximum drop of one (1) foot will be permitted at the downstream end if an adequate jumping pool is maintained below the drop. (3-18-22)

b. Downstream control structures such as are shown in Figure 18 in APPENDIX I, located at the end of this chapter, can be used to reduce downstream erosion and improve fish passage. They may be constructed with gabions, pilings and rock drop structures. (3-18-22)

06. Multiple Openings. Where a multiple opening will consist of two (2) or more separate culvert structures, they shall be spaced far enough apart to allow proper compaction of the fill between the individual structures. The minimum spacing in all situations shall be one (1) foot. In areas where fish passage must be provided, only one (1) opening shall be constructed to carry all low flows. Low flow baffles may be required to facilitate fish passage. (3-18-22)

07. Areas to be Filled. All areas to be filled shall be cleared of vegetation, topsoil, and other unsuitable material prior to placing fill. Material cleared from the site shall be disposed of above the high water line of the stream. Fill material shall be reasonably well-graded and compacted and shall not contain large quantities of silt, sand, organic matter, or debris. In locations where silty or sandy material must be utilized for fill material, it will be necessary to construct impervious sections both upstream and downstream to prevent the erodible sand or silt from being carried away (see Figure 19, APPENDIX J, located at the end of this chapter), Sideslopes for fills shall not exceed one and one half to one (1.5:1). Minimum cover over all culvert pipes and arches shall be one (1) foot. (3-18-22)

08. Installation of Pipe and Arch Culvert. All pipe and arch culverts shall be installed in accordance with manufacturer's recommendations. (3-18-22)

a. The culvert shall be designed so that headwaters will not rise above the top of the culvert entrance unless a headworks is provided. (3-18-22)

JOINT APPLICATION FOR PERMITS

U.S. ARMY CORPS OF ENGINEERS - IDAHO DEPARTMENT OF WATER RESOURCES - IDAHO DEPARTMENT OF LANDS

Authorities: The Department of Army Corps of Engineers (Corps), Idaho Department of Water Resources (IDWR), and Idaho Department of Lands (IDL) established a joint process for activities impacting jurisdictional waterways that require review and/or approval of both the Corps and State of Idaho. Department of Army permits are required by Section 10 of the Rivers & Harbors Act of 1899 for any structure(s) or work in or affecting navigable waters of the United States and by Section 404 of the Clean Water Act for the discharge of dredged or fill materials into waters of the United States, including adjacent wetlands. State permits are required under the State of Idaho, Stream Protection Act (Title 42, Chapter 38, Idaho Code and Lake Protection Act (Section 58, Chapter 13 et seq., Idaho Code). In addition the information will be used to determine compliance with Section 401 of the Clean Water Act by the appropriate State, Tribal or Federal entity.

Joint Application: Information provided on this application will be used in evaluating the proposed activities. Disclosure of requested information is voluntary. Failure to supply the requested information may delay processing and issuance of the appropriate permit or authorization. **Applicant will need to send a completed application, along with one (1) set of legible, black and white (8½"x11"), reproducible drawings that illustrate the location and character of the proposed project / activities to both the Corps and the State of Idaho.**

See Instruction Guide for assistance with Application. Accurate submission of requested information can prevent delays in reviewing and permitting your application. Drawings including vicinity maps, plan-view and section-view drawings must be submitted on 8-1/2 x 11 papers.

Do not start work until you have received all required permits from both the Corps and the State of Idaho

FOR AGENCY USE ONLY

USACE NWW-	Date Received:	<input type="checkbox"/> Incomplete Application Returned	Date Returned:
Idaho Department of Water Resources No.	Date Received:	<input type="checkbox"/> Fee Received DATE:	Receipt No.:
Idaho Department of Lands No.	Date Received:	<input type="checkbox"/> Fee Received DATE:	Receipt No.:

INCOMPLETE APPLICANTS MAY NOT BE PROCESSED

1. CONTACT INFORMATION - APPLICANT Required:			2. CONTACT INFORMATION - AGENT:		
Name: Jesse Barrus (District Engineer) or Scott Malone (Engineer Manager)			Name: Nathan Jerke		
Company: Idaho Transportation Department (ITD) District 4			Company: Idaho Transportation Department (ITD) District 4		
Mailing Address: 216 South Date Street			Mailing Address: 216 South Date Street		
City: Shoshone	State: ID	Zip Code: 83352-1521	City: Shoshone	State: ID	Zip Code: 83352-1521
Phone Number (include area code): 208-886-7800	E-mail: scott.malone@itd.idaho.gov		Phone Number (include area code): 208-886-7809	E-mail: nathan.jerke@itd.idaho.gov	

3. PROJECT NAME or TITLE: SH-75, Elkhorn Rd to River St			4. PROJECT STREET ADDRESS: SH-75 MP 126.4 to MP 128.2		
5. PROJECT COUNTY: Blaine	6. PROJECT CITY: Ketchum	7. PROJECT ZIP CODE: 83340	8. NEAREST WATERWAY/WATERBODY: Trail Creek		
9. TAX PARCEL ID#:	10. LATITUDE: 43.667041 (approx. center) LONGITUDE: -114.355657	11a. 1/4:	11b. 1/4:	11c. SECTION: 18, 19, 30	11d. TOWNSHIP: 4N
12a. ESTIMATED START DATE: Jan 1, 2025	12b. ESTIMATED END DATE: Oct 31, 2027	13a. IS PROJECT LOCATED WITHIN ESTABLISHED TRIBAL RESERVATION BOUNDARIES? <input checked="" type="checkbox"/> NO <input type="checkbox"/> YES Tribe:			
13b. IS PROJECT LOCATED IN LISTED ESA AREA? <input type="checkbox"/> NO <input checked="" type="checkbox"/> YES		13c. IS PROJECT LOCATED ON/NEAR HISTORICAL SITE? <input checked="" type="checkbox"/> NO <input type="checkbox"/> YES			

14. DIRECTIONS TO PROJECT SITE: Include vicinity map with legible crossroads, street numbers, names, landmarks.

The Project begins on SH-75 at approximately mile post (MP) 126.4 and ends near MP 128.2 at the intersection of River Street. The Project may be accessed from I-84 by taking US-93 (which transitions to SH-75) north to Ketchum, Idaho. From the City of Ketchum, take Main St south which transitions to SH-75.

15. PURPOSE and NEED: Commercial Industrial Public Private Other

Describe the reason or purpose of your project; include a brief description of the overall project. Continue to Block 16 to detail each work activity and overall project.

This Project aims to improve safety and capacity on SH-75 between the Big Wood River Bridge near Elkhorn Road and River Street in the City of Ketchum in Blaine County, mileposts (MP) 126.4 to 128.2. Project development will include roadway widening with curb, gutter, sidewalk, intersection improvement, retaining walls, drainage, public involvement, and replacing a box culvert and constructing a reinforced slope along Trail Creek.

16. DETAILED DESCRIPTION OF EACH ACTIVITY WITHIN OVERALL PROJECT. Specifically indicate portions that take place within waters of the United States, including wetlands: Include dimensions; equipment, construction, methods; erosion, sediment and turbidity controls; hydrological changes: general stream/surface water flows, estimated winter/summer flows; borrow sources, disposal locations etc.:

The wetland and stream impacts are a result of road widening, bridge replacement (construction of a reinforced slope to stabilize the stream bank on Trail Creek and construction of wildlife bench), and the installation of a stormwater facility. Work within wetlands consists of fill placement for roadway widening, scour protection, and stream bank grading to increase hydraulic flow. Additionally, culvert work will be required. This will include installation of a concrete box and headwalls, modification of stormwater pond, and replacement of three irrigation culverts and irrigation crossing. Construction equipment will include rollers, backhoes, excavators, cranes, and other construction equipment typical for a roadway and bridge construction project. All materials sources will be determined by the contractor and approved by the project engineer. Waste materials will be disposed of in an approved upland location. All bridge improvements will be located outside of the existing and proposed stream channels. The project is designed to restore a more natural channel gradient, bed, and width, and improved bank stability through the structure. New bridge footings will be constructed above OHWM. (See Attachment C, page 6 and 7). Equipment will include an excavator operating from the bank/existing roadway. The construction area below the OHWM of the open waters will be dewatered using sandbags or another similar temporary dewatering method. A qualified Biologist will capture and remove fish from the dewatered work area if needed. A pump with a fish screen will be used to transfer water. The in-water work window will be observed for construction from July 15 to March 15, which was confirmed by Idaho Department of Water Resources (IDWR) and Idaho Department of Fish and Game (IDFG), see interagency meeting minutes dated October 12 & 13, 2021.

An ITD approved Storm Water Pollution Prevention Plan (SWPPP) will be prepared for this project to comply with the Construction General permit. The SWPPP will include measures to address sediment and erosion control with both temporary and permanent measures. Critical areas including wetlands will be marked to retain and protect on Design Plans and SWPPP Plans except as allowed in 404 and other permits. The perimeter of the wetlands that are not permitted to be impacted will be clearly marked with high visibility silt fence.

17. DESCRIBE ALTERNATIVES CONSIDERED to AVOID or MEASURES TAKEN to MINIMIZE and/ or COMPENSATE for IMPACTS to WATERS of the UNITED STATES, INCLUDING WETLANDS: See Instruction Guide for specific details.

The do nothing alternative is not practicable because it does not meet the purpose and need of the project. Improvements that will not result in wetland impacts are not prudent or practicable since the highway must be widened in order to build the alternative and improve safety and capacity on SH-75 as described in the SH-75 Timmerman to Ketchum Final Environmental Impact Statement (FEIS) and Record of Decision (ROD) which was approved in August 2008. The FEIS-ROD was reevaluated in 2023 and approved by FHWA.

Tree removal along the riparian corridor will be minimized by using retaining walls and a reinforced slope along Trail Creek. The disturbed riparian area and reinforced slope will be planted with native plant species.

The existing box culvert at Trail Creek will be replaced with a clear span bridge which will improve hydrological flow and increase the amount of available aquatic habitat.

18. PROPOSED MITIGATION STATEMENT or PLAN: If you believe a mitigation plan is not needed, provide a statement and your reasoning why a mitigation plan is NOT required. Or, attach a copy of your proposed mitigation plan.

The total wetland impacts are 1,956 square feet (SF) (0.0449 acres). The total open water impacts are 1,555 SF (0.0358 acres). The streambed impacts at Trail Creek are temporary, and beneficial improvements would be about 175 SF. Additional self-mitigating stabilization will be through a vegetated wall along the stream bank for 716 SF; therefore, mitigation is not expected through the USACE. The old SH-75 bridge will be removed, and the new bridge will have a 30 feet longer span than the current design and will increase the available streambed by 1,642 SF (0.0377 acres). Mitigation will be on-site at Trail Creek for EO 11990. (The mitigation plan for FHWA is available upon request.)

19. TYPE and QUANTITY of MATERIAL(S) to be discharged below the ordinary high water mark and/or wetlands:

Dirt or Topsoil: _____ cubic yards
 Dredged Material: _____ cubic yards
 Clean Sand: _____ cubic yards
 Clay: _____ cubic yards
 Gravel, Rock, or Stone: _____ cubic yards
 Concrete: _____ cubic yards
 Other (describe): See Attachments : _____ cubic yards
 Other (describe): _____ : _____ cubic yards

TOTAL: _____ cubic yards

20. TYPE and QUANTITY of impacts to waters of the United States, including wetlands:

Filling: _____ acres _____ sq ft. _____ cubic yards
 Backfill & Bedding: _____ acres _____ sq ft. _____ cubic yards
 Land Clearing: _____ acres _____ sq ft. _____ cubic yards
 Dredging: _____ acres _____ sq ft. _____ cubic yards
 Flooding: _____ acres _____ sq ft. _____ cubic yards
 Excavation: _____ acres _____ sq ft. _____ cubic yards
 Draining: _____ acres _____ sq ft. _____ cubic yards
 Other: See Attachments : _____ acres _____ sq ft. _____ cubic yards

TOTALS: _____ acres _____ sq ft. _____ cubic yards

21. HAVE ANY WORK ACTIVITIES STARTED ON THIS PROJECT? NO YES If yes, describe ALL work that has occurred including dates.

22. LIST ALL PREVIOUSLY ISSUED PERMIT AUTHORIZATIONS:
 Floodplain Management Permit (3/30/2020 application, pending). A final floodplain permit application would be approved by the City of Ketchum Floodplain Administrator within 180 days prior to construction under authority of FEMA's National Flood Insurance Program (NFIP) and the City of Ketchum's floodplain management ordinance (Ordinance 1120 §17.88.070 C.1).
 USACE identifies this job as --SH-75, Elkhorn Rd. to River St. (KN 20033), NWW-2020-0050 from the PJD issued January 2024.

23. YES, Alteration(s) are located on Public Trust Lands, Administered by Idaho Department of Lands

24. SIZE AND FLOW CAPACITY OF BRIDGE/CULVERT and DRAINAGE AREA SERVED: 69 Square Miles

25. IS PROJECT LOCATED IN A MAPPED FLOODWAY? NO YES If yes, contact the floodplain administrator in the local government jurisdiction in which the project is located. A Floodplain Development permit and a No-rise Certification may be required.

26a WATER QUALITY CERTIFICATION: Pursuant to the Clean Water Act, anyone who wishes to discharge dredge or fill material into the waters of the United States, either on private or public property, must obtain a Section 401 Water Quality Certification (WQC) from the appropriate water quality certifying government entity. See *Instruction Guide for further clarification and all contact information.*

The following information is requested by IDEQ and/or EPA concerning the proposed impacts to water quality and anti-degradation:
 NO YES Is applicant willing to assume that the affected waterbody is high quality?
 NO YES Does applicant have water quality data relevant to determining whether the affected waterbody is high quality or not?
 NO YES Is the applicant willing to collect the data needed to determine whether the affected waterbody is high quality or not?

26b. BEST MANAGEMENT PRACTICES (BMP's): List the Best Management Practices and describe these practices that you will use to minimize impacts on water quality and anti-degradation of water quality. All feasible alternatives should be considered - treatment or otherwise. Select an alternative which will minimize degrading water quality

1. Measures will be taken to minimize the potential for debris (e.g., dirt, concrete, etc.) to enter the area of wetlands not being impacted while removing and constructing structures.
2. A spill plan will be prepared by the construction contractor and approved by ITD D4 prior to project implementation.
3. An ITD approved SWPPP will be prepared for this project. The SWPPP will include measures to address sediment and erosion control with both temporary and permanent measures. All requirements of the Water Quality Certification issued by IDEQ will be followed.
4. All disturbed soils will be reseeded following construction.
5. On-site mitigation will consist of native plantings, and retention walls at Trail Creek restoration area.
6. Dewatering may be accomplished by draining, pumping, bailing, or cribbing. If needed, temporary sump holes may be installed within the footings and abutment areas to be dewatered to create a more suitable pumping area. The water removed during footing and abutment construction will be pumped to a temporary storage location where the water will be cleaned to standards specified by Idaho Department of Environmental Quality (IDEQ) to meet the current State of Idaho requirements. If appropriate, water from the dewatering activities may be pumped to a temporary storage/treatment site, or into upland areas and allowed to flow/filter through vegetation prior to reentering the stream channel. The water behind the barrier may be pumped directly back into the stream providing the pumped water meets applicable in stream turbidity criteria.
7. Turbidity monitoring will be conducted while working on or adjacent to Trail Creek
8. All of the above will be carried out in compliance with the 2022 Construction General Permit and 2023 Standard Specifications for Highway Construction.

Through the 401 Certification process, water quality certification will stipulate minimum management practices needed to prevent degradation.


27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location.

Activity	Name of Water Body	Intermittent Perennial	Description of Impact and Dimensions	Impact Length Linear Feet
See attached narrative				
TOTAL STREAM IMPACTS (Linear Feet):				

28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.

Activity	Wetland Type: Emergent, Forested, Scrub/Shrub	Distance to Water Body (linear ft)	Description of Impact Purpose: road crossing, compound, culvert, etc.	Impact Length (acres, square ft linear ft)
See attached narrative				
TOTAL WETLAND IMPACTS (Square Feet):				

Attachment A. Vicinity Map



Attachment B.

- 19. TYPE and QUANTITY of MATERIAL(S) to be discharged below the ordinary high water mark and/or wetlands:
- 20. TYPE and QUANTITY of impacts to waters of the United States, including wetlands:
- 27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location.
- 28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.
- 29. ADJACENT PROPERTY OWNERS NOTIFICATION REQUIREM: Provide contact information of ALL adjacent property owners below.

BLOCK 19

TYPE and QUANTITY of MATERIALS to be discharged
below ordinary high water mark and/or wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Wetland G</i>							
-Sand and Topsoil for Pond			1100	0.5	26.2	2	1' Sand/6" Topsoil on Bottom; 6" Topsoil on Sides
-Backfill Wetland G	-	-	350.0	2	25.9	2	Backfill Remaining Area of Wetland G
<i>Fill Sub-Total</i>					<i>52.1</i>		
Gravel, Rock, or Stone							
<i>Wetland G</i>							
-Gravel Access Road			220	0.5	4.1	2	6" of 3/4" Aggregate for Access Road
-Riprap/Erosion Control	-	-	102	1.5	5.7	2	Stone Riprap for Outfall to Pond
<i>Fill Sub-Total</i>					<i>9.7</i>		
Concrete, Metal, & Plastic							
<i>Wetland G</i>							
-New 24" Pipe	70	1.5	-	-	3.9	2	
-New Outlet	-	-	5.0	4	0.7	2	
-New 12" Pipe	30	0.5	-	-	0.6	2	
<i>Fill Sub-Total</i>					<i>5.2</i>		
Dirt or Topsoil							
<i>Ditch 3</i>							
-Backfill Ditch 3	55	2	-	-	4.1	2	Backfill Ditch 3 Including Access Road
<i>Fill Sub-Total</i>					<i>4.1</i>		
Concrete, Metal, & Plastic							
<i>Ditch 3</i>							
-New Concrete Manhole (TY D)	-	-	8.6	4.5	1.4	2	
-New Sediment and Oil Trap	-	-	45	6.0	10.0	2	
<i>Fill Sub-Total</i>					<i>11.4</i>		
Dirt or Topsoil							
<i>Wetland F</i>							
-Backfill Wetland F	-	-	180	1.5	10.0	3	Backfill Wetland F During Roadway Slope Construction
<i>Fill Sub-Total</i>					<i>10.0</i>		
Concrete, Metal, & Plastic							
<i>Ditch 2</i>							
-New Concrete 18" Pipe with Steel Aprons	15	0.9	-	-	1.5	4	Install New Concrete 18" Pipe with Aprons
-New Concrete 18" Pipe with Steel Aprons	21	0.9	-	-	1.7	4	Install New Concrete 18" Pipe with Aprons
-New Concrete 18" Pipe with Steel Aprons	22	0.9	-	-	1.7	4	Install New Concrete 18" Pipe with Aprons
-New Concrete Structure	-	-	25	5.5	5.1	4	New 5'x5' Concrete Irrigation Box
<i>Fill Sub-Total</i>					<i>10.0</i>		
Concrete, Metal, & Plastic							
<i>Ditch 1</i>							
-New Concrete 24" Pipe	94	1.5	-	-	5.2	5	Install New Concrete 24" Pipe
-New Concrete Headwall	-	-	-	-	1.3	5	Install New Concrete 24" Headwall Rt.
-New Concrete Headwall	-	-	-	-	1.3	5	Install New Concrete 24" Headwall Lt.
<i>Fill Sub-Total</i>					<i>7.8</i>		

BLOCK 19

TYPE and QUANTITY of MATERIALS to be discharged
below ordinary high water mark and/or wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Trail Creek Bridge Replacement</i>							
Fill Soil Above Rip Rap	-	-	574.4	3	63.8	6	Soil above rip w/i OHW at Trail Creek Bridge
Fill Bench	80	3.2	-	-	9.5	6	Fill for south bench
<i>Fill Sub-Total</i>					<i>73.3</i>		
Gravel, Rock, or Stone							
<i>Trail Creek Bridge Replacement</i>							
Install Riprap	-	-	574.4	3	71.4	6	Rip rap installation w/i OHW at Trail Creek Bridge
Install Geotextile Fabric under Riprap	-	-	574.4	0	0.0	6	Geotextile fabric installation w/i OHW at Trail Creek Bridge
<i>Fill Sub-Total</i>					<i>71.4</i>		
Dirt or Topsoil							
<i>Wetland A</i>							
Wetland A Disturbed for Planting, Fill			51.2	0.5	0.9	6	Native plantings for riparian area restoration in wetland A, fill
Wetland A Temp Disturbed for Planting, Fill			22	0.5	0.4	6	Fill below OHW for Planting plan in wetland A
<i>Fill Sub-Total</i>					<i>0.9</i>		
Gravel, Rock, or Stone							
<i>Wetland A</i>							
Riprap installation in wetland			0.5	3	0.1	6	Rip rap installation w/i OHW at Trail Creek Bridge
Geotextile Fabric under Riprap in wetland			0.5	0	0.0	6	Geotextile fabric installation within Wetland, permanent
<i>Fill Sub-Total</i>					<i>0.1</i>		
Dirt or Topsoil							
<i>Trail Creek Slope Stabilization</i>							
Water Diversion (Sandbags), Temporary	125	9.0	-	-	41.7	7	Temporary water diversion
Earth Fill Above RipRap			716	0.5	13.3	7	Earth Fill Above RipRap
<i>Fill Sub-Total</i>					<i>13.3</i>		
Gravel, Rock, or Stone							
<i>Trail Creek Slope Stabilization</i>							
Installation for RipRap			716	4	106.1	7	Riprap installation in front of reinforced slope
Install Geotextile Fabric under Riprap			716	0	0.0	7	Geotextile fabric installation w/i OHW at Trail Creek Slope
<i>Fill Sub-Total</i>					<i>106.1</i>		
Total Project Fill					375.4		
Total Project Net Materials Discharged Below OHW/Wetlands					375.4		

BLOCK 20

TYPE and QUANTITY of impacts to waters of the United States, including wetlands

	Length (ft)	X-Section Area Below OHW (SF)	Plan Area (SF)	Depth (ft)	Volume (CY)	Figure	Comments
Dirt or Topsoil							
<i>Wetland G</i>							
-Excavate for New Riprap, Perm	-	-	102.0	1.5	-5.7	2	
-Excavate for New 24" Pipe, Temp	70	3.2	-	-	-8.3	2	Temporary excavation for pipe installation
-Excavate for New 24" Pipe, Perm	70	1.5	-	-	-3.9	2	Permanent excavation for pipe installation
-Excavate for New Outlet, Temp	-	-	45	4	-6.7	2	Temporary excavation for outlet installation
-Excavate for New Outlet, Perm	-	-	5	4	-0.7	2	Permanent excavation for outlet installation
-Excavate for New 12" Pipe, Temp	30	0.8	-	-	-0.9	2	Temporary excavation for pipe installation
-Excavate for New 12" Pipe, Perm	30	0.5	-	-	-0.6	2	Permanent excavation for pipe installation
-Excavate for Pond Expansion, Perm	-	-	1100	7	-285.2	2	
-Excavate for Access Road, Perm	-	-	300	2	-22.2	2	Permanent excavation for access road
Permanent Excavation Sub-Total					-318.3		
<i>Ditch 3</i>							
-Excavate for New Manhole, Temp	-	-	20	5	-3.7	2	Temporary excavation for manhole installation
-Excavate for New Manhole, Perm	-	-	8.6	4.5	-1.4	2	Permanent excavation for manhole installation
-Excavate for New Sed and Oil Trap, Temp	-	-	81	7	-21.0	2	Temporary excavation for sed trap installation
-Excavate for New Sed and Oil Trap, Perm	-	-	45	6	-10.0	2	Permanent excavation for sed trap installation
Permanent Excavation Sub-Total					-11.4		
Dirt or Topsoil							
<i>Wetland F</i>							
-Excavate Wetland F			180	1.5	-10.0	3	Excavate Wetland F During Roadway Slope Construction
Permanent Excavation Sub-Total					-10.0		
Dirt or Topsoil							
<i>Ditch 2</i>							
-Excavate for new Concrete Structure, Temp	-	-	77	6	-17.1	4	Temporary Excavation for New 5'x5' Irrigation Box
-Excavate for new Concrete Structure, Perm	-	-	25	5.5	-5.1	4	Permanent excavation for New 5'x5' Irrigation Box
Permanent Excavation Sub-Total					-5.1		
Concrete, Metal, & Plastic							
<i>Ditch 2</i>							
-Remove Ex. CMP 18" Pipe	10	0.9	-	-	-0.3	4	Remove Existing CMP 18" Pipe
-Remove Ex. CMP 18" Pipe	21	0.9	-	-	-0.7	4	Remove Existing CMP 18" Pipe
-Remove Ex. CMP 18" Pipe	20	0.9	-	-	-0.7	4	Remove Existing CMP 18" Pipe
Permanent Excavation Sub-Total					-1.7		
Dirt or Topsoil							
<i>Ditch 1</i>							
-Excavate for Concrete Headwall, Temp	-	-	40.0	3.5	-5.2	5	Temporary excavation for 24" Concrete Headwall Rt.
-Excavate for Concrete Headwall, Perm	-	-	-	-	-1.3	5	Permanent excavation for 24" Concrete Headwall Rt.
-Excavate for Concrete Headwall, Temp	-	-	40.0	3.5	-5.2	5	Temporary excavation for 24" Concrete Headwall Lt.
-Excavate for Concrete Headwall, Perm	-	-	-	-	-1.3	5	Permanent excavation for 24" Concrete Headwall Lt.
-Regrade Ditch 1	-	-	15	2	-1.1	5	Temporay Excavation - Regrade Ditch 1 after Headwall Installation
Permanent Excavation Sub-Total					-2.6		
Concrete, Metal, & Plastic							
<i>Ditch 1</i>							
-Remove 24" CMP	94	1.5	-	-	-5.2	5	Remove Existing 24" Pipe
Permanent Excavation Sub-Total					-5.2		
Dirt or Topsoil							
<i>Wetland D</i>							
-Regrade Ditch 1	-	-	20	2	-1.5	5	Temporary Excavation - Regrade Ditch 1 after Headwall Install
Permanent Excavation Sub-Total					0.0		
Dirt or Topsoil							
<i>Trail Creek Bridge Replacement</i>							
Excavate to Remove Bridge & Install Riprap			574.4	6	-127.6	6	Excavation for bridge removal and riprap installation w/i OHW
Excavate Channel to Install Riprap, Temporary			1428.0	5.1	-269.7	6	Temporary excavation for rip rap installation w/i OHW, fill back
Permanent Excavation Sub-Total					-127.6		
<i>Wetland A</i>							
Wetland A Disturbed for Planting, Excavation			51.2	0.5	-0.9	6	Native plantings for riparian area restoration in wetland A, excavation
Permanent Excavation Sub-Total					-0.9		
Dirt or Topsoil							
<i>Trail Creek Slope Stabilization</i>							
Excavation for Riprap installation			716	4.5	-119.4	7	Riprap excavation in front of reinforced slope
Excavation for Riprap, Temporary			883	2	-65.4	7	Temporary excavation for rip rap installation
Permanent Excavation Sub-Total					-119.4		
Total Project Excavation					-602.3		
Total Quantity of Excavation in WOTUS					-602.3		

Block 20

TYPE and QUANTITY of impacts to waters of the United States, including wetlands

Fig. #	Backfill and Bedding	Area (AC)	Impact Area (SF)	Volume (CY)	
2	Wetland G	0.0391	1,705	67.0	Pond Expansion, Access Road and Storm Drain
2	Ditch 3	0.0037	160	15.5	Pond Expansion, Access Road and Storm Drain
3	Wetland F	0.0041	180	10.0	Roadway and Slope Construction
4	Ditch 2	0.0014	60	10.0	Install new concrete box and Replace 3 Irrigation culverts
5	Ditch 1	0.0010	45	7.8	Replace Irrigation Crossing and Add Headwalls
6	Trail Creek Bridge Replacement	0.0132	574	144.7	Install Riprap & Bench for Bridge Abutments
6	Bridge - Geotextile	0.0132	574	0.0	Install Geotextile under Riprap at Bridge Abutments
6	Wetland A	0.0005	23	1.0	Install Riprap For Bridge Abutments/Native Plantings Area
6	Wetland A - Geotextile	0.0000	1	0.0	Install Geotextile under Riprap at Bridge Abutments
7	Trail Creek Slope Stabilization	0.0164	716	119.3	Riprap installation in front of Reinforced Slope
7	Trail Creek Slope - Geotextile	0.0164	716	0.0	Riprap installation in front of Reinforced Slope
<i>Bedding and Backfill Sub-Total</i>				375.4	

Fig. #	Excavation	Area (AC)	Impact Area (SF)	Volume (CY)	Pond Expansion, Access Road and Storm Drain
2	Wetland G	0.0391	1,705	-318.3	Pond Expansion, Access Road and Storm Drain
2	Ditch 3	0.0037	160	-11.4	Pond Expansion, Access Road and Storm Drain
3	Wetland F	0.0041	180	-10.0	Roadway and Slope Construction
4	Ditch 2	0.0014	60	-6.8	Install new concrete box and Replace 3 Irrigation culverts
5	Ditch 1	0.0010	45	-7.8	Replace Irrigation Crossing and Add Headwalls
5	Wetland D	0.0005	20	0.0	Replace Irrigation Crossing and Add Headwalls-Temporary impact only
6	Trail Creek Bridge Replacement	0.0132	574	-127.6	Excavate for Bridge Removal and Riprap Installation
6	Wetland A	0.0012	51	-0.9	Native plantings for riparian area restoration in wetland A
7	Trail Creek Slope Stabilization	0.0164	716	-119.4	Excavate for riprap in front of Reinforced Slope
<i>Excavation Sub-Total</i>				-602.3	
<i>Project Net Materials Total</i>				-226.9	

27. LIST EACH IMPACT to stream, river, lake, reservoir, including shoreline: Attach site map with each impact location

Table 1: Waterbody Impacts

Resource	Figure	Activity	Cowardin	Intermittent/ Perennial	Description of Impact	Permanent Impacts (SF)	Permanent Impacts (Acres)	Impact Length (LF)
Ditch 1	5	Pipe/headwalls installation	R4EM	Intermittent	Replace Irrigation Crossing and Add Headwalls	45	0.0010	22
Ditch 2	4	Pipe/Box installation	R4EM	Intermittent	Install new concrete box and Replace 3 Irrigation culverts	60	0.0014	30
Ditch 3	2	Pond Expansion & Storm Drain	R4EM	Intermittent	Pond Expansion, Access Road and Storm Drain	160	0.0037	80
Trail Creek*	6	Riprap installation	R2UB	Perennial	Bench for bridge abutments	574	0.0132	82
Trail Creek	7	Slope Stabilization (vegetated wall)	R2UB	Perennial	Riprap installation for Reinforced Slope	716	0.0164	98
Total						1,555	0.0358	312
*175 SF increase in hydraulic opening (full opening of old culvert to full opening of new bridge)								

28. LIST EACH WETLAND IMPACT include mechanized clearing, fill excavation, flood, drainage, etc. Attach site map with each impact location.

Table 2: Wetland Impacts

Resource	Figure	Activity	Cowardin	Distance to waterbody (lin. feet)	Description of Impact	Total Impact (Sq Ft)	Total Impact (Acres)
Wetland A	6	Riprap installation	PFO	0	Install Riprap for bridge abutments, native riparian planting area	51	0.0012
Wetland D	5	Pipe/headwalls installation	PEM	0	Replace Irrigation Crossing and add headwalls	20	0.0005
Wetland F	3	Roadway Construction	PEM	120	Roadway and Slope Construction	180	0.0041
Wetland G	2	Pond Expansion & Storm Drain	PSS	0	Pond Expansion, Access Road and Storm Drain	1,705	0.0391
Total						1,956	0.0449


29. ADJACENT PROPERTY OWNERS NOTIFICATION: Provide contact information of ALL adjacent property owners

Table 3. Adjacent Property Owners

Assessor's Parcel No.	Adjacent Impacted Resources	Contact Name	Phone	Email	Mailing Address
RPK05030000010	Wetland F	Joseph Reali	Not Provided	Joe.reali@gmail.com	100 Neils Way, PO Box 88, Hauley, ID 83333
RPS05200050000	Wetland G Ditch 3	Weyyakin Ranch Property Owner Association	208-726-3858	scm@suncountrysv.com	PO Box 728 Ketchum, ID 83340
RPK4N180190790 RPK4N180190780	Ditch 2	Idaho Park Foundation Inc Kendra Kenyon	208-860-0311	office@idaholands.org	5657 WARM SPRINGS AVE BOISE, ID 83716
RPK4N180190820	Ditch 2 Ditch 1 Wetland D	Douglas Bradshaw Trustee	775-782-1959	DJBradshaw1@live.com	PO Box 7180 Gardnerville, NV 89460
RPK4N17024662M	Ditch 1 Wetland D	Sun Valley Resorts Tim Silva	208-622-2042	tsilva@sunvalley.com	PO BOX 10 SUN VALLEY, ID 83353
RPK07070030000	Trail Creek	Andora Villa Condos Will Schuckert	602-524-1797	will@edgescottsdale.com	15100 N 78 th Way #207 Scottsdale, AZ 85250
RPK0000082003A	Trail Creek Wetland A	PEG Ketchum Hotel LLC	801-655-1998	Not Provided	145 W 200 N Ste 100 Provo, UT 84601
RPK0000082022A	Trail Creek	Jeffrey Barber	206-795-9321	Jeffbarber7@gmail.com	PO Box 2174 Sun Valley, ID 83353
RPK07770000000	Trail Creek	Habitat 2000 Condo Owners Tamara Code	208-726-8584	mgr.habitatontrailcreek@gmail.com	219 S 1 st Ave St 101 Hailey, ID 83333
RPK09590000000	Trail Creek	Trail Creek LLC John Sahlberg	Not Provided	johntsahlberg@gmail.com	PO Box 2251 Ketchum, ID 83340

Assessor's Parcel No.	Adjacent Impacted Resources	Contact Name	Phone	Email	Mailing Address
RPK00000830020	Trail Creek	Harriman Ketchum Hotel LLC Jack Bariteau	Not Provided	jack@waypointsunvalley.com	PO Box 84 Sun Valley, ID 83353

Attachment C. Plan Sheets with Impacts





**SH 75, ELKHORN RD
TO RIVER ST, KETCHUM
KEY NO. 20033**

SH-75, ELKHORN RD TO
RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050


VICINITY MAP

FIGURE 1


MAY 13
2024



- LEGEND**
- - - Existing Pipe
 - - - F/L - Existing Ditch
 -)SS - Existing Storm Sewer
 -)SS - Proposed Storm Sewer
 -)IRR - Proposed Irrigation Pipe
 - Wetland Boundary
 - R/W - Existing Right-of-Way
 - P/L - Property Line
 - R/W - Acquired ITD Right-of-Way



SH-75, ELKHORN RD TO RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: DITCH 3 & WETLAND G
 Proposed Activity: Pond Expansion & Storm Drain
 Lat.: 43.667° N Long.: 114.356° W




SCALE: 1"=40'

LEGEND

- - - Existing Pipe
- - F/L - Existing Ditch
-)SS - Existing Storm Sewer
-)SS - Proposed Storm Sewer
-)IRR - Proposed Irrigation Pipe
- Wetland Boundary
- R/W - Existing Right-of-Way
- P/L - Property Line
- **R/W** - Acquired ITD Right-of-Way

WETLAND F
 Permanent
 Impact Area: 180 SF
 (0.0041 AC)
 Filled with 10.0 CY of
 Backfill and Bedding




SECTION A-A

WETLAND F

FIGURE 3

MAY 13
2024

SH-75, ELKHORN RD TO RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: WETLAND F
 Proposed Activity: Roadway Construction
 Lat.: 43.667° N Long.: 114.356° W
 Sheet 3 of 7



DITCH 2 TOTALS


Temporary
Impact Length: 92 LF
Impact Area: 184 SF

Permanent
Impact Length: 30 LF
Impact Area: 60 SF
(0.0014 AC)
Filled with 10.0 CY of
Backfill and Bedding

SCALE: 1"=50'

LEGEND

- Existing Pipe
- F/L — Existing Ditch
-)SS — Existing Storm Sewer
-)ss — Proposed Storm Sewer
-)IRR — Proposed Irrigation Pipe
- ▬▬▬▬ Wetland Boundary
- R/W — Existing Right-of-Way
- P/L — Property Line
- R/W — Acquired ITD Right-of-Way



DITCH 2
Temporary
Impact Area: 58 SF

Permanent
Impact Area: 16 SF

DITCH 2
Temporary
Impact Area: 52 SF

Permanent
Impact Area: 16 SF


DITCH 2
Temporary
Impact Area: 28 SF

Permanent
Impact Area: 16 SF


DITCH 2
Temporary
Impact Area: 46 SF

Permanent
Impact Area: 12 SF

SH-75, ELKHORN RD TO
RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050
Waterway: DITCH 2
Proposed Activity: Pipe/Box Installation
Lat.: 43.667° N Long.: 114.356° W



SCALE: 1"=50'



LEGEND

- Existing Pipe
- F/L - Existing Ditch
-)SS Existing Storm Sewer
-)SS Proposed Storm Sewer
-)IRR Proposed Irrigation Pipe
- Wetland Boundary
- R/W - Existing Right-of-Way
- P/L Property Line
- R/W Acquired ITD Right-of-Way

DITCH 1 TOTALS

Permanent
 Impact Length: 22 LF
 Impact Area: 45 SF
 (0.0010 AC)
 Filled with 7.8 CY of
 Backfill and Bedding

WETLAND D TOTALS

Temporary
 Impact Area: 20 SF
 (0.0005 AC)

SH-75, ELKHORN RD TO
 RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: DITCH 1 & WETLAND D
 Proposed Activity: Pipe/Headwalls Installation
 Lat.: 43.667° N Long.: 114.356° W



Memo

Date: Friday, March 08, 2024

Project: KN 20033; SH-75, Elkhorn Rd to River St

To: Nathan Jerke

From: Peter Eschbacher, PE

Subject: Retaining Wall/ Slope Stabilization Options at Trail Creek

The SH-75 Elkhorn Rd to River St project widens SH-75 north of Serenade Lane from two lanes to two lanes, a center lane, two bike lanes, and two sidewalks. Northeast of the SH-75 bridge, Trail Creek approaches SH-75 from the west at a nearly 90-degree angle, before turning north and continuing on the east side of the road. This is where Trail Creek is at its closest proximity to SH-75, and where the widened roadway section extends beyond the existing roadway limits, shifting the top of slope towards the creek. At this location, existing trees and roots provide slope stabilization for the nearly 1:1.6 (H:V) slope. The roadway widening requires that these trees be removed. Additional measures are recommended to prevent erosion and stabilize the widened roadway embankment during highwater events on Trail Creek. The affected area is approximately 90-feet long and located between Sta. 476+20 and Sta. 477+05. Additional site improvement alternatives include installing a soldier pile retaining wall, geosynthetic mat with anchor rods, or a wrapped face geosynthetic slope.



Figure 1 – Site Plan (Not to Scale)



Site Improvement Location

Recommended improvements will be located within the existing right-of-way, between the back of proposed sidewalk and Trail Creek on the east side of SH-75. The goal for this design is to stay within existing right-of-way, and not require any permanent easements, although construction easements are acceptable. Figure 1 provides a plan view with an approximate location of the proposed retaining wall or slope. The proposed retaining wall or slope will retain approximately 16 feet of fill at its highest location. There is an existing pedestrian bridge near the south end of the proposed retaining wall or slope, which can also be seen in Figure 2. The overhead power utilities shown in Figure 2 have previously been relocated.



Figure 2 - Approximate Wall or Slope Location

Alternative 1 – Soldier Pile Retaining Wall:

A soldier pile wall uses top-down construction by drilling holes, setting the piles in place in concrete, and installing concrete or timber lagging between piles. Figure 3 provides elevation and section views of an example soldier pile wall. Since the wall will be built using top-down construction, excavation on the roadway side of the wall is not required. Excavation on the creek side would be required to install timber lagging to below the low point of the creek bed. A 2:1 (H:V) slope, starting outside of the ordinary high water, would be placed in front of the wall to reduce the cantilevered length. A riprap toe would be placed on the creek side embankment to protect the wall from scour. The soldier pile wall alternative would not impact existing right-of-way but would require a temporary construction easement for riprap installation. The disadvantages of the soldier pile wall alternative are the low aesthetic value and the high unit cost. The design retained height of the wall would reach 16 feet at its highest point, which may require tiebacks. This wall would require comparatively smaller pile spacings and larger piles than the proposed soldier pile wall on SH-75 near Gem Street. The estimated construction cost for the soldier pile wall alternative is \$380 per square foot of wall face area, for an estimated total of \$550,000.




Figure 3 – Example Soldier Pile Wall Elevation & Typical Section

Alternative 2 – Geosynthetic Slope Stabilization Mat:

A geosynthetic slope stabilization mat with anchor rods consists of laying a geosynthetic mat atop a proposed slope and drilling reinforcing anchor rods into the soil beneath to allow for additional shear support to prevent soil from sliding and eroding. Figure 4 provides a section view of a geosynthetic mat with anchor rods. This alternative allows for vegetation to grow through or be planted within the geosynthetic mat, providing additional stability along the slope with a more natural look that will complement the surrounding area. See Figures 5 and 6 showing a geosynthetic mat at time of installation and matured, respectively. Irrigation is recommended until the vegetation is strongly established. A geosynthetic mat requires minimal excavation at installation when compared to other alternatives. Once the proposed slope has been cleared, graded, and compacted, the anchor rods are drilled into the proposed slope rather than excavating soil to place reinforcement within retained backfill. Limiting excavation to regrading efforts eliminates the need for temporary shoring. The maximum estimated slope of the retained soil would be $\frac{3}{4}:1$ (H:V), approximately matching the existing slope. A slope stability analysis would be required to verify the safety of this steep slope. A riprap key would be placed at the toe of the slope to protect the slope from scour. See Figure 7 for a roadway cross section. One disadvantage of this option is that it may be difficult for vegetation to be established on the steepest part of the slope, especially in arid areas. Another disadvantage is that if the slope stability analysis determines that the slope is too steep, excavation and slope reinforcement would be required. The estimated construction cost for the geosynthetic mat with anchor rods is \$80 per square foot for an estimated total of \$145,000.




Figure 4 – Geosynthetic Mat with Anchor Rods




Figure 5 – Geosynthetic Mat Installed



Figure 6 – Geosynthetic Mat Matured




Figure 7 – Geosynthetic Mat Roadway Cross Section

Alternative 3 – Green Wrapped Face Geosynthetic Reinforced Slope

A wrapped face geosynthetic reinforced slope consists of permanent geosynthetic material that is interlaced in layers and has internal bracing, enhancing material connection and system performance. The geosynthetic material has a service life of 75 years. Figure 8 provides a section view of a wrapped face geosynthetic reinforced slope. This alternative also allows for a fully seeded face, so vegetation can grow through the geosynthetic material, providing



additional stability along the slope with a more natural look that will complement the surrounding area, see Figure 9. The slope is also recommended to be built to include level benches, which would allow planting for more extensive vegetation, although it is unlikely that trees could be planted. It is recommended that willow stakes be planted on a bench above the high-water elevation, which would establish dense roots and provide further slope stability. A planting plan would be included in the specifications and would be coordinated with the City of Ketchum. Irrigation is recommended until the vegetation is strongly established. Additional primary reinforcement is required for slope heights greater than 7 feet which also requires further excavation at installation. The bottom of the slope will be set above the ordinary high water elevation to avoid regular saturation and loss of fines. This option requires excavation to install the geosynthetic reinforcement into the backfill. The reinforcement would extend horizontally 70% of the wall height (pending the stability analysis), or a minimum of 8 feet, from the front of the slope, and be excavated at a 1.5:1 (H:V) slope. This cut into the embankment would require temporary shoring for live traffic on SH-75, as it would encroach on the existing edge of pavement for a portion of the wall construction. See Figure 10 for section sketch. Temporary shoring would also be required at the approach to the pedestrian bridge. Riprap will be installed up to the bottom of the slope and a riprap key below bendway scour would be placed at the toe of the slope to protect from scour. Per discussion with GeoEngineers, the material at the base of the reinforced slope would need to be angular to provide uniform support for the reinforced zone. A combination of riprap and rock cap would likely work well in this situation. The estimated construction cost for the wrapped face geosynthetic reinforced slope alternative is \$100 per square foot of slope, for an estimated total of \$120,000 (including \$20,000 for temporary shoring), making it cheaper than a geosynthetic mat with anchor rods, even including the temporary shoring required.



Figure 8 - Wrapped-Face Geosynthetic Reinforced Slope



Figure 9 - Wrapped-Face Geosynthetic Reinforced Slope, Installed




Figure 10 – Wrapped Reinforced Slope Roadway Cross Section



Recommendation

Per discussions with the City of Ketchum at the 7/19/2023 field visit, the City's preference is a green option with natural vegetation. Alternative 3, a Green Wrapped Face Geosynthetic Reinforced Slope is recommended for this site improvement along SH-75. This alternative provides a more reinforced slope that will better support a moment slab and MASH railing. Re-vegetation on a steep slope will also be more effective than the geosynthetic mat with anchor rods, with the ability to provide benches as practicable. The geosynthetic mat with anchor rods is very comparable cost wise and may be used if preferred by the City and ITD.

ALTERNATIVE COST COMPARISON		
Alternative	Unit Cost per SF	Total Cost
Alt. 1 – Soldier Pile Wall	\$380	\$550,000
Alt. 2 – Anchored Geosynthetic Mat	\$80	\$145,000
Alt. 3 – Green Wrapped Geosynthetic Reinforced Slope	\$100	\$120,000

Note: Costs are for structure cost comparison only, and do not include riprap or moment slab.

All alternatives will require a moment slab and MASH railing at the edge of the widened sidewalk. The edge of sidewalk is outside of the 10 ft. clear zone, but the steep slope or vertical drop presents a safety hazard for pedestrians and vehicular traffic. ITD's possible future condition could eliminate the turn lane and convert SH-75 to a four-lane section, which would place the railing within the clear zone. All alternatives also include a recommendation to add riprap along the length of the proposed improvement and in front of the west abutment of the existing pedestrian bridge. The bridge shows signs of scour and undermining, which can be seen in Figure 11. Scour countermeasures placed below ordinary highwater will need to be evaluated for project-wide environmental permitting purposes.



Figure 11 – Pedestrian Bridge & Abutment

SH 75, ELKHORN RD. TO RIVER ST., KETCHUM

Blaine County, Idaho

Wetlands Mitigation Plan for EO 11990 requirements

KEY No. 20033

Prepared By:
Connie Jones
ITD District 4 – Senior Environmental Planner

March 27, 2023

Prepared For:
Nathan Jerke
ITD District 4 – Project Manager
Idaho Transportation Department (ITD)
216 South Date Street
Shoshone, ID
Ph: 208-886-7809
Nathan.Jerke@itd.idaho.gov

FIGURES

Figure 1: Vicinity Map 3
Figure 2: Wetland Overview Map 5
Figure 3: Wetlands A 6
Figure 4: Wetland F 7
Figure 5: Wetland G 8

LIST OF ACRONYMS AND ABBREVIATIONS

AEC	Anderson Environmental Consulting, LLC
ITD	Idaho Transportation Department
Project	SH-75 Elkhorn to River Street Project
EIS	Environmental Impact Statement
ROD	Record of Decision
MP	Mile Post
MDT	Montana Department of Transportation
USACE	United States Army Corps of Engineers
WMVC	Western Mountains Valleys and Coast

Location - The Project is located Sections 18, 19, and 30 in Township 04 North, Range 18 East, just south of the city of Ketchum on SH-75 in Blaine County, Idaho. See below.




Figure 1: Vicinity Map

PROJECT DESCRIPTION

This Project is the third roadway construction project to be developed from the SH-75 Timmerman to Ketchum Environmental Impact Statement (EIS)/Record of Decision (ROD) issued in August 2008. The purpose of this Project is to improve safety and capacity on SH-75 between the Big Wood River Bridge near Elkhorn Road and River Street in the City of Ketchum in Blaine County, mileposts (MP) 126.4 to 128.2. Project development will include roadway widening with curb, gutter and sidewalk, intersection improvement, retaining walls, drainage, public involvement, and replacing a box culvert over Trail Creek in Ketchum, ID.

The Project is in the Big Wood River Valley just south of the city of Ketchum, Idaho. The valley is surrounded by mountains and lies on the border between the arid west, scrub/shrub environment of southern Idaho and the western mountains, forested Rocky Mountains environments of northern Idaho. The area along the SH-75 corridor is developed and consists of residential, commercial, and some agricultural properties.

An Aquatic Resources Delineation Report was prepared by Anderson Environmental Consulting, LLC (AEC) in January of 2020. Seven wetlands were identified and delineated. See **Figure 2**. The Montana Wetland Assessment Method (MDT 2008) was used to assess the wetland categories of each wetland. This rating system differentiates wetlands based on their sensitivity to disturbance, their significance, their rarity, our ability to replace them, and the functions they provide. Wetlands are given a rating from Category I to Category IV. Category I wetlands typically have the highest functions and values and Category IV wetlands typically have the lowest.

See **Figure 2** on the following page for a map of the study area and wetlands overview.

There will be filling of three wetlands associated with this construction phase project since the highway is being rebuilt to accommodate increased traffic volumes. The do nothing alternative is not practicable because it would not correct the existing deficiency in width and the resulting safety hazards. Improvements that will not result in wetland impacts are not prudent or practicable since the highway must be widened in order to build the alternative as described in the SH-75 Timmerman to Ketchum Environmental Impact Statement (FEIS) and Record of Decision (ROD) which was approved in August 2008.

ITD's proposal is to perform wetland restoration and enhancement within the Trail Creek local watershed on this phase of construction. To ensure that there is no net loss, a target mitigation ratio of 1.2 to 1 as recommended will be used so that if the mitigation effort is somewhat less than 100% successful, additional mitigation work will not be required to make up the difference. The current estimated impacts to existing wetlands are 2135 SF of impacts and the mitigation will be to restore 2562 SF for 1.2 times the area within the Trail Creek drainage on ITD right-of-way (R/W). The SH-75 R/W is owned by ITD.

QUALITY AND QUANTITY OF THE WETLANDS INVOLVED (Description of wetlands impacted):

Wetland A is impacted by the replacement of the structure over Trail Creek with a wider structure to carry SH-75. Wetland F is impacted by the widening of SH-75. Wetland G is impacted by the proposed storm water facility need to accommodate the drainage from SH=75. Each of these impacted wetlands is described on the following pages. See Figures 3, 4 and 5 on the following pages for a map of each of the impacted wetlands.




Figure 2: Wetland Overview Map




Figure 3: Wetlands A

Wetlands A is a palustrine, forested wetlands along the banks of Trail Creek and extend approximately 1-4 feet upslope from the edge of the stream. These wetlands are dominated by black cottonwood. The understory is comprised of Spike rush and Orchard grass and has approximately 70% bare ground. There are signs of seasonal flooding and alluvial shifting. This wetland is a Category III wetlands. It is rated high for sediment and shoreline stabilization. It is rated moderate for general fish habitat, short- and long-term surface water, and production export/food chain support. Trail Creek is the location for the onsite mitigation.



Figure 4: Wetland F

Wetland F is a small emergent wetland located directly adjacent to SH-75 on the slope of a landscaped berm in a residential area near MP 127.3. The wetland is seeping out of a man-made mound (5-10 feet tall) surrounded by otherwise flat ground. This hillside is landscaped and heavily irrigated and the wetland appears to receive its hydrology from the irrigation or a leak in an irrigation line. Soils were saturated at the surface. The wetland does not appear to outlet directly to a stream or waterbody but drains to the existing ditch. Vegetation included quaking aspen saplings, cattail, reed canarygrass, lupines, Canada thistle, and Kentucky bluegrass. This wetland was rated as a Category IV. It rated high for Sediment/Nutrient/Toxicant Removal and groundwater discharge/recharge.



Figure 5: Wetland G PSS

Wetland G is a scrub-shrub wetland located at the inlet to a stormwater pond located near MP127. The stormwater system drains from a culvert flowing under SH-75, into a ditch, and then a large stormwater pond. Although there was no flowing or open water, or saturation found during the site visits, facultative wet (FACW) and obligate (OBL) species near the inlet to the stormwater pond suggested a wetland in this area. This wetland was rated as a Category IV. It rated moderately for General Wildlife Habitat, Sediment/Nutrient/Toxicant Removal and groundwater discharge/recharge.

PHOTOS



Photo PFO: Wetland A looking east
At Trail Creek, site where mitigation will take place.



Photo PFO: Wetland A looking west
At Trail Creek, site where mitigation will take place.



Photo PEM: Wetland F looking south
seeping out of a man-made mound (5-10 feet tall)
surrounded by otherwise flat ground.



Photo PSS: Wetland G looking north
scrub-shrub wetland located at the inlet to a
stormwater pond near MP 127 SH-75.

Details of how mitigation will be achieved;

ITD D4 proposes to provide compensatory mitigation for permanent impacts to wetlands and open waters of the U.S. to be achieved by removing the existing structure and restoring a more natural stream channel for Trail Creek. Mitigation for permanent wetland impacts will occur by taking out the existing structure and then restoring the channel and stream banks. The existing structure is reinforced concrete stiffleg bridge with a clear span of 20 feet and width (parallel to creek) of 48 feet. The proposed structure would be a prestressed, concrete-voided, slab bridge with a clear span of 52 feet and a width of approximately 62 feet. The new bridge is designed such that the low chord will be higher than the existing bridge's low chords. The mitigation provided for temporary impacts to wetlands will consist of revegetating those wetlands with native wetland species.

Benefits to the more natural riparian area are:

- 1) The small wildlife passage benches will be constructed with native materials with a $\frac{3}{4}$ inch base cover on top of riprap.
- 2) Substrate within the proposed channel would be cobble similar to existing.
- 3) The disturbance area outside of proposed riprap will be planted with native riparian shrubs, which would include black cottonwood (*Populus trichocarpa*) and coyote willow (*Salix exigua*) within approximately 5-ft of the OHWM and quaking aspen (*Populus tremuloides*) and wood's rose (*Rosa woodsia*) beyond that. D4 would require 2 gallon pots for the Woods Rose and Quaking aspen to increase the chances of survival.

Existing Conditions:

The existing structure is a reinforced concrete stiffleg bridge with a clear span of 20 feet and width (parallel to creek) of 48 feet. The channel at above and below the bridge is incised with side slopes generally ranging from 1V:2H to 1V:3H. The creek bottom has a substrate of primarily cobble and small boulders, with some alluvial sand deposits along the banks and on the point bar upstream of the bridge. Existing banks are stabilized by tree roots and riprap (D50) between 0.5 and 1.0 ft.) placed above the ordinary high-water mark (OHWM) upstream and downstream of the bridge.

Proposed Conditions:

The proposed structure would be a prestressed, concrete-voided, slab bridge with a clear span of 52 feet and a width of approximately 62 feet. The bridge is designed such that the low chord clears the Q₁₀₀ and will be over 2 ft. higher than the Q₅₀ water surface elevation. A 3-ft horizontal bench will be constructed at the face of each abutment. Below these benches, a 2V:1H slope constructed out of riprap (D₅₀ of 1.5 ft.) placed to a depth of 3-ft. and on top of riprap/erosion control geotextile will extend down to another 3-ft horizontal bench just above the OHWM (as defined in the Aquatic Resource Delineation Report) for wildlife passage of small mammals. The wildlife passage benches will be constructed with native materials with a ¾ inch base cover on top of riprap. Additionally, riprap will be installed along the abutment embankment for approximately 10 feet upstream and downstream of the bridge. Substrate within the proposed channel would be cobble similar to existing.

The disturbance area outside of proposed riprap will be planted with riparian shrubs, which may include black cottonwood (*Populus trichocarpa*) and coyote willow (*Salix exigua*) within approximately 5-ft of the OHWM and quaking aspen (*Populus tremuloides*) and wood's rose (*Rosa woodsia*) beyond that.

Construction Sequencing:

The Bridge will be constructed in two stages. Work within the OHWM will be within the IDFG and Idaho Department of Water Resources (IDWR) approved work window between July 15 and March 15. General construction sequencing will be determined by the contractor but is anticipated to be as follows.

- Install erosion and sediment control and spill control measures which may include silt fencing, straw wattles, and other standard best management practices
- Place temporary stream diversion measures and dewater work area. Remove any fish present in dewatered areas and release them downstream using approved methods.
- Remove portion of existing bridge using approved containment methods to ensure no debris enters the water
- Excavate streambank and channel
- Construct new abutments. Proposed substructure will be located outside the OHWM
- Place geotextile, riprap, and streambed materials and construct benches
- Construct new bridge superstructure
- Install topsoil, plantings and seed as applicable to disturbed areas
- Remove all temporary erosion and sediment control BMP's once site is stabilized

Short-Term Effects:

Short-term construction impacts will include potential erosion and sedimentation on disturbed soils adjacent to creek. Removal of vegetation and construction work activities may impact riparian wildlife habitat and movement through the Project area. In-water work may disturb aquatic organisms and stress fish present during construction.

Construction stormwater will be treated through the use of standard BMPs for erosion, sedimentation and spills which will be outlined in Storm Water Pollution Prevention Plan (SWPPP). BMPs may include limiting soil disturbance, controlling dust through watering, soil stabilization through revegetation, use of silt fences, and wattles, having spill kits on site, proper chemical storage and proper waste disposal.

Dewatering methods have not been approved at this time but will likely include sandbags or another temporary shoring method. A qualified Biologist will capture and remove fish from the dewatered work area if needed. Equipment will operate from the banks or existing roadway and will not enter the water.

Long-Term Effects:

The Project will have a long-term benefit to wildlife in the area by increasing water conveyance capacity and floodplain function and improving fish passage and habitat. The wider clear span and benches will allow better movement of small mammals through the Project area. Revegetation with native poplars and willows will provide habitat, shade, and erosion control in the long-term.

Attachments:

Bridge exhibit

Planting Plan exhibit

U:\Bois\Projects\Clients\4006-ITD\314-4006-071\SH-75 Elkhorn to River\955vcs\CADD\DCN\sheet\20033_land_001.dgn
 2/14/2022 4:04:36 PM




Table 1: Native Planting

Scientific Name	Common Name	Type	Percent by cover	Appx. Spacing (ft)
Planting Area 1-Shoreline				
<i>Populus trichocarpa</i>	Black Cottonwood	live stakes/poles	50	10
<i>Salix exigua</i>	Coyote Willow	live stakes/poles	50	5
Total Zone 1-Shoreline			100	
Planting Area 2-Riparian-Upland				
<i>Populus tremuloides</i>	Quaking Aspen	1-2-gallon or bareroot	50	8
<i>Rosa Woodsii</i>	Woods Rose	1-2-gallon or bareroot	50	8
Total Zone 2-Riparian			100	


*Planting Area 1- Within 5-10 ft of the stream (Roots should reach below the water table), Planting Area 2- Upslope from Planting Area 1

Construction Notes:

- Live stakes/pole plantings to appx. 24-36" and buried so that the bottom of the stakes/poles are below the OHWM of Trail Creek. Should be buried with shoots upward and at least ¾ of the pole should be buried.
- Plants should be placed at a recommended spacing of and clustered with like species as possible

LEGEND

- Zone 1 Planting Area (Shoreline) With Riparian Seeding
- Zone 2 Planting Area (Riparian) With Riparian Seeding
- Riprap areas



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED	JLJ	SCALES SHOWN ARE FOR 11" X 17" PRINTS ONLY CADD FILE NAME 20033_land_001.dgn DRAWING DATE: February 2022
DESIGN CHECKED	TMJ	
DETAILED	TM	
DRAWING CHECKED	JLJ	

IDAHO TRANSPORTATION DEPARTMENT
 YOUR Safety→YOUR Mobility→YOUR Economic Opportunity

Parametrix

PROJECT NO.	A020(033)
-------------	-----------

TRAIL CREEK PLANTING PLAN
SH-75, ELKHORN RD TO RIVER ST, KETCHUM

ENGLISH
COUNTY Blaine
KEY NUMBER 20033
SHEET 200 OF 249

NOT APPROVED
PRELIMINARY
 FOR CONSTRUCTION

REFERENCES

AEC. 2020. Aquatic Resources Delineation Report SH-75 Elkhorn Road To River Street Key No. 20033.
02/26/2020

AEC. 2020. Wetland Functional Assessment Report SH-75 Elkhorn Road to River Street Key No. 20033.
03/30/2020

AEC. 2022. Memo – Trail Creek Bridge Description of existing and proposed Trail Creek bridge crossing
08/18/2022

HDR. 2021. SH-75 Trail Creek Bridge. Hydraulic Report. April 28, 2021



DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS
BOISE REGULATORY OFFICE
720 EAST PARK BOULEVARD, SUITE 245
BOISE, IDAHO 83712-7757

September 17, 2024

WALLA WALLA DISTRICT
REGULATORY DIVISION

SUBJECT: NWW-2024-00333, SH-75, Elkhorn Road to River Street Road
Improvements

Idaho Transportation Department, District 4 (POC Jesse Barrus)
216 South Date Street
Shoshone, Idaho 83352-1521

Dear Mr. Barrus:

We have determined that your proposed project, SH-75, Elkhorn Road to River Street, is authorized in accordance with Department of the Army (DA) **Nationwide Permit (NWP) No. 14: Linear Transportation Projects**. This project is located along State Highway 75 from mile post 126.4 to mile post 128.2, within Sections 18, 19, and 30 of Township 4 North, Range 18 East, near coordinates 43.667041° N latitude and -114.355657° W longitude, near Ketchum, Blaine County, Idaho. Please refer to File Number NWW-2024-00333 in all future correspondence with our office regarding this project.

Project activities include the discharge of approximately 376 cubic yards of fill into Trail Creek, 3 unnamed ditches, and adjacent wetlands. Activities are associated with road widening and bridge replacement in order to improve safety and compacity of State Highway 75 between Elkhorn Road and River Street in the City of Ketchum. The work within Trail Creek and adjacent wetlands entails the replacement of the existing bridge, the replacement of rip rap, and excavation and grading of the stream bank. Additional work includes the installation of a concrete irrigation box and headwalls, modification of an existing storm water retention pond, and the replacement of four irrigation culverts. Activities will permanently impact 0.0436 acres of wetlands, 0.0296 acres of streambed, and 207 linear feet of ditches. Activities will also temporarily impact 0.020 acres of stream bed for the utilization of cofferdams. All work shall be done in accordance with the enclosed drawings, titled: *SH-75, ELKHORN RD TO RIVER ST, KETCHUM (figure 2-7), dated, May 13, 2024*.

DA permit authorization is necessary because your project may involve the discharge of fill material into waters of the U.S. This authorization is outlined in Section 404 of the Clean Water Act (33 U.S.C. 1344).

You must comply with all general, regional, and special conditions for this verification letter to remain valid and to avoid possible enforcement actions. The general and regional permit conditions for *NWP No. 14: Linear Transportation Projects* are attached and also available online¹. In addition, you must also comply with the special conditions listed below.

The following Special Conditions include:

Special Condition: The permittee is responsible for all work done by any contractor. Permittee shall ensure any contractor who performs the work is informed of and follows all the terms and conditions of this authorization. Permittee shall also ensure these terms and conditions are incorporated into engineering plans and contract specifications.

You must also comply with the conditions detailed in the attached Section 401 Water Quality Certification (WQC) issued for this project on July 29, 2024, by the Idaho Department of Environmental Quality (IDEQ). If you have any questions regarding the conditions set forth in the WQC, please contact IDEQ directly at 208-736-2190, Twin Falls Regional Office..

Nationwide Permit General Condition 30 (Compliance Certification) requires that every permittee who has received NWP verification must submit a signed certification regarding the completed work and any required mitigation. This Compliance Certification form is enclosed for your convenience and must be completed and returned to us within 30 days of your project's completion.

This letter of authorization does not convey any property rights, or any exclusive privileges and does not authorize any injury to property or excuse you from compliance with other Federal, State, or local statutes, ordinances, regulations, or requirements which may affect this work.

This verification is valid until **March 14, 2026**, unless the NWP is modified, suspended or revoked. If your project, as permitted under this NWP verification, is modified in any way you must contact our office prior to commencing any work activities. In the event that you have not completed construction of your project by March 14, 2026, please contact us at least 60-days prior to this date. A new application and verification may be required.

¹ <http://www.nww.usace.army.mil/Business-With-Us/Regulatory-Division/Nationwide-Permits/>

We actively use feedback to improve our delivery and provide you with the best possible service. If you would like to provide feedback, please take our online survey². If you have questions or if you would like a paper copy of the survey, please contact the Walla Walla District Regulatory. For more information about the Walla Walla District Regulatory program, you can visit us online³.

If you have any questions or need additional information about this permit authorization, you can contact Jacob Cordtz by phone at 208-433-4466, by mail at the address in the letterhead, or email at Jacob.W.Cordtz@usace.army.mil. For informational purposes, a copy of this letter has been sent to: Idaho Department of Environmental Quality and Idaho Department of Water Resources.

Sincerely,



Tracy Peak
Acting Chief, Regulatory Division

Encls

Transfer of Nationwide Permit Form
Compliance Certification
Nationwide Permit 14 Terms & Conditions
Individual Water Quality Certification
Drawings titled: *SH-75, ELKHORN RD TO RIVER ST, KETCHUM (figure2-7)*, dated,
May 13, 2024.

² <https://regulatory.ops.usace.army.mil/customer-service-survey/>

³ <http://www.nww.usace.army.mil/Business-With-Us/Regulatory-Division/>

TRANSFER OF NATIONWIDE PERMIT

When the structures or work authorized by this Nationwide Permit, **NWW-2024-00333, SH-75, Elkhorn Road to River Street Road Improvements**, are still in existence at the time the property is transferred. The terms and conditions of this Nationwide Permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this Nationwide Permit, the associated liabilities and compliance with the terms and conditions the transferee must sign and date below.

Name of New Owner:

Street Address:

Mailing Address:


City, State, Zip:

Phone Number:


Signature of TRANSFEREE

DATE

COMPLIANCE CERTIFICATION



US Army Corps of Engineers
Walla Walla District



Permit Number: NWW-2024-00333

Name of Permittee: Idaho Transportation Department, District 4

Date of Issuance: September 17, 2024

Upon completion of the activity authorized by this permit and any mitigation required by the permit, please sign this certification and return it to the following address:


U.S. Army Corps of Engineers
Walla Walla District
Boise Regulatory Office
720 East Park Blvd., Suite 245
Boise, Idaho 83712-7757

Please note that your permitted activity is subject to a compliance inspection by a U.S. Army Corps of Engineers representative. If you fail to comply with all terms and conditions of this permit, the permit is subject to suspension, modification, or revocation and you are subject to an enforcement action by this office.


I hereby certify that the work authorized by the above-referenced permit has been completed in accordance with the terms and conditions of the said permit. The required mitigation was also completed in accordance with the permit conditions.

Signature of PERMITEE

DATE




SH-75, ELKHORN RD TO RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050



WETLAND F
 Permanent
 Impact Area: 180 SF
 (0.0041 AC)
 Filled with 10.0 CY of
 Backfill and Bedding

LEGEND

- - - Existing Pipe
- F/L - Existing Ditch
-)SS - Existing Storm Sewer
-)SS - Proposed Storm Sewer
-)IRR - Proposed Irrigation Pipe
- Wetland Boundary
- R/W - Existing Right-of-Way
- P/L - Property Line
- **R/W** - Acquired ITD Right-of-Way



SECTION A-A


SH-75, ELKHORN RD TO
 RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(033) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: WETLAND F
 Proposed Activity: Roadway Construction
 Lat.: 43.667° N Long.: 114.356° W

WETLAND F

FIGURE 3

MAY 13
2024

Sheet 3 of 7



DITCH 2 TOTALS


Temporary
Impact Length: 92 LF
Impact Area: 184 SF

Permanent
Impact Length: 30 LF
Impact Area: 60 SF
(0.0014 AC)
Filled with 10.0 CY of
Backfill and Bedding


SCALE: 1"=50'

LEGEND


- Existing Pipe
- F/L - Existing Ditch
-)SS - Existing Storm Sewer
-)ss - Proposed Storm Sewer
-)IRR - Proposed Irrigation Pipe
- Wetland Boundary
- R/W - Existing Right-of-Way
- P/L - Property Line
- R/W - Acquired ITD Right-of-Way



SH-75, ELKHORN RD TO
RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050
Waterway: DITCH 2
Proposed Activity: Pipe/Box Installation
Lat.: 43.667° N Long.: 114.356° W



SCALE: 1"=50'



LEGEND

- Existing Pipe
- F/L - Existing Ditch
-)SS Existing Storm Sewer
-)SS Proposed Storm Sewer
-)IRR Proposed Irrigation Pipe
- Wetland Boundary
- R/W Existing Right-of-Way
- P/L Property Line
- R/W Acquired ITD Right-of-Way



DITCH 1 TOTALS

Permanent
Impact Length: 22 LF
Impact Area: 45 SF
(0.0010 AC)
Filled with 7.8 CY of
Backfill and Bedding

WETLAND D TOTALS

Temporary
Impact Area: 20 SF
(0.0005 AC)


SH-75, ELKHORN RD TO RIVER ST, KETCHUM
BLAINE COUNTY, IDAHO
ITD Project No. A020(033) Key No. 20033
File No. : NWW-2020-0050
Waterway: DITCH 1 & WETLAND D
Proposed Activity: Pipe/Headwalls Installation
Lat.: 43.667° N Long.: 114.356° W



WETLAND A
 PERMANENT IMPACT = 51 SF
 EXCAVATION = 0.9 CY
 FILL W/ PLANTING = 0.9 CY
 ROCK FILL = 0.1 CY
 GEOTEXTILE IMPACT = 0.5 SF
 TEMPORARY IMPACT = 22 SF
 TEMPORARY EXCAVATION = 0.4 CY
 TEMPORARY FILL = 0.4 CY

IMPACTS FOR BRIDGE REMOVAL AND RIPRAP INSTALLATION
 PERMANENT IMPACT AREA = 574 SF
 GEOTEXTILE IMPACT AREA = 574 SF
 EXCAVATION = 127.6 CY
 ROCK FILL = 73.4 CY
 TEMPORARY IMPACT AREA = 1428 SF
 TEMPORARY EXCAVATION = 269.7 CY
 TEMPORARY EARTH FILL = 269.7 CY

PLAN
1"=30'-0"



LEGEND

- ORDINARY HIGH WATER (OHW) BOUNDARY
- DELINEATED WETLAND BOUNDARY
- EXISTING RIGHT-OF-WAY
- ACQUIRED RIGHT-OF-WAY
- PERMANENT IMPACTS BELOW OHW (574 S.F., 0.013 ACRE)
- TEMPORARY IMPACTS BELOW OHW (1428 S.F., 0.033 ACRE)
- PERMANENT IMPACTS TO WETLANDS (51 S.F., 0.001 ACRE)
- TEMPORARY IMPACTS TO WETLANDS (22 S.F., 0.001 ACRE)

EXISTING HYDRAULIC OPENING = 158 S.F., 0.003 ACRE
 PROPOSED HYDRAULIC OPENING = 333 S.F., 0.008 ACRE
 HYDRAULIC OPENING CHANGE = INCREASE 175 S.F., 0.004 ACRE

SH-75, ELKHORN RD TO RIVER ST, KETCHUM
 BLAINE COUNTY, IDAHO
 ITD Project No. A020(003) Key No. 20033
 File No. : NWW-2020-0050
 Waterway: Trail Creek
 Proposed Activity: Bridge Replacement
 Lat.: 43.667° N Long.: 114.356° W
 Sheet 6 of 7

TRAIL CREEK BRIDGE

FIGURE 6

MAY 13 2024

NATIONWIDE PERMIT 14

Linear Transportation Projects:

Activities required for crossings of waters of the United States associated with the construction, expansion, modification, or improvement of linear transportation projects (e.g., roads, highways, railways, trails, driveways, airport runways, and taxiways) in waters of the United States. For linear transportation projects in non-tidal waters, the discharge of dredged or fill material cannot cause the loss of greater than 1/2-acre of waters of the United States. For linear transportation projects in tidal waters, the discharge of dredged or fill material cannot cause the loss of greater than 1/3-acre of waters of the United States. Any stream channel modification, including bank stabilization, is limited to the minimum necessary to construct or protect the linear transportation project; such modifications must be in the immediate vicinity of the project.

This NWP also authorizes temporary structures, fills, and work, including the use of temporary mats, necessary to construct the linear transportation project. Appropriate measures must be taken to maintain normal downstream flows and minimize flooding to the maximum extent practicable, when temporary structures, work, and discharges of dredged or fill material, including cofferdams, are necessary for construction activities, access fills, or dewatering of construction sites. Temporary fills must consist of materials, and be placed in a manner, that will not be eroded by expected high flows. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The areas affected by temporary fills must be revegetated, as appropriate.

This NWP cannot be used to authorize non-linear features commonly associated with transportation projects, such as vehicle maintenance or storage buildings, parking lots, train stations, or aircraft hangars.

Notification: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if: (1) the loss of waters of the United States exceeds 1/10-acre; or (2) there is a discharge of dredged or fill material in a special aquatic site, including wetlands. (See general condition 32.) (Authorities: Sections 10 and 404)

Note 1: For linear transportation projects crossing a single waterbody more than one time at separate and distant locations, or multiple waterbodies at separate and distant locations, each crossing is considered a single and complete project for purposes of NWP authorization. Linear transportation projects must comply with 33 CFR 330.6(d).

Note 2: Some discharges of dredged or fill material for the construction of farm roads or forest roads, or temporary roads for moving mining equipment, may qualify for an exemption under Section 404(f) of the Clean Water Act (see 33 CFR 323.4).

Note 3: For NWP 14 activities that require pre-construction notification, the PCN must include any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings that require Department of the Army authorization but do not require pre-construction notification (see paragraph (b)(4) of general condition 32). The district engineer will evaluate the PCN in accordance with Section D, "District Engineer's Decision." The district engineer may require mitigation to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see general condition 23).

WATER QUALITY CERTIFICATION, NWP 14:

Agency responsible for administration of water quality, based on project location is listed below. If **DENIED**, then an Individual Water Quality Certification or Waiver of Certification is required, prior to the commencement of any work activities and/or issuance of a DA verification, authorization and/or permit.

State of Idaho: **PARTIALLY DENIED**; activities requiring a Pre-Construction Notification (PCN) for NWP 14 are **not certified**.

Coeur d'Alene Tribal Lands: **DENIED**

Shoshone-Bannock Tribal Lands: **DENIED**

U.S. Environmental Protection Agency for all other Tribal Lands: **PARTIALLY DENIED**: activities are denied when the project will result in:

- Greater than 1/10 acre of impacts to waters of the U.S.; or
 - Greater than 300 linear feet of impacts to waters of the U.S.
-

**2021/2022 Nationwide Permits
Regional Conditions
Walla Walla District Regulatory Division (State of Idaho)**

January 13, 2021

The following Nationwide Permit (NWP) regional conditions are required in the state of Idaho and apply to all 2021/2022 NWPs¹. Regional conditions are established by individual Corps Districts to ensure projects result in no more than minimal adverse impacts to the aquatic environment and to address local resources concerns. This document also includes regional additions to the NWP General Conditions, notification procedures pertaining to certain NWP's, and regional additions to the definitions.

REGIONAL CONDITIONS

A. Watersheds Requiring Pre-Construction Notification, Specific to Anadromous Fish

This Regional Condition applies to all 2021/2022 NWPs.

- Pre-construction notification (PCN) will be required for the above listed nationwide permits in the geographic area as shown on Figure 1: *Watersheds Requiring Pre-Construction Notification*, dated January 6, 2021.

B. Vegetation Preservation and Replanting

- To avoid impacts to aquatic habitat and to reduce sedimentation and erosion, permittee shall avoid and minimize the removal of vegetation in waters of the U.S. to the maximum extent practicable. Areas subject to temporary vegetation removal in waters of the U.S. during construction shall be replanted with appropriate native² species by the end of the first growing season, unless conditioned otherwise. Permittee shall avoid introducing or spreading noxious or invasive plants³.
- Replanted vegetation that does not survive the first growing season shall be replanted before the end of the next growing season. Re-plantings shall continue to occur until desired vegetation densities are achieved. Re-vegetation densities should be based on reference conditions.

¹ For the list of 2021/2022 Nationwide Permits please see: <https://www.nww.usace.army.mil/Business-With-Us/Regulatory-Division/Nationwide-Permits/>

² Idaho Department of Transportation, Native Plants for Idaho Roadside Restoration and Revegetation Programs: https://itd.idaho.gov/wp-content/uploads/2016/06/RP171Roadside_Revegetation.pdf

³ U.S. Department of Agriculture, Natural Resource Conservation Service Plant Database of introduced, invasive, and noxious plants for Idaho: <https://plants.usda.gov/java/noxious?rptType=State&statefips=16>.

C. De-watering & Re-watering (as applicable)

- Cofferdams shall be constructed of non-erosive material such as concrete jersey barriers, bulk bags, water bladders, sheet pile, and other similar non-erosive devices. Cofferdams may not be constructed by using mechanized equipment to push streambed material through flowing water.
- Diversion channels constructed to bypass flow around the construction site shall be lined with plastic, large rock, pipe or otherwise protected from erosion prior to releasing flows into or through the diversion channel.
- Water removed from within the coffered area shall be pumped to a sediment basin or otherwise treated to remove suspended sediments prior to its return to the waterway.
- To prevent unwanted passage of state or federally-protected fish, if present, from the coffered area, Water pipe intakes shall be screened with openings measuring < 3/32 inch to prevent entrainment of fish trapped in the coffered area.
- Should fish be present within the coffered areas contact your local Idaho Department of Fish and Game (IDFG) office prior to performing fish removal or salvage. Fish shall be collected by electrofishing, seining or dip net, or otherwise removed and returned to the waterway upstream of the project area. If electrofishing is used, the National Marine Fisheries Service (NMFS) guidelines for electrofishing should be followed⁴, unless conditioned otherwise.
- Stream channels that have been dewatered during project construction shall be re-watered slowly to avoid lateral and vertical erosion of the de-watered channel, prevent damage to recently reclaimed work areas and/or damage to permitted work.
- Temporary stockpiles in waters of the United States shall be removed in their entirety so as not to form a berm or levee parallel to the stream that could confine flows or restrict overbank flow to the floodplain.

D. In-Water Structures and Complexes

- PCN notification in accordance with General Condition 32 is required for all non-federal applicants with activities involving gabion baskets placed below the ordinary high water mark.
- Stream meanders, riffle and pool complexes, pool stream structures, rock/log barbs, rock J-hooks, drop structures, sills, engineered log jams or similar structures/features when used shall be site specifically designed by an appropriate professional with experience in hydrology or fluvial geomorphology.

⁴ Guidelines for Electrofishing Waters Containing Salmonids Listed Under the Endangered Species Act (June 2000)
http://www.westcoast.fisheries.noaa.gov/publications/reference_documents/esa_refs/section4d/electro2000.pdf

E. Temporary Sidecasting

- Materials from exploratory trenching and installation of utility lines may be temporarily side cast into a de-watered coffered area for up to 30 days but not within flowing waters. Material from exploratory trenching and installation of utility lines in wetlands may be temporarily side cast for up to 30 days.

F. Suitability of Sediments for Open Water Disposal and us as Fill

- Sampling for determination of suitability of sediments for open water disposal or for use as fill, must comply with the Sediment Evaluation Framework for the Pacific Northwest (SEF)⁵.

G. Avoidance and Minimization

- In addition to information required under General Condition 32(b), the applicant shall include information about previous discharges of fill material into waters of the United States within the project area. This is only for non-federal applicants where a PCN is required.
- Discharges of dredged or fill material into waters of the U.S., including wetlands, to meet set back requirements are not authorized under NWP.

H. Erosion Control

- Erosion control blanket or fabric used in or adjacent to waters of the U.S. shall be comprised of biodegradable material, to ensure decomposition and reduced risk to fish, wildlife and public safety, unless conditioned otherwise. If the applicant proposes to use materials other than as indicated above they must demonstrate how the use of such materials will not cause harm to fish, wildlife and public safety.

I. Reporting Requirement for Federal Permittees

- Federal Agencies with projects that require compensatory mitigation for loss of waters of the U.S. and who propose to purchase credits from an approved wetland and/or stream mitigation bank must provide proof of purchase within 30 days of when the credits were purchased. Purchase of credits from an approved mitigation bank must be IAW the Mitigation Banking Instrument of Record.

⁵ Northwest Regional Sediment Evaluation Team (RSET) 2016. Sediment Evaluation Framework for the Pacific Northwest. Prepared by the RSET Agencies, July 2016, 160 pp plus appendices. <http://nwd.usace.army.mil/Missions/Civil-Works/Navigation/RSET/SEF>

REGIONAL ADDITIONS TO THE GENERAL CONDITIONS

General Condition 4. Migratory Bird Breeding Areas. Regional Addition: For additional information please contact the US Fish and Wildlife Service at the following field office locations: State Office (Boise) at (208) 387-5243; Northern Idaho Field Office (Spokane) at (509) 891-6839; or the Eastern Idaho Field Office (Chubbuck) at (208) 237-6975.
<https://www.fws.gov/idaho/promo.cfm?id=177175802>

General Condition 6. Suitable Material. Regional Addition: Erosion control blanket or fabric used in or adjacent to waters of the U.S. shall be comprised of biodegradable material, to ensure decomposition and reduced risk to fish, wildlife and public safety, unless conditioned otherwise. If the applicant proposes to use materials other than as indicated above they must demonstrate how the use of such materials will not cause harm to fish, wildlife and public safety.

General Condition 9. Management of Water Flows. Regional Addition: To obtain information on State of Idaho definition of high water refer to Idaho Department of Water Resources (IDAPA 37.03.07. Rule 62.03.04.a). For culverts or bridges located in a community qualifying for the national flood insurance program, the minimum size culvert shall accommodate the 100-year flood design flow frequency (IDAPA 37.03.07. Rule 62.03.04.c).

General Condition 12. Soil Erosion and Sediment Controls. Regional Addition: For additional information refer to the Idaho Department of Environmental Quality Catalog of Stormwater Best Management Practices for Idaho Cities and Counties, available online at: <https://www.deq.idaho.gov/public-information/laws-guidance-and-orders/guidance/>.

General Condition 18. Endangered Species. Regional Addition: For additional information on ESA listed species in north Idaho please contact the US Fish and Wildlife Service (USFWS) Northern Idaho Field Office (Spokane) at (509) 893-8009, for all other counties in Idaho contact the USFWS State Office (Boise) at (208) 378-5388.

General Condition 20. Historic Properties. Regional Addition: Property is generally considered "historic" if it is at least 50 years old, and is not limited to buildings. For additional information on the potential for cultural resources in proximity to the project site, contact the Idaho State Historic Preservation Office at (208) 334-3847 located in Boise, Idaho.

NOTIFICATION PROCEDURES BY THE CORPS FOR CERTAIN NATIONWIDE PERMITS

Waivers: For nationwide permits with a waiver provision, District coordination with Idaho Department of Environmental Quality (IDEQ) and Environmental Protection Agency (tribal lands) will be conducted prior to the District Engineer making a waiver determination to ensure the proposed activity is in compliance with Section 401 Water Quality Standards.

Select Waters and Wetlands: The Corps will coordinate with the Idaho Department of Fish and Game (IDFG) for activities in the following waters and wetlands that require notification and are authorized by NWP:

- Waters: Waters: Anadromous waters as shown on Figure 1: *Watersheds Requiring Pre-Construction Notification*, dated January 6, 2021; Henry's Fork of the Snake River and its tributaries; South Fork Snake River and its tributaries; Big Lost River and its tributaries upstream of the US 93 crossing; Beaver, Camas, and Medicine Lodge Creeks; Snake River; Blackfoot River above Blackfoot Reservoir; Portneuf River; Bear River; Boise River including South Fork, North Fork and Middle Fork; Payette River including South Fork, North Fork and Middle Fork; Coeur d'Alene River, including the North Fork; St. Joe River; Priest River; Kootenai River; Big Wood River; and Silver Creek and its tributaries.
- Wetlands identified in Idaho Department of Fish and Game, Wetland Conservation Strategy as Class I, Class II and Reference Habitat Sites⁶.
- Wetlands identified in the Idaho Wetland Conservation Prioritization Plan-2012⁷.

NWP 27-Aquatic Habitat Restoration, Establishment, and Enhancement Activities

Prior to verification, the Corps will coordinate the project with the Idaho Department of Fish and Game for activities in perennial, fish bearing streams.


⁶ Idaho Department of Fish and Game (IDFG) Wetland Conservation Strategies have been developed for the Henrys Fork Basin, Northern Idaho, Big Wood River, Southeast Idaho, East-Central Idaho and Spokane River Basin, Middle and Western Snake River and tributaries, and the Upper Snake River-Portneuf Drainage, Weiser River Basin, and West Central Mountain Valleys and adjacent wetlands. Closed basins of Beaver-Camas Creeks, Medicine Lodge Creek, Palouse River and lower Clearwater River sub-basins, Middle Fork and South Fork Clearwater Basins and Camas Prairie in northern Idaho. Refer to the internet site at: <http://fishandgame.idaho.gov/content/page/wetlands-publications-idaho-natural-heritage-program#reports>

⁷ Murphy, C., J. Miller and A. Schmidt. 2012. [https://parksandrecreation.idaho.gov/sites/default/files/uploads/documents/SCORTP/Update/Appendix%20-%20Wetlands%20Priority%20Plan%20\(Part %20I\)%Compressed1.pdf](https://parksandrecreation.idaho.gov/sites/default/files/uploads/documents/SCORTP/Update/Appendix%20-%20Wetlands%20Priority%20Plan%20(Part%20I)%20Compressed1.pdf)

Figure 1



Watersheds Requiring Pre-Construction Notification



2021 Nationwide Permit General Conditions

Note: To qualify for NWP authorization, the prospective permittee must comply with the following general conditions, as applicable, in addition to any regional or case-specific conditions imposed by the division engineer or district engineer. Prospective permittees should contact the appropriate Corps district office to determine if regional conditions have been imposed on an NWP. Prospective permittees should also contact the appropriate Corps district office to determine the status of Clean Water Act Section 401 water quality certification and/or Coastal Zone Management Act consistency for an NWP. Every person who may wish to obtain permit authorization under one or more NWPs, or who is currently relying on an existing or prior permit authorization under one or more NWPs, has been and is on notice that all of the provisions of 33 CFR 330.1 through 330.6 apply to every NWP authorization. Note especially 33 CFR 330.5 relating to the modification, suspension, or revocation of any NWP authorization.

1. Navigation

(a) No activity may cause more than a minimal adverse effect on navigation.

(b) Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States.

(c) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his or her authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

2. Aquatic Life Movements

No activity may substantially disrupt the necessary life

cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. All permanent and temporary crossings of waterbodies shall be suitably culverted, bridged, or otherwise designed and constructed to maintain low flows to sustain the movement of those aquatic species. If a bottomless culvert cannot be used, then the crossing should be designed and constructed to minimize adverse effects to aquatic life movements.

3. Spawning Areas

Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.

4. Migratory Bird Breeding Areas

Activities in waters of the United States that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

5. Shellfish Beds

No activity may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWP 4 and 48, or is a shellfish seeding or habitat restoration activity authorized by NWP 27.

6. Suitable Material

No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see section 307 of the Clean Water Act).

7. Water Supply Intakes

No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. Adverse Effects From Impoundments

If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or restricting its flow must be minimized to the maximum extent practicable.

9. Management of Water Flows

To the maximum extent practicable, the pre-construction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization, storm water management activities, and temporary and permanent road crossings, except as provided below. The activity must be constructed to withstand expected high flows. The activity must not restrict or impede the passage of normal or high flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the pre-construction course, condition, capacity, and location of open waters if it benefits the aquatic environment (e.g., stream restoration or relocation activities).

10. Fills Within 100-Year Floodplains

The activity must comply with applicable FEMA-approved state or local floodplain management requirements.

11. Equipment

Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance.

12. Soil Erosion and Sediment Controls

Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow, or during low tides.

13. Removal of Temporary Structures and Fills

Temporary structures must be removed, to the maximum extent practicable, after their use has been discontinued. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The affected areas must be revegetated, as appropriate.

14. Proper Maintenance

Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety and compliance with applicable NWP general conditions, as well as any activity-specific conditions added by the district

engineer to an NWP authorization.

15. Single and Complete Project

The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

16. Wild and Scenic Rivers

(a) No NWP activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a “study river” for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status.

(b) If a proposed NWP activity will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a “study river” for possible inclusion in the system while the river is in an official study status, the permittee must submit a pre-construction notification (see general condition 32). The district engineer will coordinate the PCN with the Federal agency

with direct management responsibility for that river. Permittees shall not begin the NWP activity until notified by the district engineer that the Federal agency with direct management responsibility for that river has determined in writing that the proposed NWP activity will not adversely affect the Wild and Scenic River designation or study status.

(c) Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency responsible for the designated Wild and Scenic River or study river (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service). Information on these rivers is also available at: <http://www.rivers.gov/>.

17. Tribal Rights

No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.

18. Endangered Species

(a) No activity is authorized under any NWP which is likely to directly or indirectly jeopardize the continued existence of a threatened or endangered species or a

species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will directly or indirectly destroy or adversely modify designated critical habitat or critical habitat proposed for such designation. No activity is authorized under any NWP which "may affect" a listed species or critical habitat, unless ESA section 7 consultation addressing the consequences of the proposed activity on listed species or critical habitat has been completed. See 50 CFR 402.02 for the definition of "effects of the action" for the purposes of ESA section 7 consultation, as well as 50 CFR 402.17, which provides further explanation under ESA section 7 regarding "activities that are reasonably certain to occur" and "consequences caused by the proposed action."

(b) Federal agencies should follow their own procedures for complying with the requirements of the ESA (see 33 CFR 330.4(f)(1)). If pre-construction notification is required for the proposed activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate

documentation has not been submitted, additional ESA section 7 consultation may be necessary for the activity and the respective federal agency would be responsible for fulfilling its obligation under section 7 of the ESA.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat or critical habitat proposed for such designation, and shall not begin work on the activity until notified by the district engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that might affect Federally-listed endangered or threatened species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation), the pre-construction notification must include the name(s) of the endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or that utilize the designated critical habitat (or critical habitat proposed for such designation) that might be

affected by the proposed activity. The district engineer will determine whether the proposed activity “may affect” or will have “no effect” to listed species and designated critical habitat and will notify the non-Federal applicant of the Corps’ determination within 45 days of receipt of a complete pre-construction notification. For activities where the non-Federal applicant has identified listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) that might be affected or is in the vicinity of the activity, and has so notified the Corps, the applicant shall not begin work until the Corps has provided notification that the proposed activity will have “no effect” on listed species (or species proposed for listing or designated critical habitat (or critical habitat proposed for such designation), or until ESA section 7 consultation or conference has been completed. If the non-Federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(d) As a result of formal or informal consultation or conference with the FWS or NMFS the district engineer may add species-specific

permit conditions to the NWP.

(e) Authorization of an activity by an NWP does not authorize the “take” of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with “incidental take” provisions, etc.) from the FWS or the NMFS, the Endangered Species Act prohibits any person subject to the jurisdiction of the United States to take a listed species, where “take” means to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct. The word “harm” in the definition of “take” means an act which actually kills or injures wildlife. Such an act may include significant habitat modification or degradation where it actually kills or injures wildlife by significantly impairing essential behavioral patterns, including breeding, feeding or sheltering.

(f) If the non-federal permittee has a valid ESA section 10(a)(1)(B) incidental take permit with an approved Habitat Conservation Plan for a project or a group of projects that includes the proposed NWP activity, the non-federal applicant should

provide a copy of that ESA section 10(a)(1)(B) permit with the PCN required by paragraph (c) of this general condition. The district engineer will coordinate with the agency that issued the ESA section 10(a)(1)(B) permit to determine whether the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation conducted for the ESA section 10(a)(1)(B) permit. If that coordination results in concurrence from the agency that the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation for the ESA section 10(a)(1)(B) permit, the district engineer does not need to conduct a separate ESA section 7 consultation for the proposed NWP activity. The district engineer will notify the non-federal applicant within 45 days of receipt of a complete pre-construction notification whether the ESA section 10(a)(1)(B) permit covers the proposed NWP activity or whether additional ESA section 7 consultation is required.

(g) Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the FWS and NMFS or their world wide web pages at

<http://www.fws.gov/> or <http://www.fws.gov/ipac> and <http://www.nmfs.noaa.gov/pr/species/esa/> respectively.

19. Migratory Birds and Bald and Golden Eagles

The permittee is responsible for ensuring that an action authorized by an NWP complies with the Migratory Bird Treaty Act and the Bald and Golden Eagle Protection Act. The permittee is responsible for contacting the appropriate local office of the U.S. Fish and Wildlife Service to determine what measures, if any, are necessary or appropriate to reduce adverse effects to migratory birds or eagles, including whether "incidental take" permits are necessary and available under the Migratory Bird Treaty Act or Bald and Golden Eagle Protection Act for a particular activity.

20. Historic Properties

(a) No activity is authorized under any NWP which may have the potential to cause effects to properties listed, or eligible for listing, in the National Register of Historic Places until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.

(b) Federal permittees should follow their own

procedures for complying with the requirements of section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)(1)). If pre-construction notification is required for the proposed NWP activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation is not submitted, then additional consultation under section 106 may be necessary. The respective federal agency is responsible for fulfilling its obligation to comply with section 106.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if the NWP activity might have the potential to cause effects to any historic properties listed on, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including previously unidentified properties. For such activities, the pre-construction notification must state which historic properties might have the potential to be affected by the proposed NWP activity or include a vicinity map indicating the location of the historic properties or the

potential for the presence of historic properties. Assistance regarding information on the location of, or potential for, the presence of historic properties can be sought from the State Historic Preservation Officer, Tribal Historic Preservation Officer, or designated tribal representative, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). When reviewing pre-construction notifications, district engineers will comply with the current procedures for addressing the requirements of section 106 of the National Historic Preservation Act. The district engineer shall make a reasonable and good faith effort to carry out appropriate identification efforts commensurate with potential impacts, which may include background research, consultation, oral history interviews, sample field investigation, and/or field survey. Based on the information submitted in the PCN and these identification efforts, the district engineer shall determine whether the proposed NWP activity has the potential to cause effects on the historic properties. Section 106 consultation is not required when the district engineer determines that the activity does not have the potential to cause effects on historic properties (see 36 CFR 800.3(a)).

Section 106 consultation is required when the district engineer determines that the activity has the potential to cause effects on historic properties. The district engineer will conduct consultation with consulting parties identified under 36 CFR 800.2(c) when he or she makes any of the following effect determinations for the purposes of section 106 of the NHPA: no historic properties affected, no adverse effect, or adverse effect.

(d) Where the non-Federal applicant has identified historic properties on which the proposed NWP activity might have the potential to cause effects and has so notified the Corps, the non-Federal applicant shall not begin the activity until notified by the district engineer either that the activity has no potential to cause effects to historic properties or that NHPA section 106 consultation has been completed. For non-federal permittees, the district engineer will notify the prospective permittee within 45 days of receipt of a complete pre-construction notification whether NHPA section 106 consultation is required. If NHPA section 106 consultation is required, the district engineer will notify the non-Federal applicant that he or she cannot begin the activity until section 106

consultation is completed. If the non-Federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(e) Prospective permittees should be aware that section 110k of the NHPA (54 U.S.C. 306113) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless the Corps, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant. If circumstances justify granting the assistance, the Corps is required to notify the ACHP and provide documentation specifying the circumstances, the degree of damage to the integrity of any historic properties affected, and proposed mitigation. This documentation must include any views obtained from the applicant, SHPO/THPO, appropriate Indian tribes if the undertaking occurs on or affects historic properties on tribal lands or affects

properties of interest to those tribes, and other parties known to have a legitimate interest in the impacts to the permitted activity on historic properties.

21. Discovery of Previously Unknown Remains and Artifacts

Permittees that discover any previously unknown historic, cultural or archeological remains and artifacts while accomplishing the activity authorized by an NWP, they must immediately notify the district engineer of what they have found, and to the maximum extent practicable, avoid construction activities that may affect the remains and artifacts until the required coordination has been completed. The district engineer will initiate the Federal, Tribal, and state coordination required to determine if the items or remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.

22. Designated Critical Resource Waters

Critical resource waters include, NOAA-managed marine sanctuaries and marine monuments, and National Estuarine Research Reserves. The district engineer may designate, after notice and opportunity for public comment,

additional waters officially designated by a state as having particular environmental or ecological significance, such as outstanding national resource waters or state natural heritage sites. The district engineer may also designate additional critical resource waters after notice and opportunity for public comment.

(a) Discharges of dredged or fill material into waters of the United States are not authorized by NWP 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, 50, 51, 52, 57 and 58 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters.

(b) For NWP 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, 38, and 54, notification is required in accordance with general condition 32, for any activity proposed by permittees in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWPs only after she or he determines that the impacts to the critical resource waters will be no more than minimal.

23. Mitigation

The district engineer will consider the following

factors when determining appropriate and practicable mitigation necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal:

(a) The activity must be designed and constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States to the maximum extent practicable at the project site (i.e., on site).

(b) Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating for resource losses) will be required to the extent necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal.

(c) Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland losses that exceed 1/10-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. For wetland losses of 1/10-acre or less that require pre-

construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects.

(d) Compensatory mitigation at a minimum one-for-one ratio will be required for all losses of stream bed that exceed 3/100-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. This compensatory mitigation requirement may be satisfied through the restoration or enhancement of riparian areas next to streams in accordance with paragraph (e) of this general condition. For losses of stream bed of 3/100-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects. Compensatory mitigation for losses of

streams should be provided, if practicable, through stream rehabilitation, enhancement, or preservation, since streams are difficult-to-replace resources (see 33 CFR 332.3(e)(3)).

(e) Compensatory mitigation plans for NWP activities in or near streams or other open waters will normally include a requirement for the restoration or enhancement, maintenance, and legal protection (e.g., conservation easements) of riparian areas next to open waters. In some cases, the restoration or maintenance/protection of riparian areas may be the only compensatory mitigation required. If restoring riparian areas involves planting vegetation, only native species should be planted. The width of the required riparian area will address documented water quality or aquatic habitat loss concerns. Normally, the riparian area will be 25 to 50 feet wide on each side of the stream, but the district engineer may require slightly wider riparian areas to address documented water quality or habitat loss concerns. If it is not possible to restore or maintain/protect a riparian area on both sides of a stream, or if the waterbody is a lake or coastal waters, then restoring or maintaining/protecting a

riparian area along a single bank or shoreline may be sufficient. Where both wetlands and open waters exist on the project site, the district engineer will determine the appropriate compensatory mitigation (e.g., riparian areas and/or wetlands compensation) based on what is best for the aquatic environment on a watershed basis. In cases where riparian areas are determined to be the most appropriate form of minimization or compensatory mitigation, the district engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland losses.

(f) Compensatory mitigation projects provided to offset losses of aquatic resources must comply with the applicable provisions of 33 CFR part 332.

(1) The prospective permittee is responsible for proposing an appropriate compensatory mitigation option if compensatory mitigation is necessary to ensure that the activity results in no more than minimal adverse environmental effects. For the NWPs, the preferred mechanism for providing compensatory mitigation is mitigation bank credits or in-lieu fee program credits (see 33 CFR 332.3(b)(2) and (3)).

However, if an appropriate number and type of mitigation bank or in-lieu credits are not available at the time the PCN is submitted to the district engineer, the district engineer may approve the use of permittee-responsible mitigation.

(2) The amount of compensatory mitigation required by the district engineer must be sufficient to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see 33 CFR 330.1(e)(3)). (See also 33 CFR 332.3(f).)

(3) Since the likelihood of success is greater and the impacts to potentially valuable uplands are reduced, aquatic resource restoration should be the first compensatory mitigation option considered for permittee-responsible mitigation.

(4) If permittee-responsible mitigation is the proposed option, the prospective permittee is responsible for submitting a mitigation plan. A conceptual or detailed mitigation plan may be used by the district engineer to make the decision on the NWP verification request, but a final mitigation plan that addresses the applicable requirements of 33 CFR 332.4(c)(2) through (14)

must be approved by the district engineer before the permittee begins work in waters of the United States, unless the district engineer determines that prior approval of the final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation (see 33 CFR 332.3(k)(3)). If permittee-responsible mitigation is the proposed option, and the proposed compensatory mitigation site is located on land in which another federal agency holds an easement, the district engineer will coordinate with that federal agency to determine if proposed compensatory mitigation project is compatible with the terms of the easement.

(5) If mitigation bank or in-lieu fee program credits are the proposed option, the mitigation plan needs to address only the baseline conditions at the impact site and the number of credits to be provided (see 33 CFR 332.4(c)(1)(ii)).

(6) Compensatory mitigation requirements (e.g., resource type and amount to be provided as compensatory mitigation, site protection, ecological performance standards, monitoring requirements) may be addressed through conditions added to the NWP authorization, instead of

components of a compensatory mitigation plan (see 33 CFR 332.4(c)(1)(ii)).

(g) Compensatory mitigation will not be used to increase the acreage losses allowed by the acreage limits of the NWPs. For example, if an NWP has an acreage limit of 1/2-acre, it cannot be used to authorize any NWP activity resulting in the loss of greater than 1/2-acre of waters of the United States, even if compensatory mitigation is provided that replaces or restores some of the lost waters. However, compensatory mitigation can and should be used, as necessary, to ensure that an NWP activity already meeting the established acreage limits also satisfies the no more than minimal impact requirement for the NWPs.

(h) Permittees may propose the use of mitigation banks, in-lieu fee programs, or permittee-responsible mitigation. When developing a compensatory mitigation proposal, the permittee must consider appropriate and practicable options consistent with the framework at 33 CFR 332.3(b). For activities resulting in the loss of marine or estuarine resources, permittee-responsible mitigation may be environmentally preferable if there are no

mitigation banks or in-lieu fee programs in the area that have marine or estuarine credits available for sale or transfer to the permittee. For permittee-responsible mitigation, the special conditions of the NWP verification must clearly indicate the party or parties responsible for the implementation and performance of the compensatory mitigation project, and, if required, its long-term management.

(i) Where certain functions and services of waters of the United States are permanently adversely affected by a regulated activity, such as discharges of dredged or fill material into waters of the United States that will convert a forested or scrub-shrub wetland to a herbaceous wetland in a permanently maintained utility line right-of-way, mitigation may be required to reduce the adverse environmental effects of the activity to the no more than minimal level.

24. Safety of Impoundment Structures

To ensure that all impoundment structures are safely designed, the district engineer may require non-Federal applicants to demonstrate that the structures comply with established state or federal, dam safety criteria or have

been designed by qualified persons. The district engineer may also require documentation that the design has been independently reviewed by similarly qualified persons, and appropriate modifications made to ensure safety.

25. Water Quality

(a) Where the certifying authority (state, authorized tribe, or EPA, as appropriate) has not previously certified compliance of an NWP with CWA section 401, a CWA section 401 water quality certification for the proposed discharge must be obtained or waived (see 33 CFR 330.4(c)). If the permittee cannot comply with all of the conditions of a water quality certification previously issued by certifying authority for the issuance of the NWP, then the permittee must obtain a water quality certification or waiver for the proposed discharge in order for the activity to be authorized by an NWP.

(b) If the NWP activity requires pre-construction notification and the certifying authority has not previously certified compliance of an NWP with CWA section 401, the proposed discharge is not authorized by an NWP until water quality certification is obtained or waived. If the certifying authority issues a

water quality certification for the proposed discharge, the permittee must submit a copy of the certification to the district engineer. The discharge is not authorized by an NWP until the district engineer has notified the permittee that the water quality certification requirement has been satisfied by the issuance of a water quality certification or a waiver.

(c) The district engineer or certifying authority may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.

26. Coastal Zone Management.

In coastal states where an NWP has not previously received a state coastal zone management consistency concurrence, an individual state coastal zone management consistency concurrence must be obtained, or a presumption of concurrence must occur (see 33 CFR 330.4(d)). If the permittee cannot comply with all of the conditions of a coastal zone management consistency concurrence previously issued by the state, then the permittee must obtain an individual coastal zone management consistency concurrence or presumption of concurrence

in order for the activity to be authorized by an NWP. The district engineer or a state may require additional measures to ensure that the authorized activity is consistent with state coastal zone management requirements.

27. Regional and Case-By-Case Conditions

The activity must comply with any regional conditions that may have been added by the Division Engineer (see 33 CFR 330.4(e)) and with any case specific conditions added by the Corps or by the state, Indian Tribe, or U.S. EPA in its CWA section 401 Water Quality Certification, or by the state in its Coastal Zone Management Act consistency determination.

28. Use of Multiple Nationwide Permits

The use of more than one NWP for a single and complete project is authorized, subject to the following restrictions:

(a) If only one of the NWPs used to authorize the single and complete project has a specified acreage limit, the acreage loss of waters of the United States cannot exceed the acreage limit of the NWP with the highest specified acreage limit. For example, if a road crossing over tidal waters is constructed under NWP 14, with associated

bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the United States for the total project cannot exceed 1/3-acre.

(b) If one or more of the NWPs used to authorize the single and complete project has specified acreage limits, the acreage loss of waters of the United States authorized by those NWPs cannot exceed their respective specified acreage limits. For example, if a commercial development is constructed under NWP 39, and the single and complete project includes the filling of an upland ditch authorized by NWP 46, the maximum acreage loss of waters of the United States for the commercial development under NWP 39 cannot exceed 1/2-acre, and the total acreage loss of waters of United States due to the NWP 39 and 46 activities cannot exceed 1 acre.

29. Transfer of Nationwide Permit Verifications

If the permittee sells the property associated with a nationwide permit verification, the permittee may transfer the nationwide permit verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the nationwide permit verification must be attached

to the letter, and the letter must contain the following statement and signature:

“When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.”

(Transferee)

(Date)

30. Compliance Certification

Each permittee who receives an NWP verification letter from the Corps must provide a signed certification documenting completion of the authorized activity and implementation of any required compensatory mitigation. The success of any required permittee-responsible mitigation, including the achievement of

ecological performance standards, will be addressed separately by the district engineer. The Corps will provide the permittee the certification document with the NWP verification letter. The certification document will include:

(a) A statement that the authorized activity was done in accordance with the NWP authorization, including any general, regional, or activity-specific conditions;

(b) A statement that the implementation of any required compensatory mitigation was completed in accordance with the permit conditions. If credits from a mitigation bank or in-lieu fee program are used to satisfy the compensatory mitigation requirements, the certification must include the documentation required by 33 CFR 332.3(l)(3) to confirm that the permittee secured the appropriate number and resource type of credits; and

(c) The signature of the permittee certifying the completion of the activity and mitigation.

The completed certification document must be submitted to the district engineer within 30 days of completion of the authorized activity or the implementation of any required compensatory

mitigation, whichever occurs later.

31. Activities Affecting Structures or Works Built by the United States

If an NWP activity also requires review by, or permission from, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers (USACE) federally authorized Civil Works project (a "USACE project"), the prospective permittee must submit a pre-construction notification. See paragraph (b)(10) of general condition 32. An activity that requires section 408 permission and/or review is not authorized by an NWP until the appropriate Corps office issues the section 408 permission or completes its review to alter, occupy, or use the USACE project, and the district engineer issues a written NWP verification.

32. Pre-Construction Notification

(a) *Timing.* Where required by the terms of the NWP, the prospective permittee must notify the district engineer by submitting a pre-construction notification (PCN) as early as possible. The district engineer must determine if the PCN is complete within 30 calendar days of the date of receipt and, if the PCN is determined

to be incomplete, notify the prospective permittee within that 30 day period to request the additional information necessary to make the PCN complete. The request must specify the information needed to make the PCN complete. As a general rule, district engineers will request additional information necessary to make the PCN complete only once. However, if the prospective permittee does not provide all of the requested information, then the district engineer will notify the prospective permittee that the PCN is still incomplete and the PCN review process will not commence until all of the requested information has been received by the district engineer. The prospective permittee shall not begin the activity until either:

(1) He or she is notified in writing by the district engineer that the activity may proceed under the NWP with any special conditions imposed by the district or division engineer; or

(2) 45 calendar days have passed from the district engineer's receipt of the complete PCN and the prospective permittee has not received written notice from the district or division engineer. However, if the permittee was required to notify the Corps pursuant to general condition 18 that

listed species or critical habitat might be affected or are in the vicinity of the activity, or to notify the Corps pursuant to general condition 20 that the activity might have the potential to cause effects to historic properties, the permittee cannot begin the activity until receiving written notification from the Corps that there is "no effect" on listed species or "no potential to cause effects" on historic properties, or that any consultation required under Section 7 of the Endangered Species Act (see 33 CFR 330.4(f)) and/or section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)) has been completed. If the proposed activity requires a written waiver to exceed specified limits of an NWP, the permittee may not begin the activity until the district engineer issues the waiver. If the district or division engineer notifies the permittee in writing that an individual permit is required within 45 calendar days of receipt of a complete PCN, the permittee cannot begin the activity until an individual permit has been obtained. Subsequently, the permittee's right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).

(b) *Contents of Pre-Construction Notification:*

The PCN must be in writing and include the following information:

- (1) Name, address and telephone numbers of the prospective permittee;
- (2) Location of the proposed activity;
- (3) Identify the specific NWP or NWP(s) the prospective permittee wants to use to authorize the proposed activity;
- (4) (i) A description of the proposed activity; the activity's purpose; direct and indirect adverse environmental effects the activity would cause, including the anticipated amount of loss of wetlands, other special aquatic sites, and other waters expected to result from the NWP activity, in acres, linear feet, or other appropriate unit of measure; a description of any proposed mitigation measures intended to reduce the adverse environmental effects caused by the proposed activity; and any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings for linear projects that require Department of

the Army authorization but do not require pre-construction notification. The description of the proposed activity and any proposed mitigation measures should be sufficiently detailed to allow the district engineer to determine that the adverse environmental effects of the activity will be no more than minimal and to determine the need for compensatory mitigation or other mitigation measures.

(ii) For linear projects where one or more single and complete crossings require pre-construction notification, the PCN must include the quantity of anticipated losses of wetlands, other special aquatic sites, and other waters for each single and complete crossing of those wetlands, other special aquatic sites, and other waters (including those single and complete crossings authorized by an NWP but do not require PCNs). This information will be used by the district engineer to evaluate the cumulative adverse environmental effects of the proposed linear project, and does not change those non-PCN NWP activities into NWP PCNs.

(iii) Sketches should be provided when necessary to show that the activity complies with the terms of the NWP. (Sketches usually

clarify the activity and when provided results in a quicker decision. Sketches should contain sufficient detail to provide an illustrative description of the proposed activity (e.g., a conceptual plan), but do not need to be detailed engineering plans);

(5) The PCN must include a delineation of wetlands, other special aquatic sites, and other waters, such as lakes and ponds, and perennial and intermittent streams, on the project site. Wetland delineations must be prepared in accordance with the current method required by the Corps. The permittee may ask the Corps to delineate the special aquatic sites and other waters on the project site, but there may be a delay if the Corps does the delineation, especially if the project site is large or contains many wetlands, other special aquatic sites, and other waters. Furthermore, the 45-day period will not start until the delineation has been submitted to or completed by the Corps, as appropriate;

(6) If the proposed activity will result in the loss of greater than 1/10-acre of wetlands or 3/100-acre of stream bed and a PCN is required, the prospective permittee must submit a statement describing how the mitigation requirement will be satisfied, or explaining

why the adverse environmental effects are no more than minimal and why compensatory mitigation should not be required. As an alternative, the prospective permittee may submit a conceptual or detailed mitigation plan.

(7) For non-federal permittees, if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat (or critical habitat proposed for such designation), the PCN must include the name(s) of those endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or utilize the designated critical habitat (or critical habitat proposed for such designation) that might be affected by the proposed activity. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with the Endangered Species Act;

(8) For non-federal permittees, if the NWP activity might have the potential to cause effects to a historic property listed on,

determined to be eligible for listing on, or potentially eligible for listing on, the National Register of Historic Places, the PCN must state which historic property might have the potential to be affected by the proposed activity or include a vicinity map indicating the location of the historic property. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with section 106 of the National Historic Preservation Act;

(9) For an activity that will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a “study river” for possible inclusion in the system while the river is in an official study status, the PCN must identify the Wild and Scenic River or the “study river” (see general condition 16); and

(10) For an NWP activity that requires permission from, or review by, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers federally authorized civil works project, the pre-construction notification must include a statement confirming that the project proponent has submitted a written request

for section 408 permission from, or review by, the Corps office having jurisdiction over that USACE project.

(c) *Form of Pre-Construction Notification:* The nationwide permit pre-construction notification form (Form ENG 6082) should be used for NWP PCNs. A letter containing the required information may also be used. Applicants may provide electronic files of PCNs and supporting materials if the district engineer has established tools and procedures for electronic submittals.

(d) *Agency Coordination:* (1) The district engineer will consider any comments from Federal and state agencies concerning the proposed activity’s compliance with the terms and conditions of the NWPs and the need for mitigation to reduce the activity’s adverse environmental effects so that they are no more than minimal.

(2) Agency coordination is required for: (i) all NWP activities that require pre-construction notification and result in the loss of greater than 1/2-acre of waters of the United States; (ii) NWP 13 activities in excess of 500 linear feet, fills greater than one cubic yard per running foot, or involve discharges of dredged or fill material into special aquatic sites; and (iii)

NWP 54 activities in excess of 500 linear feet, or that extend into the waterbody more than 30 feet from the mean low water line in tidal waters or the ordinary high water mark in the Great Lakes.

(3) When agency coordination is required, the district engineer will immediately provide (e.g., via e-mail, facsimile transmission, overnight mail, or other expeditious manner) a copy of the complete PCN to the appropriate Federal or state offices (FWS, state natural resource or water quality agency, EPA, and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will have 10 calendar days from the date the material is transmitted to notify the district engineer via telephone, facsimile transmission, or e-mail that they intend to provide substantive, site-specific comments. The comments must explain why the agency believes the adverse environmental effects will be more than minimal. If so contacted by an agency, the district engineer will wait an additional 15 calendar days before making a decision on the pre-construction notification. The district engineer will fully consider agency comments received within the specified time frame concerning the proposed activity's

compliance with the terms and conditions of the NWPs, including the need for mitigation to ensure that the net adverse environmental effects of the proposed activity are no more than minimal. The district engineer will provide no response to the resource agency, except as provided below. The district engineer will indicate in the administrative record associated with each pre-construction notification that the resource agencies' concerns were considered. For NWP 37, the emergency watershed protection and rehabilitation activity may proceed immediately in cases where there is an unacceptable hazard to life or a significant loss of property or economic hardship will occur. The district engineer will consider any comments received to decide whether the NWP 37 authorization should be modified, suspended, or revoked in accordance with the procedures at 33 CFR 330.5.

(4) In cases of where the prospective permittee is not a Federal agency, the district engineer will provide a response to NMFS within 30 calendar days of receipt of any Essential Fish Habitat conservation recommendations, as required by section 305(b)(4)(B) of the Magnuson-Stevens Fishery

Conservation and Management Act.

(5) Applicants are encouraged to provide the Corps with either electronic files or multiple copies of pre-construction notifications to expedite agency coordination.



Idaho Department of Environmental Quality Final Section 401 Water Quality Certification

July 29, 2024

Project Name: SH-75, Elkhorn Road to River Street (Key # 20033), NWW-2024-00333

Permit Name and Number: Nationwide Permit 14, Linear Transportation

Applicant/Authorized Agent: Jesse Barrus and Scott Malone, Idaho Transportation Department District 4

Project Location: Ketchum, Blaine County, Idaho; 43.667041°, -114.355657°

Receiving Water Body: Trail Creek

Pursuant to the provisions of Section 401(a)(1) of the Federal Water Pollution Control Act (Clean Water Act), as amended; 33 U.S.C. Section 1341(a)(1); 40 C.F.R. § 121; and Idaho Code §§ 39-101 et seq. and 39-3601 et seq., the Idaho Department of Environmental Quality (DEQ) has authority to review activities receiving federal permits or licenses and issue water quality certification decisions.

In accordance with federal regulations at 40 C.F.R. § 121.4, all project proponents must submit a request for a prefiling meeting at least thirty days in advance of submitting a certification request. A prefiling meeting request was received by DEQ on 6/25/2024. To facilitate early engagement and project coordination, DEQ accepted an opportunity to host a prefiling meeting which was conducted on 10/12/2021 and 6/25/2024, to seek clarification as well as to discuss the project and potential information needs.

Based upon review of the federal permit application, readily available water quality related materials, and certification request in accordance with 40 C.F.R. §§ 121.5 (b) and (c) and 121.7 (c), received on, 6/27/2024, DEQ, certifies that if the permittee complies with the terms and conditions imposed by the federal permit and the conditions set forth in this water quality certification, then it is reasonable for DEQ to conclude that the activity will comply with water quality requirements, including applicable requirements of the Clean Water Act §§ 301, 302, 303, 306, and 307, Idaho's "Water Quality Standards" (IDAPA 58.01.02), and other appropriate water quality requirements of state law.

Pursuant to Clean Water Act § 401 (a)(1) and 40 C.F.R. § 121.7 (d); and IDAPA 58.01.02.052.08, DEQ issued a 21-day public notice to solicit comments on the draft certification on 7/29/2024

Accessibility Services: The Idaho Department of Environmental Quality will provide reasonable language access services and/or disability services for documents at no charge. To request an accommodation under Title VI of the Civil Rights Act of 1964 or Americans with Disabilities Act, contact DEQ's nondiscrimination coordinator at (208) 373-0271 or accessibility@deq.idaho.gov. Para obtener información en español, visite <https://www.deq.idaho.gov/about-us/accessibility/>.

through 8/18/2024. Any public comments received during the 21-day comment period were considered by DEQ to inform the certification decision and conditions.

This certification does not constitute authorization of the permitted activities by any other state or federal agency or private person or entity. This certification does not excuse the permit holder from the obligation to obtain any other necessary approvals, authorizations or permits.

1 Project Description

The project proposes to improve safety and capacity on SH-75 between the Big Wood River Bridge near Elkhorn Road and River Street in the City of Ketchum in Blaine County, mileposts (MP) 126.4 to 128.2. Project development will include roadway widening with curb, gutter, sidewalk, intersection improvement, retaining walls, drainage, and replacing a box culvert and constructing a reinforce slope along Trail Creek.

The total wetland impacts are 1,956 square feet (SF) (0.0449 acres) and the total open water impacts are 1,555 SF (0.0358 acres). The streambed impacts on Trail Creek are temporary, and beneficial improvements would be about 175 SF. Additional self-mitigating stabilization will be installed through a vegetated wall along the stream bank for 716 SF. The old SH-75 bridge will be removed, and the new bridge will have 30 feet longer span than the current design and will increase the available streambed by 1,642 SF (0.0377 acres). Mitigation will be on-site at Trail Creek.

The wetland and stream impacts are a result of road widening, bridge replacement (construction of a reinforce slope to stabilize the stream bank on Trail Creek and construction of a wildlife bench), and the installation of a stormwater facility. Work within wetlands consists of fill placement for roadway widening, scour protection, and streambank grading to increase hydraulic flow. Additionally, culvert work will be required. This will include installation of a concrete box and headwalls, modification of stormwater pond, and replacement of three irrigation culverts and irrigation crossing. Construction equipment will include rollers, backhoes, excavators, cranes, and other construction equipment typical for a roadway and bridge construction project. Waste material will be disposed of in an approved upland location. All bridge improvements will be located outside of the existing and proposed stream channels. The project is designed to restore a more natural channel, gradient, bed, and width, and improved bank stability through the structure. New bridge footings will be constructed above the ordinary high-water mark (OHWM). Equipment will include an excavator operating from the bank/existing roadway. The construction area below the OHWM of the open waters will be dewatered using sandbags or another similar temporary dewatering method. A qualified biologist will capture and remove fish from the dewatered work area if needed. A pump with a fish screen will be used to transfer water. The in-water work window will be observed for construction from March 15 to July 15, which was confirmed by Idaho Department of Water Resources and Idaho Department of Fish and Game.

An ITD approved site-specific Storm Water Pollution Prevention Plan (SWPPP) will be prepared for this project to comply with the Construction General Permit (CGP). The SWPPP will include measures to address sediment and erosion control with both temporary and permanent

measures. Critical areas including wetlands will be marked with exclusion fencing. The perimeter of the wetlands that are not permitted will be clearly marked with high visibility silt fence.

2 Antidegradation Review

As part of its water quality standards program, Idaho has an antidegradation policy providing three levels of protection to water bodies in Idaho (IDAPA 58.01.02.051). DEQ adopted regulations to implement the antidegradation policy (IDAPA 58.01.02.052).

Tier I Protection. The first level of protection applies to all water bodies subject to Clean Water Act jurisdiction and ensures that existing uses of a water body and the level of water quality necessary to protect those existing uses will be maintained and protected (IDAPA 58.01.02.051.01; 58.01.02.052.01). Additionally, a Tier I review is performed for all new or reissued permits or licenses (IDAPA 58.01.02.052.07).

Tier II Protection. The second level of protection applies to those water bodies considered high quality and ensures that no lowering of water quality will be allowed unless necessary to accommodate important economic or social development (IDAPA 58.01.02.051.02; 58.01.02.052.08).

Tier III Protection. The third level of protection applies to water bodies that have been designated outstanding resource waters and requires that activities do not lower water quality (IDAPA 58.01.02.051.03; 58.01.02.052.09).

DEQ employs a water-body-by-water-body approach to implementing Idaho's antidegradation policy. This approach means that any water body fully supporting its beneficial uses will be considered high quality (IDAPA 58.01.02.052.05.a). Any water body not fully supporting its beneficial uses will be provided Tier I protection for that use, unless specific circumstances warranting Tier II protection are met (IDAPA 58.01.02.052.05.c). The most recent federally approved [DEQ Integrated Report](#) and supporting data are used to determine support status and the tier of protection (IDAPA 58.01.02.052.05).

2.1 Pollutants of Concern

The pollutant of concern for this project is sediment. As part of the § 401 water quality certification, DEQ requires the applicant to comply with various conditions to protect water quality and meet Idaho's water quality standards, including the water quality criteria applicable to these pollutant(s).

2.2 Receiving Water Body Level of Protection

This project is located on Trail Creek within the Big Wood River subbasin assessment unit (AU) 17040219SK013_04 (Trail Creek - Corral Creek to mouth). According to DEQ's *2024 Integrated Report*, this AU has the following designated beneficial uses: Cold Water Aquatic Life and Salmonid Spawning. Secondary Contact Recreation is presumed. In addition to these uses, all

waters within the state are protected for agricultural and industrial water supply, wildlife habitat, and aesthetics (IDAPA 58.01.02.100). According to DEQ's 2024 Integrated Report, this receiving water body AU is fully supporting its assessed existing and presumed uses (IDAPA 58.01.02.052.05.a). As such, DEQ will provide Tier II protection in addition to Tier I for this water body (IDAPA 58.01.02.051.02; 58.01.02.051.01).

2.3 Protection and Maintenance of Existing Uses (Tier I Protection)

A Tier I review is performed for all new or reissued permits or licenses, applies to all waters subject to the jurisdiction of the Clean Water Act, and requires demonstration that existing uses and the level of water quality necessary to protect existing uses shall be maintained and protected. The numeric and narrative criteria in the water quality standards are set at levels that ensure protection of existing and designated beneficial uses.

Water bodies not supporting existing or designated beneficial uses must be identified as water quality limited, and a total maximum daily load (TMDL) must be prepared for those pollutants causing impairment. Once a TMDL is developed, discharges of causative pollutants shall be consistent with the allocations in the TMDL (IDAPA 58.01.02.055.05). Before developing the TMDL, the water quality standards require applying the antidegradation policy and implementation provisions to maintain and protect uses (IDAPA 58.01.02.055.04).

Throughout the life of the project, the applicant will implement, install, maintain, monitor, and adaptively manage best management practices (BMPs) to reduce erosion and minimize turbidity levels in receiving water bodies downstream of the project. In addition, permanent erosion and sediment controls will be implemented that will minimize or prevent future sediment contributions from the project area.

If the project is conducted according to the provisions of the project plans, federal permit and conditions of this certification, then it is reasonable for DEQ to conclude that the project will comply with the state's numeric and narrative water quality criteria. These criteria are set at levels that protect and maintain existing and designated beneficial uses.

There is no available information indicating the presence of any existing beneficial uses aside from those that are already designated and discussed above. The conditions in this certification ensure that the level of water quality necessary to protect both existing and designated uses is maintained and protected in compliance with the Tier I provisions of IDAPA 58.01.02.051.01 and 58.01.02.052.07.

2.4 High-Quality Waters (Tier II Protection)

The Trail Creek is considered high quality for Cold Water Aquatic Life and Salmonid Spawning. The water quality relevant to these uses must be maintained and protected, unless lowering water quality is necessary to accommodate important social or economic development.

To determine whether degradation will occur, DEQ must evaluate how the activities subject to the federal permit issuance will affect water quality for each pollutant that is relevant to

aquatic life, salmonid spawning and recreation uses of Trail Creek (IDAPA 58.01.02.052.06). The pollutant of concern is sediment. BMPs selected to prevent degradation include measures to minimize the potential for debris (e.g., dirt, concrete, etc.) to enter the area of wetlands not being impacted while removing and constructing structures; an approved spill control and prevention plan; an approved site-specific SWPPP to address sediment and erosion control with both temporary and permanent measures; all disturbed soils will be reseeded following construction; on-site mitigation will consist of native plantings, and retention walls at Trail Creek restoration area; dewatering may be accomplished by draining, pumping, bailing, or cribbing; if needed, temporary sump holes may be installed within the footings and abutment areas to be dewatered to create a more suitable pumping area; water removed during footing and abutment construction will be pumped to a temporary storage location where the water will be cleaned to standards specified DEQ; if appropriate, water from the dewatering activities may be pumped to a temporary storage/treatment site, or into upland areas and allowed to flow/filter through vegetation prior to reentering the stream channel; water behind the barrier may be pumped directly back into the stream providing the pumped water meets applicable in stream turbidity criteria; and turbidity monitoring will be conducted while working on or adjacent to Trail Creek. The project complies with IDAPA 58.01.02.051.02 and IDAPA 58.01.02.052.06.

To maintain the ambient water quality conditions, permanent erosion and sediment controls must be implemented to minimize or prevent future sediment contributions from the project area. The provisions in the federal permit and the conditions of this certification ensure that degradation to the ID17040219SK013_04 AU or the Trail Creek will not occur.

DEQ concludes that this project complies with the Tier II provisions of IDAPA 58.01.02.051.02, 58.01.02.052.06, and 58.01.02.052.08.

3 Conditions Necessary to Ensure Compliance with Water Quality Standards or Other Appropriate Water Quality Requirements of State Law

The following conditions ensure the SH-75, Elkhorn Road to River Street, NWW-2024-00333 project complies with Idaho's water quality standards and other appropriate water quality requirements of state law applicable to Trail Creek.

3.1 General Conditions

This certification is based on review of the federal permit application, readily available water quality related materials, and certification request submitted by the Idaho Department of Transportation on 6/27/2024 and is conditioned upon the requirement that any modification (e.g., change in work windows, etc.) of the permitted activity shall first be provided to DEQ for review to determine compliance with Idaho's water quality standards.

Because DEQ is certifying only the activity described in the certification request, this condition ensures that discharges under circumstances that differ from those described in the certification request will comply with 33 U.S.C. § 1341, 40 C.F.R. § 121, and other applicable water quality requirements, including without limitation 33 U.S.C. § 1311(a), Idaho Code § 39-108, IDAPA 58.01.02.051, IDAPA 58.01.02.052, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. DEQ reserves the right to modify this certification in accordance with 40 C.F.R. § 121.10 if DEQ determines that, due to changes in relevant circumstances—including without limitation, changes in project activities, the characteristics of the receiving water bodies, or state water quality standards—there is no longer reasonable assurance of compliance with the water quality standards or other appropriate requirements of state law.

Because DEQ is certifying only the activity described in the certification request based on information available at the time of certification, this condition ensures that discharges from activities not described in the certification request, or where there has been a change in the characteristics of or water quality standards applicable to the receiving water body, will comply with 33 U.S.C. § 1341, 40 C.F.R. 121, and other applicable water quality requirements, including without limitation 33 U.S.C. § 1311(a), Idaho Code § 39-108, IDAPA 58.01.02.051, IDAPA 58.01.02.052, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

2. If ownership of the project changes, the certification holder shall notify DEQ, in writing, upon transferring this ownership or responsibility for compliance with these conditions to another person or party. The new owner/operator shall request, in writing, the transfer of this water quality certification to the new name. This condition ensures that, if ownership changes, DEQ has the minimum information to support ongoing compliance with 33 U.S.C. § 1341, 40 C.F.R. 121, this water quality certification, and other applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.
3. A copy of this certification must be kept on the job site and readily available for review by any contractor working on the project and any federal, state, or local government personnel.

This condition ensures all responsible parties, including on-site contractors, are aware of and comply with this water quality certification and other applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

4. The applicant is responsible for all work done by contractors and must ensure the contractors are informed of and follow all the conditions described in this certification and the federal permit.

This condition ensures all responsible parties, including on-site contractors, comply with this water quality certification and applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

5. If this project disturbs more than 1-acre and there is potential for discharge of storm water to waters of the United States, then coverage under the [IPDES Construction General Permit Program](#) may be required.

This condition ensures that work authorized under the federal permit complies with water quality requirements prohibiting unauthorized storm water discharges, including without limitation 33 U.S.C. § 1311(a), 33 U.S.C. § 1342(p), IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

3.2 Fill Material

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Fill material subject to suspension will be free of easily suspended fine material. Only clean material may be placed as fill. If dredged material is proposed for use as fill material and there is a possibility the material may be contaminated, then the permittee must assess and characterize sediment to determine the suitability of dredge material for unconfined-aquatic placement; determine the suitability of post-dredge surfaces; and predict the effect on water quality during dredging. Sediment assessment and characterization following the procedures in the *Sediment Evaluation Framework for the Pacific Northwest* (RSET 2018) satisfies this requirement. A different assessment and characterization methodology may be used if the DEQ approves the methodology in writing.
2. Temporary fills will be removed in their entirety on or before construction completion.
3. Excavated or staged fill material must be placed so it is isolated from the water edge or wetlands and not placed where it could re-enter waters of the United States.

3.3 Erosion and Sediment Control

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. BMPs for sediment and erosion control suitable to prevent exceedances of Idaho's water quality standards and consistency with TMDLs shall be selected and installed before starting construction at the site. One resource to evaluate appropriate BMPs is the *Idaho Catalog of Storm Water Best Management Practices* (DEQ 2020). Other resources may also be used for selecting appropriate BMPs.

2. Permanent erosion and sediment control measures will be installed to provide long-term sediment and erosion control and prevent excess sediment from entering waters of the United States.
3. Permanent erosion and sediment control measures will be installed at the earliest practicable time consistent with good construction practices and will be maintained as necessary throughout the project.
4. Structural fill or bank protection will consist of materials that are placed and maintained to withstand predictable high flows in the waters of the United States.
5. A BMP inspection and maintenance plan must be developed and implemented. At a minimum, BMPs must be inspected and maintained daily during project implementation and replaced or augmented if they are not effective.
6. All construction debris, scraps, particles, and other associated materials will be captured and properly disposed of so they cannot enter waters of the United States or cause water quality degradation.
7. Disturbed areas suitable for vegetation will be seeded or revegetated to prevent subsequent soil erosion (EPA 2000).
8. Maximum fill slopes will be material that is structurally stable once placed and does not slough into the stream channel during construction, during periods before revegetation, or after vegetation is established.
9. Sediment from disturbed areas or sediment that can be tracked by vehicles onto pavement must not leave the site in amounts reasonably expected to enter waters of the United States. Placement of clean aggregate at all construction entrances or exits and other BMPs such as truck or wheel washes, if needed, must be used when earth-moving equipment will be leaving the site and traveling on paved surfaces to prevent track-out.

3.4 Turbidity

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200.08, IDAPA 58.01.02.250.02.e, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Sediment resulting from this activity must be mitigated to prevent violations of the turbidity standards stipulated in Idaho's water quality standards. Any violation of this standard must be reported to the DEQ regional office immediately.
2. Containment measures such as silt curtains, geotextile fabrics, and silt fences must be implemented and properly maintained to minimize instream sediment suspension and resulting turbidity. One resource to evaluate appropriate BMPs is the *Idaho Catalog of Storm Water Best Management Practices* (DEQ 2020). Other resources may also be used for selecting appropriate BMPs.
3. All practical BMPs on disturbed banks and within the waters of the United States must be implemented to minimize turbidity. Visual observation is acceptable to determine whether BMPs are functioning properly. If a sediment plume is observed, the project may be causing an exceedance of water quality standards, and the permittee must inspect the condition of the project BMPs. If the BMPs appear to be functioning

- improperly, then corrective action must be taken, and the permittee must modify the activity or implement additional BMPs (this may also include modifying existing BMPs).
4. If the project continues to have a visual sediment plume after BMPs have been inspected and modified, turbidity monitoring consistent with Table 1, is required.
 - a. A properly and regularly calibrated turbidimeter is required for sample collection measurements to be analyzed in the field. The turbidimeter should be calibrated before each use or according to the manufacturer's recommendations. The calibration log should be maintained and made available to DEQ upon request. Instantaneous grab samples may be collected for field analysis and taken to a laboratory for analysis as needed. When turbidity monitoring is required, a grab sample must be collected at an undisturbed area immediately upstream from the in-water disturbance or discharge to establish background turbidity levels. Background turbidity, latitude/longitude, date, and time must be recorded before monitoring downstream. A sample must be collected immediately downstream from the in-water disturbance or point of discharge and within the visible sediment plume. The turbidity, latitude/longitude, date, and time must be recorded for each sample. The downstream sample must be taken immediately following the upstream sample to obtain meaningful and representative results.
 - b. Results from the downstream sampling location must be compared to the upstream sample location or background turbidity to determine whether project activities are causing an exceedance of Idaho's water quality standards. If the downstream turbidity is 50 nephelometric turbidity units (NTUs) or greater than the upstream turbidity, then the project is causing an exceedance of the water quality standards. Any exceedance of the turbidity standard must be reported to the appropriate DEQ regional office within 24-hours of the sample event.
 - c. Earth-disturbing activities may continue once turbidity readings return to within 50 NTU over background instantaneously, or if turbidity has exceeded 25 NTU over background for more than 10 consecutive days, once turbidity readings have no longer exceeded 25 NTU over background for at least 24 consecutive hours.
 - d. Copies of daily logs for turbidity monitoring must be available to DEQ upon request. The report must describe all exceedances and subsequent corrective actions taken, including the effectiveness of the action.

Table 1. Turbidimeter monitoring and sampling when a plume is observed.

Turbidity Above Background^a	Monitoring/Sampling Frequency^a	Additional Actions Required
0 to 24 NTU	Visual monitoring every 2 hours	None
25 to 49 NTU	Sample every 2 hours	STOP work after 8 hours in every 24-hour period
25 NTU for 10 or more consecutive days	Sample before and after following instructions ^b	STOP work and follow instructions^b; notify DEQ regional office
50 NTU or more	Sample before and after following instructions ^c	STOP work and follow instructions^c; notify DEQ regional office

- a. Sample and report turbidity three times at each location. Use the maximum value of three samples to determine compliance following Table 1 directions.

- b. Instructions: If BMPs appear to be functioning properly, then the permittee must modify the activity or implement corrective action such as installing additional BMPs (this may include modifying existing BMPs) until additional sampling indicates turbidity standards are met. Sampling can cease when a sediment plume is no longer observed. Work can commence when a sediment plume is no longer observed, and measurements are consecutively below 25 NTU.
- c. Instructions: If BMPs appear to be functioning properly, then the permittee must modify the activity or implement corrective action such as installing additional BMPs (this may include modifying existing BMPs) until additional sampling indicates turbidity standards are met. Sampling can cease when a sediment plume is no longer observed. Work can commence when a sediment plume is no longer observed, and measurements are below 50 NTU.

3.5 In-Water Work

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Work in open water must be kept to a minimum and only when necessary. Equipment shall work from an upland site to minimize disturbance of waters of the United States. If this is not practicable, take appropriate measures to ensure disturbance to the waters of the United States is minimized.
2. Construction affecting the bed or banks shall occur only during periods of low flow and/or corresponding with appropriate in-water work periods for aquatic life.
3. Fording the channel is not permitted. Build temporary bridges or other structures if crossings are necessary.
4. Temporary crossings shall be perpendicular to channels and located in areas with the least impact. The temporary crossings must be supplemented with clean gravel or treated with other mitigation methods at least as effective in reducing impacts. Temporary crossings must be removed as soon as possible after the project is completed or the crossing is no longer needed.
5. Heavy equipment working in wetlands shall be placed on mats or suitably designed pads to prevent damage to the wetlands.
6. In-water activities in spawning areas shall be avoided to the maximum extent practicable during spawning and incubation periods.
7. Work in waters of the United States shall be restricted to areas specified in the application.
8. Measures shall be taken to prevent wet concrete from entering waters of the United States when placed in forms and/or from truck washing.
9. Activities that construct and maintain intake structures must include adequate fish exclusion screening devices to prevent fish entrainment or capture.
10. Stranded fish found in dewatered segments should be moved to a location (preferably downstream) with water.
11. To minimize sediment transport, stream channel or streambank stabilization must be completed before returning water to a dewatered segment.

3.6 Vegetation Protection and Restoration

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. To the maximum extent practical, staging areas and access points should be placed in open, upland areas.
2. Fencing and other protective barriers should be used to mark the construction areas.
3. Where possible, alternative equipment should be used (e.g., spider hoe or crane).
4. If authorized work results in unavoidable vegetative disturbance, native riparian and wetland vegetation shall be successfully reestablished to benefit water quality at pre-project levels or improved at the completion of authorized work.

3.7 Management of Hazardous or Deleterious Materials

The following conditions are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.400, IDAPA 58.01.02.800, and IDAPA 58.01.02.850.

1. Petroleum products and hazardous, toxic, and/or deleterious materials shall not be stored, disposed of, or accumulated adjacent to or in the immediate vicinity of waters of the United States. Adequate measures and controls must ensure that those materials will not enter waters of the United States because of high water, precipitation runoff, wind, storage facility failure, accidents, or unauthorized third-party activities.
2. Secondary containment is required for chemical materials.
3. Vegetable-based hydraulic fluid should be used on equipment operating in or directly adjacent to the channel if this fluid is available.
4. Daily inspections of all fluid systems on equipment to be used in or near waters of the United States shall ensure no leaks or potential leaks exist before equipment use. A logbook of daily equipment inspections shall be kept on site and provided to DEQ upon request.
5. Equipment and machinery shall be removed from the vicinity of the waters of the United States before refueling, repair, and/or maintenance.
6. Equipment and machinery shall be steam cleaned of oils and grease in an upland location or staging area with appropriate wastewater controls and treatment capability before entering waters of the United States. Any wastewater or wash water must not enter waters of the United States.
7. Emergency spill response procedures shall be in place and include a spill response kit (e.g., oil absorbent booms or other equipment).
8. If an unauthorized release of hazardous material to waters of the United States or to land occurs and there is a likelihood it will enter waters of the United States, the responsible persons in charge must:
 - a. Make every reasonable effort to abate and stop a continuing spill.

- b. Make every reasonable effort to contain spilled material so it will not reach surface or ground waters of the United States.
 - c. Call 911 if immediate assistance is required to control, contain, or clean up the spill. If no assistance is needed in cleaning up the spill, contact the appropriate DEQ regional office during normal working hours or Idaho State Communications Center after normal working hours (1-800-632-8000). If the spilled volume is above federal reportable quantities, contact the National Response Center (1-800-424-8802).
 - d. Contact Twin Falls Regional Office: (208) 736-2190.
9. Collect, remove, and properly dispose of spill and cleanup materials in a manner approved by DEQ.

3.8 Culverts

The following conditions to control erosion, sediment, and turbidity are necessary for the protection of beneficial uses according to Idaho's water quality standards, including without limitation IDAPA 58.01.02.200 and IDAPA 58.01.02.250.

1. To prevent road surface and culvert bedding material from entering a stream, culvert crossings must include BMPs to retain road base and culvert bedding material. For perennial waters, the permittee should consider Idaho's "Stream Channel Alterations Rules" (IDAPA 37.03.07). Another source of BMPs for culvert installation are found in the "Rules Pertaining to the Idaho Forest Practices Act" (IDAPA 20.02.01). Examples of BMPs include, but are not limited to: parapets, wing walls, inlet and outlet rock armoring, compaction, suitable bedding material, antiseep barriers such as bentonite clay, or other acceptable roadway retention systems.
2. The culvert must not constrict the stream channel and shall not be angled so the outflow is directed toward the streambank. The culvert's flow line shall match the existing stream invert at its entrance and exit. Adequate grade control must be installed to prevent channel down cutting or excessive deposition from occurring.
3. Culverts for fish-bearing waterways shall be installed so they do not impede fish passage.
4. The culvert outflow shall be armored with riprap to provide erosion control. This riprap will be clean, angular, dense rock that is free of fines and resistant to aquatic decomposition.
5. Culverts shall be sized appropriately to maintain the natural drainage patterns.

3.9 Treated Wood

The following condition meets Idaho's water quality standards, including without limitation IDAPA 58.01.02.200 and IDAPA 58.01.02.210.

This condition ensures that toxic chemicals are not introduced into waters of the United States. The *Guidance for the Use of Wood Preservatives and Preserved Wood Products In or Around Aquatic Environments* (DEQ 2008) must be considered when using treated wood materials in the aquatic environment. The DEQ guidance references the *Best Management Practices for the*

Use of Treated Wood in Aquatic and Wetland Environments (Western Wood Preservers Institute et al. 2011). This BMP document provides recommended guidelines for producing and installing treated wood products for use in sensitive environments.

3.10 Dredge Material Management

Upland disposal of dredged material must prevent the material from reentering waters of the United States.

This condition ensures that there is no unauthorized discharge from upland disposal sites according to 33 U.S.C. § 1311(a) and Idaho's water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400

3.11 Pollutants/Toxins

In conformance with IDAPA 58.01.02.200, the use of chemicals such as sterilants, growth inhibitors, fertilizers, and deicing salts during construction should be limited to the best estimate of optimum application rates. All reasonable measures shall be taken to avoid excess application and introduction of chemicals into waters of the United States.


4 Required Notification

The permittee must notify the Twin Falls Regional Office when authorized work begins and if the applicant or organization is transferred or changes.

5 Right to Appeal Final Certification

The final § 401 Water Quality Certification may be appealed by submitting a petition to initiate a contested case, pursuant to Idaho Code § 39-107(5) and the "Rules of Administrative Procedure before the Board of Environmental Quality" (IDAPA 58.01.23), within 35-days of the date of the final certification.

Questions or comments regarding the actions taken in this certification should be directed to Sean Woodhead, Twin Falls Regional office, 208-736-2190, sean.woodhead@deq.idaho.gov.




Sue Switzer
Regional Administrator
Twin Falls Regional Office

References

- DEQ (Idaho Department of Environmental Quality). 2008. *Guidance for the Use of Wood Preservatives and Preserved Wood Products in or Around Aquatic Environments*. Boise, ID: DEQ. <https://www2.deq.idaho.gov/admin/LEIA/api/document/download/4838>
- DEQ (Idaho Department of Environmental Quality). 2020. *Idaho Catalog of Storm Water Best Management Practices*. Boise, ID: DEQ. <https://www.deq.idaho.gov/water-quality/wastewater/storm-water/>
- DEQ (Idaho Department of Environmental Quality). 2022. *Idaho Department of Environmental Quality 2022 Integrated Report*. Boise, ID: DEQ. <https://www2.deq.idaho.gov/admin/LEIA/api/document/download/16619>
- EPA (US Environmental Protection Agency). 2000. *National Menu of Best Management Practices (BMPs) for Stormwater*. <https://www.epa.gov/npdes/national-menu-best-management-practices-bmps-stormwater>
- RSET (Northwest Regional Sediment Evaluation Team). 2018. *Sediment Evaluation Framework for the Pacific Northwest*. Prepared by the RSET Agencies.
- Western Wood Preservers Institute, Wood Preservation Canada, Southern Pressure Treaters' Association, and Southern Forest Products Association. 2011. *Best Management Practices: For the Use of Treated Wood in Aquatic and Wetland Environments*. Vancouver, WA: Western Wood Preservers Institute.

Attachment B:
Trail Creek Bridge
Planting Plan

8/26/2024 2:49:06 PM
 U:\Bois\Projects\Clients\4006-ITD\314-4006-071\SH-75 Elkhorn to River\995vcs\CADD\DCN\sheet\20033_land_001.dgn



- 620-020A PLANTING TREE (SEEDLING OR CONTAINER)**
28 EACH 474+29.00 (58.00 L & 56.00 R) - 475+11.00 (51.00 L & 51.00 R)
 - 620-025A PLANTING SHRUB (BARE ROOT OR CONTAINER)**
20 EACH 474+29.00 (58.00 L & 56.00 R) - 475+11.00 (51.00 L & 51.00 R)
- NOTE:
SEE SWPP PLAN SHEETS FOR RIPARIAN SEED QUANTITIES

Table 1: Native Planting

Scientific Name	Common Name	Type	Percent by cover	Appx. Spacing (ft)
Planting Area 1-Shoreline				
<i>Populus trichocarpa</i>	Black Cottonwood	live stakes/poles	50	10
<i>Salix exigua</i>	Coyote Willow	live stakes/poles	50	5
Total Zone 1-Shoreline			100	
Planting Area 2-Riparian-Upland				
<i>Populus tremuloides</i>	Quaking Aspen	1-2-gallon	50	8
<i>Rosa Woodsii</i>	Woods Rose	1-2-gallon	50	8
Total Zone 2-Riparian			100	


*Planting Area 1- Within 5-10 ft of the stream (Roots should reach below the water table), Planting Area 2- Upslope from Planting Area 1

Construction Notes:

- o Live stakes/pole plantings to appx. 24-36" and buried so that the bottom of the stakes/poles are below the OHWM of Trail Creek. Should be buried with shoots upward and at least 3/4 of the pole should be buried.
- o Plants should be placed at a recommended spacing of and clustered with like species as possible

LEGEND

- Zone 1 Planting Area (Shoreline) With Riparian Seeding
- Zone 2 Planting Area (Riparian) With Riparian Seeding
- Coyote Willow Live Stakes/Poles in Riprap Areas (5' Spacing)
- Riprap areas
- Riprap Areas Underneath Natural Streambed Material



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED	JLJ	SCALES SHOWN ARE FOR 11" X 17" PRINTS ONLY
DESIGN CHECKED	TMJ	
DETAILED	JRA	CADD FILE NAME 20033_land_001.dgn
DRAWING CHECKED	PSA	DRAWING DATE: August 2024

IDAHO TRANSPORTATION DEPARTMENT
 YOUR Safety→YOUR Mobility→YOUR Economic Opportunity

Parametrix

PROJECT NO.
A020(033)

TRAIL CREEK PLANTING PLAN
 SH-75, ELKHORN RD TO RIVER ST, KETCHUM

ENGLISH
 COUNTY Blaine
 KEY NUMBER 20033
 SHEET 263 OF 381