LEGEND

- CONCRETE PAVILION
- EXISTING FENCE TO REMAIN
- NEW FENCE- 4'-0" HEIGHT; GALVANIZED CHAIN LINK
- NEW FENCE- 4'-0" HEIGHT; GALVANIZED CHAIN LINK 6'-0" HEIGHT; MESH NET TOP

CONSTRUCTION NOTES

1. DEMOLITION AND DISPOSAL OF EXISTING CHAIN LINK FENCE THAT IS IMPACTED BY THE NEW PLAZA AREA.
2. GRADING TO PREPARE SUBGRADE FOR NEW CONCRETE PLAZA.
3. HAUL OFF AND DISPOSAL OF DIRT SPOILS.
4. PLACE 4" OF STONE FOR SUBBASE
5. POUR AND PLACE A 4" CONCRETE SLAB WITH AIR ENTRAINED CONCRETE
6. PROVIDE AND INSTALL 200'(+/-) X 4' GALVANIZED CHAIN LINK FENCE
   A. 80' (+/-) OF THIS FENCE WILL HAVE A 6' HIGH MESH NET PLACED ON TOP OF THE 4' HIGH CHAIN LINK FENCE.
7. RELATIVE DIMENSIONS--TO BE VERIFIED

PROPOSAL FOR CONCRETE PLAZA

HUNTER WRIGHT STADIUM

3/16/2023

GRC Construction

Cain Rash West Architects