

ESTIMATE

Walk by Faith Roofing and Remodeling
2932 Creek Valley Ln
Appleton, WI 54914

james@walkbyfaithroofing.com
+1 (920) 977-9306
www.walkbyfaithroofingandremodeling.com



Lisa Kerstner

Bill to

Dan Hekrdle
Kronenwetter Municipal Center
1582 Kronenwetter Drive
Kronenwetter, Wisconsin 54455
United States

Estimate details

Estimate no.: 0066
Estimate date: 07/31/2023
Expiration date: 08/14/2023

Product or service	Amount
1. Introduction	1 unit × \$0.00
This estimate is for the tear off and installation of a new asphalt shingle roof of the Kronenwetter Municipal Building.	
2. Tear off	350 units × \$50.00
Remove existing asphalt shingles, underlayment and metal edge leaving only bare decking.	
3. Check for damaged or weak decking.	1 unit × \$0.00
Estimate includes up to 10- 4ft by 8ft sheets of 7/16 or 1/2 inch OSB Decking	
4. Metal edge	185 units × \$20.00
2x2 True size drip edge-----185 pcs at 10 Linear feet each	
5. Install synthetic underlayment	\$0.00
Purchased by the roll -----42 rolls	
6. Install Ice and water shield	14 units × \$100.00
14 rolls. State code calls for 3 feet of coverage on rake edges, we exceed that by doing 6 feet giving more coverage against Ice Dam issues.	
7. Install Dimensional Laminate shingle	380 units × \$800.00
Shingle price includes starter, underlayment, hip and ridge cap, all vents, flashings and shingles	
8. Install Starter strip	\$0.00
Starter strip along rakes.-----13 bundles	
9. Install hip and ridge cap	\$0.00
18 bundles	

- | | | |
|---|--------------------------|-----------------|
| <p>10. Services</p> <p>Patch and reseal all penetrations in your EPDM roof areas</p> | <p>1 unit x \$750.00</p> | <p>\$750.00</p> |
| | | |
| <p>11. Notice</p> <p>Please note the following----</p> <p>1. Gas Furnace and water heater exhaust pipes, if not correctly installed, may become dislodged during roof replacement. We highly recommend the homeowner have these connections checked by their A/C or Plumbing Service professional following new roof installation.</p> | | <p>\$0.00</p> |
| | | |
| <p>12. Notice--2</p> <p>Installing the roof requires nailing through the roof deck. Items such as conduit lines and T.V, Cable or refrigerant lines installed closer than 1 1/2 inches of the underside of roof decking shall be protected from damage by nails and other fasteners. As per the current International Residential building code.</p> | | <p>\$0.00</p> |
| | | |
| <p>13. Complete and seal</p> <p>Seal all roof penetrations.
 Remove and dispose of all job related debris.
 Provide Contractor 5 year roof installation warranty.
 Provide Material Manufacturers Warranty.</p> | | <p>\$0.00</p> |

	Subtotal	\$327,350.00
--	----------	--------------

	Discount	-\$17,350.00
--	----------	--------------

Note to customer

Thank you for the opportunity to serve.
Due to the immensity of the project We would require a material purchase deposit of 50% for securing materials and delivery.

	Total	\$310,000.00
--	--------------	---------------------


	Expiry date	08/14/2023
--	-------------	------------

ESTIMATE

Walk by Faith Roofing and Remodeling

2932 Creek Valley Ln
Appleton, WI 54914

james@walkbyfaithroofing.com
+1 (920) 977-9306
www.walkbyfaithroofingandremodeling.com



Lisa Kerstner

Bill to

Kronenwetter Municipal Center
1582 Kronenwetter Drive
Kronenwetter, Wisconsin 54455
United States

Ship to

Kronenwetter Municipal Center
1582 Kronenwetter Drive
Kronenwetter, Wisconsin 54455
United States

Estimate details

Estimate no.: 0051

Estimate date: 07/31/2023

Expiration date: 08/07/2023

Product or service		Amount
1. Introduction	1 unit x \$0.00	\$0.00
This estimate contains the scope of work and total cost of repairs to the roof of the facility.		
2. Scope of work	1 unit x \$0.00	\$0.00
1. Remove and replace all damaged shingles. Approximately 150 shingles		
2. Remove and replace 30 linear feet of hip and ridge cap.		
3. Reseal all roof penetrations plumbing vents		
4. Reseal cracks in the chimney. Approximately 10 Linear feet		
5. Clean and cover failing seams in the EPDM Low slope roof system. Approximately 25 Linear feet		
6. Repair cracked and/or failing patches using manufacturer recommended seam/lap caulk. Approximately 10 Linear feet		
7. Repair cracks and holes in A/C Unit curbs--Approximately 4		
8. Seal holes in siding, fascia using weather resistant caulk.		
9. Repair cracks and holes in wall seams.		
10. Remove all job related debris.		
3. Roof Repair	1 unit x \$4,500.00	\$4,500.00
See scope of work details.		
4. Thank you		\$0.00
Thank you for the opportunity to serve your needs.		
	Total	\$4,500.00

Note to customer

A 50% materials deposit is due prior to job commencement and remaining balance due upon completion.

Expiry
date

08/07/2023

