

Village of Kronenwetter Lift Station #2 and Lift Station #6 Upgrades				Contract #1 - Lift Station #2 and Liftstation #6 Upgrades Bid Deadline: Friday, December 13, 2024 at 10:00 a.m.			
Item #	Bid Item Description	# of Units	Units	Bidder #1 Pember Companies, Inc.		Bidder #2 August Winters & Sons, Inc	
				Unit Price	Total	Unit Price	Total
1.1	Performance and Payment Bonds	1	LS	Lump Sum	\$4,000.00	Lump Sum	\$6,500.00
1.2	LS6. Material and Labor to replace 4" piping and valves in existing LS6 valve vault in accordance with plans/specifications & AWWA requirements, including temporary provisions to continue LS6 operation, reuse of existing stainless steel bolts. (2) Swing Check Valves, (2) Plug Valves, Bends, Fittings, Adjustable SS Pipe Cradle with SS Standpipe 2", Bypass Extension Piping & Stainless Steel Camlock Termini (Male) with New Stainless Steel Pipe Attachments and Anchorments	1	LS	Lump Sum	\$51,000.00	Lump Sum	\$73,300.00
1.3	LS6. Material and Labor to clean and inspect Valve Vault Floor Drain	1	LS	Lump Sum	\$1,700.00	Lump Sum	\$2,500.00
1.4	LS6. Allowance for repairs to Valve Vault Floor Drain pending inspection	Allowance	LS	Allowance	\$1,000.00	Allowance	\$1,000.00
1.5	LS6. Labor to core sidewall from Valve Vault to WetWell, for sealed Bypass 4" pipe extension to Wetwell	1	LS	Lump Sum	\$7,000.00	Lump Sum	\$2,500.00
1.6	LS6. Material and Labor to replace existing exterior control panel system and instrumentation on existing LS6 in accordance with plans/specifications and NEC requirements, including VFD phase conversion system, including junction boxes, seals, and vents	1	LS	Lump Sum	\$129,000.00	Lump Sum	\$155,000.00
1.7	LS6. Material and Labor to replace 15 hp Shinmaywa pumps, pump motor cables, level sensor and cables, alarm floats and cables, within existing conduits to new panels, including replacement of existing guide rail caps	1	LS	Lump Sum	\$55,000.00	Lump Sum	\$88,000.00
1.8	LS6. Material and Labor for Complete Install of Light Fixture, Pole, Base, Sonotube, Breaker and Switch at New Panel	1	LS	Lump Sum	\$2,100.00	Lump Sum	\$7,000.00
1.9	LS6. Materials and Labor for Complete Install of Sonotube Base and Bracket for Fall Protection Tie-off	1	LS	Lump Sum	\$2,800.00	Lump Sum	\$3,500.00
1.10	LS6. Materials and Labor for Complete Retrofit of Fall Protection Leaf Grate for Wet Well Opening and Valve Vault Opening	1	LS	Lump Sum	\$2,750.00	Lump Sum	\$4,000.00
1.11	LS6. Start-up and Testing	1	LS	Lump Sum	\$2,850.00	Lump Sum	\$2,500.00
2.1	LS2. Material and Labor to clean and inspect Valve Vault Floor Drain	1	LS	Lump Sum	\$1,700.00	Lump Sum	\$2,500.00
2.2	LS2. Allowance for repairs to Valve Vault Floor Drain pending inspection	Allowance	LS	Allowance	\$1,000.00	Allowance	\$1,000.00
2.3	LS2. Material and Labor for Generator and Transformer Concrete Pads to suit generator/transformer size/configuration, Including Necessary Penetrating Conduits, Base, Compaction, and Coordination for Anchorments	1	LS	Lump Sum	\$9,000.00	Lump Sum	\$5,000.00
2.4	LS2. Generator, 80 KVA minimum	1	LS	Lump Sum	\$66,385.00	Lump Sum	\$72,000.00
2.5	LS2. Materials and Labor for Automatic Transfer Switch installation rated for generator system and exterior enclosure, including mounting, conduits & controls	1	LS	Lump Sum	\$7,400.00	Lump Sum	\$9,000.00
2.6	LS2. Material and Labor to replace existing exterior control panel system and instrumentation on existing LS6 in accordance with plans/specifications and NEC requirements, including disconnect, VFD motor starter system, junction boxes, seals, and vents	1	LS	Lump Sum	\$131,500.00	Lump Sum	\$140,000.00
2.7	LS2. Material and Labor to replace existing guide rail caps	1	LS	Lump Sum	\$7,750.00	Lump Sum	\$4,000.00
2.8	LS2. Material and Labor for Complete Install of Light Fixture, Pole, Base, Sonotube, Breaker and Switch at New Panel	1	LS	Lump Sum	\$2,100.00	Lump Sum	\$7,000.00
2.9	LS2. Materials and Labor for Complete Install of Sonotube Base and Bracket for Fall Protection Tie-off	1	LS	Lump Sum	\$2,850.00	Lump Sum	\$3,500.00
2.10	LS2. Materials and Labor for Complete Retrofit of Fall Protection Leaf Grate for Wet Well Opening and Valve Vault Opening	1	LS	Lump Sum	\$6,800.00	Lump Sum	\$4,000.00
2.11	LS2. Start-up and Testing	1	LS	Lump Sum	\$2,850.00	Lump Sum	\$2,500.00
Total Base Bid Contract #1					\$498,535.00		\$596,300.00
A1	Addendum Number #1, December 10, 2024 LS6 - 316 Stainless Steel Piping in Value Vault, AWWA 312, ANSI B36			ADDITIONAL	\$25,000.00	DEDUCT	-\$7,000.00
Total Contract #1 if Alternate A1 is Utilized					\$523,535.00		\$589,300.00



Engineering | Consulting | Design | Facilitation