

AMERICAN ASPHALT

PO Box 98 Mosinee, WI 54455 (715) 693-5200 americanasphaltofwi.com

A DIVISION OF MATHY CONSTRUCTION CO. • MOSINEE, WI

EOE, including disability / vets

| To: | Village Of Kronenwetter | | Contact: | Brad Jacobson | |
|-------------------------|---------------------------------|--------------------|-------------|---------------|--------------|
| Address: | 1582 Kronenwetter Drive | | Phone: | 715-693-4200 | |
| | Kronenwetter, WI 54455 MARATHON | | Fax: | | |
| Project Name: | Sunny Court Reconstruct | | Bid Number: | 7567-2024 | |
| Project Location: | Sunny Court, Kronenwetter, WI | | Bid Date: | 8/27/2024 | |
| Attachments: | BID TERMS AND CONDITIONS.pdf | | | | |
| Item Description | | Estimated Quantity | Unit | Unit Price | Total Price |
| Sunny Court Reconstruct | | 1.00 | LS | \$130,655.00 | \$130,655.00 |

Sunny Court Reconstruct

- Provide Traffic Control Signing And Flagging As Needed For Our Operations.
- Pulverize Existing Asphalt For Base Course Material.
- Furnish And Install 4 Inches Of Compacted WisDOT Spec. 1-1/4"
- Dense Graded Base Course Material To Add Structure.
- Saw Cut Driveways Back An Average Of 5'.
- Fine Grade, Water, And Compact The Base Course Material.
- Pave With WisDOT Spec. Type MT 58-28S Asphalt Mix
- Compacted To An Average Thickness Of 3 Inches In 2 Lifts.
- Apply Tack Coat Prior To Paving The Surface Course.

| | Total Bid Pri | ce: | \$130,655.00 | |
|--|---------------|------------|--------------|--|
| Shouldering Shouldering Option | 1.00 TON | \$6,950.00 | \$6,950.00 | |
| · Install And Compact 3/4 Inch Base For 2' Shoulders | | | | |

Notes:

- A signed contract is required prior to the start of work. ٠
- This proposal shall be included in contract. Progress payments shall be invoiced and paid monthly.
- Final price will be determined by Unit(s) Used & Unit Price(s) listed above.
- After signing, please retain one copy and forward a copy to our office on or before the cancellation date. ٠
- This proposal shall be automatically cancelled if written acceptance has not been received by Contractor with in 30 days of the Proposal Date and/or • at any time before performance of the work hereunder upon CONTRACTOR'S determination that there is inadequate assurance of payment.
- Low shoulder signs are required on this project when pavement drop-offs exist. The Prime Village of Kronenwetter is responsible to have these signs in place and takes all liability for this condition.
- Bond NOT Included.

Payment Terms:

Payment due within 10 days of prime contractor receiving payment from state or municipality.

| ACCEPTED: The above prices, specifications and conditions are satisfactory and hereby accepted. | CONFIRMED: American Asphalt | | |
|--|-----------------------------------|--|----------------|
| Buyer: | | | |
| Signature: | Authorized Signature: Lori Studin | | Lori Studinski |
| Date of Acceptance: | Estimator: | ator: Lori Studinski 715-218-7252 Jori studinski@americanasphaltofwi.com | |