



August 13, 2024

Kronenwetter Water Utility
Attn: Mr. Mark Mackey
1582 Kronenwetter Drive
Kronenwetter, WI 54455

RE: Well No. 1 Main Piping

Dear Mark,

This proposal is for the replacement of the spool with the cracked flanges and the existing butterfly valve. The spool would be tapped for the existing injection fittings, so they could be moved onto the new spool. The valve would be another gear-operated butterfly valve, since a gate valve would add another \$3,800 to the project.

Please review the following scopes and the associated cost for the project:

1. Load and mobilize to job site.
2. Remove the existing spool and butterfly valve.
3. Provide and install the new spool and butterfly valve.
4. Relocate the exiting injection fittings.
5. Test for leaks.
6. Demobilize from job site.

.....**Lump Sum: \$ 6,890**

We trust you will find this correspondence to your understanding. Should you have any questions or concerns regarding this proposal, or if there is any other way we can be of assistance to your community, please contact our offices at your earliest convenience. We appreciate this opportunity to provide you with this proposal and look forward to the opportunity to provide the Kronenwetter Water Utility continued expert service on this project.

Sincerely,
MUNICIPAL WELL & PUMP

Marty Van Ells
Project Manager

C:\Users\Marty Van Ells\Desktop\Proposals\Marty's Proposals 2024\Kronenwetter Piping\Kronenwetter Main Piping_8-13-24.doc