

K&B Pump & Electrical

Quote

1225 Commerce Drive
Labelle, FL 33935
Phone 863-675-2265 Fax 863-675-7126

QUOTE:110325
DATE:11/03/2025

City of LaBelle / Juan / Sal

SALESPERSON	P.O. NUMBER	REQUISITIONER	SHIPPED VIA	F.O.B. POINT	TERMS
					Due on receipt

QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL
	Helms Well #2 Troubleshoot Well #2 VFD, power, pump, motor, controls and check valve. Found VFD checked out ok, check valve appears to be working correctly, well head shows signs of vibrating and motor is drawing high amperage. Pump was faulting on over current. Pump appears to be making correct flow rates according to tests performed. Estimate to stop well from flowing, supply and install new SME 150hp, 460 volt, 3 phase SS submersible motor and necessary fittings and fasteners. M&L 1 to 2 weeks Estimate to stop well from flowing, supply and install new Grundfos 150hp, 460 volt, 3 phase SS submersible motor and necessary fittings and fasteners. M&L 3 to 4 weeks <ul style="list-style-type: none">Exact amount of salt required to remove pump unknown.Condition of motor, pump, coupling and submersible cable are unknown until pump is removed from well.		\$395.00 \$26,750.00 to \$29,520.00 \$37,740.00 to \$39,920.00

Approved by:

SUBTOTAL
SALES TAX
SHIPPING & HANDLING
TOTAL DUE

Est.
\$675.00

Make all checks payable to K&B Pump & Electrical
If you have any questions concerning this Quote, contact me.
Thank You, Chuck Holt