

THE LANE GROUP INC  
C. DOUGLAS LANE, AIA

3514 OAK STREET  
JACKSONVILLE, FL 32205  
904.874.1766  
www.LaneGroupInc.com  
FL Lic #AR0010878


Preservation Improvements for  
**Lake Park Historic Evergreen House**  
601 Federal Highway  
Lake Park City, FL 33403-2603

The entire contents of this document, including all sketches, plans, studies, drawings, schedules and specifications, and all copyright therein, are and shall remain the sole and exclusive property of The Lane Group, Inc. The documents and their contents may not be used, photocopied or reproduced digitally, electronically or in any other manner without the express written consent of The Lane Group, Inc.

No.	Date	Revisions
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		
Commission No. _____		
Date 02.13.26		
Scale As Noted		
Drawn by Lucia R. Lane		
Checked by Doug Lane		
Sheet No. of _____		

Demolition Plan

D-1.0



**DEMOLITION NOTES - INTERIOR**

- D-1 REMOVE DIY CLOSET WALLS & MIRROR GLASS SLIDING DOORS.
- D-2 REMOVE DIY CLOSET W/LOUVERED BI-FOLD DOOR. RELOCATE WATER HEATER TO PANTRY. SEE NEW FLOOR PLAN.
- D-3 REMOVE FLYWD DOORS, SHELVING, ETC. PREP FOR NEW USE PER NEW FLOOR PLAN.
- D-4 REMOVE ALL SHELVING, BASEBOARD WOOD FLOORING. REMOVE WALL & CEILING FINISHES IN THE PANTRY.
- D-5 REMOVE APPLIANCES, COUNTERTOPS, CABINETS, SINK, DISHWASHER, WOOD BASEBOARDS, WOOD FLOORING & ANY DAMAGED SUB-FLOORING TO PROVIDE ACCESS TO CRAWL SPACE BY TRADES TO REPLACE/UPDATE ELECTRICAL, HVAC DUCTWORK & PLUMBING, ETC. REMOVE INTERIOR WALL FINISHES TO THE STUDS TO ROUTE NEW UTILITIES. MAINTAIN & PROTECT THE EXIST. WOOD CEILING, SCHEDULED TO REMAIN IN THE KITCHEN.
- D-6 REMOVE BATHROOM TOILET, LAVATORY, GRAB BARS, SOAP & PAPER DISPENSERS, WOOD BASEBOARD, WOOD WAINSCOTING, PLASTER/GUWB WALLS BACK TO STUDS, REMOVE EXISTING DOOR, DOOR CASING, JAMB. ENLARGE ROUGH OPENING TO INCREASE DOOR WIDTH, SEE THE NEW FLOORPLAN. MAINTAIN THE EXIST. WOOD CEILING.
- D-7 REMOVE ENOUGH OF THE HALLWAY CLOSET WALL TO PROVIDE A 5'-3" FINISHED. NEW ACCESS TO THE BATHROOM PER THE NEW FLOOR PLAN. SAVE WOOD FLOOR FROM INSIDE CLOSET FOR REUSE IN THE NEW WIDER SECTION OF THE HALLWAY. MAINTAIN & PROTECT THE EXISTING WOOD CEILING. PREP TO PATCH IN AS REQUIRED AFTER ENLARGEMENT OF THE HALLWAY.
- D-8 REMOVE EXISTING PAINTED BASEBOARD & SHOEMOLD IN EVERY ROOM TYP.
- D-9 REMOVE 24" DOOR IN THE BEDROOM CLOSET, DOOR CASING & JAMB, PREP OPENING TO FILL IN. SAVE THE DOOR TO REINSTALL ON THE OPPOSITE WALL. CREATE A NEW ROUGH OPENING FOR THE DOOR TO OPEN ON THE OPPOSITE SIDE.
- D-10 REMOVE DOOR CASING, JAMBS, DOORS, ETC. PREP FOR NEW IMPACT RATED DOORS.
- D-11 REMOVE EXISTING HVAC SYSTEM, REMOVE FLOORING AND SUB-FLOOR, PREP FOR REPLACEMENT DUE TO DAMAGE. REMOVE FINISHES TO THE STUDS INSIDE THE MECH. CLOSET INCLUDING THE CEILING SO THAT THE ATTIC AREA CAN BE MADE ACCESSIBLE DURING THE CONSTRUCTION PROCESS.
- D-12 REMOVE AND DISPOSE OF THE SLIDING DOORS, PREP OPENING FOR NEW DOOR PER THE FLOOR PLAN.

**DEMOLITION NOTES - EXTERIOR**


- E-1 REMOVE ALL HURRICANE SHUTTER BRACKETS FROM THE WINDOWS & DOORS. DISPOSE OF BRACKETS. PATCH ALL HOLES IN THE STUCCO LEFT BY THE FASTENERS, PREP FOR PAINT. TYPICAL ALL CONDITIONS.
- E-2 REMOVE ALL EXIST. WINDOWS AND DOORS & PREP THE EXTERIOR R.O. & M.O. FOR NEW REPLACEMENT UNITS TYP.
- E-3 SCRAPE FAILING FINISH FROM THE CONC. SLAB ON THE REAR TERRACE. PREP FOR NEW FINISH.
- E-4 REMOVE CLAY TILE & SAVE FOR REUSE, REMOVE EXIST. KITCHEN DOOR CANOPY/HOOD. SAVE PARTS TO USE AS A TEMPLATE TO RE-CREATE THE FEATURES.
- E-5 REMOVE ALL ABANDONED UTILITY PIPES, CONDUITS, BOXES, ETC., PENETRATING AND/OR MOUNTED TO THE EXTERIOR & PREP TO PATCH FINISH.

**DEMOLITION GENERAL NOTES**

1. PROVIDE & MAINTAIN SECURITY & WEATHER PROTECTION TO THE INTERIOR OF THE BUILDING THROUGHOUT THE PROJECT.
2. COVER WITH PROTECTION BOARD THE EXISTING WOOD FLOORS SCHEDULED TO REMAIN THROUGHOUT THE PROJECT.
3. PROTECT THE EXISTING WOOD CEILINGS & CROWN MOLDINGS SCHEDULED TO REMAIN. ALL WOOD CEILINGS & CROWN TO BE REMOVED SHALL BE SAVED FOR REUSE.
4. COVER & PROTECT THE TILE HEARTH & THE CUT STONE MANTLE AND FIREPLACE SURROUND THROUGHOUT THE PROJECT.
5. REMOVE AND SAVE FOR POTENTIAL REUSE ALL THE METAL FLOOR SUPPLY GRILLES.
6. CARE SHALL BE SUPPLIED TO THE AREA'S SCHEDULED TO HAVE THE PLASTER FINISHES REMOVED ON ONE SIDE OF THE WALL, SO AS NOT TO DISTURB/DAMAGE THE OTHER SIDE OF THE WALL FINISH SCHEDULED TO REMAIN.
7. MAINTAIN POWER, WATER & LIGHTS NECESSARY FOR WORK & NIGHT TIME SECURITY THROUGHOUT THE PROJECT.
8. PROVIDE BARRIERS, SIGNS AND/OR TAPE LINES TO DEFINE THE CONSTRUCTION AREA SURROUNDING THE PROJECT. PROVIDE BARRIERS AROUND THE TREES ON SITE.
9. PLACE DUMPSTER LOCATED ON THE STREET AND/OR PAVED AREAS ON PLYWOOD TO MINIMIZE DAMAGE.
10. DO NOT BLOCK ANY SIDEWALKS AND/OR PATHWAY SURROUNDING THE PROJECT, STORE ALL CONSTRUCTION MATERIALS INSIDE THE IDENTIFIED CONSTRUCTION AREA.




**DEMOLITION PLAN**  
D-1.0 SCALE: 3/8" = 1'-0"



THE LANE GROUP INC  
C. DOUGLAS LANE, AIA

3514 OAK STREET  
JACKSONVILLE, FL 32205  
904.874.1766  
www.LaneGroupInc.com  
FL Lic #AR0010878

Preservation Improvements for  
**Lake Park Historic Evergreen House**  
601 Federal Highway  
Lake Park City, FL 33403-2603



EXISTING LEGEND & NOTES	
	EMERGENCY LIGHTING MOUNTED ON CEILING
	EXIT SIGN MOUNTED ON CEILING
	FLOOR SUPPLY GRILLES
	THERMOSTAT
	WALL MOUNTED FIXTURE
	CEILING MOUNTED FIXTURE
	CEILING FAN W/LIGHTS
<b>OWNER</b>	
TOWN OF LAKE PARK 535 PARK AVENUE, EST PALM BEACH FL, 33403-2603	

**EXISTING FLOOR PLAN**  
A-1.0 SCALE: 3/8" = 1'-0"  
SQUARE FOOTAGE - 1396 S.F. CONDITIONED

The entire contents of this document, including all sketches, plans, studies, drawings, schedules and specifications, and all copyright therein, are and shall remain the sole and exclusive property of The Lane Group, Inc. The documents and their contents may not be used, photocopied or reproduced digitally, electronically or in any other manner without the express written consent of The Lane Group, Inc.


No.	Date	Revisions
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		

Commission No.	
Date	02.13.26
Scale	As Noted
Drawn by	Lucia R. Lane
Checked by	Doug Lane
Sheet No.	of

Existing Floor Plan

**GENERAL NOTES**

1. ALL WORK MUST BE COMPLETED PER THE 2023 FBC AND PER THE SECRETARY OF INTERIORS STANDARDS U.N.O.
2. MAINTAIN SECURITY LIGHTING, ELECTRICAL POWER, AND WATER IN SUFFICIENT SUPPLY DURING CONSTRUCTION TO FACILITATE THE WORK.
3. REFER TO M.E.D. DRAWINGS FOR LIGHTING OUTLETS, SWITCH LOCATIONS, HVAC FLOOR SUPPLIES, ETC., U.N.O.
4. PROTECT THE EXISTING WOOD FLOORS & CEILINGS SCHEDULED TO REMAIN THROUGHOUT THE PROJECT.
5. ALL DISTURBED, ALTERED AND/OR DAMAGE TO THE WOOD FLOORS AND CEILINGS SCHEDULED TO REMAIN SHALL BE PATCHED, REPAIRED OR REPLACED TO MATCH.
6. ALL DIMENSIONS SHOWN ARE FOR CONVENIENCE, IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS SHOWN WITH THE ACTUAL SITE CONDITIONS. THIS INCLUDES WINDOW AND DOOR M.O. & R.O.



THE LANE GROUP INC  
C. DOUGLAS LANE, AIA

3514 OAK STREET  
JACKSONVILLE, FL 32205  
904.874.1766  
www.LaneGroupInc.com  
FL Lic #AR0010878

Preservation Improvements for  
**Lake Park Historic Evergreen House**  
 601 Federal Highway  
 Lake Park City, FL 33403-2603

The entire contents of this document, including all sketches, plans, studies, drawings, schedules and specifications, and all copyright therein, are and shall remain the sole and exclusive property of The Lane Group, Inc. The documents and their contents may not be used, photocopied or reproduced digitally, electronically or in any other manner without the express written consent of The Lane Group, Inc.



No.	Date	Revisions
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		


Commission No.	
Date	02.13.26
Scale	As Noted
Drawn by	Lucia R. Lane
Checked by	Doug Lane
Sheet No.	of

New Floor Plan

A-1.1




**NEW FLOOR PLAN**  
 A-1.1 SCALE: 3/8" = 1'-0"




THE LANE GROUP INC  
C. DOUGLAS LANE, AIA

3514 OAK STREET  
JACKSONVILLE, FL 32205  
904.874.1766  
www.LaneGroupInc.com  
FL Lic #AR0010878


Preservation Improvements for  
**Lake Park Historic Evergreen House**  
601 Federal Highway  
Lake Park City, FL 33403-2603




**1 ENLARGED BATHROOM PLAN**  
A-1.2 SCALE: 1" = 1'-0"



**2 EAST ELEVATIONS**  
A-1.2 SCALE: 1" = 1'-0"



**3 EAST ELEVATION**  
A-1.2 SCALE: 1" = 1'-0"



**4 WEST ELEVATION**  
A-1.2 SCALE: 1" = 1'-0"

The entire contents of this document, including all sketches, plans, studies, drawings, schedules and specifications, and all copyright therein, are and shall remain the sole and exclusive property of The Lane Group, Inc. The documents and their contents may not be used, photocopied or reproduced digitally, electronically or in any other manner without the express written consent of The Lane Group, Inc.

No.	Date	Revisions
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		

Commission No.	
Date	02.13.26
Scale	As Noted
Drawn by	Lucia R. Lane
Checked by	Doug Lane
Sheet No.	of

Enlarged Bathroom Plan

A-1.2