

1st Stakeholders Meeting on the 10th Street Ovalabout Initiative



Department of Public Works



Project Team



- **John D'Agostino** – Town Manager
- **Roberto Travieso** – Public Works Director
- **Nadia DiTommaso**– Community Development Director
- **Adam Swaney, P.E.** – Civil Engineer
- **John Wille** – Capital Projects Manager



Meeting Agenda




1. Introductions
2. Project Background
3. What is an Ovalabout?
4. Is this improvement needed?
5. Conceptual Design
6. Construction Cost Estimate
7. Table Discussions & Activity
8. Implementation Timeline and Next Steps
9. Q&A
10. Closing Comments



Project Background

ROBERTO TRAVIESO, DIRECTOR OF PUBLIC WORKS

Project Area



Project Background



- History of frequent and severe traffic accidents in project area
- Conducted Traffic Study in **2020** (O'Rourke Engineering & Planning)
 - Report available on Town's website
- Developed three (3) options:
 - Implement signalization improvements
 - Construct round-about (rotary) traffic element
 - Construct oval-about traffic element

Project Background



- Conducted traffic Study in 2020
- Engaged with Palm Beach County
- Engaged with Engenuity Group to perform Feasibility Study and develop opinion of costs



What is an Ovalabout?



- A type of oval-shaped intersection or junction in which road traffic is permitted to flow in one direction (counterclockwise) around a oval-shaped island
- Widely consider a mobility and traffic safety-enhancement
- Traffic Calming benefits



How Would an Ovalabout Help?



- Increased level of service
- Increased traffic safety, reduced travel speeds,
- Increased mobility (I.e. protected crosswalks,
- Landscape enhancements (plantings, art pedestal, etc.)







Conceptual Plans

ADAM SWANEY, PE

CONCEPTUAL SITE PLAN



- GENERAL NOTES:**
- ELEVATIONS SHOWN HEREIN ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AND ARE REFERENCED TO ORIGINATE TO 400'. ELEVATIONS ARE IN FEET (NAVD 88).
 - TOPOGRAPHIC SURVEY PERFORMED BY CH2M HILL INC. IN NOVEMBER 2020.
 - ALL REMOVED CURBS & EXISTING MATERIAL TO BE REMOVED FROM THE SITE AND LEGALLY RECYCLED OR.
 - ALL ORIGINALS SHALL MEET AASHTO CROSS SLOPE SHALL EXCEED 2%.
 - IF PROPOSED WORK INVOLVES PALM BEACH COUNTY ROADWAY, SIDEWALK AND/OR DRAINAGE SYSTEMS, THEN THEY WILL BE COORDINATED, REVIEWED OR RELATED TO ITS OWNERS OR AGENCIES AT NO COST TO THE PALM BEACH COUNTY.
 - PAVED AREAS AND DRIVEWAYS IN PALM BEACH COUNTY MUST BE IN ACCORDANCE WITH THE MANUAL OF STANDARD PRACTICE CONTROL DESIGN FOR DRIVEWAYS AND DRIVEWAYS AND PALM BEACH COUNTY TYPICAL 1-1-17.
 - CONTRACTOR SHALL CONTACT THE PALM BEACH COUNTY AT 361-333-3333 (EXT. 444) PRIOR TO CONSTRUCTION IF WORK IS DONE WITHIN 10 FEET OF ANY SIGNAL EQUIPMENT.
 - ANY DAMAGE TO SIGNAL EQUIPMENT CAUSED BY THE CONSTRUCTION OF THIS PROJECT MUST BE REPAIRED OR REPLACED TO ORIGINAL OR BETTER CONDITION AT NO COST TO PALM BEACH COUNTY.


- LEGEND: (ABBREVIATIONS)**
- CB CATCH BASIN
 - E EAST
 - EL ELEVATION
 - EXIST EXISTING
 - FT FEET OR FOOT
 - HDPE HIGH DENSITY POLYETHYLENE PIPE
 - INV INVERT
 - L LEFT
 - LF LINEAR FEET
 - N NORTH
 - NTS NOT TO SCALE
 - ORB OFFICIAL RECORD BOOK
 - OS OFFSET
 - R RADIUS OR RIGHT
 - RM RM ELEVATION
 - PVC POLYVINYL CHLORIDE PIPE
 - RCP REINFORCED CONCRETE PIPE
 - RAW RIGHT-OF-WAY
 - S SOUTH
 - SVC SERVICE
 - TYP TYPICAL
 - W WEST
 - ME MATCH EXISTING GRADE

CONCEPTUAL
DESIGN PHASE




ADAM SWARTY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 72335
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWARTY, P.E. UNDER A 256-BIT AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE 256-BIT AUTHENTICATION CODE MUST BE VERIFIED ON ANY
ELECTRONIC COPIES.



CONCEPTUAL DEMOLITION PLAN



LEGEND	
	DEMOLITION



- SILT FENCE NOTES:**
1. THE HEIGHT OF A SILT FENCE SHALL NOT EXCEED 36 INCHES (90 CM).
 2. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS.
 3. POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET (3 M) APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 10 INCHES (25 CM) WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE MESH SUPPORT FENCE. POST SPACING SHALL NOT EXCEED 8 FEET (2.5 M).
 4. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES (10 CM) WIDE AND 4 INCHES (10 CM) DEEP ALONG THE LINE OF POSTS AND UP SLOPE FROM THE BARRIER.
 5. WHEN STANDARD STRENGTH FILTER FABRIC IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UP SLOPE SIDE OF THE TRENCH USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH (25 MM) LONG. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2 INCHES (5 CM) AND SHALL NOT EXTEND MORE THAN 36 INCHES (90 CM) ABOVE THE ORIGINAL GROUND SURFACE.
 6. THE STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WARED TO THE FENCE, AND 8 INCHES (20 CM) OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES (90 CM) ABOVE THE ORIGINAL GROUND SURFACE.
 7. FILTER CLOTH TO BE FASTENED SECURELY TO POSTS WITH TIES SPACED EVERY 24 INCHES AT TOP AND MID SECTION. WHEN TWO SECTIONS OF FILTER CLOTH JOIN IN ANY OTHER, THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED.
 8. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGING" DEVELOPS IN THE SILT FENCE OR DEPTH OF ACCUMULATED SEDIMENT REACHES 8 INCHES.
 9. SILT FENCE SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS PRIOR TO THE START OF CONSTRUCTION AND SHALL NOT BE REMOVED UNTIL CONSTRUCTION IS COMPLETE.
 10. THE CONTRACTOR SHALL INSPECT AND REPAIR THE SILT FENCE AFTER EACH RAIN EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
 11. REMOVED SEDIMENT SHALL BE DEPOSITED IN AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFFSITE AND CAN BE PERMANENTLY STABILIZED.
 12. THE SILT FENCE SHALL BE PLACED ON SLOPE CONTOUR TO MAXIMIZE ITS DRAINAGE EFFICIENCY.
 13. IF DITCH LEVEL IS DEEPER THAN 30", THEN A FLOTTING SILT SCREEN SHALL BE USED.
 14. THE TRENCH SHALL BE BACKFILLED AND THE SEAL COMPACTED OVER THE FILTER FABRIC.
 15. ALL PROJECTS REQUIRE SUBMITTAL OF POLLUTION PREVENTION PLAN.
 16. ALL PROJECTS 1 AC. OR MORE MUST SUBMIT NOTICE OF INTENT (NOI) TO FDEP.



CONCEPTUAL
DESIGN PHASE

ADAM SWANNY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 72338
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANNY, P.E. USING A DIGITAL AUTHENTICATION CODE
PROVIDED COMES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SEAL AUTHENTICATION CODE MUST BE VIEWED ON ANY
ELECTRONIC COPIES

CONCEPTUAL PAVING, GRADING AND DRAINAGE PLAN



ENGINEERING LEGEND

- PROPOSED ASPHALT PAVEMENT
- PROPOSED CONCRETE SIDEWALK
- PROPOSED LANDSCAPE AREA
- PROPOSED PAVERS
- TRAFFIC FLOW DIRECTION
- CATCH BASIN / YARD DRAIN
- FINISHED GRADE ELEVATION
- DRAINAGE FLOW DIRECTION

GENERAL NOTES:

- ELEVATIONS SHOWN HEREIN ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AND ARE REFERENCED TO SEASIDE, FL 400'.
- TOPOGRAPHIC SURVEY PERFORMED BY ENGINEER GROUP INC. IN NOVEMBER 2020.
- ALL EXISTING CURBS AND SIDEWALKS TO BE REMOVED FROM THE SITE AND RECONSTRUCTED.
- ALL CROSSLANES SHALL MEET ARA. NO CROSS SLOPE SHALL EXCEED 2%.
- IF PROPOSED WERE DRAINAGE PALM BEACH COUNTY HIGHWAY, SIDEWALK AND/OR DRAINAGE SYSTEM, THEY SHALL BE CONSTRUCTED PERMANENT OR RELATED TO ITS OPERAL OR DETENTION CONSTRUCTION AT NO COST TO THE PALM BEACH COUNTY.
- PAVEMENT MATERIALS AND TYPES IN PALM BEACH COUNTY SHALL BE IN ACCORDANCE WITH THE MANUAL OF STANDARD PRACTICE CONTROL. DESIGN FOR STRENGTH AND PERFORMS AND PALM BEACH COUNTY TYPICAL PAVEMENT.
- CONTRACTOR SHALL CONTACT THE PALM BEACH COUNTY (PBC) ENGINEER AT 304-333-3333 (EXT. 2424) PRIOR TO CONSTRUCTION IF MORE IS SHOWN CONSTRUCTION IS NOT OF ANY OTHER EQUIPMENT.
- ANY DAMAGE TO EXISTING EQUIPMENT CAUSED BY THE CONSTRUCTION OF THIS PROJECT MUST BE REPAIRED OR REPLACED TO ORIGINAL OR BETTER CONDITION AT NO COST TO PALM BEACH COUNTY.

LEGEND: (ABBREVIATIONS)

- CB CATCH BASIN
- E EAST
- EL ELEVATION
- EXIST EXISTING
- FT FEET OR FOOT
- HDPE HIGH DENSITY POLYETHYLENE PIPE
- INV INVERT
- L LEFT
- LF LINEAR FEET
- N NORTH
- NTS NOT TO SCALE
- ORIS OFFICIAL RECORD BOOK
- OS OFFSET
- R RADIUS OR RIGHT
- R/E RADIUS ELEVATION
- PVC POLY(VINYL CHLORIDE) PIPE
- RCR REINFORCED CONCRETE PIPE
- RAW RIGHT-OF-WAY
- S SOUTH
- SVC SERVICE
- TYP TYPICAL
- W WEST
- ME MATCH EXISTING GRADE

CONCEPTUAL
DESIGN PHASE




ADAM SWARTY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 72235.
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWARTY, P.E., USING A SW-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SW-1 AUTHENTICATION CODE MUST BE REPRODUCED ON ANY
ELECTRONIC COPIES.

VEHICLE TRACKING EXHIBIT



LEGEND	
	PROPOSED LANDSCAPE AREA
	TRAFFIC FLOW DIRECTION
	PROPOSED CONCRETE SIDEWALK
	PAVERS



WB-50 - Intermediate Semi-Trailer	55.000ft
Overall Length	8.500ft
Overall Width	12.052ft
Overall Body Height	1.334ft
Min Body Ground Clearance	8.500ft
Max Track Width	6.00s
Lock-to-lock time	17.90°
Max Steering Angle (Virtual)	

CONCEPTUAL
ENGINEERING PLAN



ADAM SWANNY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 72385
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANNY, P.E. USING A SHA-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
VALID AND THE SHA-1 AUTHENTICATION CODE MUST BE VERIFIED ON ANY
ELECTRONIC COPY.

Know what's below.
Call before you dig.



Conceptual Cost Estimate

ADAM SWANEY, PE

Conceptual Cost Estimates



Description	Estimated Cost
SITE PREPARATION	\$122,000.00
ROADWAY CONSTRUCTION	\$308,941.95
SIDEWALK & ROAD CONSTRUCTION	\$43,310.55
DRAINAGE CONSTRUCTION	\$81,625.00
ADDITIONAL ITEMS	\$275,000.00
MOBILIZATION & OTHER COSTS	\$556,687.93
TOTAL:	\$1,387,565.43



Table Discussion

DURATION: UP TO 30 MINUTES



Implementation Timeline & Next Steps

JOHN WILLE, CAPITAL PROJECTS MANAGER

Implementation Timeline & Next Steps



Town Staff will:

- Prepare and submit Conceptual Plans for submittal to the County's Five-Year Work Plan (beginning with FY-24)
- Continue to collaborate with PBC to prioritize and fund design and implementation of project in the next five years (FY's 2024-2029)
- Continue to provide input to PBC regarding project design and implementation timeline
- Continue to engage with Stakeholders regarding project design and implementation timeline



Questions & Closing Comments



**Please scan for additional
information on this project:**

