



Stakeholders' Meeting

10th Street Ovalabout Initiative

Monday, November 14, 2022, 6:00 PM - 8:00 PM
Commission Chambers, Town Hall

Meeting Agenda

Facilitator: Roberto Travieso, Director of Public Works

WELCOME/OPENING COMMENTS
INTRODUCTIONS/BACKGROUND

ROBERTO TRAVIESO

PRESENTATION

ROBERTO TRAVIESO
ADAM SWANEY, P.E.
JOHN WILLE

TABLE DISCUSSION

TOWN AND ENGENUITY
STAFFS

CONSTRUCTION TIMELINE

JOHN WILLE
NADIA DITOMMASO

Q&A

ROBERTO TRAVIESO

CLOSING COMMENTS

JOHN D'AGOSTINO

1st Stakeholders Meeting on the 10th Street Ovalabout Initiative

Monday, November 14, 2022



Department of Public Works



Project Team



- **John D'Agostino** – Town Manager
- **Roberto Travieso** – Public Works Director
- **Nadia DiTommaso**– Community Development Director
- **Adam Swaney, P.E.** – Civil Engineer
- **John Wille** – Capital Projects Manager



Meeting Agenda




1. Introductions
2. Project Background
3. What is an Ovalabout?
4. Why is this improvement needed?
5. Conceptual Design
6. Construction Cost Estimate
7. Table Discussions & Activity
8. Implementation Timeline and Next Steps
9. Q&A
10. Closing Comments



Project Background

ROBERTO TRAVIESO, DIRECTOR OF PUBLIC WORKS



PROJECT LOCATION

Project Background



- History of frequent and severe traffic accidents in project area
- Conducted Traffic Study in **2020** (O'Rourke Engineering & Planning)
 - Report available on Town's website
- Developed three (3) option:
 - Implement signalization improvements
 - Construct round-about (rotary) traffic element
 - Construct oval-about traffic element

Project Background



- Partnered with Palm Beach County (PBC) to design and construct the project
- Contracted with Engenuity Group to perform Feasibility Study and develop opinion of costs



What is an Ovalabout?



- A type of oval-shaped intersection or junction in which road traffic is permitted to flow in one direction (counterclockwise) around a oval-shaped island
- Widely consider a mobility and traffic safety-enhancement
- Traffic Calming benefits



How Would an Ovalabout Help?



- Increased level of service
- Increased traffic safety, reduced travel speeds
- Increased mobility (I.e. protected crosswalks)
- Landscape enhancements (plantings, art pedestal, etc.)













Conceptual Plans

ADAM SWANEY, PE

GRAPHIC SCALE
0 20 30
SCALE: 1" = 30'



	PROPOSED ASPHALT PAVEMENT
	PROPOSED CONCRETE SIDEWALK
	PROPOSED LANDSCAPE AREA
	PROPOSED PAVERS
	TRAFFIC FLOW DIRECTION
	CATCH BASIN / YARD DRAIN
	FINISHED GRADE ELEVATION
	DRAINAGE FLOW DIRECTION

GENERAL NOTES:

1. ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AND ARE REFERENCED TO BENCHMARK "V 402". ELEVATION=16.708' (NAVD 88).
2. TOPOGRAPHIC SURVEY PERFORMED BY EXCELUTY GROUP INC. IN NOVEMBER 2020.
3. ALL REMOVED TREES & DEMOLISHED MATERIAL TO BE REMOVED FROM THE SITE AND LEGALLY DISPOSED OF.
4. ALL CROSOWALKS SHALL MEET ADA. NO CROSS SLOPE SHALL EXCEED 2%.
5. IF PROPOSED WORK DAMAGE PALM BEACH COUNTY ROADWAY, SEWER AND/OR DRAINAGE SYSTEMS, THEY WILL BE CONSTRUCTED/REPAIRED/REPLACED TO ORIGINAL OR BETTER CONDITION AT NO COST TO THE PALM BEACH COUNTY.
6. PAVEMENT MARKINGS AND SIGNING IN PALM BEACH COUNTY RIGHT OF WAY, SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS AND PALM BEACH COUNTY TYPICAL T-1--T-21.
7. CONTRACTOR SHALL CONTACT PBC TRAFFIC OPERATIONS AT 561-233-3800 FORTY-EIGHT (48) HOURS PRIOR TO CONSTRUCTION IF WORK IS BEING DONE WITHIN 10 FEET OF ANY SIGNAL EQUIPMENT.
8. ANY DAMAGE TO SIGNAL EQUIPMENT CAUSED BY THE CONSTRUCTION OF THIS PROJECT MUST BE REPAIRED OR REPLACED TO ORIGINAL CONDITION AT NO COST TO THE PALM BEACH COUNTY.

LEGEND: (ABBREVIATIONS)

CB	CATCH BASIN
E	EAST
EL	ELEVATION
EXIST	EXISTING
FT	FEET OR FOOT
HDPE	HIGH DENSITY POLYETHYLENE PIPE
INV	INVERT
L	LEFT
LF	LINEAR FEET
N	NORTH
NTS	NOT TO SCALE
ORB	OFFICIAL RECORD BOOK
OS	OFFSET
R	RADIUS OR RIGHT
RM	RM ELEVATION
PVC	POLYVINYL CHLORIDE PIPE
RCP	REINFORCED CONCRETE PIPE
RW	RIGHT-OF-WAY
S	SOUTH
SVC	SERVICE
TYP	TYPICAL
W	WEST
ME	MATCH EXISTING GRADE

CONCEPTUAL DESIGN PHASE




Know what's below.
Call before you dig.

ADAM SWANEY, P.E. PROFESSIONAL ENGINEER LICENSE NO. 73226
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANEY, P.E. USING A SHA-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SHA-1 AUTHENTICATION CODE MUST BE VERIFIED ON ANY
E L E C T R O N I C C O P I E S .



CONCEPTUAL DEMOLITION PLAN



LEGEND	
	DEMOLITION



- SILT FENCE NOTES:**
1. THE HEIGHT OF A SILT FENCE SHALL NOT EXCEED 36 INCHES (90 CM).
 2. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS.
 3. POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET (3 M) APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 12 INCHES (30 CM). WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE SUPPORT FENCE, POST SPACING SHALL NOT EXCEED 6 FEET (1.8 M).
 4. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES (10 CM) WIDE AND 4 INCHES (10 CM) DEEP ALONG THE LINE OF POSTS AND UP SLOPE FROM THE BARRIERS.
 5. WHEN STANDARD STRENGTH FILTER FABRIC IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UP SLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH (25 MM) LONG. THE WIRE, OR HOOK RINGS, THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2 INCHES (5 CM) AND SHALL NOT EXTEND MORE THAN 36 INCHES (90 CM) ABOVE THE ORIGINAL GROUND SURFACE.
 6. THE STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WARED TO THE FENCE, AND 6 INCHES (15 CM) OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES (90 CM) ABOVE THE ORIGINAL GROUND SURFACE.
 7. FILTER CLOTH TO BE FASTENED SECURELY TO POSTS WITH TIES SPACED EVERY 24 INCHES AT TOP AND MID. SECTION. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 60 INCHES AND FOLDED.
 8. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE OR DEPTH OF ACCUMULATED SEDIMENT REACHES 6 INCHES.
 9. SILT FENCE SHALL BE INSTALLED PER MANUFACTURES SPECIFICATIONS PRIOR TO THE START OF CONSTRUCTION AND SHALL NOT BE REMOVED UNTIL CONSTRUCTION IS COMPLETE.
 10. THE CONTRACTOR SHALL INSPECT AND REPAIR THE SILT FENCE AFTER EACH RAIN EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
 11. REMOVED SEDIMENT SHALL BE DEPOSITED IN AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFFSITE AND CAN BE PERMANENTLY STABILIZED.
 12. THE SILT FENCE SHALL BE PLACED ON SLOPE CONTOUR TO MAXIMIZE ITS PONDING EFFICIENCY.
 13. IF DITCH LEVEL IS DEEPER THAN 30", THEN A FLOATING SILT SCREEN SHALL BE USED.
 14. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC.
 15. ALL PROJECTS REQUIRE SUBMITTAL OF POLLUTION PREVENTION PLAN.
 16. ALL PROJECTS 1 AC. OR MORE MUST SUBMIT NOTICE OF INTENT (NOI) TO FDEP.



CONCEPTUAL
DESIGN PHASE


ADAM SWANEY, P.E. PROFESSIONAL ENGINEER LICENSE NO. 72235
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANEY, P.E. USING A SIGNATURE AUTHENTICATION
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SIGNATURE AUTHENTICATION CODE MUST BE VERIFIED BY AN
ELECTRONIC COPIES



CONCEPTUAL PAVING, GRADING AND DRAINAGE PLAN



GRAPHIC SCALE
0 10 20 30 40
SCALE: 1" = 30'



ENGINEERING LEGEND:

	PROPOSED ASPHALT PAVEMENT
	PROPOSED CONCRETE SIDEWALK
	PROPOSED LANDSCAPE AREA
	PROPOSED PAVERS
	TRAFFIC FLOW DIRECTION
	CATCH BASIN / YARD DRAIN
	FINISHED GRADE ELEVATION
	DRAINAGE FLOW DIRECTION

GENERAL NOTES:

1. ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AND ARE REFERENCED TO BENCHMARK "14 422", ELEVATION 118.730' (NAVD 88).
2. TOPOGRAPHIC SURVEY PERFORMED BY EMERGENCY GROUP INC. IN NOVEMBER 2020.
3. ALL REMOVED DEBRIS & UNWANTED MATERIAL TO BE REMOVED FROM THE SITE AND LEGALLY DEPOSITED OFF.
4. ALL CROSSWALKS SHALL MEET ADA. NO CROSS WALKS SHALL EXCEED 20'.
5. IF PROPOSED WORK DAMAGES PALM BEACH COUNTY HIGHWAY, SIDEWALK AND/OR DRAINAGE SYSTEMS, THEN THEY SHALL BE CONSTRUCTED REPAIRED OR REPLACED TO ITS ORIGINAL OR BETTER CONDITION AT NO COST TO THE PALM BEACH COUNTY.
6. TRAFFIC SIGNALS AND SIGNALS IN PALM BEACH COUNTY MUST BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS AND PALM BEACH COUNTY TYPICAL DETAILS.
7. CONTRACTOR SHALL CONTACT 311 FOR OPERATIONS AT 561-233-3600 FORTY-EIGHT (48) HOURS PRIOR TO CONSTRUCTION IF WORK IS BEING DONE WITHIN 10 FEET OF ANY SIGNAL EQUIPMENT.
8. ANY DAMAGE TO SIGNAL EQUIPMENT CAUSED BY THE CONSTRUCTION OF THIS PROJECT MUST BE REPAIRED OR REPLACED TO ORIGINAL OR BETTER CONDITION AT NO COST TO PALM BEACH COUNTY.

LEGEND: (ABBREVIATIONS)


CB	CATCH BASIN
E	EAST
EL	ELEVATION
EXIST	EXISTING
FT	FEET OR FOOT
HDPE	HIGH DENSITY POLYETHYLENE PIPE
INV	INVERT
L	LEFT
LF	LINEAR FEET
N	NORTH
NTS	NOT TO SCALE
ORB	OFFICIAL RECORD BOOK
OS	OFFSET
R	RADIUS OR RIGHT
RIM	RIM ELEVATION
PVC	POLYVINYL CHLORIDE PIPE
RCP	REINFORCED CONCRETE PIPE
RAW	RIGHT-OF-WAY
S	SOUTH
SVC	SERVICE
TYP	TYPICAL
W	WEST
ME	MATCH EXISTING GRADE

CONCEPTUAL
DESIGN PHASE




ADAM SWANEY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 79230.
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANEY, P.E. USING A SHA-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SHA-1 AUTHENTICATION CODE MUST BE VERIFIED ON ANY
ELECTRONIC COPIES.

VEHICLE TRACKING EXHIBIT (FIRETRUCK)



LOCATION MAP
N.T.S.

LEGEND:	
	PROPOSED LANDSCAPE AREA
	TRAFFIC FLOW DIRECTION
	PROPOSED CONCRETE SIDEWALK
	PAVERS



Pumper Fire Truck
Overall Length
Overall Width
Overall Body Height
Min Body Ground Clearance
Track Width
Lock-to-lock time
Max Wheel Angle

40.000ft
8.167ft
7.745ft
0.656ft
80.167ft
5.00s
45.00°


CONCEPTUAL
ENGINEERING PLAN



ADAM SWANEY, P.E. - PROFESSIONAL ENGINEER LICENSE NO. 73205
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANEY, P.E. USING A SHA-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SHA-1 AUTHENTICATION CODE MUST BE VERIFIED ON ANY
ELECTRONIC COPIES.


Know what's below.
Call before you dig.

VEHICLE TRACKING EXHIBIT (SEMI-TRAILER)



LOCATION MAP
N.T.S.

LEGEND:	
	PROPOSED LANDSCAPE AREA
	TRAFFIC FLOW DIRECTION
	PROPOSED CONCRETE SIDEWALK
	PAVERS



WB-50 - Intermediate Semi-Trailer
Overall Length 55.000ft
Overall Width 8.500ft
Overall Body Height 12.052ft
Min Body Ground Clearance 1.334ft
Max Track Width 8.500ft
Lock-to-lock time 6.00s
Max Steering Angle (Virtual) 17.90°

CONCEPTUAL
ENGINEERING PLAN



ADAM SWANEY, P.E., PROFESSIONAL ENGINEER LICENSE NO. 73236.
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND
SEALED BY ADAM SWANEY, P.E. USING A SHA-1 AUTHENTICATION CODE.
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND
SEALED AND THE SHA-1 AUTHENTICATION CODE MUST BE VERIFIED ON ANY
ELECTRONIC COPIES.

Know what's below.
Call before you dig.



Conceptual Cost Estimate

ADAM SWANEY, PE

Conceptual Cost Estimates



Description	Estimated Cost
SITE PREPARATION	\$122,000
ROADWAY CONSTRUCTION	\$308,941
SIDEWALK & ROAD CONSTRUCTION	\$43,310
DRAINAGE CONSTRUCTION	\$81,625
ADDITIONAL ITEMS	\$275,000
MOBILIZATION & OTHER COSTS	\$556,687
TOTAL:	\$1,387,563



Table Discussion

DURATION: UP TO 30 MINUTES



Implementation Timeline & Next Steps

JOHN WILLE, CAPITAL PROJECTS MANAGER

Implementation Timeline & Next Steps



- Perform traffic study to confirm Ovalabout service level supports projected increases to densities in the project area
- Prepare Conceptual Plans for submittal to PBC's Five-Year Work Plan (beginning with FY-24)
- Continue to collaborate with PBC to prioritize, fund, design and implement project within the next five years (FY's 2024-2029)
- Continue to engage with Stakeholders regarding project design and implementation



Questions & Closing Comments



**Please scan for additional
information on this project:**

