

CONTRACT FOR SYSTEM HARDENING AND RELIABILITY IMPROVEMENTS
WORK ORDER NO. 7

THIS WORK ORDER for System Hardening and Reliability Improvements (“Work Order” hereafter) is made on the _____, between the **City of Lake Worth Beach**, a Florida municipal corporation located at 7 North Dixie Highway, Lake Worth Beach, Florida 33460 (“City” hereafter) and **Hooper Corporation**, a foreign for profit corporation authorized to do business in State of Florida (“Contractor” hereafter).

1.0 Project Description:

The City desires the Contractor to provide all goods, services, materials and equipment as identified herein related to the System Hardening and Reliability Improvements project generally described as: 6th Ave S 0601 System Hardening and Voltage Conversion (the “Project”). The Project is more specifically described in the plans prepared by Hooper Corporation, dated May 29, 2024, and which are incorporated herein by reference.

2.0 Scope

Under this Work Order, the Contractor will provide the City of Lake Worth Beach with construction services for the Project as specified in the Contractor’s proposal and drawings attached hereto and incorporated herein as Exhibit “1”.

3.0 Schedule and Liquidated Damages

Substantial completion of all services and work under this Work Order shall be within 180 calendar days from the Effective Date of this Work Order. Final completion of all services and work (and all punch-list items (if any)) under this Work Order shall be within 210 calendar days from the Effective Date of this Work Order. The Effective Date of this Work Order is the date following the parties’ execution of this Work Order and the City’s delivery of a Notice to Proceed to the Contractor via e-mail, facsimile or other form of delivery as documented by the City. Substantial completion occurs when the services and work has progressed to the point where, in the opinion of the City, the work is sufficiently complete in accordance with the Contract Documents and this Work Order, so that the Project can be utilized for the purposes for which it is intended. Final completion occurs when all services and work (including punch-list items) has been completed and the project becomes fully operational and accepted by the City.

Liquidated Damages. The City and Contractor recognize that time is of the essence under this Work Order and the Contract Documents, and that the City will suffer financial loss if the services and work described in this Work Order and the Contract Documents are not completed within the times specified in this Work Order. The City and Contractor recognize, agree and acknowledge that it would be impractical and extremely difficult to ascertain and fix the actual damages that the City would suffer in the event Contractor neglects, refuses, or otherwise fails to complete the services and work within the time specified. Accordingly, instead of requiring any such proof, the City and Contractor agree that as liquidated damages for delay (but not as a penalty) Contractor shall pay the City Five hundred dollars (\$500.00) for each day that expires after the time specified in this Work Order.

4.0 Compensation and Direct Purchases

This Work Order is issued for a lump sum, not to exceed amount of **\$550,912.07**. The total not to exceed amount includes contingency of **\$91,818.68**. The attached proposal identifies all costs and expenses included in the Work Order.

5.0 The following Direct Purchases are to be made under this Work Order by the City: N/A

The Project Manager for the Contractor is Gary Shortridge, phone: 313-573-5165; email: gshortridge@hoopercorp.com; and, the Project Manager for the City is David Martyniuk, phone: 561-586-1629; email: dmartyniuk@lakeworthbeachfl.gov.

6.0 Progress Meetings

The Contractor shall schedule periodic progress review meetings with the City Project Manager as necessary but every 30 days as a minimum.

7.0 Contractor's Representations

In order to induce the City to enter into this Work Order, the Contractor makes the following representations:

7.1 Contractor has familiarized itself with the nature and extent of the Contract Documents including this Work Order, work, site, locality, and all local conditions and laws and regulations that in any manner may affect cost, progress, performance or furnishing of the work.

7.2 Contractor has obtained at his/her own expense and carefully studied, or assumes responsibility for obtaining and carefully studying, soil investigations, explorations, and test reports which pertain to the subsurface conditions at or contiguous to the site or otherwise may affect the cost, progress, performance or furnishing of the work as Contractor considers necessary for the performance or furnishing of the work at the stated work order price within the Work Order stated time and in accordance with the other terms and conditions of the Contract Documents, including specifically the provisions of the IFB; and no additional examinations, investigations, explorations, tests, reports, studies or similar information or data are or is deemed necessary by Contractor for such purposes.

7.3 Contractor has reviewed and checked all information and data shown or indicated on the Contract Documents with respect to existing Underground Facilities at or contiguous to the site and assumes responsibility for the accurate location of said Underground Facilities. No additional examinations, investigations, explorations, tests, reports, studies or similar information or data in respect of said Underground Facilities are or is deemed necessary by the Contractor in order to perform and furnish the work under this Work Order price, within the Work Order time and in accordance with the other terms and conditions of the Contract Documents.

7.4 Contractor has correlated the results of all such observations, examinations, investigations, explorations, tests, reports and studies with the terms and conditions of the Contract Documents.

7.5 Contractor has given the City's Contract Administrator written notice of all conflicts, errors or discrepancies that he or she has discovered in the Contract Documents and the written resolution thereof by City or its designee is acceptable to the Contractor.

8.0 Warranty. The Contractor warrants and guarantees to the City that all services and work provided under this Work Order will be in accordance with this Work Order and the other Contract Documents. The Contractor warrants that (a) all materials and parts supplied under this Work Order shall be free from defects for one (1) year from the final completion of all work (unless a longer manufacturer warranty applies); (b) all services and work performed under this Work Order will be free from defects for one (1) year from the final completion of all work and the project shall be fully operational without unreasonable downtime or failures; and (c) that the services and work will conform to the requirements of the Contract Documents. If, at any time prior to the expiration of the one (1) year warranty period, the City discovers any failure or breach of the Contractor's warranties or the Contractor discovers any failure or breach of the Contractor's warranties, the Contractor will, upon written notice from City or of its own accord, at the Contractor's sole cost and expense, promptly correct such failure or breach (which corrective action must include, without limitation, any necessary removal, disassembly, reinstallation, repair, replacement, reassembly, retesting, and/or re-inspection of any part or portion of the work and any other property damaged or affected by such failure, breach, or corrective action). The Contractor will remedy any such failure or breach so, to the extent possible, to avoid unnecessary disruptions to the operations of City or its systems. In the event the Contractor fails to initiate and diligently pursue corrective action within five (5) days of the Contractor's receipt of the City's notice or the Contractor's discovery of the same, the City may undertake such corrective action at the Contractor's expense.

9.0 Authorization

This Work Order is issued pursuant to the System Hardening and Reliability Improvements Contract for between the City of Lake Worth Beach and the Contractor, dated 09/28/2023, ("Contract" hereafter). If there are any conflicts between the terms and conditions of this Work Order and the Contract, the terms and conditions of the Contract shall prevail.

REMAINDER OF THIS PAGE INTENTIONALLY LEFT BLANK

SIGNATURE PAGE FOLLOWS

IN WITNESS WHEREOF, the parties hereto have made and executed this Work Order as of the day and year set forth above.

CITY OF LAKE WORTH BEACH, FLORIDA

By: _____
Betty Resch, Mayor

ATTEST:


By: _____
Melissa Ann Coyne, MMC, City Clerk

APPROVED AS TO FORM AND
LEGAL SUFFICIENCY:

By: _____
Glen J. Torcivia, City Attorney

APPROVED FOR FINANCIAL
SUFFICIENCY

By: _____
Yannick Ngendahayo, Financial Services Director



CONTRACTOR:

HOOPER CORPORATION

By: _____


Print Name: Bruce Cram

Title: Vice President

STATE OF Wisconsin)
COUNTY OF Dane)

THE FOREGOING instrument was acknowledged before me by means of • physical presence or • online notarization on this 10th day of June 2024, by Bruce Cram, as the Vice President [title] of **Hooper Corporation**, a foreign profit Corporation, who is personally known to me or who has produced _____ as identification, and who did take an oath that he or she is duly authorized to execute the foregoing instrument and bind the CONTRACTOR to the same.

Notary Seal:



Notary Public Signature
My Commission Expires 02/01/2027

Exhibit “1”
(Contractor’s Proposal – 34 pages)



May 29, 2024

Reference: 6th Ave S Hardening Circuit 4R0601 R2

Start Date: TBD

Completion Date: TBD

Project: 6th Ave. S 0601 System Hardening and Voltage Conversion.

Project Location: 6th Ave. S., Lake Worth Beach FL 33460

Scope of Work: Voltage conversion and system hardening of 0601 feeder. The feeder will be re-energized to 26kV at the pole that is east of 7th Ave S and S K Street. This location is identified on page 7 of the construction prints. All work that shall be included is identified in a revised drawing for the contractor. This includes overhead feeder lines with ductile iron poles with 3 phase conductor runs. Step down transformers must be installed to maintain the laterals operating on 4kV. The 3-phase feeder will be re-conductored with 3-556 and 4/ON and removal of existing conductors. All existing open wire secondary will be replaced with 4/0 triplex. When the open wire extends outside of the work area the secondary will be replaced to the first adjacent pole. All lateral work will be constructed by City of Lake Worth Beach staff. All locations of poles and conductor runs are identified in construction prints. Specifications will take precedence over drawings if Owner confirms accuracy of contradiction agrees with specification.

Controlling Documents:

- Distribution Hardening and Voltage Conversion Project email received 4/30/2024 (Attached)
- IFB 0601 Storm Hardening and Voltage Conversion.docx
- Circuit 0601_Issued For Construction 04_16_2024 Rev1.pdf
- Circuit 0601_Issued For Construction 04_16_2024.pdf

Clarifications:

- Pole Location 4-558 does not include any UG Feeder installation.
- City of Lake Worth Beach will provide laydown yard.
- City of Lake Worth Beach will provide all materials.
- Hooper is responsible for sidewalk and asphalt repairs.
- Hooper shall have access to all work locations.
- Hooper will notify Lake Worth Beach of any conflicts with other utilities.
- All poles with 3rd party attachments will be top cut.
- Hooper doesn't foresee any required MOT permit being required. In the event it is needed Hooper will be responsible for the MOT permit.

- Pole Location 108 & 111 have been changed from Ductile Iron to 55/1 Wood Poles

Estimated Duration of work for project is 16 weeks.

Proposed Pricing is: \$459,093.39.

ITEM	UOM	QTY	EXTENDED PRICE	LOCATION
Location 4-558				\$ 11,657.71
Install 55/H6 Ductile Iron Pole	Ea	1	\$ 2,147.98	
Install Crossarm	Ea	2	\$ 859.06	
Layout Primary on Hot Arms	Ea	6	\$ 1,288.56	
Transfer Primary to New Pole	Ea	6	\$ 1,288.56	
Install Bracket for 900 amp Disconnects	Ea	1	\$ 128.87	
Install 900 amp Disconnects	Ea	3	\$ 386.61	
Install Lightning Arresters	Ea	3	\$ 386.61	
Install Jumpers	Ea	3	\$ 644.28	
Install Neurtal Clevis	Ea	2	\$ 171.80	
MX Transfer	Ea	4	\$ 859.04	
Neutral Transfer	Ea	1	\$ 171.79	
Remove Crossarm	Ea	2	\$ 343.58	
Top Cut Pole	Ea	1	\$ 128.87	
Install Ground Rod	Ea	1	\$ 171.79	
Install Guys	Ea	2	\$ 429.52	
Install Anchors	Ea	2	\$ 515.46	
Install 3 - 556 & 1 4/0N	LF	97	\$ 1,201.83	
Remove 3 - 336 & 4/0TN	LF	97	\$ 533.50	
Location 4-559 (16)				\$ 15,472.92
Install 55/H5 Ductile Iron	Ea	1	\$ 2,147.98	
Install 9/16" Guy	Ea	1	\$ 214.76	
Install 7/16" Guy	Ea	1	\$ 214.76	
Install MH-25" LD	Ea	1	\$ 257.73	
Install MH-30" LD	Ea	1	\$ 257.73	
Install Tangent Cross Arm	Ea	2	\$ 687.26	
Install Cross Arm Deadend	Ea	1	\$ 429.53	
Install Jumpers	Ea	5	\$ 858.95	
Install Ground Rod	Ea	1	\$ 171.79	
Install St. Light	Ea	1	\$ 171.79	
Lay Out Conductor	Ea	9	\$ 1,855.71	
Transfer Conductor to New Pole	Ea	12	\$ 3,092.76	
Transfer Secondary	Ea	2	\$ 429.52	
Neutral Transfer	Ea	1	\$ 171.79	
Remove Tangent Cross Arm	Ea	2	\$ 343.58	
Remove Cross Arm Deadend	Ea	1	\$ 257.73	
Saw Cut Concrete	Ea	1	\$ 257.73	
Remove 9/16" Guy	Ea	1	\$ 128.87	
Remove 7/16" Guy	Ea	1	\$ 128.87	
Remove MH-25" LD	Ea	1	\$ 128.87	
Remove MH-30" LD	Ea	1	\$ 128.87	
Remove 50/3A (Concrete)	Ea	1	\$ 859.05	

Remove St Light	Ea	1	\$	85.90
Sidewalk Restoration	Ea	1	\$	688.63
Install 3 - 556 & 1 4/0N	LF	84	\$	1,040.76
Remove 3 - 336 & 4/0TN	LF	84	\$	462.00

Location 4-47 (24) \$ 16,867.09

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	6	\$	1,288.56
Transfer Duplex	Ea	1	\$	171.79
Transfer Neutral	Ea	1	\$	171.79
Lay Out Conductor	Ea	6	\$	1,546.38
Transfer Deadends	Ea	6	\$	4,123.56
Install 900 Amp Disconnect	Ea	3	\$	644.28
Install Insulators & Brackets	Ea	3	\$	515.37
Install ground rod	Ea	1	\$	171.79
Install Jumpers	Ea	6	\$	1,030.74
Install Neutral Bracket	Ea	1	\$	85.90
Transfer Neutral	Ea	1	\$	171.79
Transfer Camera	Ea	1	\$	343.63
Top Cut (Concrete)	Ea	1	\$	343.63
Remove 45II (Concrete)	Ea	1	\$	859.05
Remove 900 Amp Disconnect	Ea	3	\$	386.61
Removel Insulators & Brackets	Ea	3	\$	386.61
Sidewalk Restoration	Ea	1	\$	688.63
Install 3 - 556 & 1 4/0N	LF	100	\$	1,239.00
Remove 3 - 336 & 4/0TN	LF	100	\$	550.00

Location 4-47A (25) \$ 13,212.11

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	6	\$	1,288.56
Transfer Deadends	Ea	6	\$	3,092.52
Install Insulators & T Brackets	Ea	3	\$	515.37
Install Jumpers	Ea	6	\$	1,030.74
Install ground rod	Ea	1	\$	171.79
Install Neutral Bracket	Ea	1	\$	128.87
Transfer Neutral	Ea	1	\$	171.79
Remove 45II (Concrete)	Ea	1	\$	859.05
Top Cut (Concrete)	Ea	1	\$	343.63
Remove Insulators & Brackets	Ea	1	\$	128.87
Remove Jumpers	Ea	6	\$	515.40
Sidewalk Restoration	Ea	1	\$	688.63
Install 3 - 556 & 1 4/0N	LF	119	\$	1,474.41
Remove 3 - 336 & 4/0TN	LF	119	\$	654.50

Location 4-47A (26)				\$ 13,708.31
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	4	\$	859.04
Transfer Conductor to New Pole	Ea	3	\$	644.28
Jumpers	Ea	4	\$	687.16
Transfer Neutral	Ea	3	\$	515.37
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	2	\$	515.46
Install Crossarm	Ea	1	\$	343.63
Primary DE Transfer	Ea	4	\$	1,374.52
Install ground rod	Ea	1	\$	171.79
Cluster Mount	Ea	1	\$	128.87
Isolation Transformers	Ea	2	\$	1,546.30
Switch Bracket	Ea	1	\$	128.87
Install CO & LA	Ea	2	\$	429.52
Remove Framing	Ea	1	\$	859.05
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	142	\$	1,759.38
Remove 3 - 336 & 4/0TN	LF	142	\$	781.00

Location 6017 (39)				\$ 10,099.95
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	3	\$	1,546.26
Transfer Neutral	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	257.73
Transfer MX	Ea	2	\$	429.52
Frame Mod Vertical	Ea	1	\$	386.56
Install ground rod	Ea	1	\$	171.79
Lighting Arresters	Ea	3	\$	515.37
Ground Rod	Ea	1	\$	171.79
Top Cut Pole	Ea	1	\$	85.90
Remove Framing	Ea	1	\$	386.56
Install 3 - 556 & 1 4/0N	LF	178	\$	2,205.42
Remove 3 - 336 & 4/0TN	LF	178	\$	979.00

Location 3-916 (27)				\$ 9,364.04
DUCTILE IRON,45,H6	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	1	\$	214.76
Install Crossarm	Ea	1	\$	429.53

Transfer Deadends to New Pole	Ea	3	\$	1,030.89
Transfer Neutral	Ea	1	\$	171.79
Transfer MX	Ea	4	\$	1,030.92
Transfer St Light	Ea	1	\$	257.73
Install Cluster Mount	Ea	1	\$	128.87
Install Transformer	Ea	2	\$	1,374.52
Install CO & LA	Ea	2	\$	429.52
Install Ground rod	Ea	1	\$	171.79
Install Jumpers	Ea	3	\$	515.37
Remove Framing	Ea	1	\$	1,374.47
Top Cut Pole	Ea	1	\$	85.90

Location 3-920 (32) \$ 6,461.68

DUCTILE IRON,45,H6	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	1	\$	171.79
Frame Single Phase	Ea	1	\$	300.66
Transfer Primary	Ea	1	\$	171.79
Transfer Neutral	Ea	1	\$	128.87
Transfer St Light	Ea	1	\$	257.73
Install CO & Bracket	Ea	1	\$	214.76
Install Transformer	Ea	1	\$	687.26
Install Sec Attachment	Ea	1	\$	85.90
Install Ground Rod	Ea	1	\$	171.79
Install Jumper	Ea	1	\$	171.79
Install 4/0 Triplex	LF	141	\$	726.15
Remove OW Sec	LF	141	\$	580.92
Remove Framing	EA	1	\$	644.29

Location 3-xxx (32A) \$ 6,081.61

DUCTILE IRON,45,H6	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	1	\$	171.79
Frame Single Phase	Ea	1	\$	300.66
Transfer Primary	Ea	1	\$	171.79
Transfer Neutral	Ea	1	\$	128.87
Transfer St Light	Ea	1	\$	257.73
Install CO & Bracket	Ea	1	\$	214.76
Install Transformer	Ea	1	\$	687.26
Install Sec Attachment	Ea	1	\$	85.90
Install Ground Rod	Ea	1	\$	171.79
Install Jumper	Ea	1	\$	171.79
Install 4/0 Triplex	LF	100	\$	515.00
Remove OW Sec	LF	100	\$	412.00
Remove Framing	EA	1	\$	644.29

Location 3-836 (40) \$ **14,005.74**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	4	\$	859.04
Transfer Conductor to New Pole	Ea	3	\$	644.28
Jumpers	Ea	4	\$	687.16
Transfer Neutral	Ea	3	\$	515.37
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	3	\$	773.19
Install Crossarm	Ea	1	\$	343.63
Primary DE Transfer	Ea	2	\$	687.26
Install ground rod	Ea	1	\$	171.79
Cluster Mount	Ea	1	\$	128.87
Isolation Transformers	Ea	2	\$	1,546.30
Switch Bracket	Ea	1	\$	128.87
Install CO & LA	Ea	2	\$	429.52
Remove Framing	Ea	1	\$	859.05
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	136	\$	1,685.04
Remove 3 - 336 & 4/0TN	LF	136	\$	748.00
Install 4/0 Triplex	LF	90	\$	463.50
Remove OW Sec	LF	90	\$	370.80

Location 3-837 (44) \$ **10,858.75**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	4	\$	859.04
Transfer Conductor to New Pole	Ea	3	\$	644.28
Jumpers	Ea	4	\$	687.16
Transfer Neutral	Ea	3	\$	515.37
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Install CO & LA	Ea	3	\$	644.28
Install ground rod	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	859.05
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	182	\$	2,254.98
Remove 3 - 336 & 4/0TN	LF	182	\$	1,001.00

Location 6002 (45) \$ **24,858.16**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	3	\$	644.28
Install Crossarm	Ea	1	\$	429.53

Install Deadends	Ea	6	\$	3,092.52
Install CO's	Ea	3	\$	644.28
Install Switch Bracket	Ea	1	\$	171.79
Install Termination Bracket	Ea	1	\$	171.79
Install Terminations	Ea	3	\$	2,061.78
Install Lightning Arresters	Ea	3	\$	386.61
Install Riser	Ea	1	\$	1,030.89
Install 3 - 4/0 cables	Ea	100	\$	5,155.00
Install 4" Conduit	Ea	100	\$	3,435.00
Install Primary Elbows	Ea	3	\$	773.19
Install Ground Rod	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	687.26
Remove Primary Cable	LF	100	\$	1,373.00
Sidewalk Restoration	Ea	1	\$	2,294.47
Remove 3 - 336 & 4/0TN	LF	34	\$	187.00

Location 3-742 (46) \$ 17,673.71

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay Out Conductor	Ea	4	\$	859.04
Transfer Conductor to New Pole	Ea	9	\$	1,932.84
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Install Crossarm	Ea	2	\$	859.06
Install Primary DE	Ea	9	\$	4,638.78
Install Jumpers	Ea	6	\$	1,030.74
Install 9/16" Guy	Ea	1	\$	214.76
Install MH-20" LD	Ea	1	\$	257.73
Install MH-25" LD	Ea	1	\$	257.73
Install 3 - 556 & 1 4/0N	LF	210	\$	2,601.90
Remove 3 - 336 & 4/0TN	LF	210	\$	1,155.00
Remove Framing	Ea	1	\$	1,030.89
Top Pole	Ea	1	\$	128.87

Location 3-743 (85) \$ 1,073.81

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	300.66
Top Pole	Ea	1	\$	128.87

Location 3-743A (86) \$ 7,859.81

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	1	\$	214.76
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73

Install Lightning Arresters	Ea	3	\$	386.61
Install Ground Rod	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	601.36
Top Pole	Ea	1	\$	128.87
Install 3 - 556 & 1 4/0N	LF	132	\$	1,635.48
Remove 3 - 336 & 4/0TN	LF	132	\$	726.00

Location 3-743 (87) \$ 10,733.48

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	1	\$	214.76
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Install Deadends	Ea	3	\$	386.61
Install C/Os & Brackets	Ea	2	\$	343.58
Install Ground Rod	Ea	1	\$	171.79
Install Jumpers	Ea	2	\$	343.58
Install Ground Rod	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	300.66
Remove Transformer	Ea	1	\$	515.42
Top Pole	Ea	1	\$	128.87
Install 3 - 556 & 1 4/0N	LF	132	\$	1,635.48
Remove 3 - 336 & 4/0TN	LF	132	\$	726.00
Remove OW N&S	LF	150	\$	513.00
Install 4/0 Triplex N&S	LF	150	\$	1,287.00

Location 3-744 (48) \$ 10,450.74

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	1	\$	214.76
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	1	\$	257.73
Install 7/16" Guy	Ea	1	\$	214.76
Install MH-10'LD	Ea	1	\$	257.73
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	944.95
Install 3 - 556 & 1 4/0N	LF	200	\$	2,478.00
Remove 3 - 336 & 4/0TN	LF	200	\$	1,100.00
Top Cut Pole	Ea	1	\$	85.90

Location 3-745 (49)				\$	1,159.71
Lay Out Conductor	Ea	3	\$	644.28	
Remove Framing	Ea	1	\$	429.53	
Top Cut Pole	Ea	1	\$	85.90	
Location 3-745A (49A)				\$	1,159.71
Lay Out Conductor	Ea	3	\$	644.28	
Remove Framing	Ea	1	\$	429.53	
Top Cut Pole	Ea	1	\$	85.90	
Location 3-746 (50)				\$	8,944.26
55/H6 Ductile Iron	Ea	1	\$	2,147.98	
Frame Mod Vertical	Ea	1	\$	429.53	
Lay Out Conductor	Ea	3	\$	644.28	
Transfer Conductor to New Pole	Ea	4	\$	859.04	
Transfer MX	Ea	3	\$	773.19	
Install LA's & Brackets	Ea	3	\$	773.19	
Install Pole Ground	Ea	1	\$	171.79	
Install 3 - 556 & 1 4/0N	LF	147	\$	1,821.33	
Remove 3 - 336 & 4/0TN	LF	147	\$	808.50	
Remove Framing	Ea	1	\$	429.53	
Top Cut Pole	Ea	1	\$	85.90	
Location 3-747 (51A)				\$	1,159.71
Lay Out Conductor	Ea	3	\$	644.28	
Remove Framing	Ea	1	\$	429.53	
Top Cut Pole	Ea	1	\$	85.90	
Location 3-748? (51)				\$	7,258.89
55/H6 Ductile Iron	Ea	1	\$	2,147.98	
Frame Mod Vertical	Ea	1	\$	429.53	
Transfer Conductor to New Pole	Ea	4	\$	859.04	
Transfer MX	Ea	1	\$	257.73	
Install Transformer	Ea	1	\$	859.05	
Install CO & Bracket	Ea	1	\$	257.73	
Install Jumper	Ea	1	\$	171.79	
Install Pole Ground	Ea	1	\$	171.79	
Remove Framing	Ea	1	\$	944.95	
Install 3 - 556 & 1 4/0N	LF	60	\$	743.40	
Remove 3 - 336 & 4/0TN	LF	60	\$	330.00	
Top Cut Pole	Ea	1	\$	85.90	

Location 3-748? (52)				\$ 8,203.83
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	1	\$	257.73
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	300.66
Remove Framing	Ea	1	\$	944.95
Install 3 - 556 & 1 4/0N	LF	60	\$	743.40
Remove 3 - 336 & 4/0TN	LF	60	\$	330.00
Top Cut Pole	Ea	1	\$	85.90
Location 3- (53)				\$ 1,159.71
Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	429.53
Top Cut Pole	Ea	1	\$	85.90
Location 3-749 (54)				\$ 1,159.71
Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	429.53
Top Cut Pole	Ea	1	\$	85.90
Location 3-750 (55)				\$ 11,828.80
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	944.95
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	205	\$	2,539.95
Remove 3 - 336 & 4/0TN	LF	205	\$	1,127.50
Top Cut Pole	Ea	1	\$	85.90
Location 3-751(56)				\$ 2,018.76

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90

Location 3-752 (57) \$ 1,159.71

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	429.53
Top Cut Pole	Ea	1	\$	85.90

Location 3-753 (58) \$ 15,776.58

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay out Conductor DE's	Ea	4	\$	1,374.52
Install Primary DE	Ea	6	\$	3,092.52
Transfer Conductor to New Pole	Ea	2	\$	343.58
Install 900amp Disconnects & Brackets	Ea	3	\$	644.28
Install LA's & Brackets	Ea	6	\$	1,030.74
Install Jumpers	Ea	6	\$	1,030.74
Install Ground Rod	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	4	\$	1,030.92
Remove Framing	Ea	1	\$	944.95
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	200	\$	2,478.00
Remove 3 - 336 & 4/0TN	LF	200	\$	1,100.00

Location 3-755 (59) \$ 2,018.76

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90

Location 3-755A (59A) \$ -

NO WORK \$ -

Location 3-756 (60) \$ 9,488.60

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79

Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	429.53
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	103	\$	1,276.17
Remove 3 - 336 & 4/0TN	LF	103	\$	566.50
Top Cut Pole	Ea	1	\$	85.90

Location 3-757 (60A) \$ **2,018.76**

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90

Location 3-748 (61) \$ **8,801.14**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	3	\$	773.19
Install LA's & Brackets	Ea	3	\$	773.19
Install Pole Ground	Ea	1	\$	171.79
Install 3 - 556 & 1 4/0N	LF	139	\$	1,722.21
Remove 3 - 336 & 4/0TN	LF	139	\$	764.50
Remove Framing	Ea	1	\$	429.53
Top Cut Pole	Ea	1	\$	85.90

Location 3-759 (62) \$ -

NO WORK		\$	-
---------	--	----	---

Location 3-xxx (62A) \$ **8,397.31**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	429.53
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	42	\$	520.38
Remove 3 - 336 & 4/0TN	LF	42	\$	231.00
Top Cut Pole	Ea	1	\$	85.90

Location 3-760 (63)				\$ 10,730.44
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	1,116.78
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	134	\$	1,660.26
Remove 3 - 336 & 4/0TN	LF	134	\$	737.00
Top Cut Pole	Ea	1	\$	85.90
Location 3-762 (64)				\$ 2,018.76
Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90
Location 3-763 (65)				\$ 9,370.31
55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	1,116.78
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	130	\$	1,610.70
Remove 3 - 336 & 4/0TN	LF	130	\$	715.00
Top Cut Pole	Ea	1	\$	85.90
Location 3-xxx (66)				\$ 1,331.54
Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	601.36
Top Cut Pole	Ea	1	\$	85.90
Location 3-765 (67)				\$ 10,569.43
55/H6 Ductile Iron	Ea	1	\$	2,147.98

Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	1,116.78
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	125	\$	1,548.75
Remove 3 - 336 & 4/0TN	LF	125	\$	687.50
Top Cut Pole	Ea	1	\$	85.90

Location 3-766 (68) \$ 1,331.54

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	601.36
Top Cut Pole	Ea	1	\$	85.90

Location 3-767 (69) \$ 13,465.22

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Lay out Conductor	Ea	4	\$	1,374.52
Install Primary DE	Ea	6	\$	3,092.52
Transfer Conductor to New Pole	Ea	2	\$	343.58
Install Disconnects & Brackets	Ea	3	\$	644.28
Install LA's & Brackets	Ea	6	\$	1,030.74
Install Jumpers	Ea	6	\$	1,030.74
Install Ground Rod	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	3	\$	773.19
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	66	\$	817.74
Remove 3 - 336 & 4/0TN	LF	66	\$	363.00

Location 3-768 (xx) \$ 7,731.44

Lay out Conductor	Ea	3	\$	1,030.89
Install Primary DE	Ea	3	\$	3,092.67
Transfer Conductor to New Pole	Ea	4	\$	687.16
Install Jumpers	Ea	4	\$	1,030.92
Remove Jumpers	Ea	4	\$	687.16
Mac In/Out	Ea	4	\$	1,202.64

Location 3-xxx (87A) \$ 4,474.17

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Transfer Conductor to New Pole	Ea	4	\$	859.04
Install 3 - 556 & 1 4/0N	LF	58	\$	718.62
Remove 3 - 336 & 4/0TN	LF	58	\$	319.00

Location 3-601 (103) \$ 13,917.39

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay out Conductor	Ea	3	\$	1,030.89
Transfer Conductor to New Pole	Ea	4	\$	687.16
Install Disconnects & Brackets	Ea	1	\$	214.76
Install Jumpers	Ea	6	\$	1,030.74
Install Ground Rod	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Remove Framing	Ea	1	\$	601.36
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	178	\$	2,205.42
Remove 3 - 336 & 4/0TN	LF	178	\$	979.00
Remove OW N&S	LF	200	\$	684.00
Install 4/0 Triplex N&S	LF	200	\$	1,716.00
Limited access & fence	Ea	1	\$	1,374.47

Location 3-602 (104) \$ 1,331.54

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	601.36
Top Cut Pole	Ea	1	\$	85.90

Location 3-495 (106) \$ 9,608.24

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	1	\$	257.73
Install LA's & Brackets	Ea	3	\$	644.28
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	601.36
Transfer St Light	Ea	1	\$	300.66
Install 3 - 556 & 1 4/0N	LF	144	\$	1,784.16
Remove 3 - 336 & 4/0TN	LF	144	\$	792.00
Top Cut Pole	Ea	1	\$	85.90
Sidewalk Restoration	Ea	1	\$	889.53

Location 3-946 (107) \$ 20,011.72

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Install Cross Arms Deadend	Ea	1	\$	429.53
Install Primary DE	Ea	8	\$	4,123.36
Lay out Conductor	Ea	6	\$	2,061.78
Transfer Conductor to New Pole	Ea	10	\$	1,717.90
Install Disconnects & Brackets	Ea	2	\$	429.52
Install Jumpers	Ea	6	\$	1,030.74
Install Span Guys to east	Ea	2	\$	1,030.84
Install Ground Rod	Ea	1	\$	171.79
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	92	\$	1,139.88
Remove 3 - 336 & 4/0TN	LF	92	\$	506.00
Remove OW N&S	LF	200	\$	684.00
Install 4/0 Triplex N&S	LF	200	\$	1,716.00
Sidewalk Restoration	Ea	1	\$	889.53

Location 3-494 (107A) \$ **2,620.15**

Install 35/2 WP	Ea	1	\$	859.05
Remove 35/2 WP	Ea	1	\$	601.36
Install 7/16" Guy	Ea	1	\$	214.76
Install 9/16" Guy	Ea	2	\$	429.52
Install MH-20" LD	Ea	1	\$	257.73
Install MH-25" LD	Ea	1	\$	257.73

Location 3-493A (108A) \$ **8,354.23**

55/H6 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	5	\$	1,288.65
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Install 3 - 556 & 1 4/0N	LF	51	\$	631.89
Remove 3 - 336 & 4/0TN	LF	51	\$	280.50
Remove OW N&S	LF	51	\$	174.42
Install 4/0 Triplex N&S	LF	51	\$	437.58

Location 3-493 (108) \$ **14,316.09**

55/H6 Ductile Iron	Ea	1	\$	1,683.00
--------------------	----	---	----	----------

Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer MX	Ea	4	\$	1,030.92
Install Transformer	Ea	3	\$	2,577.15
Install CO & Bracket	Ea	3	\$	773.19
Install Jumper	Ea	3	\$	515.37
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	2,147.63
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	51	\$	631.89
Remove 3 - 336 & 4/0TN	LF	51	\$	280.50
Remove OW N&S	LF	200	\$	684.00
Install 4/0 Triplex N&S	LF	200	\$	1,716.00
Top Cut Pole	Ea	1	\$	85.90

Location 3-492 (109) \$ 3,026.76

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Remove OW N&S	LF	84	\$	287.28
Install 4/0 Triplex N&S	LF	84	\$	720.72
Top Cut Pole	Ea	1	\$	85.90

Location 3-491(110) \$ 2,474.76

Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Remove OW N&S	LF	38	\$	129.96
Install 4/0 Triplex N&S	LF	38	\$	326.04
Top Cut Pole	Ea	1	\$	85.90

Location 3-490 (111) \$ 10,994.95

55/1 Wood Pole	Ea	1	\$	1,683.00
Frame Mod Vertical	Ea	1	\$	429.53
Lay Out Conductor	Ea	3	\$	644.28
Transfer Conductor to New Pole	Ea	4	\$	859.04
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	4	\$	1,030.92
Install Transformer	Ea	1	\$	859.05
Install CO & Bracket	Ea	1	\$	257.73
Install Jumper	Ea	1	\$	171.79
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	2,147.63
Top Cut Pole	Ea	1	\$	85.90
Install 3 - 556 & 1 4/0N	LF	57	\$	706.23

Remove 3 - 336 & 4/0TN	LF	57	\$	313.50
Remove OW N&S	LF	104	\$	355.68
Install 4/0 Triplex N&S	LF	104	\$	892.32
Top Cut Pole	Ea	1	\$	85.90

Location 3-489 (112) \$ **3,270.02**


Lay Out Conductor	Ea	3	\$	644.28
Remove Framing	Ea	1	\$	1,288.58
Remove OW N&S	LF	47	\$	160.74
Install 4/0 Triplex N&S	LF	47	\$	403.26
Top Cut Pole	Ea	1	\$	85.90
Pull stub pole	Ea	1	\$	687.26

Location 3-487 (112A) \$ **15,991.12**

60/H8 Ductile Iron	Ea	1	\$	2,147.98
Frame Mod Vertical	Ea	1	\$	429.53
Install Cross Arm	Ea	1	\$	429.53
Install Primary Des	Ea	6	\$	3,092.52
Lay Out Conductor	Ea	6	\$	1,288.56
Transfer Conductor to New Pole	Ea	6	\$	1,288.56
Transfer St Light	Ea	1	\$	300.66
Transfer MX	Ea	1	\$	257.73
Install Transformer	Ea	1	\$	859.05
Install 900Amp Disconnect	Ea	3	\$	773.19
Install Jumper	Ea	9	\$	1,546.11
Install Pole Ground	Ea	1	\$	171.79
Remove Framing	Ea	1	\$	1,288.58
Top Cut Pole	Ea	1	\$	85.90
Remove OW N&S	LF	88	\$	300.96
Install 4/0 Triplex N&S	LF	88	\$	755.04
Top Cut Pole	Ea	1	\$	85.90
Sidewalk Restoration	Ea	1	\$	889.53

TOTALS: \$ **459,093.39**


CIRCUIT 4R0601



INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN

GENERAL NOTES:

- NOTIFY CUSTOMERS OF TEMPORARY POWER AND TRAFFIC INTERRUPTIONS
- PROVIDE WARNING SIGNALS FOR PEDESTRIANS AND TRAFFIC SIGNALS FOR MOTORISTS
- SERVICE TO TRAFFIC SIGNAL, SCHOOL FLASHING SIGNAL, AND LIFT STATIONS MUST REMAIN ENERGIZED AT ALL TIMES
- CITY OF LAKE WORTH TO STAKE ALL POLES
- CITY OF LAKE WORTH TO SET ALL TRIP-SAVERS AND SIZE ALL FUSES.
- EXISTING TRANSFORMERS CAN BE TRANSFERRED IF THEY ARE IN GOOD CONDITION
- ALL GUYS TO HAVE FIBERGLASS INSULATIONS THROUGH PRIMARY AND NEUTRAL IF IN-LINE
- 4KV CIRCUIT TO BE STREET SIDE ON DOUBLE CIRCUIT LOCATIONS
- ALL STREET LIGHTS TO BE TRANSFERRED UNLESS OTHERWISE NOTED. WILL NEED NEW BRACKET FOR CONCRETE POLES
- ALL POLES TO BE SET INLINE AND 2.5' FROM EXISTING POLES UNLESS OTHERWISE NOTED
- EVERY EFFORT SHALL BE MADE TO LOCATE RISERS ON THE QUADRANT OF THE POLE OPPOSITE THE FLOW OF VEHICULAR TRAFFIC
- ALL POLES TO BE TAGGED AND NUMBERED
- INSTALL AVIAN COVERS ON ALL B&W XARM S.
- INSTALL JUMPER INSULATORS ON ALL XARM JUMPERS.



LOCATION SKETCH

LEGEND

REMOVE	EXISTING	PROPOSED
?	?	OH FUSE SWITCH
?	?	OH LIGHTNING ARRESTOR
?	?	OH DS SWITCH
?	?	OH TRANSFORMER
?	?	OH TRANSFORMER 2 BANK
?	?	OH TRANSFORMER 3 BANK
?	?	PAD MOUNTED TX
?	?	WOOD POLE
?	?	CONCRETE POLE
?	?	CABLE RISER
?	?	DUCTILE IRON POLE
?	?	DOWN GUY
?	?	OH AFS/RECLOSER
?	?	STANDARD STREETLIGHT
?	?	CAPACITOR BANK
?	?	OH SECONDARY
?	?	OH CONDUCTOR
?	?	OH CONDUCTOR
?	?	UG SVC
?	?	ROW
?	?	EOP
?	?	C/L
?	?	FNC
?	?	UG FEEDER(S)
?	?	XPNYC
?	?	UG PRIMARY

KEYMAP	
11	
10	
6	9 14
5	8 13
4	7 12
3	
2	



CALL SUNSHINE # 811 48 HOURS BEFORE YOU DIG	
LOCATE MARKINGS COLOR CODE	
RED	ELECTRIC
YELLOW	GAS-OIL-STEAM
PINK	TEMP. SURVEY MARKINGS
WHITE	PROPOSED EXCAVATION
CLC	WATER
GREEN	SEWER
ORANGE	CABLE TV



Job Owner: **J. St. Simon**
Designed By: **J. Coissy**
Drawn By: **J. Coissy**
Check By:
Scale: N.T.S

Phone: 561-533-7353 JOB NUMBER: **185502**
6TH AVE S HARDENING Date: **10/27/2022**
CIRCUIT 4R0601
Print No.
LAKE WORTH, FLORIDA
1 Of 14

3	Issued For Construction	10/27/2022				Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data	
2	80% FOR REVIEW	11/12/2021				Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	
1	60% FOR REVIEW	10/04/2021				Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet	Duct Bank Feet	SWS	
	60% FOR REVIEW	6/22/2021				Posted by _____				
REV	REVISION	DATE	DRN	DSGN	CKD	APPD	PERMIT REQ'D	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>

Work Locations	Pole Description	Pole #
1	DUCTILE IRON,55,H6	1
2	WOOD,55,CLASS 1	1
3	DUCTILE IRON,55,H6	1
4	DUCTILE IRON,55,H6	1
5	DUCTILE IRON,55,H6	1
6	DUCTILE IRON,55,H6	1
7	DUCTILE IRON,55,H6	1
8	DUCTILE IRON,55,H6	1
9	DUCTILE IRON,55,H6	1
10	DUCTILE IRON,55,H6	1
12	DUCTILE IRON,60,H8	1
13	DUCTILE IRON,55,H6	1
14	DUCTILE IRON,55,H6	1
15	DUCTILE IRON,55,H6	1
16	DUCTILE IRON,55,H6	1
24	DUCTILE IRON,55,H6	1
25	DUCTILE IRON,55,H6	1
26	DUCTILE IRON,55,H6	1
27	WOOD,45,CLASS 1	1
28	WOOD,45,CLASS 1	1
29	WOOD,45,CLASS 1	1
30	WOOD,45,CLASS 1	1
31	WOOD,45,CLASS 1	1
32	WOOD,45,CLASS 1	1
33	WOOD,45,CLASS 1	1
34	WOOD,45,CLASS 1	1
35	WOOD,45,CLASS 1	1
36	WOOD,45,CLASS 1	1
37	WOOD,45,CLASS 1	1
38	WOOD,45,CLASS 1	1
39	DUCTILE IRON,55,H6	1
40	DUCTILE IRON,55,H6	1
41	WOOD,45,CLASS 1	1
42	WOOD,45,CLASS 1	1
43	WOOD,45,CLASS 1	1
44	DUCTILE IRON,55,H6	1
45	DUCTILE IRON,55,H6	1
46	DUCTILE IRON,55,H6	1
48	WOOD,55,CLASS 1	1
49	WOOD,55,CLASS 1	1
50	WOOD,55,CLASS 1	1
51	WOOD,55,CLASS 1	1
52	WOOD,55,CLASS 1	1
54	WOOD,55,CLASS 1	1
55	WOOD,55,CLASS 1	1
56	WOOD,55,CLASS 1	1
57	WOOD,55,CLASS 1	1
58	WOOD,55,CLASS 1	1
59	WOOD,55,CLASS 1	1
60	WOOD,55,CLASS 1	1

Work Locations	Pole Description	Pole #
61	WOOD,55,CLASS 1	1
62	WOOD,55,CLASS 1	1
62A	WOOD,55,CLASS 1	1
63	WOOD,55,CLASS 1	1
64	WOOD, 55, CLASS 1	1
65	WOOD,55,CLASS 1	1
67	WOOD,55,CLASS 1	1
68	WOOD,55,CLASS 1	1
69	DUCTILE IRON,55,H6	1
71	WOOD,45,CLASS 1	1
71B	WOOD,45,CLASS 1	1
72	WOOD,45,CLASS 1	1
73	WOOD,45,CLASS 1	1
74	WOOD,45,CLASS 1	1
75	WOOD,45,CLASS 1	1
76	WOOD,45,CLASS 1	1
77	WOOD,45,CLASS 1	1
78	WOOD,45,CLASS 1	1
79	WOOD,45,CLASS 1	1
81	WOOD,45,CLASS 1	1
85	DUCTILE IRON,55,H6	1
86	DUCTILE IRON,55,H6	1
87	DUCTILE IRON,55,H6	1
87A	DUCTILE IRON,55,H6	1
89	WOOD,45,CLASS 1	1
90	WOOD,45,CLASS 2	1
91	WOOD,45,CLASS 1	1
93	WOOD,45,CLASS 1	1
94	WOOD,45,CLASS 1	1
95	WOOD,45,CLASS 1	1
96	WOOD,45,CLASS 1	1
97	WOOD,45,CLASS 1	1
97A	WOOD,45,CLASS 1	1
100	WOOD,45,CLASS 1	1
101	WOOD,45,CLASS 1	1
103	DUCTILE IRON,55,H6	1
106	DUCTILE IRON,55,H6	1
107	DUCTILE IRON,55,H6	1
108	WOOD,55,CLASS 1	1
109	WOOD,55,CLASS 1	1
110	WOOD,55,CLASS 1	1
112	WOOD,55,CLASS 1	1
112A	DUCTILE IRON,60,H6	1
113	WOOD,45,CLASS 1	1
114	WOOD,45,CLASS 1	1
115	WOOD,45,CLASS 1	1
117	WOOD,45,CLASS 1	1
118	WOOD,45,CLASS 1	1
119	WOOD,45,CLASS 1	1
120	WOOD,45,CLASS 1	1

Work Locations	Pole Description	Pole #
121A	WOOD,45,CLASS 1	1
122	WOOD,45,CLASS 1	1
123	WOOD,45,CLASS 1	1
124	WOOD,45,CLASS 1	1
125	WOOD,45,CLASS 1	1
127	WOOD,45,CLASS 1	1
128	WOOD,45,CLASS 1	1
130	WOOD,45,CLASS 1	1
131	WOOD,45,CLASS 1	1
32A	WOOD,45,CLASS 1	1
98	WOOD,45,CLASS 1	1
43A	WOOD,45,CLASS 1	1
107A	WOOD,35,CLASS 4	1
53	WOOD,35,CLASS 4	1
1A	DUCTILE IRON,55,H6	1
16A	DUCTILE IRON,55,H6	1
17	DUCTILE IRON,55,H6	1
18	WOOD,55,CLASS 1	1
19	DUCTILE IRON,55,H6	1
20	DUCTILE IRON,55,H8	1
19A	WOOD, 35, CLASS 4	1
108A	WOOD, 55, CLASS 1	1

Transformer Fusing 26kV-OH			
Transformer Size	Fuse Size	Type	Warehouse ID
15kVA	1A	T	285-34-13181
25kVA	2A	T	285-34-13175
37kVA	3A	T	285-34-13176
50kV	5A	T	285-34-13177
75kVA	6A	T	285-34-13178
100kVA	8A	T	285-34-13180
167kVA	12A	T	285-34-13179
250kVA	20A	T	285-34-13183
333kVA	25A	T	285-34-13171
500kVA	40A	T	285-34-13155

Lateral Fusing			
	Fuse Size	Fuse Size	Warehouse ID
1st Stage	100A	80A	K
2nd Stage	65A	40A	K
3rd Stage	40A	20A	-
(Revisions shown in red)			

Pole Setting Depths (in feet)				
	Wood Poles	Wood Poles	Concrete Poles	
Pole Length	Class 1-2	All Poles	8 Kip	12 Kip
35	6	6	11	
40	6.5	6.5	11.5	
45	7	7	11.5	13
50	7	7	11.5	13.5
55	7.5	7.5	12	14
60	8	8	12	14
65	8.5	8.5	12	14
70	9	9		14.5
75	9.5	9.5		15
80	10	10		15




Job Owner: J. St. Simon Phone: 561-533-7353 JOB NUMBER: 185502
 Designed By: J. Coissy Date:
 Drawn By: J. Coissy 6TH AVE S HARDENING CIRCUIT 4R0601
 Check By: 10/27/2022
 Scale: N.T.S Print No.
 REV REVISION DATE DRN DSGN CKD APPD Telephone Request? CATV Request?


LAKE WORTH, FLORIDA

TABLES


INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN




REV	REVISION	DATE	DRN	DSGN	CKD	APPD	Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data			Job Owner: J. St. Simon	Phone: 561-533-7353	Job Number: 185502
							Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS		Designed By: J. Coissy	Date: 10/27/2022	
2	80% FOR REVIEW	11/12/2021				Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet		Duct Bank Feet				Drawn By: J. Coissy		
1	60% FOR REVIEW	10/04/2021				Posted by	PERMIT REC'D	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>			Check By:	610 S H ST		
	60% FOR REVIEW	6/22/2021					Telephone Request? <input type="checkbox"/>	CATV Request? <input type="checkbox"/>					LAKE WORTH, FLORIDA	Print No.	
													Scale: 1" = 50'	2 Of 14	




REV	REVISION	DATE	DRN	DSGN	CKD	APPD	Easement?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Work With SMO?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit Data			Job Owner:	J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502	
							Tree Work?	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake?	YES <input type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS		Designed By:	J. Coissy	6TH AVE S HARDENING	Date:	
1	60% FOR REVIEW	10/04/2021					Map Posting?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Trench Feet						Drawn By:	J. Coissy	10/27/2022			
2	80% FOR REVIEW	11/12/2021					Posted by	PERMIT REQD	CITY <input type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>		COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>		WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>		Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>			Check By:	610 S H ST	Print No.
3	Issued For Construction	10/27/2022													LAKE WORTH, FLORIDA		Scale: 1" = 50'	3 Of 14		




INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN




						Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Survey/Stake? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Work With SMO? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Circuit Data			Job Owner: J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502
3	Issued For Construction	10/27/2022				Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Designer/Stake? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> CT/Special Mtr? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Circuit <td></td> <td>SWS</td> <td>Designed By: J. Coissy</td> <td></td> <td>Date: 10/27/2022</td>		SWS	Designed By: J. Coissy		Date: 10/27/2022
2	80% FOR REVIEW	11/12/2021				Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Trench Feet			Drawn By: J. Coissy		
1	60% FOR REVIEW	10/04/2021				Posted by _____			Check By: _____		
	60% FOR REVIEW	6/22/2021				PERMIT REQ'D: CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/> WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>			Scale: 1" = 50'		
REV	REVISION	DATE	DRN	DSGN	CKD	APPD	Telephone Request? <input type="checkbox"/>	CATV Request? <input type="checkbox"/>			Print No. 5 Of 14



					Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data		 CITY OF LAKE WORTH, FLORIDA	Job Owner: J. St. Simon	Phone: 561-533-7353	Job Number: 185502
3	Issued For Construction	10/27/2022			Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS		Designed By: J. Coissy	Date: 10/27/2022	
2	80% FOR REVIEW	11/12/2021			Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet	Duct Bank Feet				Drawn By: J. Coissy		
1	60% FOR REVIEW	10/04/2021			Posted by _____						Check By: _____		
	60% FOR REVIEW	6/22/2021			PERMIT REQ'D	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	Telephone Request? <input type="checkbox"/>	CATV Request? <input type="checkbox"/>		Scale: 1" = 50'	Lake Worth, Florida	
REV	REVISION	DATE	DRN	DSGN	CKD	APPD					Print No.: 6 Of 14		



INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN




3	Issued For Construction	10/27/2022			
2	80% FOR REVIEW	11/12/2021			
1	60% FOR REVIEW	10/04/2021			
	60% FOR REVIEW	6/22/2021			
REV	REVISION	DATE	DRN	DSGN	CKD APPD

Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data	
Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS
Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet		Duct Bank Feet	
Posted by PERMIT REQ'D	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>	


Job Owner: **J. St. Simon** Phone: 561-533-7353 JOB NUMBER: **185502**
 Designed By: **J. Coissy** Date: **10/27/2022**
 Drawn By: **J. Coissy**
 Check By:
 Scale: 1" = 50'
6TH AVE S HARDENING CIRCUIT 4R0601
 Print No.
LAKE WORTH, FLORIDA
 8 Of 14

INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN




3	Issued For Construction	10/27/2022				
2	80% FOR REVIEW	11/12/2021				
1	60% FOR REVIEW	10/04/2021				
REV	REVISION	DATE	DRN	DSGN	CKD	APPD
Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Survey/Stake? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Work With SMO? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Circuit Data						
Tree Work? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Designer/Stake? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> CT/Special Mtr? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> Circuit				SWS		
Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> Trench Feet <input type="checkbox"/> Duct Bank Feet						
Posted by _____						
<input type="checkbox"/> PERMIT REC'D <input type="checkbox"/> CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/> <input type="checkbox"/> WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/> <input type="checkbox"/> Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>						



CITY OF LAKE WORTH FLORIDA
6TH AVE S HARDENING CIRCUIT 4R0601
Date: 10/27/2022
Print No. 9 Of 14




						Easement? <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit Data		 LAKE WORTH FLORIDA	Job Owner: J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502	
3	Issued For Construction	10/27/2022				Tree Work? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS		Designed By: J. Coissy	6TH AVE S HARDENING CIRCUIT 4R0601		Date: 10/27/2022
2	80% FOR REVIEW	11/12/2021				Map Posting? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Trench Feet		Duct Bank Feet			Drawn By: J. Coissy			
1	60% FOR REVIEW	10/04/2021				Posted by _____	PERMIT REQ'D		CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>			Check By: _____	610 S H ST	Print No.	
	60% FOR REVIEW	6/22/2021					WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>		Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>			Scale: 1" = 50'	LAKE WORTH, FLORIDA	10 Of 14	
REV	REVISION	DATE	DRN	DSGN	CKD	APPD									



					Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data		Job Owner: J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502
3	Issued For Construction	10/27/2022			Tree Work? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS	Designed By: J. Coissy	6TH AVE S HARDENING CIRCUIT 4R0601	
2	80% FOR REVIEW	11/12/2021			Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet	Duct Bank Feet			Drawn By: J. Coissy	Date: 10/27/2022	
1	60% FOR REVIEW	10/04/2021			Posted by _____	PERMIT REQD	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>			Check By: _____	Print No. 610 S H ST	
	60% FOR REVIEW	6/22/2021				WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	Telephone Request? <input type="checkbox"/>	CATV Request? <input type="checkbox"/>		Scale: 1" = 50'	LAKE WORTH, FLORIDA	
REV	REVISION	DATE	DRN	DSGN	CKD	APPD						11 Of 14




					Easement? <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data			
3	Issued For Construction	10/27/2022			Tree Work? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	SWS		
2	80% FOR REVIEW	11/12/2021			Map Posting? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	Trench Feet		Duct Bank Feet			
1	60% FOR REVIEW	10/04/2021			Posted by	<input type="checkbox"/> PERMIT REQD	CITY <input checked="" type="checkbox"/>	DR. DIST. <input type="checkbox"/>	COUNTY AIR <input type="checkbox"/>	TRANSM. <input type="checkbox"/>	FAA <input type="checkbox"/>
	60% FOR REVIEW	6/22/2021				<input type="checkbox"/> WMD	<input type="checkbox"/> RR XING	<input type="checkbox"/> COUNTY RD	<input type="checkbox"/> STATE RD	<input type="checkbox"/>	
REV	REVISION	DATE	DRN	DSGN	CKD	APPD	Telephone Request? <input type="checkbox"/> CATV Request? <input type="checkbox"/>				



	Issued For Construction	10/27/2022			Easement? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Work With SMO? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit Data	Job Owner: J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502
3	80% FOR REVIEW	11/12/2021		Tree Work? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Circuit	Designed By: J. Coissy	Date: 10/27/2022		
2	60% FOR REVIEW	10/04/2021		Map Posting? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	Trench Feet	Duct Bank Feet	SWS	Drawn By: J. Coissy	Print No.		
1	60% FOR REVIEW	6/22/2021		Posted by	PERMIT REQD	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	CATV Request? <input type="checkbox"/>	Check By:	Scale: 1" = 50'	
REV	REVISION	DATE	DRN DSGN CKD APPD							LAKE WORTH, FLORIDA	13 Of 14

INACCESSIBLE 4KV FUTURE 26KV 26KV SALT SPRAY ROCK AVIAN



					Easement?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Survey/Stake?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Work With SMO?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit Data	Job Owner:	J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502
3	Issued For Construction				Tree Work?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Designer/Stake?	YES <input type="checkbox"/> NO <input type="checkbox"/>	CT/Special Mtr?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Circuit	Job Owner:	J. St. Simon	Phone: 561-533-7353	JOB NUMBER: 185502
2	80% FOR REVIEW				Map Posting?	YES <input type="checkbox"/> NO <input type="checkbox"/>	Trench Feet		Duct Bank Feet		SWS	Designed By:	J. Coissy	6TH AVE S HARDENING CIRCUIT 4R0601	Date: 10/27/2022
1	60% FOR REVIEW				Posted by		PERMIT REC'D	CITY <input checked="" type="checkbox"/> DR. DIST. <input type="checkbox"/> COUNTY AIR <input type="checkbox"/> TRANSM. <input type="checkbox"/> FAA <input type="checkbox"/>	WMD <input type="checkbox"/> RR XING <input type="checkbox"/> COUNTY RD <input type="checkbox"/> STATE RD <input type="checkbox"/>	Telephone Request? <input type="checkbox"/>	CATV Request? <input type="checkbox"/>	Drawn By:	J. Coissy	610 S H ST	Print No.
REV	REVISION	DATE	DRN	DSGN	CKD	APPD						Check By:		LAKE WORTH, FLORIDA	14 Of 14