



City of Lake Worth Beach
Compliance Checklist

IFB#26-101 Intracoastal Waterway Crossing Horizontal Directional Drilling (ICWW HDD) for Underground Distribution Project

	DBE Management, LLC dba DBE Utility Services	Accurate Drilling Systems, Inc.	Restore It All, Inc.
BID FORM 00300-1 - 00300-5	Submitted	Submitted	Submitted
PRICE SCHEDULE 00300-6	Submitted	Submitted	Submitted
TRENCH SAFETY AFFIDAVIT 00300-7	Submitted	Submitted	Submitted
SCHEDULE OF MAJOR SUBCONTRACTORS 00300-8	Submitted	Submitted	None
SCHEDULE OF MAJOR EQUIPMENT & MATERIALS 00300-9	Submitted	Submitted	Submitted
PUBLIC ENTITY CRIMES STATEMENT 00300-10 - 00300-11	Submitted	Submitted	Submitted
DRUG FREE WORKPLACE PROGRAM 00300-12	Submitted	Submitted	Submitted
VETERAL BUSINEES ENTERPRISE, SMALL BUSINESS AND LOCAL BUSINESS PREFERENCE FORM 00300-13	N/A	N/A	N/A
BIDDER'S QUALIFICATION QUESTIONNAIRE Pages 7 - 9	Submitted	Submitted	Submitted
CONTRACTOR SAFETY FORM	Submitted	Submitted	Submitted
CAMPAIGN CONTRIBUTION STATEMENT 00850-1 - 00850-2	Submitted	Submitted	Submitted
SCRUTINIZED COMPANIES CERTIFICATION FORM 00851-1	Submitted	Submitted	Submitted
AFFIDAVIT OF COMPLIANCE WITH ANIT-HUMAN TRAFFICKING LAWS 00852-1	Submitted	Submitted	Submitted
Bid Bond	Yes	Yes	Yes
Other qualification documents to be submitted:			
Construction Schedule	Yes	Yes	No
All Project Team Resumes - HDD	Yes	Yes	Yes
Commission Test Plan	Yes	Yes	No
HDD			
HDD Equipment Information	Yes	Yes	Yes
HDD Material Information	Yes	Yes	No
HDD Project Site Plan & Preliminary Drawings	Yes	Yes	No
HDD Casing Size & Material	Yes	Yes	No
HDD Spacer Design	Yes	Yes	No
HDD Methods & Work Plan	Yes	Yes	No
HDD Lay Down & Pull Back Methodology	Yes	Yes	No
HDD Overall Design Changes	Yes	Yes	No
HDD De-Beading Plan & Methodology	No	Yes	No
HDD Drill Fluid Management and Contingency Release Plan	Yes	Yes	No
HDD Fuel and Hydraulic Fluid Containment and Contingency Spill Plan	Yes	Yes	No
HDD Noise Mitigation Plan	Yes	Yes	Yes
Compliance:	Yes	Yes	No
Comments:	<p>Construction Schedule acceptable (assumed NTP 7/02/26, total 106 work days; can mobilize sooner). All resumes provided but no electric experience shown (only HDD/FPVC stormwater, forcemain, potable water); bores longer and subaqueous similar to project. Commission Test Plan acceptable (not planning to upsize). Seagrass Surveying Plan acceptable (subcontracted to T2, 23 days prior – permit compliant). HDD equipment, material (2-8" + 1-6" DR9 HDPE), site plan, methods & work plan, laydown & pullback, overall design changes (DR-9, 13" exit, 55ft cover), drill fluid management, spill plan, and noise plan all acceptable. De-Beading plan NOT acceptable – no plan or methodology provided. Mostly compliant; missing highlighted de-beading info.</p>	<p>Construction Schedule acceptable (109 work days). All resumes provided with strong experience and customer feedback; primarily water/wastewater/gas but recent electrical transmission HDDs, larger bores, subaqueous similar. Commission Test Plan acceptable (more info from UES desired post-award). Seagrass Surveying Plan acceptable (subcontracted to Atlas, 2 days prior – permit compliant). All HDD items acceptable: equipment, material (2-10" + 1-6" DR9, upsized to compensate for no de-beading), site-specific plan, methods, laydown (fused in sections during pullback), design changes (DR-9, West to East), de-beading (no internal/external; upsized), fluid management, spill plan, noise plan. Fully compliant.</p>	<p>Construction Schedule Not Acceptable (not provided). Commission Test Plan Not Acceptable (not provided). Seagrass Surveying Plan Not Acceptable (not provided). Resumes acceptable but electric-focused, not large HDDs, not primarily subaqueous, shorter experience, no OSHA rate. HDD Equipment acceptable but WSP unfamiliar with some. All other HDD items Not Acceptable / Not Provided (material, site plan, casing, spacer, methods & work plan, laydown, design changes, de-beading, fluid management, spill plan). Incomplete unit pricing (Items 3, 8 & 9). Not compliant. WSP recommends disqualifying this contractor.</p>



City of Lake Worth Beach

Bid Tabulation

IFB#26-101R Intracoastal Waterway Crossing Horizontal Directional Drilling (ICWW HDD) for Underground Distribution Project

				DBE Management, LLC dba DBE Utility Services			Accurate Drilling Systems, Inc.			Restore It All, Inc.			
Item #	DESCRIPTION	QUANTITY	UNIT	Material Unit Rate	Installation Unit Rate	Exended Cost	Material Unit Rate	Installation Unit Rate	Exended Cost	Material Unit Rate	Installation Unit Rate	Exended Cost	
1	MOBILIZATION	1	Lt.		\$61,132.00	\$61,132.00		\$21,120.00	\$21,120.00		\$40,000.00	\$40,000.00	
2	Dewatering (Engineering & execution)	1	Lt.		\$9,446.00	\$9,446.00		\$19,000.00	\$19,000.00		\$0.00	\$10,000.00	
3	Excavations and Shoring	1	Lt.		\$6,885.00	\$6,885.00		\$20,900.00	\$20,900.00		-	0	
4	HDD (Includes Boring, all HDPE power conduits, capping ducts at each end, and all other miscellaneous material for a complete HDD)	3350	Lt.	\$41.50	\$323.85	\$1,223,922.50	\$51.00	\$284.40	\$1,123,590.00	\$320.00	0	\$ 1,072,000.00	
5	Restoration	1	Lt.			\$38,610.00			\$20,300.00			\$10,000.00	
6	Demobilization	1	Lt.			\$36,036.00			\$7,490.00			\$30,000.00	
Other Costs													
7	Miscellaneous administrative costs to include quality/assurance, geotechnical and engineering verifications, site surveys, etc.	1	Lt.			\$15,444.00			\$51,950.00			\$16,160.00	
8	Construction Management	1	Lt.			\$7,722.00			\$18,550.00			0	
9	Testing	1	Lt.			\$9,652.00			\$15,250.00			0	
10	Bond	1	Lt.			\$31,500.00			\$19,000.00			\$23,840.00	
SUBTOTAL:						\$1,440,349.50				\$1,317,150.00			\$1,202,000.00
CONTINGENCY/BID ALLOWANCE:						\$150,000.00				\$150,000.00			\$150,000.00
BID TOTAL:						\$1,590,349.50				\$1,467,150.00			\$1,352,000.00
Comments:												Incomplete Bid, rates not provided for Items 3, 8 & 9	

Corrected Bid

Unit Rates not provided