

## **PSI Technologies Inc**

3520 Investment Lane Unit #3 Riviera Beach, Florida 33404

Phone: 561-660-0022 Email: tom@psi-techinc.com

## **Master Lift Station Pump - Quotation**

Company: City of Lake Worth Date: 09-30-2025 Contact: Judy Love Quote#: TK0933-2025

Street: 1820 2<sup>nd</sup> Ave. North Quote Valid: 30 Days CSZ: Lake Worth Beach, FL 33460 Terms: 30 Days Phone: (561) 586-1719 Shipping: Included

Email: jlove@lakeworthbeachfl.gov Prepared By: Thomas Kalinski

Quantity	Description	Unit Price	Total Price
1	WILO pump model # FA30.78D-740/FKT 57-8/76GEx-E3.  Impeller diameter: 740.00 mm – 12" discharge duty point - volume flow Q: 5000 - head H: 176 discharge connection pump: DN300 PN10 material hydraulic casing: GGG 50 (0.7050) material impeller: SS 1.4517 material casing wear ring: 1.4462/1.4470 material impeller ring: 1.4308 motor description: FKT 57-8/76GEx-E3 efficiency class: IE3 based on IEC 60034-30 - approval: FM voltage V: 460 ~3 - rated current: 475.00 a - starting current: 2,710.00 a rated power: 280.00 KW - frequency: 60 Hz full load speed: 894 RPM type of starting: direct - parallel service factor: 1.15 max. power input: 300.0 KW monitoring windings internal: 3 BI-130°+3 BI-140°C mon.motor/sealing chamber int.: motor chamber monitoring terminal chamber: terminal chamber monitoring leakage chamber: float switch for leakage chamb material motor casing parts: GG 25 (0.6025) material sealing casing: GG 25 (0.6025) material motor shaft: 1.7225 cable length: 15.0 m protection hose length: 0.0 m cable 1: number: 2 power supply 1: NSSHÖU-J RU 3x95/50 cable4: number: 1 control cable: NSSHÖU-J RU 7x1,5 Includes - Coating of volute interior and entire exterior of pump with Ceram C0 Includes - part # 6070034 Lifting "Y" Chain assembly Lead Time = 36-40 Weeks	\$325,250.00	\$325,250.00
	6% Tarriff Price Increase		\$19,515.00
	Delivery Included		
	Total Cost		\$344,765.00

Accepted By / Date: