2025 DISTRICT 1 SIDEWALK IMPROVEMENTS
LOCATION LIST

ADDRESS	Est. Area (SF)	Section		ADDRESS	Est. Area (SF)	Section	
101 W Church	48	4"		248 N Lapeer	32	4"	
103 N Broadway	50	4"		248 N Lapeer	16	4"	
111 E Flint	48	4"		249 N Lapeer	64	4"	
111 W Church	128	4"		250 N Park Blvd	40	4"	
117 E Church	64	4"		28 N Slater	96	4"	
120 S Broadway	40	4"		28 N Slater	32	4"	
123 S Slater	16	4"		305 E Jackson	40	4"	
140 E Flint	16	4"		305 E Jackson	32	4"	
140 E Flint	20	4"		317 E Jackson	16	4"	
140 E Jackson	32	Ramp 6"		330 N Anderson	80	4"	
144 N Washington	16	4"		357 E Flint	32	4"	
144 N Washington	16	4"		357 E Flint	32	4"	
144 N Washington	16	4"		40 N Washington	40	4"	
145 Hauxwell	32	4"		42 W Church	32	4"	
165 S Broadway	32	4"		437 E Flint	48	4"	
17 S Broadway	16	4"		44 E Shadbolt	32	4"	
201 N Lapeer	64	6"		44 E Shadbolt	32	4"	
207 N Slater	120	Ramp 6"		44 N Slater	64	4"	
209 E Flint	16	6"		450 N Park Blvd	20	4"	
209 E Flint	32	4"		47 E Flint	160	Thick 4"	
209 E Jackson	32	4"		505 E Flint	16	4"	
21 E Church	100	4"		505 E Flint	40	4"	
211 E Church	32	4"		52 S Slater	40	4"	
218 N Anderson	16	4"		540 E Flint	25	4"	
225 E Shadbolt	16	4"		55 W Elizabeth	50	4"	
229 E Jackson	32	4"		567 E Flint	64	6"	
229 E Jackson	16	4"		59 N Washington	32	4"	
230 E Church	32	4"		80 Perry	50	4"	
240 E Flint	40	4" / 6"					
242 N Anderson	32	6"		**TOTALS**	**2427**		

Wendy Spence:
DPW estimate used 4", but photos show driveway thus 6".

Wendy Spence:
DPW used 4" but photos show half in driveway thus split half 4" and half 6".

Wendy Spence:
DPW esitmate used 4" but photos show half in drive crossing thus 6". SHOULD HAVE LISTED IN BID AS 4"/6", my quantities used half 4" and half 6".

2025 DISTRICT 1 SIDEWALK IMPROVEMENTS
LOCATION LIST

140 E Jackson	32						
207 N Slater	120						
	152						
	2427						