

**YATES & FUNDERBURK CONCRETE FINISHING, INC.**  
**P.O Box 870**  
**China Grove, NC 28023**  
**704-202-6197**

**Proposal**

Date: 9-27-23

Re: N. Chapel St. Sidewalk Replacement

Michael,

We propose to provide all labor, equipment, material, and supervision to demo approx. 1,150SF of sidewalk and dispose of off-site. We will install a new 4' wide sidewalk with 4" deep concrete. All concrete will be a 3,000psi mix. I have listed out the two driveway aprons (225SF) for First Reform Church separately below. Driveways and sidewalks behind driveways will be 6" deep concrete to support vehicle traffic. We will backfill and seed all disturbed grass areas.

Sidewalk: \$11,452.00

Driveway Aprons: \$1,580.00

Sincerely,

**Greg Honeycutt**

Greg Honeycutt

**Exclusions/Notes:** No rebar or wwm in sidewalk/aprons, we will replace aprons separately for access, unsuitable soil replacement.