

CAROLINA SITEWORKS, INC
Post Office Box 280
China Grove, NC 28023
Telephone: 704-855-7483
Fax: 704-855-9676
NC License No. 45224

September 6, 2023

To: Chris England

Project: Speed Tables on S. Zion St.

We propose to furnish all the necessary supervision, labor, equipment, and materials required to complete the following work as outlined below and incorporated as part of this proposal.

Set up and maintain traffic control. Saw cut and mill tie ins at ends of proposed speed table. Dispose of excess material off-site. Install two asphalt speed tables with 6' long ascending and descending ramps, and 10' tables. Each table section will be approx. 4" in height. The total table will be approximately 22' in length. Stripe one directional arrow with glass beads on each side of each ramp.

LUMP SUM TOTAL: \$12,230.00

Due to the level of volatility in the petroleum market, we must index our pricing on this project. Prices for asphalt are based on the August 2023 NCDOT Asphalt Binder Index of \$618.13 per ton. Invoice calculations will be based on the NCDOT index for the month the asphalt is placed. An additional fuel surcharge, based on the current US EIA Fuel index, may also be applicable to your project.

NOTE: Price based on observations taken from site visit, and by typical speed table specifications and designs. If Carolina Siteworks, Inc. is awarded this contract, the quoted prices including the escalation clause are good through for 30 days, after that, Carolina Siteworks, Inc. may need to renegotiate prices. Exact speed table location to be provided by Town of Landis. Price includes one mobilization. Items not included in price: any extra grading, testing, any landscaping, rock excavation, undercut of unsuitable soils, repair of damage caused by others, relocation, or repair of utilities; prime coat or herbicide treatment, or anything else not specifically mentioned above.

Respectfully Submitted,
Mark Hoesman
Carolina Siteworks, Inc.

Accepted as Contract:

Carolina Siteworks, Inc.

