

**YATES & FUNDERBURK CONCRETE FINISHING, INC.**

**P.O Box 870**

**China Grove, NC 28023**

**704-202-6197**

**Change Order #1**

Date: 5-23-25

Re: S. Central Ave Sidewalk (Fifth Third)

Micheal,

We propose to provide all labor, materials, equipment, and supervision to demo sidewalk, existing curb and angle parking areas in front of Fifth Third bank along the east side of S. Central Ave. Curb and gutter elevations will be adjusted for new sidewalk to meet ADA cross slope. A new 4" thick sidewalk will be poured back between the new curb and existing building. We will install 2 handicap ramps in the same existing locations with yellow truncated domes to meet ADA codes. We will point up the existing storm drain catch basin at intersection with non-shrink grout to close off any leaks. All drive entrances will be 6" thick concrete. The angled parking areas will be replaced with 4" ABC stone and 6" of 6,000psi concrete to make them usable in 48 hours. We will stripe parking areas to match the existing layout.

Project Total: \$33,435.00

Respectfully,

**Greg Honeycutt**

Greg Honeycutt