

**William Mack Harrington  
5495 Enochville School Rd.  
China Grove, North Carolina 28023  
Telephone: 704-791-5987**

**February 5, 2026**

**PROPOSAL**

To: Matthew Geelen

**Project: Landis Town Hall Sewer Line Rehabilitation**

Utility locate by NC811

Meet with town officials to discuss logistics, coordination with town employees, and job schedule

Cut and remove 3' x 60' of asphalt driveway, 3' x 14' of concrete sidewalk and load on truck supplied by town for removal

Excavate soils in trench and load on truck supplied by town

Remove and re-lay new 4" PVC DWV Sch.40 pipe with all fittings and tracer wire

Backfill with ABC aggregate, supplied by town, and compact up to grade ready for patching of asphalt (asphalt by others)

Place and finish concrete that will be removed for trenching, place and finish 3' x 4' x 6" pad around sewer cleanout at area near payment drop box (concrete to be supplied by town)

(approximately 1 yard)

Caution tape in areas needed

General cleanup

**Total Proposed Cost: \$9,466.00**

**NOTE:** No provision has been made for extra labor and resources for unseen conditions (rock and or buried objects underground). No signage included in this quote.

This is a proposed cost

Respectfully submitted,

William M. Harrington

Accepted as Contract:

\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_