

Jimmy's Paving & Grading

6767 DEER HAVEN DRIVE
MOUNT PLEASANT NC

jjsmithasphalt@gmail.com

Date	
11/8/2025	

WARRIOR GOLF CLUB
1300 LAKE WRIGHT ROAD
CHINA GROVE NC

	Project	Terms	Due Date
Description	Qty	Unit Cost	Total Cost
MAINTENANCE SHOP AREA			
SAW-CUT AND EXCAVATE DAMAGED ASPHALT HAUL OFF SITE TO RECYCLE SITE COMPACT BASE INSTALL 2" OF BINDER COURSE ASPHALT AND COMPACT APPLY TACKOTE FOR BONDING OF SURFACE LAYER INSTALL 2" OF SURFACE COURSE ASPHALT APPROX. 1,600 SQ. FT.			\$14,000
CLEAN CRACKS 1/4" AND LARGER WITH POWER BLOWER APPLY HOT POUR CRACKFILLER FLUSH TO TOP OF CRACKS APPROX. 6,000 LF			\$6,000
CLEAN AREA OF GRASS AND LOOSE DEBRIS MACHINE SPRAY 2 COATS OF COMMERCIAL SAND SEALER STRIPE ANY LINES ON COMPLETION APPROX. 38,000 SQ FT			\$11,400
		TOTAL	\$31,400

Thank you for your business.