QUOTE

106612-01-07 • 10/26/2026

2026 Playground Proposal - Grant Check with Order - Additional Concrete and drainage work - Artificial turf surfacing

Customer:

CITY OF LATHRUP VILLAGE
27400 SOUTHFIELD RD
LATHRUP VILLAGE, MI 48076-3489
United States

Ship to Zip: 48076-3489

Prepared for:

Mike Green
Phone: 248-557-2600 Ext. 225
mgreene@lathrupvillage.org

Prepared by:

Playcore Wisconsin Inc, dba GameTime
150 Playcore Drive SE
Fort Payne, AL 35967
Ph: 800-444-4954
Fax: 616-392-8634

Quantity	Part #	Description	Unit Price	Amount
3876	TURF	**GT-Impax - Artificial turf surfacing, 3.5" thick system for a 12' Critical fall height** Price includes supply and installation of 8.5" of stone subbase and nailer board for turf installation	$39.65	$153,683.40
1	6263	**GameTime - Inclusive Whirl - Natural**	$18,034.00	$18,034.00
1	RDU	**GameTime - Swings with Seats** Does not include safety belt for the Adaptive Expression swing as it does not meet ASTM 1487 guidelines for public use playgrounds. • *(2) 5287 – Belt Seat for 8' Toprail* • *(2) 5295 – Expression Swing 8' Toprail Height* • *(1) 5299 – Expression Swing w/Adaptive Seat* • *(1) 5320 – 8' ADA Primetime Swing Frame* • *(2) 5321 – 8' ADA Primetime Swing Add-A-Bay* • *(1) 5378 – Zero-G (5-12) Beige 8' Height*	$12,869.00	$12,869.00
1	RDU	**GameTime - Modified Dallas Dazzler Unit for 5-12 year olds** • *(2) 6880RP – Aventus Talk Tube* • *(1) 3903 – Hypentic Wheel 12" 2S* • *(1) 3904 – Bells 20" 1S* • *(1) 3945 – Rain 12" 2S* • *(1) 3949 – Pachinko 20" 1S* • *(1) 3960 – Maze Panel Sensor 20" One Sided* • *(1) 3961 – Buzz Game Sensor 20" one sided* • *(1) 3965 – Rotogen Piano 20" Sensor with Adaptive* • *(7) 16701 – Ada 49"Tri Punch Steel Dk* • *(2) 6284RP – Aventus Entryway* • *(1) 6863RP – Arise Climber* • *(2) 6865RP – Inclusive Play Pocket* • *(1) 6867RP – Aventus Tower 12' Slide* • *(1) 6869RP – Arise Climber w/Cover* • *(1) 6870RP – Inclusive Play Pocket (Tower)* • *(1) 7294RP – Aventus Tower* • *(2) 7295RP – Aventus Tw Steel Panel Med* • *(1) 7296RP – Aventus Tw Steel Panel Sm* • *(1) 7297RP – Aventus Internal Climber-Steel* • *(4) 80001 – 49"Tri Punched Steel Deck* • *(2) 81680 – Single Seat* • *(1) 81688 – Therapeutic Rings Attch* • *(1) 90218 – Rung Encl Mold S. Whl & Bar,Above Dk* • *(2) 90266 – 8' Upright, Alum*	$191,264.00	$191,264.00

		• *(1) 90267 – 9' Upright, Alum* • *(3) 90268 – 10' Upright, Alum* • *(1) 90269 – 11' Upright, Alum* • *(1) 90272 – 14' Upright, Alum* • *(2) 90273 – 15' Upright, Alum* • *(1) 90286 – 8' Sky Hi Spiral Tube Slide, 30" Dia* • *(1) 91375 – PS Sensory Wave Up & Around (3' & 3'* • *(1) 91457 – Sensory Wave Entryway* • *(1) 91595 – Composer* • *(1) 91604 – HDPE Vertical Ladder 4'0"* • *(1) 91713 – Modern Transfer w/Guard 2'-6" Rise* • *(1) 91739 – Narrows Climber (3'-4'6")* • *(1) 91827 – 5" Upright Extension w/ Cap 5'* • *(5) 91832 – 5" Upright Extension w/o Cap 8'* • *(1) 91846 – 5" Upright Extension w/o Cap 7'* • *(2) G90269 – 11' Upright, Galv* • *(5) G90271 – 13' Upright, Galv* • *(2) G90273 – 15' Upright, Galv*		

1	INSTALL	**Installation - Installation of GameTime equipment and Freenotes musical instruments**
		Price includes:
		• Remove and dispose of existing structure and swings
		• Excavate the existing 3,000 SF of EWF play area toa depth of 12" and haul spoils offsite.
		• Excavate 1,000 Sf of new playground area outside of the existing area to a depth of 9.5" and haul spoils offsite
		• Install all proposed playground equipment
		• Furnish and install reinforced concrete border with keyway for PIP
		• Furnish and install concrete walkway
		• Saw-cut and remove the curb and gutter in parking lot and install an ADA ramp with tactile mat and a 20' x 6' x 4" concrete walkway to the existing
		• sidewalk.
		• Restore all areas disturbed to construction
		• Drainage system
		  ◦ Remove and dispose of 15' x 5' x 4" existing sidewalk so we can trench in 4" perforated drain pipe
		  ◦ Provide 255 LF 4" perforated drain pipe in sock in trench with peastone
		  ◦ Tap the drain pipe into the existing catch basin
		  ◦ Reinstall the 15' x 5' x 4" concrete sidewalk over a compacted 4" aggregate base
			$136,985.00	$136,985.00

1	Freenotes Flowers Ensemble IG	**Freenotes Harmony Park - Freenotes Flowers Inground Ensemble Collection**	$6,373.00	$6,373.00
1	TREE-IG	**Freenotes Harmony Park - Tenor Tree - (With Inground Mount Kit)**	$6,868.00	$6,868.00

QUOTE

106612-01-07 • 10/26/2026

Contract: OMNIA #2017001134

Sub Total	$526,076.40
Grant	($99,532.06)
Freight	$6,060.00
Grand Total	**$432,604.34**

Comments

Matching Grant Funds are available until October 23rd, 2026at 12PM EST **or** until Grant funds are no longer available. Approved grant application is required. To receive full grant funding, a check of $141,935.94 **must be received at the time of order.**

This quotation is subject to policies in the current GameTime Playground Catalog and the following terms and conditions. Our quotation is based on shipment of all items at one time to a single destination, unless noted, and changes are subject to price adjustment. Purchases to be supported by your written purchase order made out to vendor listed on quote acceptance. **A 2.5% PROCESSING FEE WILL BE ADDED TO ALL ORDERS PAID VIA CREDIT CARD.**

Pricing: f.o.b. factory, firm for 30 days from date of quotation unless otherwise noted on quotation. Sales tax will be added at time of invoicing unless a tax exemption certificate is provided at time of order entry.

Shipment: Order shall ship within 12-14 weeks after GameTime's receipt and acceptance of your purchase order, color selections, approved submittals, and receipt of deposit, if required.

NOTE: To qualify for the GameTime Grant, you must complete the application form for pre-approval. Upon approval, a Partial Matching Grant (reflected in the pricing shown above) is good toward the purchase of a new Powerscape, PrimeTime, XScape or Ionix Structure only. The order MUST be received no later than October 30th, with full payment to allow for processing, and your order will ship within 6-10 weeks from date of order placement and must ship prior to December 31st. The Grant does not apply toward Freight, Freestanding Items, Surfacing or Installation. To qualify for the matching grant amount shown above, a check for the **full** amount **MUST** accompany your order.

Installation: Shall be by a Certified GameTime Installer. Customer shall be responsible for scheduling coordination and site preparation. Site should be level and permit installation equipment access. Purchaser shall be responsible for unknown conditions such as buried utilities, tree stumps, bedrock or any concealed materials or conditions that may result in additional labor or material costs. Payment terms for installation is Net 10 Days.

NOTE: PRICING **DOES NOT** INCLUDE ANY DAVIS BACON OR PREVAILING WAGE RATES UNLESS SPECIFICALLY IDENTIFIED ABOVE IN QUOTE. THERE WILL BE A BACKCHARGE FOR THE INSTALLATION TO BE DONE THROUGH FELT, PEASTONE, SURFACING, OR WOODCHIPS, UNLESS SPECIFICALLY LISTED IN ABOVE QUOTE.

QUOTE

106612-01-07 • 10/26/2026

Exclusions: Unless specifically included, this quotation excludes all site work and landscaping; removal of existing equipment; acceptance of equipment and off-loading; storage of goods prior to installation; equipment assembly and installation; safety surfacing; borders, drainage provisions, or any local/municipal/state/federal permits or paperwork that may be required.

Acceptance of quotation:

Accepted By (printed): _____ P.O. No: _____

Please make P.O.s out to Playcore Wisconsin dba GameTime

Signature: _____

Title: _____ Date: _____

Facsimile: _____ Phone: _____

Email: _____ Purchase Amount: $432,604.34

REQUIRED ORDER INFORMATION:

Bill To: _____ Ship To: _____

Contact: _____ Contact: _____

Address: _____ Address: _____

Address: _____ Address: _____

City, State, Zip: _____ City, State, Zip: _____

Tel: _____ Tel: _____
(For Accounts Payable) (To call before delivery)

Email: _____ Email: _____

COLOR SELECTIONS: _____

SALES TAX EXEMPTION CERTIFICATE #: _____ (PLEASE PROVIDE A COPY OF CERTIFICATE)

NOTE: IF INSTALLATION IS BEING QUOTED, THERE WILL BE A BACKCHARGE FOR THE INSTALLATION TO BE DONE THROUGH FELT, PEASTONE, SURFACING, OR WOODCHIPS. PRICING VALID FOR 30 DAYS FROM THE DATE OF QUOTATION UNLESS OTHERWISE NOTED. ANY MODIFICATIONS TO AN ACCEPTED QUOTATION MUST BE DOCUMENTED IN WRITING OR WITH A NEW OR SEPARATE QUOTE. VERBAL MODIFICATIONS TO PREVIOUSLY SIGNED QUOTES WILL NOT BE ACCEPTED.