

Kickin' Asphalt, LLC
PO Box 127
Saint Hedwig, TX 78152
+12103858103
contactus@kickinasphaltdx.com



ADDRESS

City of La Vernia
La Vernia, Texas

Estimate

DATE 04/15/2025

DATE	ACTIVITY	AMOUNT
04/15/2025	Asphalt Custom Silverado St and Jessica St. Total sqft for both road 12,700 1. mill out existing road way areas to be included 120x30 380x20 75x20 2. Re work existing base (make sure proper drainage is set) 3. Add base where is needed 4. Wet and compact base 5. Spay aep primer onto base 6. Lay 2.5" of type D hot mix asphalt 7. Wet and compact to 2" 8. Finish roll asphalt with rubber tire roller	48,260.00
Notes: Re working existing base includes fixing the existing fail areas after road is milled out		

Thank you for your business! We accept cash, checks, and credit cards (paid thru Quickbooks online with a fee associated)

** Estimate must be signed and returned via email to Kickin' Asphalt, LLC before work will begin. By signing this estimate you agree to the terms listed below.

** Please note that payments are due: half down at start of job and FINAL PAYMENT DUE AT COMPLETION OF JOB - unless otherwise approved by Kickin' Asphalt, LLC

** If final payment is NOT received at completion of job there will be a 30% late fee added to the remaining balance.

** If Final payment is not received with in 10 days of completion of job, Kickin' Asphalt, LLC will - under Chapter 53 of the Texas Property Code - file a lien on the customer's property at which the work by Kickin' Asphalt, LLC was completed. Customers will be responsible for ALL legal fees incurred if a lien is placed on customer's property due to nonpayment.

** Please note that the email will also have warranty information documentation. Email delivery of this document acts as acknowledgement/agreement with Kickin' Asphalt's warranty agreement

TOTAL	\$48,260.00
-------	-------------

Accepted By

Accepted Date