

Kickin' Asphalt, LLC  
PO Box 127  
Saint Hedwig, TX 78152  
+12103858103  
contactus@kickinasphaltrx.com



**ADDRESS**

City of La Vernia  
La Vernia, Texas

Estimate

DATE 04/15/2025

DATE	ACTIVITY	AMOUNT
04/15/2025	<b>Asphalt Custom</b> Newton Street: Total sqft 10,800  1. 225x 8 area Concrete stabilize existing surface 6" deep with Portland mix cement 2. Wet and compact the 225x8 area 3. Mill out 2" of existing roadway 540x20 4. Clean loose derbies from road 5. Spray AEP primer onto road way 540x20 are (this bonds asphalt to road) 6. Lay 2.5" of type D hot mix asphalt 7. Wet and compact asphalt to 2" 8. Finish roll asphalt with rubber tire roller	39,420.00

Thank you for your business! We accept cash, checks, and credit cards (paid thru Quickbooks online with a fee associated)

\*\* Estimate must be signed and returned via email to Kickin' Asphalt, LLC before work will begin. By signing this estimate you agree to the terms listed below.

\*\* Please note that payments are due: half down at start of job and FINAL PAYMENT DUE AT COMPLETION OF JOB - unless otherwise approved by Kickin' Asphalt, LLC

\*\* If final payment is NOT received at completion of job there will be a 30% late fee added to the remaining balance.

\*\* If Final payment is not received within 10 days of completion of job, Kickin' Asphalt, LLC will - under Chapter 53 of the Texas Property Code - file a lien on the customer's property at which the work by Kickin' Asphalt, LLC was completed. Customers

will be responsible for ALL legal fees incurred if a lien is placed on customer's property due to nonpayment.

\*\* Please note that the email will also have warranty information documentation. Email delivery of this document acts as acknowledgement/agreement with Kickin' Asphalt's warranty agreement

TOTAL

\$39,420.00

Accepted By

Accepted Date