

Kickin' Asphalt, LLC
PO Box 127
Saint Hedwig, TX 78152
+12103858103
contactus@kickinasphalttp.com



ADDRESS

City of La Vernia
La Vernia, Texas

Estimate

DATE 04/15/2025

DATE	ACTIVITY	AMOUNT
04/15/2025	Asphalt Custom Kyle & King street Total sqft for both streets 14,490 1. Mill out existing roadway Kyle St. 505x18 and King St. 300x18 2. Re work existing base 3. Add base where needed 4. Wet and compact base 5. Spray AEP primer onto base (this bonds asphalt to base) 6. Lay 2.5" of type D hot mix asphalt 7. Wet and compact to 2" 8. Finish roll asphalt with rubber tire roller	47,092.50

Thank you for your business! We accept cash, checks, and credit cards (paid thru Quickbooks online with a fee associated)

** Estimate must be signed and returned via email to Kickin' Asphalt, LLC before work will begin. By signing this estimate you agree to the terms listed below.

** Please note that payments are due: half down at start of job and FINAL PAYMENT DUE AT COMPLETION OF JOB - unless otherwise approved by Kickin' Asphalt, LLC

** If final payment is NOT received at completion of job there will be a 30% late fee added to the remaining balance.

** If Final payment is not received within 10 days of completion of job, Kickin' Asphalt, LLC will - under Chapter 53 of the Texas Property Code - file a lien on the customer's property at which the work by Kickin' Asphalt, LLC was completed. Customers will be responsible for ALL legal fees incurred if a lien is placed

on customer’s property due to nonpayment.

** Please note that the email will also have warranty information documentation. Email delivery of this document acts as acknowledgement/agreement with Kickin’ Asphalt’s warranty agreement

TOTAL	\$47,092.50
-------	-------------

Accepted By

Accepted Date