

Kickin' Asphalt, LLC
PO Box 127
Saint Hedwig, TX 78152
+12103858103
contactus@kickinasphaltrx.com



ADDRESS

City of La Vernia
La Vernia, Texas

Estimate

DATE 10/31/2024

DATE	ACTIVITY	AMOUNT
10/31/2024	Asphalt Overlay Walking Path in City Park 1. Remove vegetation in designated area 2. Clean all loose debris off designated area 3. Saw cut and remove asphalt in designated area 4. If necessary fill in any low spots in designated area 5. Spray a tac coat onto existing asphalt (this help bonds new asphalt to old asphalt) 6. Lay 2.5" of type D hot mix asphalt 7. Wet and compact asphalt to 2" 8. Finish roll asphalt with rubber tire roller	44,154.00

Thank you for your business! We accept cash, checks, and credit cards (paid thru Quickbooks online with a fee associated)

** Estimate must be signed and returned via email to Kickin' Asphalt, LLC before work will begin. By signing this estimate you agree to the terms listed below.

** Please note that payments are due: half down at start of job and FINAL PAYMENT DUE AT COMPLETION OF JOB - unless otherwise approved by Kickin' Asphalt, LLC

** If final payment is NOT received at completion of job there will be a 30% late fee added to the remaining balance.

** If Final payment is not received within 10 days of completion of job, Kickin' Asphalt, LLC will - under Chapter 53 of the Texas Property Code - file a lien on the customer's property at which the work by Kickin' Asphalt, LLC was completed. Customers will be responsible for ALL legal fees incurred if a lien is placed on customer's property due to nonpayment.

** Please note that the email will also have warranty information documentation. Email delivery of this document acts as acknowledgement/agreement with Kickin' Asphalt's warranty agreement

TOTAL	\$44,154.00
-------	-------------

Accepted By

Accepted Date