

Kickin' Asphalt, LLC  
PO Box 127  
Saint Hedwig, TX 78152  
210.385.8103  
contactus@kickinasphalmtx.com



**ADDRESS**

City of La Vernia  
La Vernia, Texas

Estimate

DATE 04/01/2024

DATE	ACTIVITY	AMOUNT
04/01/2024	<b>Asphalt Custom</b> City of La Vernia  Project 3 - Chihuahua  2100sqft  1) remove 6" of materials 2) haul off debris 3) lay 4" of black base 4) wet and compact black base 5) spray tac coat 6) lay 2.5" of type D hot mix asphalt 7) wet and compact hot mix asphalt to 2" 8) finish roll asphalt with rubber tire roller  Total 31,500.00	26,500.00

Please note that payments are due: half down at start of job and final payment due at completion of job - unless otherwise discussed and approved.

Please note that the email will also have warranty information documentation. Email delivery of this document acts as acknowledgement/agreement with Kickin' Asphalt's warranty agreement

**TOTAL \$26,500.00**

Accepted By

Accepted Date