



December 6, 2023

Ms. Alice Lalonde
Levy County Road Department
PO Box 336
Bronson, Fl. 32621

RE: Levy County Road CR 345
FPID: 443407-1
NFPS: L220622LCB

Dear Ms. Lalonde,

The bid for CR 345 was received on 11/20/2023 using Demand Star.

The bids that were received are listed below:

Anderson Columbia (Lake City, FL)	\$	1,564,078.80
V.E. Whitehurst and Sons, Inc (Williston, FL)	\$	1,754,209.20

Anderson Columbia is a qualified FDOT approved contractor for the work mixes required for this project.

The bid summary is attached comparing the average unit prices to the bid prices for the bid's submitted. The summary includes an assessment evaluating the unit prices that are over by a percentage greater than 20% to ensure that there isn't any unit price loading in the contract. There was four pay item that were found to be more than 20% by the low bidding contractor, 104-10-3 Sediment Barrier, 110-4-10 Removal of Existing Conc, 110-7-1 Mailbox F&I, and 120-6 Embankment. The plans have been reviewed to ensure that the quantities for this pay item are correct.

Based on the Bid Summary and the evaluation, I recommend the County enter a contract with Anderson Columbia to construct the improvements on CR 347 from US 27 to 1.76 miles south.

If there are any questions or concerns, please don't hesitate to contact me as I am happy to assist.

Thank you,

Ryan D. Asmus, P.E.
FL PE #66626

Bid Summary CR 345 Widen and Resurface

FPID # 443407-1 L220622LCB

from SR 500 to US 129

Length (Miles):	2.37	Existing Pavement width 18' +/-
Project Scope:	Widening and resurfacing of CR 345, to provide 11' travel lanes and 6' grass shoulders. Also includes drainage upgrades, turnout construction, new signs and pavement markings.	

Pay Item No.	Pay Item Description	Quantity	Units	VE Whitehurst & Sons, Inc	Anderson Columbia	Average Unit Price
101-1	Mobilization	1.0	LS	\$286,185.00	\$219,152.96	\$252,668.98
101-2	Maintenance of Traffic	1.0	LS	\$204,995.00	\$149,578.84	\$177,286.92
104-10-3	Sediment Barrier	3000.0	LF	\$1.75	\$4.45	\$3.10
110-1-1	Clearing and Grubbing	5.70	AC	\$7,000.00	\$6,376.72	\$6,688.36
110-4-10	Removal of Existing Concrete	15.0	SY	\$165.00	\$270.61	\$217.81
110-7-1	Mailbox F&I	7.0	EA	\$300.00	\$566.82	\$433.41
120-1	Regular Excavation	2107.0	CY	\$10.00	\$15.75	\$12.88
120-6	Embankment	693.0	CY	\$15.00	\$44.23	\$29.62
121-70	Flowable Fill	23.0	CY	\$390.00	\$383.62	\$386.81
285-708	Optional Base Group 08	7008.0	SY	\$22.80	\$20.36	\$21.58
286-1	Turnout Construction	1023.0	SY	\$30.00	\$40.02	\$35.01
327-70-6	Milling Existing Asphalt 1.5"	25014.0	SY	\$2.65	\$2.93	\$2.79
334-1-13	Superpave Asphalt Concrete, Traffic C (Structural Course)	3922.0	TN	\$163.00	\$161.53	\$162.27
430 175 115	Pipe Culvert, Optional Round, 15" CD	240.0	LF	\$375.00	\$89.25	\$232.13
430-175-124	Pipe Culvert, Optional Round, 24" CD	10.0	LF	\$1,515.00	\$431.16	\$973.08
430-982-123	Mitered End Section, Round, 15" CD	12.0	EA	\$3,110.00	\$1,640.57	\$2,375.29
430-982-129	Mitered End Section, Round, 24" CD	2.0	EA	\$4,755.00	\$1,658.37	\$3,206.69
546-71-1	Raised Rumble Strips	12.0	EA	\$913.75	\$1,027.08	\$970.42
570-1-1	Performance Turf	27793.0	SY	\$0.35	\$0.36	\$0.36
570-1-2	Performance Turf, Sod	9754.0	SY	\$2.15	\$2.42	\$2.29
700-1-11	Single Post Sign (Less than 12 SF)	16.0	EA	\$430.00	\$543.75	\$486.88
700-1-60	Single Post Sign, Remove	17.0	EA	\$67.20	\$60.42	\$63.81
700-13-15	Retro Reflective Sign Strips	11.0	EA	\$67.20	\$102.71	\$84.96
700-142-111	Enhanced Highway Sign Assembly, Solar, F&I w/Beacon	4.0	EA	\$12,120.00	\$10,270.00	\$11,195.00
705-10-2	Object markers, Type 2	8.0	EA	\$205.00	\$78.54	\$141.77
706-1-3	Retro Reflective Pavement Markers	311.0	EA	\$5.65	\$6.34	\$6.00
710-90	Painted Pavement Markings, Standard, White, Solid, 6"	4.7	GM	\$2,690.00	\$3,020.82	\$2,855.41
710-90	Painted Pavement Markings, Standard, Yellow, Solid, 6"	2.0	GM	\$2,690.00	\$3,020.82	\$2,855.41
710-90	Painted Pavement Markings, Standard, Yellow, Skip, 6"	1.740	GM	\$1,290.00	\$1,449.99	\$1,370.00
710-90	Painted Pavement Markings, Standard, White, Solid, 24"	204.0	LF	\$10.75	\$12.08	\$11.42
	Indicates greater than 20% of Average Unit Price					

