FIRST AMENDMENT TO TASK ASSIGNMENT 2024-6 ISSUED UNDER AN AGREEMENT FOR CONTINUING PROFESSIONAL SERVICES

THIS AMENDMENT is entered into by and between LEVY COUNTY, a political subdivision of the State of Florida (the "County") and KISINGER CAMPO & ASSOCIATES (KCA) (the "Consultant") pursuant to the Agreement for Continuing Professional Services dated November 21, 2023 (the "Continuing Professional Services Agreement.")

WHEREAS, the County and Consultant entered into Task Assignment 2024-6 on June 4, 2024 for the Consultant to perform engineering services for the Cedar Key Big Dock FEMA Repairs; and

WHEREAS, the Consultant performed those services and delivered the final product for bidding purposes; however, the County did not issue an invitation to bid due to Hurricane Helene; and

WHEREAS, the Big Dock sustained additional damage during Hurricane Helene and the County determined it would like to revise the bid specifications to include repair of the additional damage.

NOW THEREFORE, the parties agree as follows:

- 1. <u>Scope of Services.</u> Consultant shall provide the services and materials (the "Scope of Services" or "Services) described in the attached Exhibit "A."
- 2. <u>Compensation.</u> County shall compensate Consultant for its performance of the Scope of Services a not to exceed amount of Twenty Two Thousand Three Hundred Ninety Six Dollars and Sixteen Cents (\$22,396.16) as set forth in the Proposal. Invoices or requests for payments to Consultant shall be made in accordance with the Florida Local Government Prompt Payment Act, sections 218.70 through 218.79, Fla. Stat.
- 3. <u>Precedence</u>. In the event of a conflict between the documents attached or incorporated by reference to this Task Assignment, the documents will be given precedence in the following order: (1) This Amendment; (2) Task Assignment 2024-6; and (3) The Continuing Professional Services Agreement. Except as amended herein, all other terms and conditions of the Continuing Professional Services Agreement and Task Assignment 2024-6 remain in full force and effect.

IN WITNESS WHEREOF, the parties have entered into this Amendment as of the last date of signature for parties set forth below.

| CONSOLI7((V) |
|-----------------------------------|
| Kisinger Campo & Associates Corp. |
| Ву: |
| Title: |
| Date: |

CONSULTANT

BOARD OF COUNTY COMMISSIONERS OF LEVY COUNTY, FLORIDA

| | Desires Mills Chair |
|---|---|
| | Desiree Mills, Chair |
| ATTEST: Matt Brooks, Clerk of Circuit Court and Ex-Officio Clerk to the Board of County Commissioners | |
| Matt Brooks | Approved as to form and legal sufficiency |
| | Nicolle M. Shalley, County Attorney |



January 29, 2025

Mr. Matt Weldon Director Parks & Recreation Levy County 310 School St Bronson, Florida 32621

Re: Cedar Key Big Dock FEMA Repairs

Dear Mr. Weldon:

We are pleased to submit this proposal for engineering services for supplemental services for the above referenced project. The scope of services will consist of developing repairs to Cedar Key Big Dock and Dock St to return it to its state prior to Hurricanes Idalia & Helene. Repairs will be for in-kind restoration to current codes and standards, and FEMA requirements. The services will be performed in conformance with Levy County policies and in accordance with the following:

1. PROJECT OBJECTIVES

The Consultant will develop the repairs for the damage which occurred during Hurricanes Idalia and Helene.

2. SPECIFIC SERVICES

The aluminum railing in front of the overwater business lot will be removed and replaced with a standard FDOT Aluminum Picket Railing with 4" maximum gap between pickets.

The concrete post & rail barrier and aluminum handrail west of the fishing dock ramp will be removed and replaced with a standard FDOT Aluminum Picket Railing with 4" maximum gap between pickets.

The concrete post & rail barrier and aluminum handrail east of the fishing dock ramp will be repaired.

The aluminum handrail in front of the fishing dock ramp will be replaced in-kind.

A 9" high sidewalk will be constructed west of the fishing dock ramp and in front of the overwater business lot.

The fishing dock ramp will be entirely removed and replaced in-kind.

Plan quantities will be based on existing plans, inspection reports, and cursory field measurements with any necessary adjustments due to current as-built conditions to be reviewed during construction.

The Consultant will provide bid assistance and post design assistance during construction. Post Design assistance will consist of pre-construction meeting attendance, site visits upon County request, responding to requests for information, reviewing material requests and shop drawings, and general coordination with the County.

The Consultant will make one submittal. Associated cost estimates will be included at each submittal.



3. <u>COUNTY RESPONSIBILITIES</u>

The County shall provide copies of any original pertinent or more recent information at the Consultant's request. In addition, the County shall provide access to the site for the Consultant as required.

4. <u>LIMITATIONS</u>

This scope does not include hydraulic analysis, survey, geotechnical efforts, or subsurface utility exploration (SUE).

Post Design assistance during construction does not include full time CEI supervision of the contractor. It is assumed the County will provide CEI.

Utility reconnections to the fishing dock will be coordinated by the Contractor.

5. BEGINNING AND LENGTH OF SERVICES

The above outlined services shall begin upon the receipt of the Notice to Proceed from the County. Final plans and specifications will be delivered in accordance with the County's production schedule.

6. <u>COMPENSATION</u>

Compensation for the above services shall be a Not To Exceed amount in accordance with the attached fee sheet.

Sincerely,

Patrick D. Mulhearn, P.E.

Project Manager

KISINGER CAMPO & ASSOCIATES CORP. LEVY COUNTY CEDAR KEY BIG DOCK FEMA REPAIRS Supplemental Agreement 01 - Helene Repairs

1/29/2025

| | | | | | | | S | UMMARY F | EE SHE | ET | | | | | | | | | | |
|--|------------------|----------------------------|-------------------|----------------------------|-------------------|----------------------------|-------------------|----------------------------|---------------|----------------------------|--------------------|----------------------------|----------------------------------|----------------------------|------------------------------------|----------------------------|-----------------------------|----------------------------|--------------------------|--------------------------|
| ACTIVITY | Chief Engineer 2 | | Project Manager 2 | | Senior Engineer 2 | | Senior Engineer 1 | | Engineer 1 | | Engineering Intern | | Senior Engineering Technician | | Senior Environmental Specialist | | Environmental Specialist | | | |
| | Man- Hours | Hourly Rate \$293.14 | Man- Hours | Hourly Rate \$257.34 | Man- Hours | Hourly Rate \$268.03 | Man- Hours | Hourly Rate \$260.48 | Man- Hours | Hourly Rate \$157.70 | Man- Hours | Hourly Rate \$124.07 | Man- Hours | Hourly Rate \$117.98 | Man- Hours | Hourly Rate \$165.15 | Man- Hours | Hourly Rate \$102.07 | Total Activity Fee | Manhrs By Activity |
| | | , | | , | | , | İ | + | | , | | , | | * | | , | | , | | |
| Update Key Sheet | | | | | | | | | | | 2 | \$248.14 | | | | | | | \$248.14 | 2.0 |
| Update General Notes | | | | | | | | | 2 | \$315.40 | | | 2 | \$235.96 | | | | | \$551.36 | 4.0 |
| Plan View/Repair Locations Sheet | | | 2 | \$514.68 | | | | | | | 8 | \$992.56 | | | | | | | \$1,507.24 | 10.0 |
| Sidewalk and Barrier Details (5 sheets) | | | 2 | \$514.68 | | | 2 | \$520.96 | | | 16 | \$1,985.12 | | | | | | | \$3,020.76 | 20.0 |
| Rebar Table | | | | | | | 2 | \$520.96 | 2 | \$315.40 | | | 2 | \$235.96 | | | | | \$1,072.32 | 6.0 |
| Traffic Control Details | | | | | | | | | 4 | \$630.80 | 6 | \$744.42 | | | | | | | \$1,375.22 | 10.0 |
| Incorporate Standard Plans | | | | | | | | | | | | | 2 | \$235.96 | | | | | \$235.96 | 2.0 |
| Incorporate Existing Plans | | | | | | | | | | | | | 2 | \$235.96 | | | | | \$235.96 | 2.0 |
| Quantities | | | 2 | \$514.68 | 4 | \$1,072.12 | | | | | 4 | \$496.28 | | | | | | | \$2,083.08 | 10.0 |
| Cost Estimate | | | | | 4 | \$1,072.12 | | | | | 4 | \$496.28 | | | | | | | \$1,568.40 | 8.0 |
| Post Design & Construction Assistance | | | 24 | \$6,176.16 | | | | | 4 | \$630.80 | 12 | \$1,488.84 | | | | | | | \$8,295.80 | 40.0 |
| - 3 site reviews, bid evaluation, bid questions, submittal reviews | | | | | | | | | | | | | | | | | | | | |
| SUBTOTAL | 0 | \$0.00 | 30 | \$7,720.20 | 8 | \$2,144.24 | 4 | \$1,041.92 | 12 | \$1,892.40 | 52 | \$6,451.64 | 8 | \$943.84 | 0 | \$0.00 | 0 | \$0.00 | \$20,194.24 | 114.0 |
| Quality Control | 4 | \$1,172.56 | | | | | | | | | | _ | | | | | | | \$1,172.56 | 4.0 |
| Project Management | | | 4 | \$1,029.36 | | | | | | | | | | | | | | | \$1,029.36 | 4.0 |
| TOTALS | 4 | \$1,172.56 | 34 | \$8,749.56 | 8 | \$ 2,144.24 | 4 5 | 1,041.92 | 12 | \$ 1,892.40 | 52 | \$ 6,451.64 | 8 | \$ 943.84 | 0 | \$ - | 0 | \$ - | \$22,396.16 | 122.0 |

TOTAL CONTRACT FEE COMPUTATIONS

| | KCA Activities Fees | | = | \$22,396.16 |
|--|--|-------------|---|--------------------------|
| | (a) Overhead Activities: | | | |
| | Admin., General, & Fringe Combined @ | 0.00% | = | \$ |
| FP No. | SUBTOTAL (Salary & Overhead) | | = | \$22,396.16 |
| | (b) Lump Sum for Operating Margin @ | 0.0% | = | \$ - |
| Contract No. | SUBTOTAL (Salary Related Costs) | | = | \$22,396.16 |
| F.A.P. No.: N/A | (c) Direct (Out of Pocket) Expenses (LS) | 0.00% | = | \$ - |
| | (d) Facilities Capital Cost of Money (FCCM) @ | 0.000% | = | \$ - |
| Project Name: Cedar Key Big Dock FEMA Repairs - Helene Updates | | | | Multiplier: |
| | SUBTOTAL (Cost Elements applied to Basic Activities) | | = | \$22,396.16 1.000 |
| | SUBCONSULTANTS: | | | |
| | (e) Subconsultant Services: | | = | <u>\$</u> |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | TOTAL AMOUNT | | = | \$22,396.16 |