

Ocala Fence, LLC
311 NW 11th Pl
Ocala, FL 34475 US
+13522740823
ar@ocalafence.com
www.ocalafence.com



Estimate

ADDRESS

Levy County Board of County
Commissioners
310 School Street , P.O. Box 310
Bronson, FL 32621

ESTIMATE # E-9910

DATE 06/05/2025

JOB NAME

CEDAR KEY AIRPORT

	DESCRIPTION	QTY	AMOUNT
BLK 1 5/8" X 21' TOP RAIL PP40	*BP1582140 - BLK PLY 1-5/8" x 21' x PP40	4,895.64	15,954.87
BLK 8 1/4" TIE 6GA	*BALUMTIE6814 - BLK VNL ALUM TIE 6gax8-1/4in 100 per bag	4,895.64	1,615.56
BLK 9 CORE FABRIC - 48"	*BVNL269C48KK - BLK VNL EXT 2x6(9core)x48in KK 25ft/rl	4,895.64	24,050.45
BLK BOTTOM TENSION WIRE 6GA	*BVTENWIRE6 - BLK VNL TENSION WIRE 6ga per ft	4,895.64	1,395.26
BLK HOG RINGS	*BPSTEELHOG - BLK VNL STEEL HOG RING	2,448	367.29
BLK 2" X 1 5/8" PS LOOP CAP	*BPSLOOP2158 - BLK PLY PS LOOP CAP 2X1-5/8in	480	2,505.60
BLK 2" X 7' POST PP40	*BPP2740 - BLK PLY 2" x 7' x PP40	480	21,339.36
BLK 3" PS DOME CAP	*BPSDOME3 - BLK PLY PS DOME CAP 3in	17	107.30
BLK 3" X 7' POST PP40	*BPP3740 - BLK PLY 3" x 7' x PP40	17	1,192.89
BLK 4" PS DOME CAP	*BPSDOME4	8	91.08
BLK 4" X 7' POST PP40	*BPP47PP40	8	703.08
5/16" X 1 1/4" BOLT/NUT	*BN516114 - BOLT/NUT 5/16x1-1/4"	175	31.50
BLK 1 5/8" PS RAIL END COMBO	*BPRE158PS - BLK PLY PS RAIL END COMBO 1-5/8in	35	172.20
BLK 3" BRACE BAND	*BPBB3 - BLK PLY BRACE BAND 3in	46	125.58

	DESCRIPTION	QTY	AMOUNT
BLK 3" TENSION BAND	*BPTB3 - BLK PLY TENSION BAND 3in	69	166.64
BLK 4" BRACE BAND	*BPBB4 - BLK PLY BRACE BAND 4"	24	54.00
BLK 4" TENSION BAND	*BPTB4	36	74.52
BLK 48" TENSION BAR	*BPTBAR4858 - BLK PLY TENSION BAR 48" x 5/8"	35	135.45
48"H X 5'W BLK IND SNG GATE	*45BSNGIND15840 - BLK SNG GATE 4'wx5h x1-5/8" SP40	2	578.19
BLK 1 5/8" PS DOME CAP	*BPSDOME158 - BLK PLY PS DOME CAP 1-5/8in	4	4.82
BLK 1 5/8" X 3" LATCH	*BPINDLATCH1583MAL - BLK PLY IND LATCH 1-5/8x3in MAL	2	54.87
BLK 3" PS BULLDOG HINGE	*BPPSBULLDOG3 - BLK PLY BULLDOG HINGE 3in PS	4	106.74
BLK 48"H X 20'W CANTILEVER GATE	*204BSNGCANT - BLK GATE 20'W x 4' SS40	4	4,431.66
WIDE MOUTH LATCH	*WIDECANT34 - WIDE MOUTH CANT POST LATCH 3in / 4in	4	315.96
4" NYLON ROLLER	*4NYLONROLLER - WI-CR3-N 4in NYLON CANTILEVER ROLLER	16	3,350.40
CONCRETE	* 60lbs Bags High-Strength Concrete	1,442	7,671.44
GATE INSTALLATION	GATE INSTALLATION	2	150.00
INSTALLATION - [4', 5' & 6'] CHAIN LINK	INSTALLATION - [4', 5' & 6'] CHAIN LINK	4,895.64	24,478.20
INSTALLATION - CANTILEVER GATE	INSTALLATION - CANTILEVER GATE	4	1,700.00
TEAR OUT	TEAR OUT	4,941.11	7,411.50
*PERFBOND	P & P BOND	1	2,328.00
SIGNS	SIGNS	1	875.00

Thank you for your business!

SUBTOTAL	123,539.41
TAX	0.00
TOTAL	\$123,539.41

Accepted By

Accepted Date