

Detention Center Parking Lot

Below is a preliminary estimate to re-build the detention center parking lot. The area on the map in yellow is priced as concrete and the magenta is asphalt over soil cement.

Preliminary Construction Estimate:

| | | | | |
|------------------------------------|------|-----|-------------|---------------------|
| Mill Asphalt | 4000 | SY | \$ 5.00 | \$ 20,000.00 |
| 12" Soil Cement | 4000 | SY | \$ 12.00 | \$ 48,000.00 |
| 3" Asphalt Paving | 690 | TON | \$ 130.00 | \$ 89,700.00 |
| Concrete (5" thick) | 367 | SY | \$ 50.00 | \$ 18,350.00 |
| Crushed Stone Base (6" thick) | 367 | SY | \$ 20.00 | \$ 7,340.00 |
| Striping | 1 | LS | \$ 2500.00 | \$ 2,500.00 |
| Concrete Curb & Gutter | 100 | LF | \$ 30.00 | \$ 3,000.00 |
| Traffic Control | 1 | LS | \$10,000.00 | \$ 10,000.00 |
| Mobilization | 1 | LS | \$12,000.00 | <u>\$ 12,000.00</u> |
| Subtotal | | | | \$210,890.00 |
| Contingency @10% | | | | \$ 21,089.00 |
| Total Estimated Construction Cost: | | | | \$231,979.00 |

