### PLANNING DATA

PROJECT ADDRESS: 962 RIVERSIDE DRIVE LOS ALTOS, CA 94024 189-42-027 ZONING DISTRICT: RI-10 11,647 SQ.FT. (0.2676 ACRES) LOT AREA: 3,494.10 SQ.FT. MAXIMUM LOT COVERAGE: 30% (2-STORY) MAXIMUM FLOOR AREA: 3,850 + 10%(11,647-11,000) = 3,914.70 SQ.FT. <u>HGT. LIMIT</u> 27'-Ø" SETBACKS (FIRST STORY): - REAR: - INT, SIDE: - EXT, SIDE: NEW FLOOR AREA: - 19T FLOOR AREA: - 2ND FLOOR AREA: - GARAGE AREA: 2,065.9 SQ. FT. 1,397.7 SQ. FT. 450.3 SQ. FT. - TOTAL FLOOR AREA: 3,913.9 SQ. FT. - BASEMENT AREA: 1,233.8 SQ. FT. NEW LOT COVERAGE AREA: - FRONT COVERED PATIO: - REAR COVERED PATIO: 99.7 SQ. FT. 256.5 SQ. FT. - TOTAL LOT COVERAGE: \2,872.4 SQ. FT. (24.6%) 265.6 SQ. FT. 28.7 SQ. FT. 90.2 SQ. FT. - LIGHT WELL #1: - LIGHT WELL #2: - 2ND FLR. DECK:

## ZONING COMPLIANCE Existing Propos

Allowed/Require Proposed LOT COVERAGE: 3,269.0 sq 2,872.4 sq ft 3,494.10 sq.ft. Land area covered by all structures 24.6% FLOOR AREA: 3,913.9 sq ft 33.6% 3,187.0 sq 3,914.70 sq.ft. Measured to the outside surfaces 27.3 % SETBACKS: 26'-0½" feet 32'-7" feet 21'-3½" feet 35'-6 ½" feet 10'-41/2" feet/ n/a feet 13'-7½" ft / 22'-0" feet 20'-5" ft / 24'-3" feet Right side (1st/2nd) 10 feet/ 7.5 feet 17'-11" feet/ n/a feet 20 feet/ 7.5 feet HEIGHT: +/- 20'-0" feet SQUARE FOOTAGE BREAKDOWN 22 Total Proposed Change in HABITABLE LIVING AREA: 1,930.4 sq ft 4,697.4 sq ff 2,767.0 sq ft Includes habitable basement areas NON-HABITABLE AREA: 30.3 450.3 sq f sq ft Does not include covered porches or open structures LOT CALCULATIONS 11,647 SQUARE FEET NET LOT AREA: FRONT YARD HARDSCAPE AREA: 999.00 SQ.FT. (37.7% of front yard area) Hardscape area in the front yard shall not exceed 50% Total hardscape area (existing and proposed): ( 5,757.6 sq ft LANDSCAPING BREAKDOWN: Existing softscape (undisturbed) area: 6,274 sq ft 6

### BUILDING CODE DATA

2021 CALIFORNIA ENERGY CODE (T-24 PART 6)

2021 CALIFORNIA GREEN BUILDING CODE (T-24 PART 11)

2021 CALIFORNIA FIRE CODE (T-24 PART 9)

OCCUPANCY:

R-3: SINGLE FAMILY RESIDENCE

U: ATTACHED GARAGE.

CONSTRUCTION TYPE: V-B

BUILDING CODES:

ALL APPLICABLE ADOPTED ORDINANCES

ALTOS. COUNTY OF SANTA CLARA. AND TH

ALL APPLICABLE ADOPTED ORDINANCES FOR THE CITY OF LOS ALTOS, COUNTY OF SANTA CLARA, AND THE STATE OF CALIFORNIA BUILDING STANDARDS CODE

2021 CALIFORNIA BUILDING CODE (T-24 PART 2)

2021 CALIFORNIA RESIDENTIAL BUILDING CODE (T-24 PART 25)

2021 CALIFORNIA ELECTRICAL CODE (T-24 PART 3)

2021 CALIFORNIA MECHANICAL CODE (T-24 PART 4)

2021 CALIFORNIA PLUMBING CODE (T-24 PART 5)

New softscape area: (-384.6) sq ft
Sum of all three should equal the site's net lot area 11,647 sq ft

### GENERAL NOTES

EXAMINATION OF SITE

THE CONTRACTOR SHALL EXAMINE THE SITE CONDITIONS AND THE STRUCTURES TO DETERMINE THE EXISTING CONDITIONS.

NO EXTRA COMPENSATION WILL BE ALLOWED FOR THE CONTRACTOR'S FAILURE TO DISCOVER CONDITIONS THAT EFFECT THE WORK.

#### LIMITATION OF THE WORK

THE LIMITS OF THE WORK ARE ESTABLISHED BY THE DRAWINGS.
THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING
TRADESMEN WITHIN THESE LIMITS.

#### DEMOLITION WORK

DEMOLISH AND REMOVE ALL ITEMS SHOWN ON THE SITE PLAN SURVEY & DEMOLITION PLAN. THE OWNER SHALL NOTIFY THE CONTRACTOR OF ALL ITEMS TO BE SALVAGED PRIOR TO COMMENCING THE DEMOLITION.

MEASUREMENTS

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS SHOWN ON THE DRAWINGS IN THE FIELD PRIOR TO COMMENCING THE WORK, NOTIFY THE ARCHITECT IMMEDIATELY OF ANY AND ALL DISCREPANCIES AT (408) 172-3502. ALL DIMENSIONS ARE GIVEN TO THE FACE OF STUDS UNLESS OTHERWISE NOTED. DO NOT SCALE THE DRAWINGS -- ALL DIMENSIONS SHALL TAKE PRECEDENCE. CALL THE ARCHITECT WITH QUESTIONS.

#### RULES AND REGULATIONS

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE CODES AND SHALL BE PER INDUSTRY STANDARDS. SEE BUILDING CODE DATA ON THIS SHEET FOR FURTHER INFORMATION.

#### OWNERSHIP OF DRAWINGS

THESE DRAWINGS ARE THE PROPERTY OF HERITAGE ARCHITECTURE
--DAVID V HERNANDEZ, ARCHITECT, THE DRAWINGS SHALL NOT BE USED
FOR ANY OTHER PURPOSE EXCEPT AS APPROVED BY THE ARCHITECT.

SEE SITE PLAN, FLOOR PLANS, MECHANICAL & ELECTRICAL PLANS, CIVIL, LANDSCAPE, ENERGY COMPLIANCE, ETC., FOR ADDITIONAL INFORMATION AND NOTES. SEE GENERAL NOTES AND INSTRUCTIONS ON SHEETS FOR FURTHER INFORMATION.

#### DEFERRAL OF SUBMITTAL ITEMS

THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL. (CBC 106.3.4.2).

#### RONT YARD LANDSCAPING

PRIOR TO THE FINAL INSPECTION, ALL LANDSCAPING IN THE FRONT YARD SHALL BE MAINTAINED OR NEW LANDSCAPING INSTALLED, SHALL BE INSTALLED AS REQUIRED BY THE PLANNING DIVISION.

#### MAIN HOUSE FIRE SPRINKLER SYSTEM:

NO FIRE SPRINKLER SYSTEM CURRENTLY EXISTS.
FUTURE REMODELING WILL TRIGGER A "SAFETY SCORE"
REQUIRING A WHOLE HOUSE SPRINKLER SYSTEM.

### ADU/GARAGE FIRE SPRINKLER SYSTEM:

A FIRE SPRINKLER SYSTEM CURRENTLY EXISTS AND WATER SERVICE HAS BEEN UPGRADED PER PREVIOUS ADU/GARAGE PERMIT.

A/C UNIT MANUFACTURER'S SPECIFICATIONS:

PRIOR TO PERMIT ISSUANCE, THE BUILDER MST PROVIDE THE
MANUFACTURER'S A/C SPECIFICATION FOR THE 16 SEER REQUIREMENT.

## SCOPE OF WORK

- I. DEMOLITION OF AN (E) SINGLE STORY RESIDENCE.
- 2. CONSTRUCTION OF A NEW 2-STORY SINGLE FAMILY RESIDENCE WITH A
  PARTIAL BASEMENT AND BASEMENT PATIO LIGHTWELL
- PARTIAL BASEMENT AND BASEMENT PATIO LIGHTWELL.
  AT-GRADE ENTERTAINMENT PATIOS AT THE REAR YARD W/ BLT.-IN BBQ.

### DEFERRED ITEMS

 NFPA 13D FIRE SPRINKLER SYSTEM DESIGN AND LAYOUT.
 SINGLE LINE DIAGRAMS (GAS, WATER, SEWER) SHALL BE PROVIDED BY BUILDER FOR REVIEW AND APPROVAL.

ABBREVIATIONS



## FRONT ELEVATION

## THE PIMPALKHARE RESIDENCE

962 RIVERSIDE DRIVE LOS ALTOS, CALIFORNIA

SHEET INDEX

FIRE DEPARTMENT NOTES

AND SPECIFICATION SI-7. PROVIDE APPROPRIATE NOTATIONS ON SUBSEQUENT

PLAN SUBMITTALS, AS APPROPRIATE TO THE PROJECT. CFC CHP. 33.

	ф	DIAMETER	(OH)	OVERHEAD			ı.	REQUIRED FIRE FLOW: THE MINIMUM REQUIRED FIRE FLOW FOR THIS PROJECT IS	GENERAL	INFORMATION	LANDS	CAPE DESIGN
	A.F.F.	ABOVE FINISH FLOOR	O.H.	OVERHANG	<u>OWNER:</u>	MANGESH & RAJASHREE PIMPALKHARE 962 RIVERSIDE DRIVE., LOS ALTOS, CA, 94Ø24		1,000 GALLONS PER MINUTE (GPM) AT 20 PSI RESIDUAL PRESSURE. THIS FIRE	+	TITLE SHEET / GENERAL NOTES / PLANNING & BUILDING DATA	L-1	MATERIALS PLAN
	BRG. PL.	BEARING PLATE	P # S	POLE AND SHELF		662 RIVERSIDE DRIVE., LOS ALTOS, CA, 54624 C: (408) 533-2954		FLOW ASSUMES INSTALLATION OF AUTOMATIC FIRE SPRINKLERS PER CFC	'	THE OHELT ALKERAL ROTES / LARRING & DOLLDING DATA	<u> </u>	TREE PROTECTION PLAN
	<b>¢</b>	CENTERLINE	R	RADIUS		E: RAJASHREEP@GMAIL.COM		[903.3.1.3].	CIVIL EN	SINEERING	L-2	COVERAGE AND LIGHTING PLAN
	C.O.	CLEAN-OUT	R/F	REFRIGERATOR/FREEZER		C: (415) 254-5641	1 2	FIRE SPRINKLERS REQUIRED: AN AUTOMATIC RESIDENTIAL FIRE SPRINKLER	<del></del>	TOPO SURVEY W/ AS-BUILT DIMENSIONS AT BLDG. FRONTAGE	L-3	LANDSCAPE PLANTING PLAN
_	CKTP.	COOKTOP	S	SINK		E: MPIMPALKHARE@GMAIL.COM	-	SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH NATIONAL FIRE PROTECTION	5u-1	10-0 SURVET W/ AS-BUILT DIFIENSIONS AT BLDG. FRONTAGE	L-3.1	SCREEN TREE SELECT GUIDE
t	0	DEGREE	S.B.	SETBACK				ASSOCIATION'S (NFPA) STANDARD I3D IN ALL NEW ONE AND TWO FAMILY	C-1.0	TITLE SHEET / NOTES	L-4	HYDRO-ZONE PLAN
$\prec$	D	DRYER	SD	STORM DRAIN	ARCHITECT:	HERITAGE ARCHITECTURE		DMELLINGS.	C-2.Ø	GRADING AND DRAINAGE PLAN	L-5 L-6	IRRIGATION PLAN CONSTRUCTION PLAN
ťΝ	D.H.	DOUBLE HEADER	S.S.D.	SEE STRUCTURAL DWGS.		DAVID V. HERNANDEZ, ARCHITECT P.O. BOX 8033			C-2.1	SITE PROFILE / CREEK SECTION	L-0	CONSTRUCTION   LAN
3	D.O.	DOUBLE OVEN	ST	STOVE		SAN JOSE, CA 95155	3.	ADDRESS IDENTIFICATION: NEW AND EXISTING BUILDINGS SHALL HAVE	C-3.0	UTILITY PLAN		
$\supset$	DN	DOWN	#	SQUARE FEET		C: (408) 172-3502		APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE	C-4.0	DETAILS		
t /	DS DS	DOWNSPOUT	T.B.D.	TO BE DETERMINED		E: DVHERNANDEZ@PACBELLNET		FROM THE STREET OR ROAD FRONTING THE PROPERTY. THESE NUMBERS SHALL	C-4.1 C-5.0	DETAILS - SUMP PUMPS GRADE SPECIFICATIONS		
${\ensuremath{f /}}$ I	DW	DISHWASHER	T.O. PL.	TOP OF PLATE		W: HTTP5://WWW.HOUZZ.COM/PRO/DVHERNANDEZ		CONTRAST WITH THEIR BACKGROUND. WHERE REQUIRED BY THE FIRE CODE	C-5.D	GRADE SPECIFICATIONS		
1	(E)	EXISTING		TOP OF SLAB				OFFICIAL, ADDRESS NUMBERS SHALL BE PROVIDED IN ADDITIONAL APPROVED	ER-I	EROSION CONTROL PLAN		
_	(E/	—			<u>CIVIL ENGINEER:</u>	LEA & BRAZE CIVIL ENGINEERING, INC. 2495 INDUSTRIAL PKWY WEST		LOCATIONS TO FACILITATE EMERGENCY RESPONSE. ADDRESS NUMBERS SHALL	ER-2	EROSION CONTROL DETAILS		
	F	FURNACE		R TOP OF SUBFLOOR		HAYWARD, CA, 94545		BE ARABIC NUMBERS OR ALPHABETICAL LETTERS. NUMBERS SHALL BE A				
$\dashv$	F.Ø.S.	FACE OF STUD		TOP OF WALL		0: (510) 887-4086 X192		MINIMUM OF 6 INCHES (101.6 MM) HIGH WITH A MINIMUM STROKE WIDTH OF 0.5 INCH	BMP-1	BLUEPRINT FOR A CLEAN BAY		
)	GSM			TOILET PAPER HOLDER		E: ZALI@LEABRAZE.COM		(12.7 MM). WHERE ACCESS IS BY MEANS OF A PRIVATE ROAD AND THE BUILDING				
	J.T.	JOINT TRENCH	V.I.F.	VERIFY IN FIELD		W: WWW.LEABRAZE.COM		CANNOT BE VIEWED FROM THE PUBLIC WAY, A MONUMENT, POLE OR OTHER SIGN OR MEANS SHALL BE USED TO IDENTIFY THE STRUCTURE. ADDRESS NUMBERS	ARCHITE	CTURAL		
	M.C.	MEDICINE CABINET	W	WASHER				SHALL BE MAINTAINED. CFC SEC. 505.1.	Δ1.1	EXISTING SITE PLAN		
	(N)	NEW	W.H.	WINDOW HEAD	LANDSCAPE ARCH'T:			SHALL DE MAINTAINED. OF O SEC. 305.1.	A1.2	NEW SITE PLAN		
	N.T.S.	NOT TO SCALE	WH	WATER HEATER		2345 TULIP ROAD, SAN JOSE, CA, 95128 C: (408) 605-9973	4.	WATER SUPPLY REQUIREMENTS: POTABLE WATER SUPPLIES SHALL BE PROTECTED	A1.3	NEIGHBORHOOD MAPS / STREETSCAPE IMAGERY		
						E: TKALBFELD@6BCGLOBALNET		FROM CONTAMINATION CAUSED BY FIRE PROTECTION WATER SUPPLIES. IT IS THE				
						F: (408) 241-6636		RESPONSIBILITY OF THE APPLICANT AND ANY CONTRACTORS AND	A2.Ø	FLOOR AREA DIAGRAMS		
								SUBCONTRACTORS TO CONTACT THE WATER PURVEYOR SUPPLYING THE SITE OF	A2.1	NEW MAIN RESIDENCE BASEMENT FLOOR PLAN		
_								SUCH PROJECT, AND TO COMPLY WITH THE REQUIREMENTS OF THAT PURVEYOR.	A2.2	NEW MAIN RESIDENCE FIRST FLOOR PLAN		
								SUCH REQUIREMENTS SHALL BE INCORPORATED INTO THE DESIGN OF ANY WATER-BASED FIRE PROTECTION SYSTEMS, AND/OR FIRE SUPPRESSION WATER	A2.3	NEW MAIN RESIDENCE SECOND FLOOR PLAN		
								SUPPLY SYSTEMS OR STORAGE CONTAINERS THAT MAY BE PHYSICALLY	A3.1	NEW MAIN RESIDENCE ROOF PLAN		
								CONNECTED IN ANY MANNER TO AN APPLIANCE CAPABLE OF CAUSING	<i></i>	TEW HAIN PLOID ENGL POOL FLAN		
								CONTAMINATION OF THE POTABLE WATER SUPPLY OF THE PURVEYOR OF	A4.Ø	MATERIALS / COLOR BOARD		
								RECORD. FINAL APPROVAL OF THE SYSTEM(S) UNDER CONSIDERATION WILL NOT	A4.1	NEW EXTERIOR ELEVATIONS - FRONT & RIGHT SIDE		
								BE GRANTED BY THIS OFFICE UNTIL COMPLIANCE WITH THE REQUIREMENTS OF	A4.2	NEW EXTERIOR ELEVATIONS - REAR & LEFT SIDE		
								THE WATER PURVEYOR OF RECORD ARE DOCUMENTED BY THAT PURVEYOR AS	A4.3	EXISTING EXTERIOR ELEVATIONS		
								HAVING BEEN MET BY THE APPLICANT(S). 2022 CFC SEC. 903.3.5 AND HEALTH	A5.1	BUILDING SECTIONS		
								AND SAFETY CODE 13114.7.	45.1 45.2	BUILDING SECTIONS		
							5	CONSTRUCTION SITE FIRE SAFETY: ALL CONSTRUCTION SITES MUST COMPLY WITH	A5.3	BUILDING SECTION		
							1	APPLICABLE PROVISIONS OF THE CFC CHAPTER 33 AND OUR STANDARD DETAIL				
				1			I	AND SPECIFICATION SUT PROVIDE APPROPRIATE MOTATIONS ON SURGEOUENT				

PROJECT CONTACT LIST

PLNG. CMNTS. 2


PEVISIONS BY

DESIGN REVIEW
SBMTL Ø1/12/2024

PLNG. PLAN CHK
Ø4/11/24 DVH

PLNG. CMNTS. 2
Ø6/26/24 DVH

HERITAGE ARCHITECTURE



HEKLI ACIE AKCHII ECTUI DAVID V. HERNANDEZ, ARCHITEC P.O. BOX 8033, San Jose, California 95155 C: (408) 772-3502 VM: (408) 298-0998 E-mail: dyhernandez@nachell net

PIMPALKHARE RESIDENCE 962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024


DRAWN: DVH

SCALE: NO SCALE

JOB NO. 2022.01

DATE: 06/26/2024

T






2221958 1-4-23 1"=10' RM

ΑO

OF 1 SHEETS

# 962 RIVERSIDE DRIVE LOS ALTOS, CALIFORNIA



## **ABBREVIATIONS**

~>· ~>> ~>>

**DESCRIPTION** 

PROPERTY LINE

SUBDRAIN LINE

TIGHTLINE

WATER LINE

JOINT TRENCH

SET BACK LINE

EARTHEN SWALE

CATCH BASIN

**JUNCTION BOX** 

AREA DRAIN

**CURB INLET** 

FIRE HYDRANT

STREET SIGN

SPOT ELEVATION

FLOW DIRECTION

BENCHMARK

**CONTOURS** 

DEMOLISH / REMOVE

TREE TO BE REMOVED

TREE PROTECTION FENCING

TOP OF WALL/FINISH GRADE

**TYPICAL** 

VERTICAL

WATER LINE

WATER METER

**VERT** 

VERTICAL CURVE

VITRIFIED CLAY PIPE

WELDED WIRE FABRIC

GAS LINE

LANDSCAPE RETAINING WALL

RAINWATER TIGHTLINE

STORM DRAIN LINE

SANITARY SEWER LINE

STORM DRAIN PRESSURE LINE

CONCRETE VALLEY GUTTER

STORM DRAIN MANHOLE

SANITARY SEWER MANHOLE

SANITARY SEWER PRESSURE LINE

BOUNDARY

**EXISTING** 

AGGREGATE BASE LINEAR FEET **ASPHALT CONCRETE** MAX MAXIMUM **ACCESSIBLE MANHOLE** AREA DRAIN MINIMUM BEGINNING OF CURVE MON. **MONUMENT BEARING & DISTANCE** MRO METERED RELEASE OUTLET BENCHMARK NEW BUB BUBBLER BOX NUMBER BW/FG BOTTOM OF WALL/FINISH NOT TO SCALE GRADE ON CENTER CATCH BASIN OVER CURB AND GUTTER PLANTING AREA CENTER LINE PEDESTRIAN CORRUGATED PLASTIC PIPE POST INDICATOR VALVE (SMOOTH INTERIOR) PUBLIC SERVICES EASEMENT ČLEANOUT PROPERTY LINE CLEANOUT TO GRADE POWER POLE CONC CONCRETE PUBLIC UTILITY EASEMENT **CONST** CONSTRUCT or -TION POLYVINYL CHLORIDE CONC COR CONCRETE CORNER CUBIC YARD REINFORCED CONCRETE PIPE DIAMETER RIM ELEVATION DROP INLET RAINWATER **DUCTILE IRON PIPE** R/W RIGHT OF WAY EACH SLOPE END OF CURVE SEE ARCHITECTURAL DRAWINGS **EXISTING GRADE** SANITARY **ELEVATIONS** STORM DRAIN **EDGE OF PAVEMENT** STORM DRAIN MANHOLE **SDMH EQUIPMENT** SHEET EACH WAY S.L.D. SEE LANDSCAPE DRAWNGS **EXISTING SPEC SPECIFICATION** FACE OF CURB SANITARY SEWER FINISHED FLOOR SSC0 SANITARY SEWER CLEANOUT FINISHED GRADE **SSMH** SANITARY SEWER MANHOLE FIRE HYDRANT STREET FLOW LINE STA STATION FINISHED SURFACE **STANDARD** STD **STRUCT STRUCTURAL** GAGE OR GAUGE **TELEPHONE** GRADE BREAK TOP OF CURB **HDPE** HIGH DENSITY CORRUGATED TOP OF WALL POLYETHYLENE PIPE **TEMP** TEMPORARY **HORIZ** HORIZONTAL TOP OF PAVEMENT

HIGH POINT

HUB & TACK

INSIDE DIAMETER

JUNCTION BOX

JOINT TRENCH

LENGTH

LANDING

LNDG

INVERT ELEVATION

JOINT UTILITY POLE

## RETAINING WALL NOTES

1. TW/FG REPRESENTS FINISHED EARTHEN GRADE OR PAVEMENT ELEVATION AT TOP OF WALL, NOT ACTUAL TOP OF WALL MATERIAL. BW/FG REPRESENTS FINISH EARTHEN GRADE OR PAVEMENT ELEVATION AT BOTTOM OF WALL NOT INCLUDING FILL FOUNDATION. GRADES INDICATED ON THESE PLANS REFER TO THE FINISHED GRADES ADJACENT TO THE RETAINING WALL, NOT INCLUDING FOOTING, FREEBOARD, ETC.

2. DIMENSIONS SHOWN IN BRACKETS SHOWN AS [X.X'] DENOTE THE EFFECTIVE WALL HEIGHT ONLY. THE ACTUAL WALL HEIGHT AND DEPTH MAY DIFFER DUE TO CONSTRUCTION REQUIREMENTS.

3. REFER TO SPECIFIC WALL CONSTRUCTION DETAIL FOR STRUCTURAL ELEMENTS, FREEBOARD, AND EMBEDMENT.

4. REFER TO ARCHITECTURAL, LANDSCAPE ARCHITECTURE, AND/OR STRUCTURAL PLANS FOR DETAILS. WALL ELEVATIONS. SUBDRAINAGE. WATERPROOFING. FINISHES, COLORS, STEEL REINFORCING, MATERIALS, ETC. PROVIDE CLIPS OR OTHER MEANS OF SECURING FINISH MATERIALS AS NECESSARY (WET SET INTO THE WALL).

5. ALL RETAINING WALLS SHOULD HAVE A BACK-OF-WALL SUB-SURFACE DRAINAGE SYSTEM INCLUDING WEEPHOLES TO PREVENT HYDROSTATIC


6. SEE DETAIL SHEET FOR SPECIFIC INFORMATION.

7. PROVIDE GUARDRAIL (WHERE APPLICABLE AND DESIGNED BY OTHERS) AS REQUIRED FOR GRADE SEPARATION OF 30 INCHES OR MORE MEASURED 5' HORIZONTALLY FROM FACE OF WALL, PER CBC.

ESTIMATED	EARTHWO	RK QUAN	TITIES
CUBIC YARDS	WITHIN BUILDING FOOTPRINT	I BUILDING	
CUT	630	0	630
FILL	210	20	230
EXPORT			400

GRADING QUANTITIES REPRESENT BANK YARDAGE. IT DOES NOT INCLUDE ANY SWELLING OR SHRINKAGE FACTORS AND IS INTENDED TO REPRESENT IN-SITU CONDITIONS. QUANTITIES DO NOT INCLUDE OVER-EXCAVATION, TRENCHING, STRUCTURAL FOUNDATIONS OR PIERS, OR POOL EXCAVATION (IF ANY). NOTE ADDITIONAL EARTHWORKS, SUCH AS KEYWAYS OR BENCHING MAY BE REQUIRED BY THE GEOTECHNICAL ENGINEER IN THE FIELD AT TIME OF CONSTRUCTION. CONTRACTOR TO VERIFY QUANTITIES.

## KEY MAP



**INSPECTIONS REQUIRED** 

LEA & BRAZE ENGINEERING, INC. TO INSPECT ALL STORM DRAINAGE AS IT IS INSTALLED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT LEA & BRAZE ENGINEERING, INC. PRIOR TO START OF CONSTRUCTION TO SET UP A PRE-CONSTRUCTION MEETING, AND TO CALL AT LEAST 48 HOURS IN ADVANCE OF ANY INSPECTIONS. PIPES ARE TO REMAIN UNCOVERED UNTIL AN INSPECTION OCCURS.

POINT OF CONTACT: JIM TOBY LEA & BRAZE ENGINEERING, INC.

(510)715-6028 jtoby@leabraze.com

#### \* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL SPACE DEPTH

TO ESTABLISH PAD

LEVEL.



C-1.0

ER-2

SHEET INDEX TITLE SHEET GRADING & DRAINAGE PLAN SITE SECTIONS C - 2.1C - 3.0UTILITY PLAN DETAILS C - 4.0C - 5.0GRADING SPECIFICATIONS ER-1 EROSION CONTROL

EROSION CONTROL DETAILS

BLUEPRINT FOR A CLEAN BAY

PROJECT SITE

**VICINITY MAP** 

OWNER'S INFORMATION

THIS **GRADING AND DRAINAGE** PLAN IS SUPPLEMENTAL TO: TOPOGRAPHIC SURVEY BY LEA&BRAZE ENGINEERING. INC

2. SITE PLAN BY HERITAGE ARCHITECTURE ENTITLED:

3. SOIL REPORT BY SILICON VALLEY SOIL ENGINEERING

RAJASHREE PIMPALKHARE 962 RIVERSIDE DRIVE

LOS ALTOS. CA

"TOPOGRAPHIC SURVEY"

'PIMPALKHARE RESIDENCE"

"GEOTECHNICAL INVESTIGATION"

962 RIVERSIDE DRIVE

962 RIVERSIDE DRIVE

962 RIVERSIDE DRIVE

DATË: NOVEMBER 2022

LOS ALTOS, CA

LOS ALTOS, CA JOB# SV2479

ENTITLED:

DATED: 04-03-2023 JOB# 2221958 SU

APN: 189-42-027

REFERENCES

 $\mathcal{O}$ 

PLAN CHECK #1 ZA REVISIONS JOB NO: 2221914 12-13-23 AS NOTED SCALE:

SHEET NO:

OF 10 SHEETS

DESIGN BY: ZA

CHECKED BY: JT


4. LANDSCAPE PLAN BY TODD KALBFELD LANDSCAPE DESIGN, ENTITLED "SINGLE FAMILY RESIDENCE" 962 RIVERSIDE DRIVE LOS ALTOS, CA THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM. CONTRACTOR SHALL OBTAIN THE PROPER PERMITS PRIOR TO ANY GRADING. A SEPARATE PERMIT IS REQUIRED FOR ANY & ALL WORK WITHIN THE CITY RIGHT-OF-WAY. THE CONTRACTOR(S) SHALL OBTAIN AN APPROVED STREET WORK (ENCROACHMENT PERMIT) PERMIT FROM THE PUBLIC WORKS

DEPARTMENT PRIOR TO THE COMMENCEMENT OF THIS WORK WITHIN THE CITY RIGHT-OF-WAY.

ALL GRADED SLOPES SHALL BE PLANTED WITH FAST GROWING, DEEP ROOTED GROUND COVER TO REDUCE THE EROSION DURING HEAVY RAINS.

REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL INFORMATION, INCLUDING BUT NOT LIMITED TO: ADDITIONAL UTILITY SERVICES, DIMENSION CONTROL, DEMOLITION, DETAILS, TREE PROTECTION MEASURES, AND LANDSCAPING.

CONTRACTOR SHALL NOTIFY THE OWNER AND/OR MAINTENANCE STAFF IN WRITING OF THE NEED OF PERIODIC MAINTENANCE OF THE DRAINAGE SYSTEM AND STRUCTURES.



FLATWORK KEYNOTES (1) TO (6)

FINISHED GRADES AT BUILDING PERIMETER SHALL BE SLOPED AT A MINIMUM OF 5% FOR THE FIRST 10' AWAY FROM THE BUILDING PER CBC 1804.4 OR TO AN APPROVED DRAINAGE SWALE OR STRUCTURE. GRADES SHALL CONTINUE TO SLOPE TOWARDS POSITIVE DRAINAGE AND A POSITIVE OUTFALL. MAINTAIN 8" CLEARANCE BETWEEN FINISH EARTHEN GRADE AND BOTTOM OF MUD SILL AT ALL TIMES PER CBC 2304.12.1.2 UNLESS STRUCTURAL DETAILING ALLOWS LESS. REFER TO STRUCTURAL PLANS FOR FOUNDATION DESIGN AND DETAILS.

SLOPE GARAGE SLAB 1% MINIMUM (1/8" PER FOOT) FROM BACK TO FRONT TO ALLOW FOR ADEQUATE DRAINAGE. MAINTAIN 1/2 TO 1 LIP BETWEEN GARAGE SLAB AND DRIVEWAY. SEE PLANS FOR SPECIFIC DROP

PROVIDE 2% SLOPE ACROSS FLAT WORK AND/OR PAVING PER CBC 1804.4. SLOPE TOWARDS POSITIVE DRAINAGE AS SHOWN ON PLAN.

INSTALL (N) CONCRETE PAVER DRIVEWAY. SEE DETAIL 1 ON SHEET C-4.0.

(N) CONCRETE PAVER PATIOS/WALKWAYS. SEE DETAIL 2 ON SHEET

(N) CONCRETE PATIOS IN LIGHTWELL AREA. SEE LANDSCAPE AND STRUCTURAL PLAN FOR PAVEMENT SPECIFICATIONS.

ENGINEERING, II BRAZE

ESIDENCE DRIVE JFORNIA

RE

- DEMOLISH (E) IMPROVEMENTS AS NECESSARY TO ACCOMMODATE (N) CONSTRUCTION. NO DEMOLITION SHALL COMMENCE WITHOUT REQUIRED DEMOLITION PERMITS.
- REMOVE (E) TREE. CONTRACTOR SHALL OBTAIN THE PROPER TREE REMOVAL PERMITS AS REQUIRED.
- PROVIDE TREE PROTECTION AROUND TREES TO REMAIN. SEE DETAIL 6 ON SHEET ER-2.

## FEMA FLOOD NOTE

FLOOD ZONE: AE

100-YEAR BASE FLOOD ELEVATION UPSTREAM AT PROPERTY LINE (BFE): 175.0' (NAVD88 DATUM) DOWNSTREAM AT PROPERTY LINE (BFE): 174.6' (NAVD88 DATUM) PER FLOOD INSURANCE STUDY FLOOD PROFILE FOR HALE CREEK

FEMA FLOOD INSURANCE RATE MAP NO.: 06085C0201H EFFECTIVE DATE: MAY 18, 2009

FEMA FLOOD INSURANCE STUDY FOR SANTA CLARA COUNTY, CA NO.: 06085CV003B REVISED: FEBRUARY 19, 2014

PORTION OF PROPERTY REMOVED FROM SPECIAL FLOOD HAZARD AREA PER LOMA CASE NO#23-09-0548A



FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116.


aabaya@leabraze.com

\* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS
FOR SLAB SECTION OR CRAWL SPACE DEPTH TO ESTABLISH PAD LEVEL.

_	_
_	_
PLAN CHECK 03-18-24	#1 ZA
REVISIONS	BY
JOB NO: 22	21914
DATE: 12-	-13-23
SCALE: AS	NOTED
DESIGN BY: ZA	
CHECKED BY: JT	
SHEET NO:	

IN(GE

2 OF 10 SHEETS





PIMPALKHARE RESIDENCE
962 RIVERSIDE DRIVE
LOS ALTOS, CALIFORNIA
(510) 8

SITE PROFILE

_		-
_		١
_		-
_		-
PLAN CHE 03-18-2	CK #1 4	ZA
REVISIONS	6	BY
JOB NO:	2221	914
DATE:	12-1	3-23

 JOB NO:
 2221914


 DATE:
 12-13-23

 SCALE:
 AS NOTED

 DESIGN BY:
 ZA

CHECKED BY: JT SHEET NO:





STORM DRAIN KEYNOTES (10) TO (21) INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" PVC (SDR 35) OR HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). MAINTAIN 24 MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS

OTHERWISE NOTED. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS.

INSTALL (N) SUBDRAIN. USE PERFORATED 4" PVC (SDR-35) WITH HOLES DOWN AND SLOPED AT 1% MINIMUM SURROUND WITH 3/4" DRAIN ROCK WRAPPED IN FILTER FABRIC (MIRAFI 140N). MIRADRAIN OR OTHER LEA & BRAZE PREAPPROVED DRAINAGE SYSTEM MAY ALSO BE USED. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION AND AT 100' MAXIMUM INTERVALS. SUBDRAIN SHALL REMAIN A DEDICATED SEPARATE SYSTEM UNTIL IT CONNECTS TO STORM DRAIN SYSTEM OR OUTFALL AS SHOWN. SEE DETAIL 3 ON SHEET C-4.0.

- CONSTRUCT (N) EARTHEN SWALE SLOPED AT 1% MINIMUM TOWARDS POSITIVE OUTFALL. SEE DETAIL 4 ON SHEET C-4.0.
- DIRECT DOWNSPOUTS TO 24 LONG PRECAST CONCRETE SPLASHBLOCKS OR OTHER HARD SURFACE. DIRECT AWAY FROM ANY STRUCTURE AND TOWARDS POSITIVE DRAINAGE. SEE DETAIL 5 ON SHEET C-4.0.
- INSTALL (N) 4" DIAMETER BRASS AREA DRAIN (AD) IN HARDSCAPE AREAS (NDS PART 906 PB). SEE DETAIL 6 ON C-4.0.
- INSTALL (N) 4" DIAMETER HEAVY DUTY PLASTIC BLACK GRATE IN LANDSCAPE OR PLANTER AREAS (NDS PART 78 OR 90 FOR 6" DIAMETER HEAVY DUTY PLASTIC BLACK GRATE). SEE DETAIL 7 ON C-4.0.
- INSTALL (N) CHRISTY V-12 CATCH BASIN W/ CONCRETE BOTTOM FLUSH W/ LOWEST OUTGOING INVERT. PLACE BOX ON 6" CLASS 2 AGGREGATE BASE MATERIAL. SEE DETAIL 8 ON SHEET C-4.0.
- INSTALL (N) LIGHTWELL OVERFLOW DRAIN. SEE DETAIL 9 ON SHEET C-4.0.
- INSTALL (N) SUMP PUMP FOR SUBDRAIN SYSTEM. SEE DETAIL 1 ON SHEET
- INSTALL (N) SUMP PUMP FOR LIGHTWELL DRAINAGE. SEE DETAIL 2 ON SHEET C-4.1 FOR LIGTHWELL 1. SEE DETAIL 3 ON SHEET C-4.1 FOR
- (N) SLOT DRAINS SHALL BE ZURN Z888-6 OR APPROVED EQUAL. CONNECT TO NEAREST STORM DRAIN LINE. USE 6" PVC (SDR-35) OR HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). SEE DETAIL 5 ON SHEET

(21) INSTALL (N) BUBBLER. SEE DETAIL 4 ON SHEET C-4.1.



INC.

BRAZE

**LEA** c iv i∟


ESIDENCE DRIVE JFORNIA RE Ah ÆR 7S,

	-				
	-				
	-				
	-				
PLAN CHECK #1 03-18-24	ZA				
REVISIONS	BY				
B NO: 2221	2221914				
TE: 12-1	3-23				
ALE: AS NOTED					

CHECKED BY: JT SHEET NO:

4 OF 10 SHEETS

DESIGN BY: ZA



REVISIONS JOB NO: 2221914 DATE: 12-13-23


NTS


CHECKED BY: JT SHEET NO:


5 OF 10 SHEETS

DESIGN BY: ZA


SCALE:









I PUMP NOTES:







ENGINEERING,

BRAZE

ංජ

LEA CIVIL

IDENCE RIVE ORNIA

RE

 $\Xi$   $\Omega$ 以及

HAF VEH

ПР 65 SS

M 90 90

0

D F(

D A

_		_
_		_
_		_
PLAN CHEC 03-18-24	ZA	
REVISIONS		BY
JOB NO:	2221	914
DATE:	12-1	3-23
SCALE:	NTS	
DESIGN BY:	ZA	
CHECKED BY:	JT	



THESE DRAWINGS AND THEIR CONTENT ARE AND SHALL REMAIN THE PROPERTY OF LEA AND BRAZE ENGINEERING, INC. WHETHER THE PROJECT FOR WHICH THEY ARE PREPARED IS EXECUTED OR NOT. THEY ARE NOT TO BE USED BY ANY PERSONS ON OTHER PROJECTS OR EXTENSIONS OF THE PROJECT EXCEPT BY AGREEMENT IN WRITING AND WITH APPROPRIATE COMPENSATION TO THE ENGINEER.

ALL WORK SHALL COMPLY WITH APPLICABLE CODES AND TRADE STANDARDS WHICH GOVERN EACH PHASE OF WORK INCLUDING, BUT NOT LIMITED TO, CALIFORNIA MECHANICAL CODE, CALIFORNIA PLUMBING CODE, CALIFORNIA ELECTRICAL CODE, CALIFORNIA FIRE CODE, CALTRANS STANDARDS AND SPECIFICATIONS, AND ALL APPLICABLE STATE AND/OR LOCAL CODES AND/OR LEGISLATION.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND ALL SUBCONTRACTORS TO CHECK AND VERIFY ALL CONDITIONS, DIMENSIONS, LINES AND LEVELS INDICATED. PROPER FIT AND ATTACHMENT OF ALL PARTS IS REQUIRED. SHOULD THERE BE ANY DISCREPANCIES, IMMEDIATELY NOTIFY THE ENGINEER FOR CORRECTION OR ADJUSTMENT THE EVENT OF FAILURE TO DO SO, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CORRECTION OF ANY ERROR.

ALL DIMENSIONS AND CONDITIONS SHALL BE CHECKED AND VERIFIED ON THE JOB BY EACH SUBCONTRACTOR BEFORE HE/SHE BEGINS HIS/HER WORK. ANY ERRORS, OMISSION, OR DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER/CONTRACTOR BEFORE CONSTRUCTION BEGINS.

COMMENCEMENT OF WORK BY THE CONTRACTOR AND/OR ANY SUBCONTRACTOR SHALL INDICATE KNOWLEDGE AND ACCEPTANCE OF ALL CONDITIONS DESCRIBED IN THESE CONSTRUCTION DOCUMENTS, OR EXISTING ON SITE, WHICH COULD AFFECT THEIR WORK.

#### WORK SEQUENCE

In the event any special sequencing of the work is required by the owner or the CONTRACTOR, THE CONTRACTOR SHALL ARRANGE A CONFERENCE BEFORE ANY SUCH WORK IS BEGUN.

SITE EXAMINATION: THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL THOROUGHLY EXAMINE THE SITE AND FAMILIARIZE HIM/HERSELF WITH THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED. THE CONTRACTOR SHALL VERIFY AT THE SITE ALL MEASUREMENTS AFFECTING HIS/HER WORK AND SHALL BE RESPONSIBLE FOR THE CORRECTIONS OF THE SAME. NO EXTRA COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR EXPENSES DUE TO HIS/HER NEGLECT TO EXAMINE, OR FAILURE TO DISCOVER, CONDITIONS WHICH AFFECT HIS/HER WORK.

LEA AND BRAZE ENGINEERING, INC. EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO A THIRD PARTY WITHOUT FIRST OBTAINING THE WRITTEN PERMISSION AND CONSENT OF LEA AND BRAZE ENGINEERING, INC. IN THE EVENT OF UNAUTHORIZED REUSE OF THESE PLANS BY A THIRD PARTY, THE THIRD PARTY SHALL HOLD HARMLESS LEA AND BRAZE ENGINEERING, INC.

CONSTRUCTION IS ALWAYS LESS THAN PERFECT SINCE PROJECTS REQUIRE THE COORDINATION AND INSTALLATION OF MANY INDIVIDUAL COMPONENTS BY VARIOUS CONSTRUCTION INDUSTRY TRADES. THESE DOCUMENTS CANNOT PORTRAY ALL COMPONENTS OR ASSEMBLIES EXACTLY. IT IS THE INTENTION OF THESE ENGINEERING DOCUMENTS THAT THEY REPRESENT A REASONABLE STANDARD OF CARE IN THEIR CONTENT. IT IS ALSO PRESUMED BY THESE DOCUMENTS THAT CONSTRUCTION REVIEW SERVICES WILL BE PROVIDED BY THE ENGINEER. SHOULD THE OWNER NOT RETAIN THE ENGINEER TO PROVIDE SUCH SERVICES, OR SHOULD HE/SHE RETAIN THE ENGINEER TO PROVIDE ONLY PARTIAL OR LIMITED SERVICES, THEN IT SHALL BE THE OWNER'S AND CONTRACTOR'S RESPONSIBILITY TO FULLY RECOGNIZE AND PROVIDE THAT STANDARD OF CARE.

IF THE OWNER OR CONTRACTOR OBSERVES OR OTHERWISE BECOMES AWARE OF ANY FAULT OR DEFECT IN THE PROJECT OR NONCONFORMANCE WITH THE CONTRACT DOCUMENTS, PROMPT WRITTEN NOTICE THEREOF SHALL BE GIVEN BY THE OWNER AND/OR CONTRACTOR TO THE ENGINEER.

THE ENGINEER SHALL NOT HAVE CONTROL OF OR CHARGE OF AND SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, OR PROCEDURES, OR FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK, FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR, SUBCONTRACTORS, OR ANY OTHER PERSONS PERFORMING ANY OF THE WORK, OR FOR THE FAILURE OF ANY OF THEM TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

### SITE PROTECTION

PROTECT ALL LANDSCAPING THAT IS TO REMAIN. ANY DAMAGE OR LOSS RESULTING FROM EXCAVATION. GRADING, OR CONSTRUCTION WORK SHALL BE CORRECTED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF ALL EXISTING SITE UTILITIES AND SHALL COORDINATE THEIR REMOVAL OR MODIFICATIONS (IF ANY) TO AVOID ANY INTERRUPTION OF SERVICE TO ADJACENT AREAS. THE GENERAL CONTRACTOR SHALL INFORM HIM/HERSELF OF MUNICIPAL REGULATIONS AND CARRY OUT HIS/HER WORK IN COMPLIANCE WITH ALL FEDERAL AND STATE REQUIREMENTS TO REDUCE FIRE HAZARDS AND INJURIES TO THE PUBLIC.

## STORMWATER POLLUTION PREVENTION NOTES

- 1) STORE, HANDLE, AND DISPOSE OF CONSTRUCTION MATERIALS AND WASTES PROPERLY, SO AS TO PREVENT THEIR CONTACT WITH STORMWATER.
- 2) CONTROL AND PREVENT THE DISCHARGE OF ALL POTENTIAL POLLUTANTS, INCLUDING SOLID WASTES, PAINTS. CONCRETE, PETROLEUM PRODUCTS, CHEMICALS, WASH WATER OR SEDIMENT, AND NON-STORMWATER DISCHARGES TO STORM DRAINS AND WATER COURSES.
- 3) USE SEDIMENT CONTROL OR FILTRATION TO REMOVE SEDIMENT FROM DEWATERING EFFLUENT.
- 4) AVOID CLEANING, FUELING, OR MAINTAINING VEHICLES ON SITE, EXCEPT IN A DESIGNATED AREA IN WHICH RUNOFF IS CONTAINED AND TREATED.
- 5) DELINEATE CLEARING LIMITS, EASEMENTS, SETBACKS, SENSITIVE OR CRITICAL AREAS, BUFFER ZONES, TREES AND DISCHARGE COURSE WITH FIELD MARKERS.
- 6) PROTECT ADJACENT PROPERTIES AND UNDISTURBED AREAS FROM CONSTRUCTION IMPACTS USING VEGETATIVE BUFFER STRIPS, SEDIMENT BARRIERS OF FILTERS, DIKES, MULCHING, OR OTHER MEASURES AS APPROPRIATE.
- 7) PERFORM CLEARING AND EARTH MOVING ACTIVITIES DURING DRY WEATHER TO THE MAXIMUM EXTENT PRACTICAL.
- 8) LIMIT AND TIME APPLICATIONS OF PESTICIDES AND FERTILIZERS TO PREVENT POLLUTED RUNOFF.

9) LIMIT CONSTRUCTION ACCESS ROUTES AND STABILIZE DESIGNATED ACCESS POINTS.

SWEEPING METHODS TO THE MAXIMUM EXTENT PRACTICAL.

10) AVOID TRACKING DIRT OR MATERIALS OFF-SITE; CLEAN OFF-SITE PAVED AREAS AND SIDEWALKS USING DRY

### SUPPLEMENTAL MEASURES

- A. THE PHRASE "NO DUMPING — DRAINS TO HALE CREEK" OR EQUALLY EFFECTIVE PHRASE MUST BE LABELED ON STORM DRAIN INLETS (BY STENCILING, BRANDING, OR PLAQUES) TO ALERT THE PUBLIC TO THE DESTINATION OF STORM WATER AND TO PREVENT DIRECT DISCHARGE OF POLLUTANTS INTO THE STORM
- B. USING FILTRATION MATERIALS ON STORM DRAIN COVERS TO REMOVE SEDIMENT FROM DEWATERING EFFLUENT.
- C. STABILIZING ALL DENUDED AREAS AND MAINTAINING EROSION CONTROL MEASURES CONTINUOUSLY FROM OCTOBER 15 AND APRIL 15.
- D. REMOVING SPOILS PROMPTLY, AND AVOID STOCKPILING OF FILL MATERIALS, WHEN RAIN IS FORECAST. IF RAIN THREATENS, STOCKPILED SOILS AND OTHER MATERIALS SHALL BE COVERED WITH A TARP OR OTHER WATERPROOF MATERIAL.
- E. STORING, HANDLING, AND DISPOSING OF CONSTRUCTION MATERIALS AND WASTES SO AS TO AVOID THEIR ENTRY TO THE STORM DRAIN SYSTEMS OR WATER BODY.
- F. AVOIDING CLEANING, FUELING, OR MAINTAINING VEHICLES ON-SITE, EXCEPT IN AN AREA DESIGNATED TO CONTAIN AND TREAT RUNOFF.

#### GRADING & DRAINAGE NOTES:

#### 1. SCOPE OF WORK

these specifications and applicable plans pertain to and include all site grading and EARTHWORK ASSOCIATED WITH THE PROJECT INCLUDING, BUT NOT LIMITED TO THE FURNISHING OF ALL LABOR, TOOLS AND EQUIPMENT NECESSARY FOR SITE CLEARING AND GRUBBING, SITE PREPARATION, DISPOSAL OF EXCESS OR UNSUITABLE MATERIAL, STRIPPING, KEYING, EXCAVATION, OVER EXCAVATION RECOMPACTION PREPARATION FOR SOIL RECEIVING FILL, PAVEMENT, FOUNDATION OF SLABS, EXCAVATION, IMPORTATION OF ANY REQUIRED FILL MATERIAL, PROCESSING, PLACEMENT AND COMPACTION OF FILL AND SUBSIDIARY WORK NECESSARY TO COMPLETE THE GRADING TO CONFORM TO THE LINES, GRADING AND SLOPE SHOWN ON THE PROJECT GRADING PLANS.

#### 2. GENERAL

- A. ALL SITE GRADING AND EARTHWORK SHALL CONFORM TO THE RECOMMENDATIONS OF THESE SPECIFICATIONS, THE SOILS REPORT BY SILICON VALLEY SOIL ENGINEERING; AND THE CITY OF LOS
- B. ALL FILL MATERIALS SHALL BE DENSIFIED SO AS TO PRODUCE A DENSITY NOT LESS THAN 90% RELATIVE COMPACTION BASED UPON ASTM TEST DESIGNATION D1557. FIELD DENSITY TEST WILL BE PERFORMED IN ACCORDANCE WITH ASTM TEST DESIGNATION 2922 AND 3017. THE LOCATION AND FREQUENCY OF THE FIELD DENSITY TEST WILL BE AS DETERMINED BY THE SOIL ENGINEER. THE RESULTS OF THESE TEST AND COMPLIANCE WITH THE SPECIFICATIONS WILL BE THE BASIS UPON WHICH SATISFACTORY COMPLETION OF THE WORK WILL BE JUDGED BY THE SOIL ENGINEER. ALL CUT AND FILL SLOPES SHALL BE CONSTRUCTED AS SHOWN ON PLANS, BUT NO STEEPER THAN TWO (2) HORIZONTAL TO ONE (1) VERTICAL.
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SATISFACTORY COMPLETION OF ALL THE EARTHWORK IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS. NO DEVIATION FROM THESE SPECIFICATIONS SHALL BE MADE EXCEPT UPON WRITTEN APPROVAL BY THE SOILS ENGINEER. BOTH CUT AND FILL AREAS SHALL BE SURFACE COMPLETED TO THE SATISFACTION OF THE SOILS ENGINEER AT THE CONCLUSION OF ALL GRADING OPERATIONS AND PRIOR TO FINAL ACCEPTANCE. THE CONTRACTOR SHALL NOTIFY THE SOILS ENGINEER AT LEAST TWO (2) WORKING DAYS PRIOR TO DOING ANY SITE GRADING AND EARTHWORK INCLUDING CLEARING.

#### CLEARING AND GRUBBING

- A. THE CONTRACTOR SHALL ACCEPT THE SITE IN ITS PRESENT CONDITION. ALL EXISTING PUBLIC IMPROVEMENTS SHALL BE PROTECTED, ANY IMPROVEMENTS DAMAGED SHALL BE REPLACED BY THE CONTRACTOR AS DIRECTED BY THE LOCAL JURISDICTION WITH NO EXTRA COMPENSATION.
- B. ALL ABANDONED BUILDINGS AND FOUNDATIONS, TREE (EXCEPT THOSE SPECIFIED TO REMAIN FOR LANDSCAPING PURPOSES), FENCES, VEGETATION AND ANY SURFACE DEBRIS SHALL BE REMOVED AND DISPOSED OF OFF THE SITE BY THE CONTRACTOR.
- C. ALL ABANDONED SEPTIC TANKS AND ANY OTHER SUBSURFACE STRUCTURES EXISTING IN PROPOSED DEVELOPMENT AREAS SHALL BE REMOVED PRIOR TO ANY GRADING OR FILL OPERATION. ALL APPURTENANT DRAIN FIELDS AND OTHER CONNECTING LINES MUST ALSO BE TOTALLY REMOVED.
- D. ALL ABANDONED UNDERGROUND IRRIGATION OR UTILITY LINES SHALL BE REMOVED OR DEMOLISHED. THE APPROPRIATE FINAL DISPOSITION OF SUCH LINES DEPEND UPON THEIR DEPTH AND LOCATION AND THE METHOD OF REMOVAL OR DEMOLITION SHALL BE DETERMINED BY THE SOILS ENGINEER. ONE OF THE FOLLOWING METHODS WILL BE USED:
  - (1) EXCAVATE AND TOTALLY REMOVE THE UTILITY LINE FROM THE TRENCH.
  - (2) EXCAVATE AND CRUSH THE UTILITY LINE IN THE TRENCH.
  - (3) CAP THE ENDS OF THE UTILITY LINE WITH CONCRETE TO PREVENT THE ENTRANCE OF WATER. THE LOCATIONS AT WHICH THE UTILITY LINE WILL BE CAPPED WILL BE DETERMINED BY THE UTILITY DISTRICT ENGINEER. THE LENGTH OF THE CAP SHALL NOT BE LESS THAN FIVE FEET, AND THE CONCRETED MIX EMPLOYED SHALL HAVE MINIMUM SHRINKAGE.

#### SITE PREPARATION AND STRIPPING

- A. ALL SURFACE ORGANICS SHALL BE STRIPPED AND REMOVED FROM BUILDING PADS, AREAS TO RECEIVE COMPACTED FILL AND PAVEMENT AREAS.
- B. UPON THE COMPLETION OF THE ORGANIC STRIPPING OPERATION, THE GROUND SURFACE (NATIVE SOIL SUBGRADE) OVER THE ENTIRE AREA OF ALL BUILDING PADS. STREET AND PAVEMENT AREAS AND ALL AREAS TO RECEIVE COMPACTED FILL SHALL BE PLOWED OR SCARIFIED UNTIL THE SURFACE IS FREE ( RUTS, HUMMOCKS OR OTHER UNEVEN FEATURES WHICH MAY INHIBIT UNIFORM SOIL COMPACTION. THE GROUND SURFACE SHALL THEN BE DISCED OR BLADED TO A DEPTH OF AT LEAST 6 INCHES. UPON ENGINEER'S SATISFACTION. THE NEW SURFACE SHALL BE WATER CONDITIONED AND RECOMPACTED PER REQUIREMENTS FOR COMPACTING FILL MATERIAL.

### **EXCAVATION**

- A. UPON COMPLETION OF THE CLEARING AND GRUBBING. SITE PREPARATION AND STRIPPING. THE CONTRACTOR SHALL MAKE EXCAVATIONS TO LINES AND GRADES NOTED ON THE PLAN. WHERE REQUIRED BY THE SOILS ENGINEER. UNACCEPTABLE NATIVE SOILS OR UNENGINEERED FILL SHALL BE OVER EXCAVATED BELOW THE DESIGN GRADE. SEE PROJECT SOILS REPORT FOR DISCUSSION OF OVER EXCAVATION OF THE UNACCEPTABLE MATERIAL. RESULTING GROUND LINE SHALL BE SCARIFIED. MOISTURE-CONDITIONED AND RECOMPACTED AS SPECIFIED IN SECTION 4 OF THESE SPECIFICATIONS. COMPACTED FILL MATERIAL SHALL BE PLACED TO BRING GROUND LEVEL BACK TO DESIGN GRADE.
- B. EXCAVATED MATERIALS SUITABLE FOR COMPACTED FILL MATERIAL SHALL BE UTILIZED IN MAKING THE REQUIRED COMPACTED FILLS. THOSE NATIVE MATERIALS CONSIDERED UNSUITABLE BY THE SOILS ENGINEER SHALL BE DISPOSED OF OFF THE SITE BY THE CONTRACTOR.

#### PLACING. SPREADING AND COMPACTING FILL MATERIAL

the materials proposed for use as compacted fill shall be approved by the soils engineer BEFORE COMMENCEMENT OF GRADING OPERATIONS. THE NATIVE MATERIAL IS CONSIDERED SUITABLE FOR FILL; HOWEVER, ANY NATIVE MATERIAL DESIGNATED UNSUITABLE BY THE SOILS ENGINEER SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR. ANY IMPORTED MATERIAL SHALL BE APPROVED FOR use by the soils engineer, in writing, before being imported to the site and shall possess sufficient fines to provide a competent soil matrix and shall be free of vegetative and ORGANIC MATTER AND OTHER DELETERIOUS MATERIALS. ALL FILL VOIDS SHALL BE FILLED AND PROPERLY COMPACTED. NO ROCKS LARGER THAN THREE INCHES IN DIAMETER SHALL BE PERMITTED.

#### B. FILL CONSTRUCTION

THE SOILS ENGINEER SHALL APPROVE THE NATIVE SOIL SUBGRADE BEFORE PLACEMENT OF ANY COMPACTED FILL MATERIAL. UNACCEPTABLE NATIVE SOIL SHALL BE REMOVED AS DIRECTED BY THE SOILS ENGINEER. THE RESULTING GROUND LINE SHALL BE SCARIFIED MOISTURE CONDITIONED AND RECOMPACTED AS SPECIFIED IN SECTION 4 OF THESE SPECIFICATIONS. COMPACTED FILL MATERIAL SHALL BE PLACED TO BRING GROUND LEVEL BACK TO DESIGN GRADE. GROUND PREPARATION SHALL BE FOLLOWED CLOSELY BY FILL PLACEMENT TO PREVENT DRYING OUT OF THE SUBSOIL BEFORE PLACEMENT of the fill.

THE APPROVED FILL MATERIALS SHALL BE PLACED IN UNIFORM HORIZONTAL LAYERS NO THICKER THAN 8" IN LOOSE THICKNESS. LAYERS SHALL BE SPREAD EVENLY AND SHALL BE THOROUGHLY BLADE MIXED DURING THE SPREADING TO ENSURE UNIFORMITY OF MATERIAL IN EACH LAYER. THE SCARIFIED SUBGRADE AND FILL MATERIAL SHALL BE MOISTURE CONDITIONED TO AT LEAST OPTIMUM MOISTURE. when the moisture content of the fill is below that specified, water shall be added until THE MOISTURE DURING THE COMPACTION PROCESS. WHEN THE MOISTURE CONTENT OF THE FILL IS above that specified, the fill material shall be aerated by blading or other satisfactory METHODS UNTIL THE MOISTURE CONTENT IS AS SPECIFIED.

AFTER EACH LAYER HAS BEEN PLACED, MIXED, SPREAD EVENLY AND MOISTURE CONDITIONED, IT SHALL BE COMPACTED TO AT LEAST THE SPECIFIED DENSITY.

THE FILL OPERATION SHALL BE CONTINUED IN COMPACTED LAYERS AS SPECIFIED ABOVE UNTIL THE FILL HAS BEEN BROUGHT TO THE FINISHED SLOPES AND GRADES AS SHOWN ON THE PLANS. NO LAYER SHALL BE ALLOWED TO DRY OUT BEFORE SUBSEQUENT LAYERS ARE PLACED.

COMPACTION EQUIPMENT SHALL BE OF SUCH DESIGN THAT IT WILL BE ABLE TO COMPACT THE FILL TO THE SPECIFIED MINIMUM COMPACTION WITHIN THE SPECIFIED MOISTURE CONTENT RANGE. COMPACTION OF EACH LAYER SHALL BE CONTINUOUS OVER ITS ENTIRE AREA UNTIL THE REQUIRED MINIMUM DENSITY HAS BEEN OBTAINED.

#### CUT OR FILL SLOPES

all constructed slopes, both cut and fill, shall be no steeper than 2 to 1 (horizontal TO VERTICAL). DURING THE GRADING OPERATION, COMPACTED FILL SLOPES SHALL BE OVERFILLED BY AT LEAST ONE FOOT HORIZONTALLY AT THE COMPLETION OF THE GRADING OPERATIONS, THE EXCESS FILL EXISTING ON THE SLOPES SHALL BE BLADED OFF TO CREATE THE FINISHED SLOPE EMBANKMENT. all cut and fill slopes shall be track walked after being brought to finish grade and then be planted with erosion control slope planting. The soils engineer shall review all CUT SLOPES TO DETERMINE IF ANY ADVERSE GEOLOGIC CONDITIONS ARE EXPOSED. IF SUCH CONDITIONS DO OCCUR, THE SOILS ENGINEER SHALL RECOMMEND THE APPROPRIATE MITIGATION MEASURES AT THE TIME OF THEIR DETECTION.

#### 8. SEASONAL LIMITS AND DRAINAGE CONTROL

FILL MATERIALS SHALL NOT BE PLACED, SPREAD OR COMPACTED WHILE IT IS AT AN UNSUITABLY HIGH MOISTURE CONTENT OR DURING OTHERWISE UNFAVORABLE CONDITIONS. WHEN THE WORK IS Interrupted for any reason the fill operations shall not be resumed until field test PERFORMED BY THE SOILS ENGINEER INDICATE THAT THE MOISTURE CONDITIONS IN AREAS TO BE FILLED ARE AS PREVIOUSLY SPECIFIED. ALL EARTH MOVING AND WORKING OPERATIONS SHALL BE CONTROLLED TO PREVENT WATER FROM RUNNING INTO EXCAVATED AREAS. ALL EXCESS WATER SHALL BE PROMPTLY REMOVED AND THE SITE KEPT DRY.

#### DUST CONTROL

the contractor shall take all steps necessary for the alleviation or prevention of any DUST NUISANCE ON OR ABOUT THE SITE CAUSED BY THE CONTRACTOR'S OPERATION EITHER DURING THE PERFORMANCE OF THE GRADING OR RESULTING FROM THE CONDITION IN WHICH THE CONTRACTOR LEAVES THE SITE, THE CONTRACTOR SHALL ASSUME ALL LIABILITY INCLUDING COURT COST OF CO-DEFENDANTS FOR ALL CLAIMS RELATED TO DUST OR WIND-BLOWN MATERIALS ATTRIBUTABLE TO HIS WORK. COST FOR THIS ITEM OF WORK IS TO BE INCLUDED IN THE EXCAVATION ITEM AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

### 10. INDEMNITY

the contractor will hold harmless, indemnify and defend the engineer. The owner and his CONSULTANTS AND EACH OF THEIR OFFICERS AND EMPLOYEES AND AGENTS, FROM ANY AND ALL LIABILITY CLAIMS, LOSSES OR DAMAGE ARISING OR ALLEGED TO HEREIN, BUT NOT INCLUDING THE SOLE NEGLIGENCE OF THE OWNER, THE ARCHITECT, THE ENGINEER AND HIS CONSULTANTS AND EACH OF THEIR OFFICERS AND EMPLOYEES AND AGENTS.

### 11. SAFETY

IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES. THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE. INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.

THE DUTY OF THE ENGINEERS TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES, IN, ON OR NEAR THE CONSTRUCTION SITE.

#### 12. GUARANTEE

ieither the final payment, nor the provisions in the contract, nor partial, nor entire use OR OCCUPANCY OF THE PREMISES BY THE OWNER SHALL CONSTITUTE AN ACCEPTANCE OF THE WORK NOT DONE IN ACCORDANCE WITH THE CONTRACT OR RELIEVES THE CONTRACTOR OF LIABILITY IN RESPECT TO ANY EXPRESS WARRANTIES OR RESPONSIBILITY FOR FAULTY MATERIAL OR WORKMANSHIP.

the contractor shall remedy any defects in work and pay for any damage to other work RESULTING THERE FROM WHICH SHALL APPEAR WITHIN A PERIOD OF ONE (1) CALENDAR YEAR FROM THE DATE OF FINAL ACCEPTANCE OF THE WORK.

#### TRENCH BACKFILL

either the on—site inorganic soil or approved imported soil may be used as trench BACKFILL. THE BACKFILL MATERIAL SHALL BE MOISTURE CONDITIONED PER THESE SPECIFICATIONS AND SHALL BE PLACED IN LIFTS OF NOT MORE THAN SIX INCHES IN HORIZONTAL UNCOMPACTED LAYERS and be compacted by Mechanical Means to a minimum of 90% relative compaction. Imported SAND MAY BE USED FOR TRENCH BACKFILL MATERIAL PROVIDED IT IS COMPACTED TO AT LEAST 90% relative compaction. Water jetting associated with compaction using vibratory equipment WILL BE PERMITTED ONLY WITH IMPORTED SAND BACKFILL WITH THE APPROVAL OF THE SOILS ENGINEER. ALL PIPES SHALL BE BEDDED WITH SAND EXTENDING FROM THE TRENCH BOTTOM TO TWELVE INCHES ABOVE THE PIPE. SAND BEDDING IS TO BE COMPACTED AS SPECIFIED ABOVE FOR SAND

#### EROSION CONTROL

- A. ALL GRADING. EROSION AND SEDIMENT CONTROL AND RELATED WORK UNDERTAKEN ON THIS SITE IS SUBJECT TO ALL TERMS AND CONDITIONS OF THE COUNTY GRADING ORDINANCE AND MADE A PART HEREOF BY REFERENCE.
- B. THE CONTRACTOR WILL BE LIABLE FOR ANY AND ALL DAMAGES TO ANY PUBLICLY OWNED AND MAINTAINED ROAD CAUSED BY THE AFORESAID CONTRACTOR'S GRADING ACTIVITIES, AND SHALL BE RESPONSIBLE FOR THE CLEANUP OF ANY MATERIAL SPILLED ON ANY PUBLIC ROAD ON THE HAUL ROUTE.
- C. THE EROSION CONTROL MEASURES ARE TO BE OPERABLE DURING THE RAINY SEASON, GENERALLY FROM OCTOBER FIRST TO APRIL FIFTEENTH, EROSION CONTROL PLANTING IS TO BE COMPLETED BY OCTOBER FIRST. NO GRADING OR UTILITY TRENCHING SHALL OCCUR BETWEEN OCTOBER FIRST AND APRIL FIFTEENTH UNLESS AUTHORIZED BY THE LOCAL JURISDICTION.
- D. ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED AND CHANGES TO THIS EROSION AND SEDIMENT CONTROL PLAN SHALL BE MADE TO MEET FIELD CONDITIONS ONLY WITH THE APPROVAL OF OR AT THE DIRECTION OF THE SOILS ENGINEER.
- E. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT—LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM.
- F. ALL EROSION CONTROL FACILITIES MUST BE INSPECTED AND REPAIRED AT THE END OF EACH WORKING DAY DURING THE RAINY SEASON.
- G. WHEN NO LONGER NECESSARY AND PRIOR TO FINAL ACCEPTANCE OF DEVELOPMENT. SEDIMENT BASINS SHALL BE REMOVED OR OTHERWISE DEACTIVATED AS REQUIRED BY THE LOCAL JURISDICTION.
- H. A CONSTRUCTION ENTRANCE SHALL BE PROVIDED AT ANY POINT OF EGRESS FROM THE SITE TO ROADWAY. A CONSTRUCTION ENTRANCE SHOULD BE COMPOSED OF COARSE DRAIN ROCK (2" TO 3") MINIMUM DIAMETER) AT LEAST EIGHT INCHES THICK BY FIFTY (50) FEET LONG BY TWENTY (20) FEET WIDE UNLESS SHOWN OTHERWISE ON PLAN AND SHALL BE MAINTAINED UNTIL THE SITE IS PAVED.
- I. ALL AREAS SPECIFIED FOR HYDROSEEDING SHALL BE NOZZLE PLANTED WITH STABILIZATION MATERIAL CONSISTING OF FIBER, SEED, FERTILIZER AND WATER, MIXED AND APPLIED IN THE FOLLOWING

SEED, 200 LBS/ACRE (SEE NOTE J, BELOW) FERTILIZER (11-8-4), 500 LBS/ACRE WATER, AS REQUIRED FOR APPLICATION

- J. SEED MIX SHALL BE PER CALTRANS STANDARDS.
- K. WATER UTILIZED IN THE STABILIZATION MATERIAL SHALL BE OF SUCH QUALITY THAT IT WILL PROMOTE GERMINATION AND STIMULATE GROWTH OF PLANTS. IT SHALL BE FREE OF POLLUTANT MATERIALS AND
- L. HYDROSEEDING SHALL CONFORM TO THE PROVISIONS OF SECTION 20. EROSION CONTROL AND HIGHWAY PLANTING". OF THE STANDARD SPECIFICATIONS OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED.
- M. A DISPERSING AGENT MAY BE ADDED TO THE HYDROSEEDING MATERIAL. PROVIDED THAT THE CONTRACTOR FURNISHES SUITABLE EVIDENCE THAT THE ADDITIVE WILL NOT ADVERSELY AFFECT THE PERFORMANCE OF THE SEEDING MIXTURE.
- N. STABILIZATION MATERIALS SHALL BE APPLIED AS SOON AS PRACTICABLE AFTER COMPLETION OF GRADING OPERATIONS AND PRIOR TO THE ONSET OF WINTER RAINS, OR AT SUCH OTHER TIME AS DIRECTED BY THE COUNTY ENGINEER. THE MATERIAL SHALL BE APPLIED BEFORE INSTALLATION OF OTHER LANDSCAPING MATERIALS SUCH AS TREES, SHRUBS AND GROUND COVERS.
- O. THE STABILIZATION MATERIAL SHALL BE APPLIED WITHIN 4-HOURS AFTER MIXING. MIXED MATERIAL NOT USED WITHIN 4-HOURS SHALL BE REMOVED FROM THE SITE.
- P. THE CONTRACTOR SHALL MAINTAIN THE SOIL STABILIZATION MATERIAL AFTER PLACEMENT. THE COUNTY ENGINEER MAY REQUIRE SPRAY APPLICATION OF WATER OR OTHER MAINTENANCE ACTIVITIES TO ASSURE THE EFFECTIVENESS OF THE STABILIZATION PROCESS. APPLICATION OF WATER SHALL BE ACCOMPLISHED USING NOZZLES THAT PRODUCE A SPRAY THAT DOES NOT CONCENTRATE OR WASH AWAY THE STABILIZATION MATERIALS.

### 15. CLEANUP

THE CONTRACTOR MUST MAINTAIN THE SITE CLEAN, SAFE AND IN USABLE CONDITION. ANY SPILLS OF SOIL. ROCK OR CONSTRUCTION MATERIAL MUST BE REMOVED FROM THE SITE BY THE CONTRACTOR DURING CONSTRUCTION AND UPON COMPLETION OF THE PROJECT. COST FOR THIS ITEM OF WORK SHALL BE INCLUDED IN THE EXCAVATION AND COMPACTION ITEM AND NO ADDITIONAL COMPENSATION SHALL

> NOTE:
> THESE NOTES ARE INTENDED TO BE USED AS A GENERAL GUIDELINE. THE REFERENCED SOILS REPORT FOR THE PROJECT AND GOVERNING AGENCY GRADING ORDINANCE SHALL SUPERSEDE THESE NOTES. THE SOILS ENGINEER MAY MAKE ON-SITE RECOMMENDATIONS DURING GRADING OPERATIONS.



OF 10 SHEETS

DESIGN BY: ZA

CHECKED BY: XX

SHEET NO:

### **PURPOSE:**

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.

### **EROSION CONTROL NOTES:**

- 1. IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- 2. THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
- 3. OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- 4. SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT—LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- 6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- 7. CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- 8. ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
- 9. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
- 10. IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- 12. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- 13. MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- 14. EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 15TH.
- 15. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM **OCTOBER 15 THROUGH APRIL 15.** WHICHEVER IS GREATER.
- 16. PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
- 17. THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN SYSTEMS.
- 18. THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 19. THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION, METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN RIGHT—OF—WAY.
- 20. SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT—OF—WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 21. THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL LANDSCAPING.
- 22. STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPAULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
- 23. EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAYOR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
- 24. TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND

### EROSION CONTROL NOTES CONTINUED:

- 24. FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM,
- 25. DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE
- 26. SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES, FOLLOWING AND DURING ALL RAIN EVENTS. TO PUBLIC OWNED FACILITIES.

#### EROSION CONTROL MEASURES:


- 1. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- 2. SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- 3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- 4. ALL EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE—STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
- 5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- 6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- 7. THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
- 8. STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURES SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

### REFERENCES:

- 1. CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- 2. CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

### PERIODIC MAINTENANCE:

- 1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
  - A. DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
  - B. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS
  - C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
  - D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
  - E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- F. RILLS AND GULLIES MUST BE REPAIRED.
- 2. GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- 3. STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- 4. SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- 5. CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- 6. ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION



EROSION CONTROL LEGEND


GRAVEL BAG

INLET PROTECTION

STRAW ROLL

— X——— SILT FENCE






CONSTRUCTION ENTRANCE



TREE PROTECTION

SEAL ALL OTHER INLETS NOT INTENDED TO ACCEPT STORM WATER AND DIRECT FLOWS TEMPORARILY TO FUNCTIONAL SEDIMENTATION BASIN INLETS. —TYP

INSTALLATION NOTE:
EROSION CONTROL MEASURES SHALL
BE INSTALLED PRIOR TO DEMOLITION.



LAND SURVEYORS
EGIONAL OFFICES:
OSEVILLE
UBLIN
AN JOSE

LEA & BRAZE ENGINEER
CIVIL ENGINEERS I LAND SU

CIVIL ENGINEERS

AIN OFFICE:

195 INDUSTRIAL PKWY WEST

AYWARD, CALIFORNIA 94545

TE

MAIN OFFICE:

2495 INDUSTRIAL
HAYWARD, CALIF

PALKHARE RESIDENCE 62 RIVERSIDE DRIVE S ALTOS, CALIFORNIA

ROSION CONTROL


 $\Box$ 

SHEET NO:

8 OF 10 SHEETS

DESIGN BY: ZA

CHECKED BY: JT





BRAZE


RESIDENCE DE DRIVE CALIFORNIA

ION ERO

PLAN CHECK #1 03-18-24 REVISIONS 12-13-23

JOB NO: 2221914 AS NOTED DESIGN BY: ZA CHECKED BY: JT

9 OF 10 SHEETS



#### **Best Management Practices for the**

- Site supervisors
- General contractors Home builders

Developers

#### from Heavy Equipment on Construction Sites Vehicle and equipment operators

Poorly maintained vehicles and heavy equipment that leak fuel, oil, antifreeze or other fluids on the construction site are common sources of storm drain pollution. Prevent spills and leaks by isolating equipment from runof channels, and by watching for leaks and other

Doing The Right Job

during dry weather

control for any site

hazardous waste.

and compost.

### Doing the Job Right

Site Planning and Preventive Vehicle

Maintain all vehicles and heavy equipment. nspect frequently for and repair leaks. Perform major maintenance, repair jobs, and

Cover exposed fifth wheel hitches and other oily

Storm water Pollution

maintenance problems. Remove construction

equipment from the site as soon as possible

Schedule grading and excavation projects

runoff away from storm drains.

Landscaping/Garden Maintenance

Use pesticides sparingly, according to

instructions on the label. Rinse empty

containers, and use rinse water as produc

Dispose of rinsed, empty containers in the

trash. Dispose of unused pesticides as

Collect lawn and garden clippings, pruning

☐ In communities with curbside pick-up of yard

to a landfill that composts vard waste. No

Use temporary check dams or ditches to divert

Protect storm drains with sandbags or other

Re-vegetation is an excellent form of erosion

or greasy equipment during rain events.

cleanup is easier.

impermeable surfaces where fluids have vehicle and equipment washing off site where spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags) whenever possible and properly If you must drain and replace motor oil, radiator dispose of absorbent materials. coolant, or other fluids on site, use drip pans or drop cloths to catch drips and spills. Collect all Sweep up spilled dry materials

Spill Cleanup

- spent fluids, store in separate containers, and immediately. Never attempt to "wash properly dispose as hazardous waste (recycle them away" with water, or bury them
- ☐ Use as little water as possible for dust Do not use diesel oil to lubricate equipment control. Ensure water used doesn't parts, or clean equipment. Use only water for leave silt or discharge to storm drains. any onsite cleaning.
  - Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.

Clean up spills immediately when they

■ Never hose down "dirty" pavement or

- Report significant spills to the appropriate local spill response agencies immediately.
- If the spill poses a significant hazard to

## Roadwork **Paving**

Best Management Practices for the Construction Industry



- human health and safety, property or the environment, you must also report it to the State Office of Emergency

#### **Best Management Practices for the** Road crews

- Driveway/sidewalk/parking lot construction Seal coat contractors
- · Operators of grading equipment, paving machines, dump trucks, concrete mixers
- Construction inspectors General contractors Home builders

Developers

## **Doing The Job Right**

#### General Business Practices

- Develop and implement erosion/sediment control plans for roadway embankments. Schedule excavation and grading work during
- Check for and repair leaking equipment. Perform major equipment repairs at designated
- areas in your maintenance yard, where cleanup is easier. Avoid performing equipment repairs at construction sites ☐ When refueling or when vehicle/equipment
- maintenance must be done on site, designate a location away from storm drains and creeks. properly dispose of contaminated soil.
- parts or clean equipment. Recycle used oil, concrete, broken asphalt, etc. whenever possible, or dispose of properly.

☐ Do not use diesel oil to lubricate equipment

### **During Construction**

- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent fresh materials from contacting stormwater runoff.
- when applying seal coat, slurry seal, fog seal or similar materials. Protect drainage ways by using earth dikes, sand bags, or other controls to divert or trap

Cover and seal catch basins and manholes

#### Storm Drain Pollution from Roadwork

Road paving, surfacing, and pavement removal happen right in the street, where there are numerous opportunities for asphalt, saw-cut slurry, or excavated material to illegally enter storm drains. Extra planning is required to store and dispose of materials properly and guard against pollution of storm drains, creeks, and the Bay.

Keep all liquid paint products and wastes

solvents, glues, and cleaning fluids are

away from the gutter, street, and storm

drains. Liquid residues from paints, thinners

hazardous wastes and must be disposed of at

a hazardous waste collection facility (contact

your local stormwater program listed on the

disposed of as garbage in a sanitary landfill.

☐ Wash water from painted buildings constructed

begin stripping paint or cleaning pre-1978

pressure, test paint for lead by taking paint

scrapings to a local laboratory. See Yellow

☐ If there is loose paint on the building, or if the

Check with the wastewater treatment plant to

Storm Drain Pollution from

Paints, Solvents, and Adhesives

creeks, San Francisco Bay, and the Pacific Ocean

Toxic chemicals may come from liquid or solid

All paints, solvents, and adhesives contain

chemicals that are harmful to wildlife in local

the sanitary sewer, or if you must send it offsite

Pages for a state-certified laboratory.

or disposal as hazardous waste.

building exteriors with water under high

Empty, dry paint cans also may be recycled as

before 1978 can contain high amounts of lead,

even if paint chips are not present. Before you

■ When thoroughly dry, empty paint cans, used

brushes, rags, and drop cloths may be

**Doing The Job Right** 

**Handling Paint Products** 

back of this brochure).

#### Never wash excess material from exposed- aggregate concrete or similar reatments into a street or storm drain Collect and recycle, or dispose to dirt

- Cover stockpiles (asphalt, sand, etc.) and other construction materials with
- plastic tarps. Protect from rainfall and prevent runoff with temporary roofs or plastic sheets and berms. Park paving machines over drip pans or
- absorbent material (cloth, rags, etc.) to catch drips when not in use. Clean up all spills and leaks using "dry" methods (with absorbent materials and/or rags), or dig up, remove, and
- Collect and recycle or appropriately dispose of excess abrasive gravel or Avoid over-application by water trucks

Avoid creating excess dust when breaking asphalt or concrete. After breaking up old pavement, be sure

Asphalt/Concrete Removal

**Painting Cleanup** 

Paint Removal

- to remove all chunks and pieces. Make sure broken pavement does not come in contact with rainfall or runoff. ■ When making saw cuts, use as little
- water as possible. Shovel or vacuum saw-cut slurry and remove from the site Cover or protect storm drain inlets during saw-cutting. Sweep up, and properly dispose of, all residues.

□ Never clean brushes or rinse paint

drain, French drain, or stream.

☐ For water-based paints, paint out

containers into a street, gutter, storm

brushes to the extent possible, and rinse

into a drain that goes to the sanitary

sewer. Never pour paint down a storm

For oil-based paints, paint out brushes to

the extent possible and clean with thinne

reuse thinners and solvents. Dispose of

excess liquids and residue as hazardous

Paint chips and dust from non-hazardous

and disposed of as trash.

dry stripping and sand blasting may be

☐ Chemical paint stripping residue and chips

and dust from marine paints or paints

containing lead, mercury or tributyl tin

Lead based paint removal requires a

exteriors with high-pressure water, block

storm drains. Direct wash water onto a dir

area and spade into soil. Or, check with

the local wastewater treatment authority to

find out if you can collect (mon or vacuum

building cleaning water and dispose to the

sanitary sewer. Sampling of the water may

treatment authority in making its decision.

be required to assist the wastewater

☐ Recycle or donate excess water-based

Reuse leftover oil-based paint. Dispose

of non-recyclable thinners, sludge and

unwanted paint, as hazardous waste.

Unopened cans of paint may be able to be

returned to the paint vendor. Check with the vendor regarding its "buy-back" policy.

(latex) paint, or return to supplier.

Recycle/Reuse Leftover Paints

Whenever Possible

■ When stripping or cleaning building

swept up or collected in plastic drop cloths

must be disposed of as hazardous wastes.

or solvent in a proper container. Filter and

Sweep, never hose down streets to clean up tracked dirt. Use a street sweeper or vacuum truck. Do not dump vacuumed liquor in storm drains.

**Fresh Concrete** 

Best Management Practices for the

and Mortar

**Application** 

Construction Industry

- Best Management Practices for the Masons and bricklayers
- Sidewalk construction crews
- Patio construction workers Construction inspectors
- General contractors

Home builders

Developers

### Concrete delivery/pumping workers

#### **Doing The Job Right**

#### **General Business Practices**

- Wash out concrete mixers only in designated wash-out areas in your vard, away from storm drains and waterways, where the water will flow into a temporary waste pit in a dirt area. Let water percolate through soil and dispose of settled, hardened concrete as garbage Whenever possible, recycle washout by
- pumping back into mixers for reuse. ☐ Wash out chutes onto dirt areas at site that do not flow to streets or drains
- ☐ Always store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Protect dry materials from wind.
- Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from streets, gutters, storm drains, rainfall, and
- Do not use diesel fuel as a lubricant on concrete forms, tools, or trailers.

## Storm Drain Pollution from Fresh

Fresh concrete and cement-related mortars that wash into lakes, streams, or estuaries are toxic to fish and the aquatic environment. Disposing of these materials to the storm drains or creeks can block storm drains, causes serious problems, and is prohibited by law.

**Concrete and Mortar Applications** 

#### **During Construction**

- Don't mix up more fresh concrete or cement than you will use in a two-hour
- Set up and operate small mixers on

dirt areas, not down the driveway or into

- tarps or heavy plastic drop cloths. ☐ When cleaning up after driveway or sidewalk construction, wash fines onto
- ☐ Protect applications of fresh concrete and mortar from rainfall and runoff until the material has dried.

the street or storm drain.

- Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) be vacuumed from a catchment created by blocking a storm drain inlet. If necessary, divert runoff with temporary berms. Make sure runoff does not reach gutters or storm drains.
- ☐ When breaking up pavement, be sure to pick up all the pieces and dispose of properly. Recycle large chunks of broken concrete at a landfill.
- Never bury waste material. Dispose of small amounts of excess dry concrete,
- Never dispose of washout into the street, storm drains, drainage ditches, or

grout, and mortar in the trash.

## **Preventing Pollution:** It's Up to Us

In the Santa Clara Valley, storm drains transport water directly to local creeks and San Francisco Bay without treatment. Storm water pollution is a serious problem for wildlife dependent on our waterways and for the people who live near polluted streams or bay lands. Some common sources of this pollution include spilled oil, fuel, and fluids from vehicles and heavy equipment; construction debris; sediment created by erosion; landscaping runoff containing pesticides or weed killers; and materials such as used motor oil. antifreeze, and paint products that people pour or spill into a street or storm drain.

Thirteen valley municipalities have joined together with Santa Clara County and the Santa Clara Valley Water District to educate local residents and businesses and fight storm water pollution. TO comply with this program, contractors most comply with the practices described this drawing sheet.

### Spill Response Agencies

DIAL 9-1-1

State Office of Emergency Services Warning Center (24 hours) 800-852-7550 Santa Clara County Environmental Health Services: (408) 299-6930

#### Local Pollution Control Agencies

County of Santa Clara Pollution Prevention (408) 441-1195 County of Santa Clara Integrated Waste

Management Program: (408) 441-1198 County of Santa Clara District Attorney Environmental Crimes Hotline:

(408) 299-TIPS

Santa Clara County 1-800-533-8414 Recycling Hotline:

Santa Clara Valley Water (408) 265-2600 Santa Clara Valley Water District Pollution

1-888-510-5151 Regional Water Quality Control Board San Francisco Bay Region: (510) 622-2300

Control Plant: (650) 329-2598 Serving East Palo Alto Sanitary District, Los Altos, Los Altos Hills, Mountain View, Palo Alto, Stanford

### City of Los Altos

Building Department: (650) 947-2752 Engineering Department: (650) 947-2780

## Landscaping, Gardening, and **Pool Maintenance**

#### Best Management Practices for the Construction Industry



- Gardeners
- Developers

Homeowners

#### **Best Management Practices for the** Landscapers

- General contractors
- Home builders

- Swimming pool/spa service and repair

## From Landscaping and

Many landscaping activities expose soils and ncrease the likelihood that earth and garden chemicals will run off into the storm drains during rrigation or when it rains. Swimming pool water containing chlorine and copper-based algaecides should never be discharged to storm drains. These chemicals are toxic to aquatic life.

## curbside pickup of yard waste is available for Storm Drain Pollution

waste, place clippings and pruning waste at the

curb in approved bags or containers. Or, take

Swimming Pool Maintenance

#### Do not blow or rake leaves, etc. into the **General Business Practices** street, or place yard waste in gutters or on Protect stockpiles and landscaping materials dirt shoulders, unless you are piling them for recycling (allowed by San Jose and from wind and rain by storing them under tarps unincorporated County only). Sweep up or secured plastic sheeting. any leaves, litter or residue in gutters or on ☐ Store pesticides, fertilizers, and other chemicals indoors or in a shed or storage

In San Jose, leave yard waste for curbside recycling pickup in piles in the street, 18 inches from the curb and completely out of the flow line to any storm drain.

Pool/Fountain/Spa Maintenance **Draining Pools Or Spas** When it's time to drain a pool, spa, or fountain, please be sure to call your local wastewater reatment plant before you start for further

prevention, and handling special cleaning waste (such as acid wash). Discharge flows shall not exceed 100 gallon per minute. Never discharge pool or spa water to a street or storm drain; discharge to a

quidance on flow rate restrictions, backflow

- sanitary sewer cleanout. If possible, when emptying a pool or spa. let chlorine dissipate for a few days and then recycle/reuse water by draining it gradually onto a landscaped area. Do not use copper-based algaecides.
- alternatives, such as sodium bromide. Never clean a filter in the street or near a storm drain. Rinse cartridge and diatomaceous earth filters onto a dirt area, and spade filter residue into soil. Dispose

Control algae with chlorine or other

of spent diatomaceous earth in the If there is no suitable dirt area, call your local wastewater treatment plant for instructions on discharging filter backwash or rinse water to the sanitary sewer.

Clean up leaks, drips and other spills

mmediately so they do not contaminate

soil or groundwater or leave residue on

paved surfaces. Use dry cleanup methods

whenever possible. If you must use water,

frequently for leaks. Place dumpsters under

roofs or cover with tarps or plastic sheeting

dumpster. Never clean out a dumpster by

hosing it down on the construction site.

Set portable toilets away from storm drains.

Make sure portable toilets are in good

working order. Check frequently for leaks.

maintenance materials such as used oil.

antifreeze, batteries, and tires.

Dispose of all wastes properly. Many

construction materials and wastes,

ncluding solvents, water-based paints

wood, and cleared vegetation can be

vehicle fluids, broken asphalt and concrete,

recycled. Materials that cannot be recycled

must be taken to an appropriate landfill or

disposed of as hazardous waste. Never

bury waste materials or leave them in the

Quality Control Board.

use just enough to keep the dust down.

Cover and maintain dumpsters. Check

secured around the outside of the

## Painting and **Application of** Solvents and

**Adhesives** Best Management Practices for the Construction Industry



## Best Management Practices for the

- Homeowners
- Painters Paperhangers Plasterers Graphic artists
- Dry wall crews Floor covering installers General contractors Home builders

Developers

#### products or from cleaning residues or rags. Paint material and wastes, adhesives and cleaning fluids should be recycled when possible, or disposed of properly to prevent these materials from flowing into storm drains and watercourses.

Best Management Practices for the



## Best Management Practices for the

- Dump truck drivers Site supervisors
- General contractors Home builders Developers

## Doing The Job Right

### dry weather. Perform major equipment repairs away from the

- location away from storm drains. ☐ Do not use diesel oil to lubricate equipment parts, or clean equipment
- absolutely necessary. Plant temporary vegetation for erosion control on slopes or where construction is not immediately planned and storm drains with wattles, or temporary drainage swales. Use check dams or ditches to divert runoff around excavations. Refer to

#### Storm Drain Pollution from Earth-Moving Activities and Dewatering

amounts of soil that can flow or blow into storn can clog storm drains, smother aquatic life, and destroy habitats in creeks and the Bay. Effective erosion control practices reduce the amount of runoff crossing a site and slow the flow with check dams or oughened ground surfaces

without treatment is prohibited.

When discharging to a storm drain, protect the inlet using a barrier of burlap bags filled with drain rock, or cover inlet with filter fabric anchored under the grate. OR pump water through a grassy swale prior to discharge.

#### Los Altos Municipal Code Requirements

- Los Altos Municipal Code Chapter 10.08.390 Non-storm water discharges Unlawful discharges. It shall be unlawful to discharge any domestic waste or industrial waste into storm drains, gutters, creeks, or San Francisco Bay. Unlawful discharges to storm drains shall include, but not be limited to, discharge from toilets; sinks; industria processes; cooling systems; boilers; fabric cleaning; equipment cleaning; vehicle cleaning; construction activities, including, but no limited to, painting, paving, concrete placement, saw cutting and grading; swimming pools; spas; and fountains, unless specifically
- permitted by a discharge permit or unless exempted pursuant to guidelines published by the superintendent. Threatened discharges. It shall be unlawful to cause hazardous materials, domestic waste, or industrial waste to be deposited in such a manner or location as to constitute a threatened discharge into storm drains, gutters, creeks or San Francisco Bay. A "threatened discharge" is a condition creating a substantial probability of harm, when the probability and potential extent of harm make it reasonably necessary to take immediate action to prevent, reduce or mitigate damages to persons, property or natural resources. Domestic or industrial wastes that are no longer contained in a pipe, tank or other container are considered to be threatened discharges unless they are actively being cleaned up.

- A spill response plan for hazardous waste, hazardous materials and uncontained construction materials shall be prepared and available at the construction sites for all projects where the proposed construction site is equal to or greater than one acre or disturbed soil and for any other projects for which the city engineer determines is necessary to protect surface waters. Preparation
- of the plan shall be in accordance with guidelines published by the city engineer. A storm water pollution prevention plan shall be prepared and available at the construction sites for all projects greater than on acre of disturbed soil and for any other projects for which the city engineer determines that a storm water management plan is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer. Prior approval shall be obtained from the city engineer or designee to discharge water pumped from construction sites to the storm drain. The city engineer or designee may require gravity settling and filtration upon a determination that either or both would
- discharge to navigable waters may not be discharged to the storm drain. Such water may be discharged to the sewer, provided that the requirements of Section 10.08.240 are met and the approval of the superintendent is obtained prior to discharge. D. No cleanup of construction debris from the streets shall result in the discharge of water to the storm drain system; nor shall an

- Los Altos Municipal Code Section 10.08.430 Requirements for construction operations
- construction debris be deposited or allowed to be deposited in the storm drain system. (Prior code § 5-5.643)

Criminal and judicial penalties can be assessed for non-compliance.

Palo Alto Regional Water Quality improve the water quality of the discharge. Contaminated groundwater or water that exceeds state or federal requirements for

## General Construction **And Site** Supervision

## For Construction

Best Management Practices

- Site supervisors Inspectors Home builders

subcontractors or employees.

General contractors

- Storm Drain Pollution from Construction Activities
- water pollution. Materials and wastes that blow o wash into a storm drain, gutter, or street have a direct impact on local creeks and the Bay. As a contractor, or site supervisor, owner o operator of a site, you may be responsible for any environmental damage caused by your

Construction sites are common sources of storm

Maintain equipment properly.

**Doing The Job Right** ☐ Keep an orderly site and ensure good housekeeping practices are used.

Cover materials when they are not in use.

Ensure dust control water doesn't leave site or discharge to storm drains. Advance Planning To Prevent Pollution Schedule excavation and grading activities for dry weather periods. To reduce soil erosion, plant temporary vegetation or place other

erosion controls before rain begins. Use the

☐ Keep materials away from streets, storm drains

- Control the amount of runoff crossing your site (especially during excavation!) by using berms or temporary or permanent drainage ditches to divert water flow around the site. Reduce storm water runoff velocities by constructing temporary check dams or berms where appropriate. Train your employees and subcontractors. Make these best management practices
- Good Housekeeping Practices Designate one area of the site for auto parking, vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets

available to everyone who works on the

contamination at the source. Cover exposed piles of soil or construction materials with plastic sheeting or temporary roofs. Before it rains, sweep and remove materials from surfaces that drain to storm drains, creeks, or channels. Keep pollutants off exposed surfaces.


Place trashcans and recycling receptacles

around the site to minimize litter.

- and drainage channels
- Materials/Waste Handling Erosion and Sediment Control Manual, available ☐ Practice Source Reduction -- minimize from the Regional Water Quality Control Board, waste when you order materials. Order as a reference. only the amount you need to finish the job Use recyclable materials whenever possible. Arrange for pick-up of recyclable materials such as concrete, asphalt, scrap metal, solvents, degreasers, cleared vegetation, paper, rock, and vehicle
- construction site. Inform subcontractors about the storm water requirements and their own
- street or near a creek or stream bed. bermed if necessary. Make major repairs of ☐ In addition to local building permits, you ☐ Keep materials out of the rain – prevent runoff will need to obtain coverage under the State's General Construction Activity Storm water Permit if your construction site disturbs one acre or more. Obtain nformation from the Regional Water

# **Earth-Moving** Dewatering

**Activities** 



- Bulldozer, back hoe, and grading machine

- General Business Practices ☐ Schedule excavation and grading work during
- When refueling or vehicle/equipment maintenance must be done on site, designate a
- **Practices During Construction** Remove existing vegetation only when Protect down slope drainage courses, streams

### the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control

soil excavation and grading operations loosen large drains when handled improperly. Sediments in runoff

Contaminated groundwater is a common problem in the Santa Clara Valley. Depending on soil types and site history, groundwater pumped from construction sites may be contaminated with toxics (such as oil or solvents) or laden with sediments. Any of these pollutants can harm wildlife in creeks or the Bay, or interfere with wastewater treatment plant operation. Discharging sediment-laden water from a dewatering site into any water of the state

#### Cover stockpiles and excavated soil with secured tarps or plastic sheeting. **Dewatering Operations** 1. Check for Toxic Pollutants

☐ Check for odors, discoloration, or an oily sheen on groundwater. Call your local wastewater treatment agency and ask whether the groundwater must be tested. If contamination is suspected, have the water tested by a certified laboratory.

Depending on the test results, you may be

to the storm drain (if no sediments

allowed to discharge pumped groundwate

less than 24 hours, and the flow rate is

less than 20 gallons per minute, you may

pump water to the street or storm drain.

- present) or sanitary sewer. OR, you may be required to collect and haul pumped groundwater offsite for treatment and disposal at an appropriate treatment Check for Sediment Levels If the water is clear, the pumping time is
- If the pumping time is more than 24 hours and the flow rate greater than 20 gpm, call your local wastewater treatment plan for guidance. If the water is not clear, solids must be


filtered or settled out by pumping to a

settling tank prior to discharge. Options


for filtering include: Pumping through a perforated pipe sunk part way into a small pit filled with gravel; Pumping from a bucket placed below water level using a submersible pump Pumping through a filtering device such as a swimming pool filter or filter fabric wrapped around end of suction

## Blueprint for a Clean Bay Remember: The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site. You may be held responsible for any environmental damage caused by your subcontractors or employees

**Best Management Practices for the Construction Industry** 



Santa Clara **Urban Runoff Pollution Prevention Program** 



DESIGNED BY: LARRY LIND	APPROVED BY:	Cľ	TY OF LOS ALTOS	DATE: OCTOBER, 2003
DRAWN BY: VICTOR CHEN	CITY ENGINEER	)	48056 R.C.E.	SCALE: N.T.S.
CHECKED BY: JIM GUSTAFSON	SHEET	OF	SHEETS	DRAWING NO:

ENGINEERING,

BRAZE

LEA

H DE 0 RE

0 > H C

PLAN CHECK #1 03-18-24 REVISIONS 2221914 JOB NO: DATE: 12-13-23


AS NOTED

DESIGN BY: ZA

CHECKED BY: JT


SHEET NO:


SCALE:



REVISIONS BY DESIGN REVIEW SBMTL Ø1/12/2024 PLNG. PLAN CHK Ø4/11/24 DVH PLNG. CMNTS. 2 12 06/26/24 DVH








REVISIONS BY DESIGN REVIEW SBMTL Ø1/12/2024 PLNG. PLAN CHK 04/11/24 DVH PLNG. CMNTS. 2 06/26/24 DVH









ITAGE ARCHITECTURE

OV. HERNANDEZ, ARCHITECT

X 8033, San Jose, California 95155

772-3502 VM: (408) 298-0998


Ivhernandez@pacbell.net

PIMPALKHARE RESIDENCE
962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024


RAWN: DVH

JOB NO. 2022.01 DATE: 01/10/2024

A1.3



ASSESSOR'S AERIAL VIEW NEIGHBORHOOD CONTEXT MAP



ASSESSOR'S PLATT MAP



LOT 27 962 RIVERSIDE DRIVE



LOT 5 965 RIVERSIDE DRIVE



LOT 16 640 COVINGTON ROAD



LOT 28 627 COVINGTON ROAD



LOT 26 954 RIVERSIDE DRIVE



LOT 6 662 ARROMOOD COURT



LOT 15 630 COVINGTON ROAD



LOT 29 933 PARMA MAY




LOT 66 938 RIVERSIDE DRIVE




LOT 6 662 ARROMOOD COURT



LOT 35 622 COVINGTON ROAD









SSIDENCE LTOS, CA 94024 RE PIMPALKHARE
962 RIVERSIDE DRIVE, LO

SCALE: 1/8" = 1'-0" JOB NO. 2022.01 DATE: 06/26/2024





### NEW 2ND FLOOR PLAN

	<b></b>	•					
Section	Dim	ensi	<u>ons</u>			Are	a
1	35'10"	×	16'0"			573.333	Sq.ft.
2	26'5.5"	×	10'8"			282.222	Sq.ft.
3	36'5"	×	13'0"			473.417	Sq.ft.
4	7'11"	×	2'0"			15.8333	Sq.ft.
5	12'1.5"	×	1'0"			12.125	Sq.ft.
6	10'0"	×	2'5"			24.1667	Sq.ft.
7	8'0"	×	2'1"			16.6667	Sq.ft.
2ND FLOOR HABITABLE AREA:						1397.7	Sq.ft.
A	9'4"	×	9'8"			90.2222	Sq.ft.
2ND FLOOR DECK AREA:						90.2222	Sq.ft.

### NEW IST FLOOR PLAN


Section	Dim	ensi	ions	Area	a
1	20'6"	×	21'6.5"	441.604	Sq.ft.
2	1'0"	×	2'6"	2.5	Sq.ft.
3	0'8.5"	×	8'0"	5.66667	Sq.ft.
4	1'10"	×	0'3.5"	0.534722	Sq.ft.
GARAGE ,	AREA:			450.3	Sq.ft.
NON-HABI	TABLE AR	EA:		450.3	Sq.ft.
5	19'4.5"	×	32'6"	629.688	Sq.ft.
6	17'0"	×	13'6"	229.5	Sq.ft.
7	21'7.5"	×	6'4"	136.958	Sq.ft.
8	7'3.5"	×	34'2"	249.132	Sq.ft.
9	16'5"	×	36'8"	601.944	Sq.ft.
10	11'3"	×	18'4"	206.25	Sq.ft.
11	2'4"	×	5'4"	12.4444	Sq.ft.
15T FL001	R HABITAE	BLE	AREA:	2065.9	Sq.ft.
TOTAL FIR	RST FLOO	2516.2	Sq.ft.		

Section	Dim	mensions Ar		Are	ea	
P1	15'9"	×	3'5.5"		54.4688	Sq.ft.
P2	7'0"	×	5'11.5"		41.7083	Sq.ft.
P3	1'0"	×	3'5.5"		3.45833	Sq.ft.
P4	19'0"	×	13'6"		256.5	Sq.ft.
COVERED PATIO AREA:					356.2	Sq.ft.

Section	Dim	ensi	ions		Are	a
1	41'0"	×	27'10"		1141.17	Sq.
2	19'10"	×	4'8"		92.5556	Sq.
BASEMENT	Γ HABITAE	LE /	AREA:		1233.8	Sq.
3	4'0"	×	7'2"		28.6667	Sq.
4	9'4"	×	21'11"		204.556	Sq.
IJ	10'2"	×	6'0"		61	Sq.
LIGHTMELI	_ AREA:		•		294.3	Sq.


TOTAL FLOOR AREA:								
15T:	2516.2	SQ.FT.						
2ND:	1397.7	SQ.FT.						
TOTAL:	3913.9	SQ.FT.						

TOTAL LOT COVERAGE AF	REA:	
1ST FLR. FOOTPRINT:	2516.2	SQ.FT.
FRONT COVERED PATIO:	112.9	SQ.FT.
REAR COVERED PATIO:	256.5	SQ.FT.
TOTAL:	2885.6	SQ.FT.



NEW BASEMENT FLOOR PLAN


FLOOR AREA DIAGRAMS A2.0




SEE SITE PLAN, SHEET A! I FOR FURTHER INFORMATION REGARDING

SEC. 807.1.


- TERRACES, STEPS, PORCHES, PATIOS, DECKS AND OTHER SITE DEVELOPMENT.
- SEE STRUCTURAL DRAWINGS FOR LOCATION OF 2x6 STUDS, WALLS, SHEAR WALLS, POSTS, FRAMES AND ALL OTHER STRUCTURAL MEMBERS.
- LOCATE ALL WATER CLOSETS AT 15" MIN. FROM CENTER TO ADJACENT WALL AND 30" MIN. CLEAR. PROVIDE 24" MIN. CLEAR IN FRONT OF FIXTURE. U.O.N. PROVIDE MINIMUM 22"x30" ATTIC ACCESS TO EACH ATTIC AREA. A 30" MIN. CLEAR HEAD ROOM SHALL BE PROVIDED ABOVE THE ACCESS. U.O.N. CRC
- ONE WINDOW/DOOR FROM EACH SLEEPING ROOM MUST HAVE A NET CLEAR OPENING OF 5.7 SQFT (5.0 SQFT, WHEN WINDOW IS AT FLOOR / GRADE LEVEL) WITH A NET CLEAR HEIGHT OF 24", A NET CLEAR WIDTH OF 20" AND THE SILL MUST BE WITHIN 44" OFF THE FLOOR.
- AN APPROVED NUMBER OR ADDRESS SHALL BE PROVIDED IN SUCH A POSITION AS TO BE PLAINLY LEGIBLE AND VISIBLE FROM THE STREET FRONTING THE PROPERTY. NUMBERS SHALL CONTRAST W/ THEIR BACKGROUND, SHALL BE ARABIC NUMERALS OR ALPHABETICAL LETTERS. NUMERALS SHALL BE A MIN. OF 4" HIGH, WITH A MIN. STROKE WIDTH OF  $last_2$ INCH. REFER TO CBC 501.2.
- PROVIDE A MINIMUM INSULATION OF R-15 AT ALL EXTERIOR WALLS, R-19 and/or R-30 INSULATION AT CEILING JOISTS LOCATED UNDER THE SLOPED ROOF ATTIC AND R-38 INSULATION AT CEILING JOISTS LOCATED AT THE FLAT ROOF, REFER TO T-24 COMPLIANCE REPORTS.
- PROVIDE MINIMUM 18"x24" (U.O.N.) UNDER-FLOOR CRAWL SPACE ACCESS PIPES, DUCTS AND OTHER NONSTRUCTURAL CONSTRUCTION SHALL NOT INTERFERE WITH THE ACCESSIBILITY TO OR WITHIN UNDER-FLOOR AREAS. CRC SEC. 408.4.
- MINIMUM OF 5% GRADE SLOPE AWAY FROM THE FOUNDATION AROUND BUILDING.
- WALL COVERING SHALL BE TILE, MIN. 72" ABOVE DRAIN AT ALL SHOWERS OR TUB / SHOWER UNITS. MATERIALS OTHER THAN STRUCTURAL ELEMENTS TO BE MOISTURE RESISTANT. (CRC 301.2).
- SHOWER AND TUB/SHOWER COMBINATIONS SHALL BE PROVIDED WITH INDIVIDUAL CONTROL VALVES OF THE PRESSURE BALANCE OR
- THERMOSTATIC MIXING TYPE. SEE INTERIOR ELEVATIONS FOR EXTENT OF CABINETRY, PANEL, CASINGS &





56'-2"

1 inch = 4 ft.



( IN FEET ) 1 inch = 4 ft.

REVISIONS BY DESIGN REVIEW SBMTL Ø1/12/2024 ↑PLNG. PLAN CHK A PLNG. CMNTS. 2 

HERITAGE




PIMPALKHAF 962 RIVERSIDE DRIVE

SCALE: 1/4" = 1'-0"


JOB NO. 2022.01 DATE: 06/26/2024

SECOND FLOOR PLAN



REVISIONS BY DESIGN REVIEW SBMTL Ø1/12/2024 PLNG. PLAN CHK Ø4/11/24 DVH PLNG. CMNTS. 2 06/26/24 DVH

HERITAGE




SCALE: 1/4" = 1'-0' JOB NO. 2022.01


DATE: 06/26/2024




STANDING SEAM ROOF COLOR: #2121-30 PEWTER BY BENJAMIN MOORE



TRIM AND GARAGE DOOR COLOR: PREPRIMED AND PAINTED W/ 2121-10 GRAY BY BENJAMIN MOORE




BODY COLOR: 1ST AND 2ND FLOORS: PREPRIMED AND PAINTED W/ #2121-20 STEEL WOOL BY BENJAMIN MOORE



WOOD TRIM BOARDS AND PROFILES BY JAMES HARDIE - SMOOTH. PREPRIMED AND PAINTED W/#2121-20 GRAY BY BENJAMIN MOORE

2121-30



1ST FLOOR SIDING: CEMENT PLASTER STUCOO FINISH: SMOOTH COLOR: #2121-20 STEEL WOOL



WAINSCOT: CULTURED STONE BY: EL DORADO. STYLE: YORK



2ND FLOOR SIDING: HORIZ. BEVELED CEDAR SIDING W/7" EXPOSURE PREPRIMED AND PAINTED W/ #2121-20 STEEL WOOL BY BENJAMIN MOORE



WINDOWS AND DOORS BY KOLBE-KOLBE: EXTRUDED ALUMINUM WOOD CLAD W/ INTEGRAL EXTRUDED ALUMINUM TRIM AND COLOR BY KOLBE-KOBLE.





SCALE:1/4" = 1'-0"

DATE: 06/26/2024

JOB NO. 2022.01


MATERIALS BOARD

DESIGN REVIEW SBMTL Ø1/12/2024 PLNG. PLAN CHK Ø4/11/24 DVH PLNG. CMNTS. 2 06/26/24 DVH



RESIDENCE SALTOS, CA 94024 RE

A4.0



REVISIONS BY DESIGN REVIEW SBMTL Ø1/12/2024 PLNG. PLAN CHK 04/11/24 DVH PLNG. CMNTS. 2 06/26/24 DVH






SIDENCE LTOS, CA 94024 RE PIMPALKHARE 962 RIVERSIDE DRIVE, LO

DRAWN: DYH SCALE:1/4" = 1'-0" JOB NO. 2022.01

DATE: 06/26/2024






PLNG. CMNTS. 2

06/26/24 DVH

HERITAGE ARCHITECTURE



HERITAGE ARCHITECTURE
DAVID V. HERNANDEZ, ARCHITECT
P.O. BOX 8033, San Jose, California 95155
C: (408) 772-3502 VM: (408) 298-0998
E-mail: dvhernandez@pacbell.net

PIMPALKHARE RESIDENCE 962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024

DRAWN: DVH

SCALE:1/4" = 1'-0"

JOB NO. 2022.01

DATE: 06/26/2024

A4.2



PLNG. PLAN CHK


PLNG. PLAN CHK

04/11/24 DVH

PLNG. CMNTS. 2

06/26/24 DVH

IAI
HERITAGE



HERITAGE ARCHITECTURE

DAVID V. HERNANDEZ, ARCHITECT

P.O. BOX 8033, San Jose, California 95155

C: (408) 772-3502 VM: (408) 298-0998


E-mail: dyhernandez@pacbell.net

PIMPALKHARE RESIDENCE 962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024

DRAWN: DVH

JOB NO. 2022.01 DATE: 06/26/2024

A4.3



REVISIONS BY

DESIGN REVIEW
SBMTL Ø1/12/2024

PLNG. PLAN CHK
Ø4/11/24 DVH

PLNG. CMNTS. 2
Ø6/26/24 DVH

HERITAGE ARCHITECTURE



HERITAGE ARCHITECTURE
DAVID V. HERNANDEZ, ARCHITECT
P.O. BOX 8033, San Jose, California 95155
C: (408) 772-3502 VM: (408) 298-0998
E-mail: dvhernandez@pacbell.net

PIMPALKHARE RESIDENCE
962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024

DRAWN: DVH


SCALE:1/4" = 1'-0"

JOB NO. 2022.01

DATE: 06/26/2024


A5.

1 inch = 4 ft.



PLNG. PLAN CHK Ø4/11/24 DVH PLNG. CMNTS. 2 06/26/24 DVH





PLNG. PLAN CHK

PLNG. PLAN CHK

### PLNG. CMNTS. 2

### PLNG. CMNTS. 2

### PLNG. CMNTS. 2





HERNANDEZ, ARCHITECT

3, San Jose, California 95155

502 VM: (408) 298-0998

PIMPALKHARE RESIDENCE 962 RIVERSIDE DRIVE, LOS ALTOS, CA 94024


DRAWN: DVH

SCALE:1/4" = 1'-0"


JOB NO. 2022.01

DATE: 06/26/2024


A5.3



## MATERIALS LEGEND




STONE PATIO AND PADS ON CONCRETE BASE. STONE TO BE SELECTED BY OWNER STONE TO BE MORTARED ON 4" MIN THICK CONC. BASE SUB BASE TO BE 16" MIN CLASS 3 BASEROCK.



STEPS DOWN TO LIGHT WELL MATERIALS CHOSEN BY OWNER




INTERLOCKING CONCRETE PAVERS DRIVEWAY AND WALKS AS SHOWN ON PLAN. STYLE AND COLOR CHOSEN BY OWNER. INSTALL PER MANUFACTURERS SPECIFICATIONS JOINTS IN BETWEEN PAVERS ARE TO BE 1.5"/2.5" COBBLE STONES



MATCHING STONE PADS ON CONCRETE BASE I"-1.5" COBBLES IN JOINTS AS SHOWN ON PLAN




STEEL BORDER EDGING FOR LAWN AREAS ETC



FRONT YARD 3' HIGH PROPERTY LINE FENCING. BUILD AS PER PLAN. OWNER TO SELECT STYLING.



BUILT UP STONE PLANTERS AS SHOWN ON PLAN BUILD WITH 4" CMU BLOCKS, #4 BARS #16" O.C. BOTH WAYS BOTTOM OPEN TO NATIVE SOIL VENEER SIDES AND CAP WITH MATCHING STONE




18" SQUARE STONE STEPPING STONES SET AS SHOWN ON PLAN



FENCE AND COLUMNS SEE DETAILS



NEW REAR YARD FENCE FENCE TO BE 6' HIGH WITH 2' OPEN LATTICE ON TOP. STYLE TO BE CHOSEN BY OWNER



BAR-B-QUE AND ARBOR SEE DETAILS

## General Project Notes

- I. I Agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package
- 2. Recirculating water systems shall be used for water features.
- 3. I have complied with the criteria of the ordinance and applied them for the efficient use of water in the landscape design plans
- 4. A diagram of the irrigation plan showing hydrozones shall be kept with the irrigation Controller for subsequent managment purposes.
- 5. A Certificate of Completion shall be filled out and certified by either the designer of the landscape plans, irrigation plan or licensed landscape contractor for the project. 6. An irrigation audit report shall be completed at the time of final inspection.
- Submit this report to San Mateo County Planning for review and acceptance. 7. At the time of final inspection, the permit applicant must provide the owner of the
- property with a certificate of completion, certificate of installation, irrigation schedule of landscape and irrigation maintenance.

## Todd Kalbfeld

Professional Landscape Designer

12/12/2023

### LEGEND


(E) EXISTING ITEM PROPERTY LINE MATER METER PG&E BOX

MM MATER MAIN

- A/C AIR CONDITION LIGHT HB HOSE BIBB
- SERVICE LINE ELECTRIC OUTLET GAS METER SEMER ACCESS MAILBOX ELECTRIC METER

PLANTING AREA


IRRIGATION CONTROLLER



PATE AUG / 2023 SCALE 1/8"=1'-0" ΤK DRAWN JOB RIVERSIDE SHEET

6/25/2024

ODD KALBFELD PROFESSIONAL LANDSCAPE DESIGNER



TREE LEGEND

Tree #	Common Name	Botanical Name	DBH (in.)	Circumference	Protected Status	Disposition
1	Modesto Ash	Fraxinus velutina 'Modesto'	28.5	89.5	Protected	Remove
2	Modesto Ash	Fraxinus velutina 'Modesto'	22.7	71.3	Protected	Remove
3	Liquidambar	Liquidambar styraciflua	18.7	58.7	Protected	Retain/Protec
4	Modesto Ash	Fraxinus velutina 'Modesto'	28.9	90.8	Protected	Remove
5	Camphor	Cinnamomum camphora	14.2	44.6	Not Protected	Remove
6	Privet	Ligustrum lucidum	6, 6, 4	18.8, 18.8, 12.6	Not Protected	Remove
7	Chinese Elm	Ulmus parvifolia	26	81.7	Protected	Retain/Protec
8	Crab Apple	Malus spp.	13.8	43.4	Not Protected	Remove
9	Coast Live Oak	Quercus agrifolia	~20	~62.8	Protected	Not at Risk
10	Liquidambar	Liquidambar styraciflua	~8, 8	~25.1, 25.1	Not Protected	Retain/Monito
11	Coast Live Oak	Quercus agrifolia	~24	~24	Not Protected	Retain/Monito
12	White Birch	Betula pendula	~8, 8, 7	~25.1, 25.1, 22	Not Protected	Retain/Monito

See Tree Protection Type for each Tree on Site Plan

6-foot-tall metal chain link type supported by


2-inch diameter metal poles pounded into the ground to a depth of no less than 2 feet.

The support poles should be spaced

no more than 10 feet apart on center.

Refer to Arborist report for further tree protection measures.

NOTE: NON ORDINANCE TREES ON THIS PLAN THAT ARE NOT SHOWN ON ARBORIST REPORT ARE TO BE PROTECTED PER OWNERS REQUEST.




CONSULT A PROFESSIONAL ARBORIST WITH ANY QUESTIONS. NO CONSTRUCTION VEHICLES DEBRIS OR TOOLS TO BE PLACED IN RESTRICTED ZONE. PROTECT THE CROWN, TRUNK, AND ROOTS FROM DAMAGE.

AVOID DISTURBING THE SOIL GRADE. PRUNE ANY LARGE ROOTS REMOVED, DO NOT TEAR THEM OUT. TUNNEL UNDER ROOTS INSTEAD OF TRENCHING .. ALLOW FOR WATERING OF TREES AND SHRUBS DURING CONSTRUCTION.

DO NOT DISPOSE OF CHEMICALS IN THE CONSTRUCTION AREA.

## TREE PROTECTION NOTES

- I. PRIOR TO INITIATING ANY CONSTRUCTION ACTIVITY IN THE AREA, INCLUDING GRADING, TEMPORARY PROTECTIVE FENCING SHALL BE INSTALLED AT EACH SITE TREE. FENCING IS IDEALLY LOCATED AT OR BEYOND THE CANOPY DRIPLINE AND AS MUCH DRIPLINE AS POSSIBLE WILL BE PROTECTED BY FENCING.
- 2. FENCING SHALL BE MINIMUM OF 5 FEET TALL AT ALL LOCATIONS, AND SHALL FORM A CONTINUOUS BARRIER WITHOUT ENTRY POINTS AROUND ALL TREES OR GROUPS OF TREES. BARRIER-TYPE FENCING SUCH AS CHAIN LINK IS PREFERRED; THE USE OF SIMPLE POST AND CABLE FENCING IS DISCOURAGED. ANY ENCROACHMENT INTO THE DRIPLINE FOR FENCING OR CONSTRUCTION PURPOSED SHOULD BE DISCUSSED AND AGREED UPON IN ADVANCE WITH THE PROJECT ARBORIST.
- 3. THIS FENCING SHALL SERVE AS A BARRIER TO PREVENT DRIPLINE ENCROACHMENT OF ANY TYPE OF CONSTRUCTION ACTIVITIES AND EQUIPMENT. ACCIDENTAL DAMAGE TO BARD, ROOT CROWN, OR LIMBS MY INCREASE POTENTIAL FOR FUTURE DECLINE.
- 4. CONTRACTORS AND SUBCONTRACTORS SHALL DIRECT ALL EQUIPMENT AND PERSONNEL TO REMAIN OUTSIDE THE FENCED AREA AT ALL TIMES UNTIL PROJECT IS COMPLETE, AND SHALL INSTRUCT EMPLOYEES AS TO THE PURPOSE AND IMPORTANCE OF FENCING.
- 5. A WARNING SIGN SHALL BE POSTED AT EACH TREE INDICATING THE PURPOSE OF THE FENCING.
- 6. THE PROJECT ARBORIST SHALL BE RESPONSIBLE FOR INSPECTION AND APPROVAL OF THE FENCING PRIOR TO ANY GRADING OPERATIONS.
- 7. FENCING MUST REMAIN IN PLACE AND SHALL NOT BE REMOVED UNTIL ALL CONSTRUCTION ACTIVITIES ARE COMPLETED. THIS SHALL INCLUDE GRADING AND COMPACTION ACTIVITIES, INSTALLATION OF UNDERGROUND UTILITIES, ALL CONSTRUCTION ACTIVITIES AND ANY OTHER CONSTRUCTION OR ACTIVITY THAT IS SCHEDULED PRIOR TO LANDSCAPE INSTALLATION.
- 8. ROOTS OF SINGLE STANDING TREES OFTEN EXTEND UP TO THREE TIMES THE DISTANCE OF THE ACTUAL DRIPLINE AND FUNCTION PRIMARILY IN THE UPTAKE OF NUTRIENTS AND WATER. THE DRIPLINE IS ARBITRARILY ESTABLISHED AS THE MINIMUM ROOT AREA GENERALLY REQUIRED TO PRESERVE TREE HEALTH. AS MUCH AREA AS POSSIBLE AROUND THE CIRCUMFERENCE OF THE TREE SHOULD HAVE MINIMUM INTRUSION TO FURTHER ENSURE TREE SURVIVAL AND HEALTH.




6/24/2024

TODD KALBFELD PROFESSIONAL

LANDSCAPE DESIGNER

PATE AUG / 2023 SCALE |/8"=|'-0" DRAWN JOB RIVERSIDE SHEET




## Front Yard Area calculation diagram



962 RIVERSIDE DRIVE LOS ALTOS, CALIFORNIA

	<u> </u>		
		A. N PAVER DRIVEWAY AND WALKS	971 SF
7		B. N FRONT PORCH	131 SF
		C. FENCE COLUMNS	8 SF
		AREA TOTAL	1,110 SF
		TOTAL FRONT YARD SQUARE FOOTAGE	2,645 SF
		TOTAL ALLOWED: 50%	1,322.5 SF
		TOTAL HARDSCAPE PROPOSED: 41.9%	1,110 SF



### LIGHTING LEGEND

SYM.	QTY.	MANUFAC	. MODEL #	DESCRIPTION	VOLT.	WATTS
•	9	Vista	GR-4006-R 4.5-W-36	SPOTLIGHT	12∨	4.5M
	10	Vista	GR-5004-R 2.5-W-60	SPOTLIGHT	12∨	2.5M
	34	Vista	GR-5105-R 2-W-FR	SPOTLIGHT	127	2M
_	42	Vista	SL-4242-WI 2.5-W-T3	STEPLIGHT	12∨	2.5M
lacktriangle	19	Vista	PR-6519-R 2.5-W-T3	PATHLIGHT	127	2.5M
	2	Vista	TCS Series	TRANS.	1207	300

## General Project Notes


- I. I Agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package
- 2. Recirculating water systems shall be used for water features.
- 3. I have complied with the criteria of the ordinance and applied them for the efficient use of water in the landscape design plans
- 4. A diagram of the irrigation plan showing hydrozones shall be kept with the irrigation Controller for subsequent managment purposes.
- 5. A Certificate of Completion shall be filled out and certified by either the designer of the landscape plans, irrigation plan or licensed landscape contractor for the project.
- 6. An irrigation audit report shall be completed at the time of final inspection. Submit this report to San Mateo County Planning for review and acceptance. 7. At the time of final inspection, the permit applicant must provide the owner of the property with a certificate of completion, certificate of installation, irrigation schedule of landscape and irrigation maintenance.


#### Todd Kalbfeld Professional Landscape Designer

MM MATER MAIN

LEGEND	
(E) EXISTING ITEM PL PROPERTY LINE W WATER METER P PG&E BOX A/C AIR CONDITION LT LIGHT HB HOSE BIBB	SL SERVICE LINE O ELECTRIC OUTLET G GAS METER S SEMER ACCESS MB MAILBOX E ELECTRIC METER PA PLANTING AREA

IRRIGATION CONTROLLER






revisions 6/25/2024

TODD KALBFELD PROFESSIONAL LANDSCAPE DESIGNER

DATE AUG / 2023 SCALE 1/8"=1'-0"  $\mathsf{T}\mathsf{K}$ DRAWN JOB RIVERSIDE



## PLANT LEGEND

TREES							
AE	24'	" B×	I	Acer p. 'Emeror I'	Emperor   Japanese Maple	Standard	P.F. 0.5 Moderate
AP	24'	" Bx	1	Acer p. 'Bloodgood'	Bloodgood Red Japanese Maple	Standard	P.F. 0.5 Moderate
AR	24	"_ Bx		Acer f. 'Autumn Blaze'	Autumn Blaze Maple	Standard	P.F. 0.2 Low
CF V	_ ^	"BX BX	$\frac{2}{2}$	Podocarpus gracillior Lagerstroemia i. 'Muskogee'	Fern Pine Lavender Crepe Myrtle	Standard Multi Trunk	P.F. 0.5 Moderate P.F. 0.2 Low
PC	24'	" Bx	1	Pistacia chinensis	Chinese Pistache	Standard	P.F. 0.2 Low
TL	24'	" Bx	5	Tristania laurina	Water Gum	Standard	P.F. 0.2 Low
UP	24'	" Bx		Ulmus parvifolia	Chinese Elm	Standard	P.F. 0.2 Low
SHRUBS							

COMMON NAME

REMARKS

MUCOLS PLANT FACTOR

6/24/2024

ODD KALBFELD

LANDSCAPE DESIGNER

01	2-1 0/	'	onnos par virona	Offinioso Lim	213113313	1 .1 . 0 .2 2071	
SHRUBS	5						
AA	15g	8	Agave attenuata	Foxtail Agave		P.F. 0.2 Low	
AB	15g	П	Agave 'Boutin Blue'	Blue Foxtail Agave		P.F. 0.2 LOW	
AH	159	1	Abutillon h. 'Tiger Eye'	Chinese Lantern	Space 30" o.c.	P.F. 0.2 LOW	
AL	15g	6	Agave 'Ray of Light'	Ray of Light Agave		P.F. 0.2 LOW	
AS	lg	4	Aeoneum 'Sunburst'	Sunburst Aeoneum	Space 18" o.c.	P.F. 0.2 LON	
CJ	1 <del>5</del> g	5	Camellia j. Red	Camellia japonica	·	P.F. 0.2 LOW	
CM	5g	17	Clivia miniata	Kaffir Lily	Space 30" o.c.	P.F. 0.5 Moderate	Z
CS	59	13	Camellia s. 'Shishi Gashira'	Sandanqua Camellia	Space 36" o.c.	P.F. 0.2 LOW	
DB	<b>5</b> g	13	Dietes bicolor	Yellow Fortnight Lily		P.F. 0.2 LOW	
DO	59	П	Daphne odora 'Aureo-marginata'	Winter Daphne		P.F. 0.5 Moderate	
GR	159	4	Grevillea 'Robyn Gordon'	NCN		P.F. 0.2 LOW	
HH	Ig	14	Hemerocallils 'Evergreen Yellow'	Day Lily	Space 30" o.c.	P.F. 0.5 Moderate	
HM	<u>5</u> g	4	Hydrangea m. 'Lacecap Blue'	Blue Lacecap Hydrangea		P.F. 0.5 Moderate	
HQ	59	7	Hydrangea quercifolia	Oak Leaf Hydrangea		P.F. 0.5 Moderate	
LC	59	8	Loropetelum c. 'Burgundy'	Chinese Fringe Flower		P.F. 0.2 LOW	
LG	5g	15	Lavandula x 'Grosso'	Lavandin		P.F. 0.2 LOW	
OH	159	2	Osmanthus fragrans	Sweet Olive		P.F. 0.2 Low	
PB	5g	3	Phormium 'Bronze Baby'	New Zealand Flax		P.F. 0.2 LOW	
PM	159	3	Pittosporum t. 'Marjorie Channon'	Marjorie Channon Pittosporum		P.F. 0.5 Moderate	
PTC	<del>5</del> g	20	Pittosporum t. 'Creme De Mint'	Creme De Mint Dwf Tobira	Space 30" o.c.	P.F. 0.2 LOW	
PTV	5g	16	Pittosporum t. variegata	Variegated Tobira		P.F. 0.2 LOW	
PY	<del>5</del> g	3	Phormium 'Yellow Wave'	New Zealand Flax		P.F. 0.2 LOW	
RI	5g	3	Ribes sanguineum	Red Flowering Current		P.F. 0.2 LON	
RO	5g	1	Rosmarinus officinalis	Rosemary Bush		P.F. 0.2 LON	
RS	5g	4	Rose Shrub 'Owner Selected'	Owner Selected Roses		P.F. 0.5 Moderate	
SL	5g	П	Salvia g. 'Hot Lips'	Hot Lips Sage		P.F. 0.2 Low	

#### VINES AND GROUND COVERS

CS	<b>5</b> g	43	Coleonemia 'Sunset Gold'	Sunset Gold Breath of Heaven	Space 39" o.c.	P.F. 0.2 Low
CT	Ig	34	Carex testacea	Orange Sedge	Space 24" o.c.	P.F. 0.2 LOW
HE	<b>5</b> g	31	Hellebore h. 'Pink Flower'	Hellebore	Space 30" o.c.	P.F. 0.2 Low
LM	lg	24	Liriope m. 'Big Blue'	Lily Turf	Space 24" o.c.	P.F. 0.5 Moderate
NF	lg	12	Nepeta fassenii	Catmint	Space 30" o.c.	P.F. 0.2 Low
RO	lg	113	Rosmarinus o. 'Irene'	Prostrate Rosemary	Space 36" o.c.	P.F. 0.2 Low
HS	lg	21	Heuchera sanguinea 'Red'	Coral Bells	Space 24" o.c.	P.F. 0.2 Low

## Planting Notes

1. All trees 15 gallons or larger to receive (2) 2'x10' Lodge Pole Pine Stakes with (1) 1"x4" backer board nailed to stakes. Tie all trees to stakes with rubber ties at mid point of trunk, and right below branck crotch. Nail with galvanized roofing nails.

2. Provide deep watering/inspection tubes on all trees. Water basins should be sufficient enough to contain water at base of tree, as necessary.

3.Fertilizer tablets shall be placed at the mid-point of root ball

per manu. recommendation. 4.Rototill and amend entire planting site with 6" or more of compost into top 6"-12" of existing soil as necessary for planting needs.

For All soils: compost at a rate of a min. of 4 cubic inches per 1000 square feet of permeable area shall be incorporated to a depth of 6" of soil.

5.Provide Min. 3" of shredded mulch under all trees, shrubs and unplanted areas for water conservation.

## General Project Notes

- I. I Agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package
- 2. Recirculating water systems shall be used for water features.

HOSE BIBB

MM MATER MAIN

- 3. I have complied with the criteria of the ordinance and applied them for the efficient use of water in the landscape design plans
- 4. A diagram of the irrigation plan showing hydrozones shall be kept with the irrigation Controller for subsequent managment purposes.
- 5. A Certificate of Completion shall be filled out and certified by either the designer of the landscape plans, irrigation plan or licensed landscape contractor for the project.
- 6. An irrigation audit report shall be completed at the time of final inspection.
- Submit this report to San Mateo County Planning for review and acceptance. 7. At the time of final inspection, the permit applicant must provide the owner of the property with a certificate of completion, certificate of installation, irrigation


schedule of landscape and irrigation maintenance. Todd Kalbfeld

Professional Landscape Designer 12/12/2023

## LEGEND

=)	EXISTING ITEM	SL	SERVICE
L	PROPERTY LINE	0	ELECTRI
	MATER METER	G	GAS ME
	PG\$E BOX	S	SEMER A
/	AIR CONDITION	MB	MAILBOX
Т	LIGHT	E	ELECTRI

LINE RIC OUTLET ACCESS ELECTRIC METER PLANTING AREA IRRIGATION CONTROLLER



	LANDSC	
DATE	AUG / 2023	
SCALE	1/8"=1'-0"	
DRAMN	TK	
JOB	RIVERSIDE	
SHEET	L-3	

JOB SHEET



SCREEN TREE IN USE



LEAVES AND FLOWERS



TREE BARK

SCREEN IREE	
BOTANICAL NAME	COMMON NAME
TRISTANIA LAURINA	MATER GUM

## SCREEN TREE CHARACTERISTICS

MAXIMUM TREE HEIGHT:	40'
CANOPY WIDTH:	15'-30'
GROWTH RATE:	12"-24" PER YEA!
WATER USAGE:	LOW





LEAVES AND FLOWERS



TREE BARK

## SCREEN TREE


BOTANICAL NAME CO	DMMON NAME

PODOCARPUS GRACILLIOR FERN PINE

## SCREEN TREE CHARACTERISTICS

50' MAXIMUM TREE HEIGHT: CANOPY WIDTH: 15'-25'

GROWTH RATE: 12"-36" PER YEAR MATER USAGE: MODERATE



### HYDRO - ZONES SQUARE FOOT CALCULATIONS LEGEND

1. FRONT YARD NON-TURF LOW WATER USE 5. REAR YARD NON-TURF LOW WATER USE 4. REAR AND SIDE YARDS NON-TURF MODERATE WATER USE 6. REAR YARD LAWN HIGH WATER USE 7. REAR YARD EDIBLES SPECIAL WATER USE	1,169 SF 1,632 SF 576 SF 464 SF 30 SF
LOW WATER USE LANDSCAPE AREA TOTAL	2,801 SF

576 SF MOD. WATER USE LANDSCAPE AREA TOTAL 464 SF HIGH WATER USE LANDSCAPE AREA TOTAL SPECIAL WATER USE LANDSCAPE AREA TOTAL 30 SF

LANDSCAPE AREA TOTAL

6/24/2024

3,871 SF

### WATER EFFICIENT LANDSCAPE WORKSHEET

This worksheet is filled out by the project applicant and it is a required element of the Landscape Documentation

Hydrozone # /Planting Description <sup>a</sup>	Plant Factor (PF)	Irrigation Method <sup>b</sup>	Irrigation Efficiency (IE) <sup>c</sup>	ETAF (PF/IE)	Landscape Area (sq, ft,)	ETAF x Area	Estimated Total Water Use (ETWU) <sup>e</sup>
Regular Landscap	e Areas		3130				
Front Low	.2	Drip	.81	.247	1169	288.74	7,697.89
Rear Low	.2	Drip	.81	.247	1632	403.10	10,743.98
Rear and Sides Mod.	.5	Drip	.81	0.617	576	355.39	9,474.70
Rear Lawn	.8	Spray	.75	1.067	464	495.09	13,199.10
				Totals	3841 <sup>A)</sup>	1542932	
Special Landscap	e Areas		•	•	•		
				1	30	30	799.8
				1			
				1			
				Totals	30 <sup>(C)</sup>	30 <sup>(D)</sup>	
				•		ETWU Total	41,917.67
			Max	imum Allowe	d Water Allowa	nce (MAWA)e	56,680.49

0.75 for spray head

0.81 for drip

<sup>b</sup>lrrigation Method <sup>a</sup>Hydrozone #/Planting Description <sup>c</sup>Irrigation Efficiency overhead spray 1.) front lawn or drip 2.) low water use plantings medium water use planting

\*MAWA (Annual Gallons Allowed) = (Eto) ( 0.62) [ (ETAF x LA) + ((1-ETAF) x SLA)] where 0.62 is a conversion factor that converts acreinches per acre per year to gallons per square foot per year, LA is the total landscape area in square feet, SLA is the total special landscape area in square feet,

and ETAF is .55 for residential areas and 0.45 for non-

 $(43.0) (.62) [(.55 \times 3841) + (1-.55 \times 30)] = 56,680.49$  $26.66 \times [(2,112.55) + (13.5)] = 56,680.49$ 

**ETAF Calculations** 

Regular Landscape Areas

residential areas.

Total ETAF x Area	(B)	1542.32
Total Area	(A)	3841
Average ETAF	B÷A	0.401

Average ETAF for Regular Landscape Areas must be 0.55 or below for residential areas, and 0.45 or below for non-residential areas.

<sup>d</sup>ETWU (Annual Gallons Required) =

where 0.62 is a conversion

factor that converts acreinches per acre per year to

gallons per square foot per

Eto x 0.62 x ETAF x Area


All Landscape Areas Total ETAF x Area 1,572.32 Total Area (A+C) 3871 Sitewide ETAF (B+D) ÷ (A+C) 0.406

A copy of this form may be obtained from Department of Water Resources website: http://www.water.ca.gov/wateruseefficiency/landscapeordinance/

## General Project Notes

- I. I Agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package
- 2. Recirculating water systems shall be used for water features." 3. I have complied with the criteria of the ordinance and applied them for the efficient
- use of water in the landscape design plans 4. A diagram of the irrigation plan showing hydrozones shall be kept with the irrigation
- Controller for subsequent managment purposes. 5. A Certificate of Completion shall be filled out and certified by either the designer of the landscape plans, irrigatin pland or licensed landscape contractor for the project.
- 6. An irrigation audit report shall be completed at the time of final inspection. Submit this report to City of Los Altos Building Dept. for review and acceptance.
- 7. At the time of final inspection, the permit applicant must provide the owner of the property with a certificate of completion, certificate of installation, irrigation schedule of landscape and irrigation maintenance.

12/12/2023 Todd Kalbfeld Professional Landscape Designer



ODD KALBFELD

PROFESSIONAL LANDSCAPE DESIGNER

DATE AUG / 2023 SCALE 1/8"=1'-0" ΤK DRAWN RIVERSIDE JOB SHEET

RIVERSIDE DRIVE (60')

IRRIGATION LEGEND

6/24/2024

ODD KALBFELD

ROFESSIONAL

LANDSCAPE DESIGNER

PATE AUG / 2023 SCALE 1/8"=1'-0" ΤK DRAWN RIVERSIDE JOB SHEET

NORTH

12/12/2023 Todd Kalbfeld

Professional Landscape Designer

REVISIONS

-NNER RAILS CUT TO RADIUS

STONE VENEER TO MATCH

3'-2½"

-RAISED INTERIM POST

STONE ON RESIDENCE


MASONRY COLUMNS


SCALE: 1/2"=1'-0"

6/24/2024

JOB

PATE SEPT / 2023 SCALE AS SHOWN DRAWN RIVERSIDE SHEET





-OPEN LATTICE

MATCHING BOARD ON BOARD

-4"x6" ACZA BROWN PRESSURE

TREATED COLUMN (TYP.)

MATCHING BOARD ON BOARD

4"x6" ACZA BROWN PRESSURE TREATED COLUMN (TYP.)

BOTTOM RAIL (TYP.)

2"x8" P.T. KICKBOARD (TYP.)—

2"x4" TOP AND

