

311 HAWTHORNE AVENUE

LOS ALTOS, CA 94024

December 20th, 2022

RECEIVED



Date: 1/20/2023

CITY OF LOS ALTOS
PLANNING

DIRECTORY	
OWNER: SF216, LLC 26880 ALISO VIEJO PARKWAY, SUITE 100 ALISO VIEJO, CA 92656 CONTACT: CYNTHIA THIEBAUT PHONE: (650) 382-0648 EMAIL: CTHIEBAUT@TJHUSA.COM	CIVIL ENGINEER: CBG 2633 CAMINO RAMON #350 SAN RAMON, CA 94583 PHONE: (925) 866-0322
ARCHITECTS: BASSENIAN LAGONI ARCHITECTS 2031 ORCHARD DRIVE NEWPORT BEACH, CA 92660 CONTACT: TERESSA OEHRLIN PHONE: (949) 553-9100 EMAIL: TERESSA@BASSENIANLAGONI.COM	
SHEET INDEX	
A0.0	COVER SHEET
CM-1	CONTEXT MAP
1	TOPOGRAPHIC SURVEY
A1.0	PROPOSED SITE PLAN
A2.0	PROPOSED FIRST FLOOR PLAN
A2.1	PROPOSED SECOND FLOOR PLAN
A2.2	SQUARE FOOTAGE CALCULATIONS: FIRST FLOOR
A2.3	SQUARE FOOTAGE CALCULATIONS: SECOND FLOOR
A3.0	PROPOSED EXTERIOR ELEVATIONS: FRONT AND REAR
A3.1	PROPOSED EXTERIOR ELEVATIONS: LEFT AND RIGHT
A3.2	PROPOSED ROOF PLAN
A3.3	PROPOSED SECTIONS
A4.0	COLOR AND MATERIALS BOARD
A4.1	COLOR AND MATERIALS DETAILS
A5.0	ARCHITECTURAL DETAILS
A6.0	PROPOSED 3D RENDERING
A6.1	PROPOSED 3D STREET SCENE
A7.0	PROPOSED 2D STREET SCENES
L1.1	LAYOUT AND MATERIALS
L1.2	CONSTRUCTION DETAILS
L2.1	IRRIGATION PLAN
L2.2	IRRIGATION DETAILS
L3.1	PLANTING PLAN
L3.2	PLANTING DETAILS AND NOTES
L3.3	TREE PROTECTION PLAN
GP-1	NOTES, LEGEND, ABBREVIATIONS, SITE PLAN
GP-2	CITY STANDARD DETAILS
GP-3	CLEAN BAY BLUEPRINT
ECP-1	EROSION CONTROL NOTES & SITE PLAN
ECP-2	EROSION CONTROL DETAILS

PROJECT DATA	
LEGAL DESCRIPTION :	LOT 1 LOT NO. 16 L.S. CLARK SUBDIVISION SANTA CLARA COUNTY, CALIFORNIA
APN :	170-28-045
PROJECT ADDRESS :	311 HAWTHORNE LOS ALTOS, CA 94024
ZONING :	R-1-10
GENERAL PLAN DESIGNATION :	SMALL LOT - 4 du/net acre FIRE SPRINKLERS PER CRC R313.3
TYPE OF CONSTRUCTION :	TYPE V-B
BUILDING TYPE :	SFD
FIRE ZONE :	N/A
CODES :	2019 CALIFORNIA BUILDING CODE 2019 CALIFORNIA RESIDENTIAL CODE 2019 CALIFORNIA MECHANICAL CODE 2019 CALIFORNIA PLUMBING CODE 2019 CALIFORNIA FIRE CODE 2019 CALIFORNIA ELECTRICAL CODE 2019 CALIFORNIA ENERGY CODE 2019 CALIFORNIA GREEN BUILDING STANDARDS CODE
GOVERNING BODY :	CITY OF LOS ALTOS
PROJECT DESCRIPTION	
<p>THIS PROPOSED HOME IS A TWO-STORY SINGLE FAMILY DETACHED RESIDENCE. IN 3,261 SQUARE FEET, THERE ARE A TOTAL OF 4 BEDROOMS AND 4.5 BATH WITH THE ADDITION OF A LOFT AND OFFICE. THE HOME ALSO INCLUDES A SEPARATE ENTRANCE LEADING TO A 568 SQUARE FOOT ADU WITH SITTING AREA, BEDROOM AND BATH.</p> <p>THE TRANSITIONAL STYLE DESIGN HELPS MINIMIZE THE OVERALL SCALE OF THE HOME BY USING LOW PITCHED ROOFS, MINIMIZED OVERHANGS, AND AN INCREASED SECOND FLOOR SETBACKS. THE SHINGLE SIDING, BOTH COMPETITIONS AND CEDAR, FURTHER HELP BALANCE THIS HOME WITH THE SURROUNDING TRADITIONAL STYLE HOMES.</p>	

ZONING COMPLIANCE			
	EXISTING	PROPOSED	ALLOWED/REQUIRED
LOT COVERAGE:	N/A	23% (2,519 SQ. FT.)	30% (3,332 SQ. FT.)
FLOOR AREA:	N/A	3,850 SQ. FT.	3,861 SQ. FT.
First Floor	N/A	2,090 SQ. FT.	
Second Floor	N/A	1,760 SQ. FT.	
SETBACKS:	N/A		
Front	N/A	25'-0"	25'-0"
Rear (1st/2nd)	N/A	37'-11.5" / 41'-2.5"	25'-0"
Right Side (1st/2nd)	N/A	20'-0" / 23'-9"	20'-0" / 20'-0"
Left Side (1st/2nd)	N/A	15'-0" / 24'-0"	10'-0" / 17'-5"
HEIGHT:	N/A	26'-7"	27'-0"
SQUARE FOOTAGE BREAKDOWN			
	EXISTING	CHANGE IN	PROPOSED
HABITABLE LIVING AREA:	N/A	3,829 SQ. FT.	3,829 SQ. FT.
NON-HABITABLE LIVING AREA:	61 SQ. FT. (SHED) 105 SQ. FT. (SHED)	279 SQ. FT.	445 SQ. FT.
LOT CALCULATIONS			
NET LOT AREA:	11,108 SQ. FT.		
FRONT YARD HARDSCAPE AREA:	690 SQ. FT. (33%)		
LANDSCAPE BREAKDOWN:			
Total Hardscape Area	4,816 SQ. FT.		
Existing Softscape Area	5,285 SQ. FT.		
New Softscape Area	1,007 SQ. FT.		
VICINITY MAP			



VICINITY MAP
NOT TO SCALE

EXISTING TREES TO BE REMOVED

TREE NUMBER	COMMON NAME	DBH (IN)	HERITAGE TREE	OFF-SITE	STREET TREE
2	COAST REDWOOD	52	NO	NO	NO
3	ITALIAN CYPRESS	15	NO	YES	YES
4	ITALIAN CYPRESS	17	NO	YES	YES
5	ITALIAN CYPRESS	11	NO	YES	YES

EXISTING TREES TO REMAIN

TREE NUMBER	COMMON NAME	DBH (IN)	HERITAGE TREE	OFF-SITE	STREET TREE
1	COAST REDWOOD	51	NO	NO	NO
6	SWEETGUM	10	NO	NO	NO
7	SWEETGUM	19	NO	NO	NO



LEGEND

- BOUNDARY LINE
- EXISTING RIGHT OF WAY
- EXISTING CENTERLINE
- ADJACENT PROPERTY LINE
- EXISTING STRUCTURE
- EXISTING DRIVEWAY
- PROPOSED RESIDENCE
- PROPOSED SECOND FLOOR OF RESIDENCE
- PROPOSED CURB AND GUTTER
- PROPOSED CONCRETE
- PROPOSED AC
- PROPOSED ARTIFICIAL GRASS
- PROPOSED GRAVEL
- EXISTING TREE TO REMAIN
- EXISTING TREE TO BE REMOVED
- EXISTING TREE

- NOTES:
- THE TABLES ABOVE CONTAIN A SUMMARY OF INFORMATION PRESENT IN THE ARBORIST REPORT. PLEASE REFER TO THE ARBORIST REPORT DATED OCTOBER 27, 2021 AND PREPARED BY CALIFORNIA TREE & LANDSCAPE CONSULTING, INC. FOR MORE INFORMATION.
 - TREES SHOWN TO BE REMOVED ON PLAN WITHOUT A NUMBER ARE NON-PROTECTED TREES.
 - STRUCTURES, IMPROVEMENTS AND TREES ON ADJACENT PROPERTIES HAVE NOT BEEN SURVEYED. LOCATIONS DEPICTED HEREIN ARE APPROXIMATE.



311 HAWTHORNE WAY
CONTEXT MAP
THOMAS JAMES HOMES

CITY OF LOS ALTOS SANTA CLARA COUNTY CALIFORNIA
SCALE: 1" = 20' DATE: OCTOBER 18, 2022



SAN RAMON (925) 866-0322
ROSEVILLE (916) 375-1877
WWW.CBANDG.COM
CIVIL ENGINEERS SURVEYORS PLANNERS

SHEET NO.
CM-1
OF 1 SHEETS



TITLE REPORT

FIDELITY NATIONAL TITLE COMPANY
 TITLE NO.: FSBC-0302101657-DG
 DATED: AUGUST 31, 2021

LEGAL DESCRIPTION:

THE LAND REFERRED TO HEREIN BELOW IS SITUATED IN THE CITY OF LOS ALTOS, COUNTY OF SANTA CLARA, STATE OF CALIFORNIA AND IS DESCRIBED AS FOLLOWS:

LOT 1, AS SHOWN ON THE MAP OF RECORD OF SURVEY PORTION OF LOT NO. 16 L.S. CLARK SUBDIVISION - MAP 2, ACCORDING TO THE MAP THEREOF FILED FOR RECORD IN THE OFFICE OF THE RECORDER OF THE COUNTY OF SANTA CLARA, STATE OF CALIFORNIA, ON MAY 13, 1965 IN BOOK 194 OF MAPS, AT PAGE 32.

EXCEPTIONS AND EXCLUSIONS:

INDICATES TITLE REPORT ITEM NUMBER
 ITEMS ① THROUGH ⑦ RELATE TO TAXES, LIENS, AND DEED OF TRUST AND CANNOT BE PLOTTED.

BENCHMARK:

BENCHMARK ID: BM 19 (CITY OF LOS ALTOS)
 DESCRIPTION: 3.5" BRASS DISC ON TOP OF CURB AT NORTHWEST RETURN OF HAWTHORNE AVENUE AND SOUTH GORDON WAY AT EDGE OF HC RAMP.
 ELEVATION: 181.640' (NAVD 88)

ASSESSOR'S PARCEL NUMBER:

170-28-045

AREA:

11,108 SQ. FT. MORE OR LESS.

NOTES:

- RECORD INFORMATION AND PROPERTY DESCRIPTION ARE PER TITLE REPORT LISTED HEREON. THIS IS NOT A BOUNDARY SURVEY.
- UTILITIES SHOWN ARE BASED ON OBSERVED EVIDENCE AT THE TIME OF THE FIELD SURVEY. ADDITIONAL RESEARCH AND INVESTIGATION WOULD BE REQUIRED TO DETERMINE THE EXACT LOCATIONS OF UNDERGROUND UTILITIES. DO NOT RELY ON THIS SURVEY FOR SUCH LOCATIONS. SOME UTILITIES COULD BE COVERED BY STRUCTURES OR OBJECTS SUCH AS AUTOMOBILES, TRUCKS, CONTAINERS, ETC.
- ALL DISTANCES SHOWN ARE FEET AND DECIMALS THEREOF.
- NO SANITARY SEWER CLEANOUT WAS LOCATED DURING FIELD SURVEY.
- STRUCTURES, TREES AND IMPROVEMENTS ON ADJACENT PROPERTIES HAVE NOT BEEN SURVEYED. LOCATIONS DEPICTED HEREIN ARE APPROXIMATE.

FLOOD ZONE:

ZONE X (SHADED): AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

SOURCE: FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA), FLOOD INSURANCE RATE MAP, MAP NUMBER 06085C0038H

DATED: MAY 18, 2009

LEGEND & ABBREVIATIONS

	PROPERTY BOUNDARY LINE
	EXISTING RIGHT OF WAY
	EXISTING EASEMENT LINE
	CENTERLINE
	EXISTING UTILITY AS NOTED
	TIE LINE
	ADJACENT PROPERTY BOUNDARY LINE
	EXISTING STRUCTURE
	OVERHEAD WIRES
	FENCE LINE
	FOUND STREET MONUMENT
	UTILITY MANHOLE
	EXISTING WATER METER
	EXISTING ELECTRIC METER
	EXISTING WATER FAUCET
	EXISTING GAS METER
	EXISTING FIRE HYDRANT
	GROUND ELEVATION

AC	ASPHALT CONCRETE
CONC	CONCRETE
DW	DRIVEWAY
EL	ELEVATION
EX	EXISTING
FF	FINISHED FLOOR
INV	INVERT
LAT	LATERAL
OHW	OVERHEAD WIRES
PUE	PUBLIC UTILITY EASEMENT
ROW	RIGHT OF WAY
SS	SANITARY SEWER
SSMH	SANITARY SEWER MANHOLE
W	WATER
WM	WATER METER
WS	WATER SERVICE



**311 HAWTHORNE AVENUE
 TOPOGRAPHIC SURVEY**

CITY OF LOS ALTOS SANTA CLARA COUNTY CALIFORNIA
 SCALE: 1" = 10' DATE: OCTOBER 15, 2021

SURVEYOR'S STATEMENT:


THIS TOPOGRAPHIC SURVEY REPRESENTS A SURVEY BY ME OR UNDER MY DIRECTION.

MARK H. WEHBER
 REGISTERED L.S. NO. 7960
 DATE: 10/15/21




SAN RAMON • (925) 866-0322
 SACRAMENTO • (916) 375-1877
 WWW.CBANDG.COM
 CIVIL ENGINEERS • SURVEYORS • PLANNERS


SHEET NO.
1
 OF 1 SHEETS



TREE PROTECTION CHART

Keynote	Tag #	Protected	Offsite	Common Name	Botanical Name	DBH (inches)	Status	Note
1	9543	Y	N	Coast Redwood	Sequoia sempervirens	51	Retain and Protect	
2	9544	Y	N	Coast Redwood	Sequoia sempervirens	52	Remove	Poor Condition (See Arborist Report)
3	9545	Y	N	Italian Cypress	Cupressus sempervirens	15	Remove	
4	9546	Y	N	Italian Cypress	Cupressus sempervirens	17	Remove	
5	9547	N	N	Italian Cypress	Cupressus sempervirens	11	Remove	
6	9548	N	N	Sweetgum	Liquidambar	10	Retain and Protect	
7	9549	N	N	Sweetgum	Liquidambar	9	Retain and Protect	





4 BEDROOMS / 4.5 BATHS / LOFT + ADU
2 - CAR GARAGE

FLOOR AREA TABLE

1ST FLOOR	1654 SQ. FT.
2ND FLOOR	1613 SQ. FT.
ADU	577 SQ. FT.

TOTAL LIVING	3844 SQ. FT.
2 - CAR GARAGE	436 SQ. FT.
OUTDOOR LIVING	251 SQ. FT.
PORCH	169 SQ. FT.

LOT COVERAGE (30% max.) 23%


FAR TABLE

1ST FLOOR	1654 SQ. FT.
2ND FLOOR	1760 SQ. FT.
GARAGE	436 SQ. FT.

TOTAL FAR (3861 MAX) 3850 SQ. FT.

NOTE: SQUARE FOOTAGE MAY VARY DUE TO METHOD OF CALCULATION

NOTE: SQUARE FOOTAGE MAY VARY DUE TO METHOD OF CALCULATION



4 BEDROOMS / 4.5 BATHS / LOFT + ADU
2 - CAR GARAGE

FLOOR AREA TABLE

1ST FLOOR	1654 SQ. FT.
2ND FLOOR	1613 SQ. FT.
ADU	577 SQ. FT.
TOTAL LIVING	3844 SQ. FT.
2 - CAR GARAGE	436 SQ. FT.
OUTDOOR LIVING	251 SQ. FT.
PORCH	169 SQ. FT.
LOT COVERAGE (30% max.)	23%

NOTE: SQUARE FOOTAGE MAY VARY DUE TO METHOD OF CALCULATION

FAR TABLE

1ST FLOOR	1654 SQ. FT.
2ND FLOOR	1760 SQ. FT.
GARAGE	436 SQ. FT.

TOTAL FAR (3861 MAX) 3850 SQ. FT.


NOTE: SQUARE FOOTAGE MAY VARY DUE TO METHOD OF CALCULATION

FLOOR PLAN

Second Floor


311 HAWTHORNE AVE


Los Altos, Ca



918.21372

B38A - TS






AREA CALCULATION		
LABEL	DIMENSIONS	AREA
A	21'-3" X 21'-10"	464 SQ. FT.
B	22'-5" X 21'-10"	452 SQ. FT.
C	44'-9 1/2" X 13'-6"	605 SQ. FT.
D	11'-1 1/2" X 12'-0"	133 SQ. FT.
E	33'-5 1/2" X 12'-6 1/2"	420 SQ. FT.
F	8'-2 1/2" X 12'-1"	99 SQ. FT.
G	17'-4" X 20'-7 1/2"	358 SQ. FT.
H	13'-1" X 29'-6"	386 SQ. FT.
I	18'-4 1/2" X 20'-2"	371 SQ. FT.
J	12'-5 1/2" X 7'-3 1/2"	91 SQ. FT.
K	4'-0" X 9'-2"	37 SQ. FT.
L	15'-2" X 20'-11 1/2"	318 SQ. FT.
M	11'-1 1/2" X 21'-1 1/2"	235 SQ. FT.
N	4'-8 1/2" X 1'-8"	25 SQ. FT.
O	3'-4.5" X 15'-11.5"	35 SQ. FT.
P	9'-1.5" X 10'-7.5"	134 SQ. FT.
Q	14'-8" X 4'-10.5"	184 SQ. FT.
R	4'-10.5" X 14'-6"	67 SQ. FT.
S	4'-6.5" X 13'-4.5"	436 SQ. FT.
FLOOR AREA		
	FIRST FLOOR AREA (A-D)	1,654 SQ. FT.
	SECOND FLOOR (E-K)	1,760 SQ. FT.
	GARAGE (S)	436 SQ. FT.
	TOTAL	3,850 SQ. FT.
	ADU (L-N)	577 SQ. FT.
	PORCH (O-P)	169 SQ. FT.
	OUTDOOR LIVING (Q-R)	251 SQ. FT.
F.A.R.		
	LOT SIZE	11,108 SQ. FT.
	ALLOWABLE F.A.R.	3,861 SQ. FT.
	PROPOSED F.A.R.	3,850 SQ. FT.
LOT COVERAGE		
	ALLOWABLE COVERAGE (30% MAX.)	3,332 SQ. FT.
	PROPOSED COVERAGE (A-D, O-S) (23%)	2,510 SQ. FT.

FIRST FLOOR PLAN


TN
SCALE: 1/4"=1'-0"



AREA CALCULATION		
LABEL	DIMENSIONS	AREA
A	21'-3" X 21'-10"	464 SQ. FT.
B	22'-5" X 21'-10"	452 SQ. FT.
C	44'-9 1/2" X 13'-6"	605 SQ. FT.
D	11'-1 1/2" X 12'-0"	133 SQ. FT.
E	33'-5 1/2" X 12'-6 1/2"	420 SQ. FT.
F	8'-2 1/2" X 12'-1"	99 SQ. FT.
G	17'-4" X 20'-7 1/2"	358 SQ. FT.
H	13'-1" X 29'-6"	386 SQ. FT.
I	18'-4 1/2" X 20'-2"	371 SQ. FT.
J	12'-5 1/2" X 7'-3 1/2"	91 SQ. FT.
K	4'-0" X 9'-2"	37 SQ. FT.
L	15'-2" X 20'-11 1/2"	318 SQ. FT.
M	11'-1 1/2" X 21'-1 1/2"	235 SQ. FT.
N	4'-8 1/2" X 1'-8"	25 SQ. FT.
O	3'-4.5" X 15'-11.5"	35 SQ. FT.
P	9'-1.5" X 10'-7.5"	134 SQ. FT.
Q	14'-8" X 4'-10.5"	184 SQ. FT.
R	4'-10.5" X 14'-6"	67 SQ. FT.
S	4'-6.5" X 13'-4.5"	436 SQ. FT.
FLOOR AREA		
	FIRST FLOOR AREA (A-D)	1,654 SQ. FT.
	SECOND FLOOR (E-K)	1,760 SQ. FT.
	GARAGE (S)	436 SQ. FT.
	TOTAL	3,850 SQ. FT.
	ADU (L-N)	577 SQ. FT.
	PORCH (O-P)	169 SQ. FT.
	OUTDOOR LIVING (Q-R)	251 SQ. FT.
F.A.R.		
	LOT SIZE	11,108 SQ. FT.
	ALLOWABLE F.A.R.	3,861 SQ. FT.
	PROPOSED F.A.R.	3,850 SQ. FT.
LOT COVERAGE		
	ALLOWABLE COVERAGE (30% MAX.)	3,332 SQ. FT.
	PROPOSED COVERAGE (A-D, O-S) (23%)	2,510 SQ. FT.

SECOND FLOOR PLAN

TN
SCALE: 1/4" = 1'-0"



FRONT

TRANSITIONAL


1/4"=1'-0"

MATERIALS LEGEND:

- 1. COMPOSITION SHINGLE ROOF
- 2. CEMENTITIOUS VERTICAL SIDING
- 3. CEMENTITIOUS HORIZONTAL SIDING
- 4. CEMENTITIOUS TRIM
- 5. DECORATIVE WOOD COLUMN
- 6. COACH LIGHT
- 7. SECTIONAL GARAGE DOOR
- 8. FIBERGLASS ENTRY DOOR
- 9. FIBERGLASS WINDOW





REAR



MATERIALS LEGEND:

- 1. COMPOSITION SHINGLE ROOF
- 2. CEMENTITIOUS VERTICAL SIDING
- 3. CEMENTITIOUS HORIZONTAL SIDING
- 4. CEMENTITIOUS TRIM
- 5. DECORATIVE WOOD COLUMN
- 6. COACH LIGHT
- 7. SECTIONAL GARAGE DOOR
- 8. FIBERGLASS ENTRY DOOR
- 9. FIBERGLASS WINDOW





ROOF PLAN


PITCH: 4:12
 RAKE: 12"
 EAVE: 12"
 ROOF MATERIAL: COMPOSITE SHINGLES

ELEVATIONS

Roof Plan

311 HAWTHORNE AVE




Los Altos, Ca



918.21372

B38A - TS





TRANSITIONAL




CEMENTITIOUS HORIZONTAL
& VERTICAL SIDING
SW 9165 GOSSAMER VEIL



WOOD FASCIA, EAVES, TAILS, HEADERS,
BEAMS, DECORATIVE WOOD COLUMNS
& CEMENTITIOUS TRIM
SW 7005 PURE WHITE



FAUX STAINED FIBERGLASS ENTRY DOOR
(OPTION) THERMATRU - RAVEN



WOOD SHUTTERS, FIBERGLASS ENTRY DOOR
& SECTIONAL GARAGE DOOR
SW 7069 IRON ORE



FIBERGLASS WINDOW FRAME



COMPOSITION SHINGLE ROOF
GAF - CHARCOAL



WOODEN FENCE STAIN
CABOT SEMI-TRANSPARENT- SPANISH MOSS

ARCHITECTURAL DETAILS

311 HAWTHORNE AVE

Los Altos, Ca

918.21372

<p>WINDOW FRAME</p> <p>WHERE OCCURS</p> <p>1" X 3-1/2" CEMENTITIOUS O/ 3/4" X 3-1/2" BACKING</p> <p>EXTERIOR CEMENT BOARD SIDING (V- RUSTIC)</p> <p>SEE ELEVATION FOR WINDOW BREAK-UP PATTERNS</p>	<ol style="list-style-type: none"> EXTERIOR V - RUSTIC' CEMENT BOARD SIDING. INSTALL PER MFR. FRAMING (SEE STRUCTURAL PLANS) APPROVED FLASHING MATERIAL (2) LAYERS WATER-RESISTANT PAPER (60 MINUTE, GRADE 'D' MINIMUM) WINDOW FRAME SEALANT, TYPICAL CEMENTITIOUS TRIM (SEE WINDOW TRIM DETAIL FOR SIZE) SELF SEALING, SELF ADHERING BITUMINOUS MEMBRANE APPLIED OVER SOLID BACKING 26 GA. G.I. FLASHING <p>REFER TO DETAIL 4/D.2 FOR FLASHING MATERIALS, SEALANT AND WATER-RESISTANT PAPER.</p>
<p>WINDOW TRIM AT EXTERIOR SIDING</p> <p>SCALE : 1/2" = 1'-0"</p> <p>4</p> <ol style="list-style-type: none"> SELF SEALING, SELF ADHERING BITUMINOUS MEMBRANE APPLIED OVER SOLID BACKING FRAMING (SEE STRUCTURAL PLANS) APPROVED FLASHING MATERIAL (12" WIDE) CEMENTITIOUS TRIM, CUT TO FIT (SEE WINDOW TRIM DETAIL) WINDOW FRAME NON-HARDENING SEALANT TYPICAL (2) LAYERS WATER-RESISTANT PAPER (60 MINUTE, GRADE 'D' MINIMUM) <p>REFER TO DETAIL 4/D.2 FOR FLASHING MATERIALS, SEALANT, AND WATER-RESISTANT PAPER.</p>	<p>WINDOW HEAD AT EXTERIOR SIDING</p> <p>SCALE : 3" = 1'-0"</p> <p>1</p> <ol style="list-style-type: none"> WINDOW FRAME APPROVED FLASHING MATERIAL (2) LAYERS WATER-RESISTANT PAPER (60 MINUTE, GRADE 'D' MINIMUM) EXTERIOR V - RUSTIC' CEMENT BOARD SIDING. INSTALL PER MFR. SEALANT, TYPICAL FRAMING (SEE STRUCTURAL PLANS) SELF SEALING, SELF ADHERING BITUMINOUS MEMBRANE APPLIED OVER SOLID BACKING CEMENTITIOUS TRIM (SEE WINDOW TRIM DETAIL FOR SIZE) BUILT-UP TRIM WHERE OCCURS NON-HARDENING SEALANT <p>REFER TO DETAIL 4/D.2 FOR FLASHING MATERIALS, SEALANT AND WATER-RESISTANT PAPER.</p>
<p>WINDOW POST AT CEMENTITIOUS TRIM</p> <p>SCALE : 3" = 1'-0"</p> <p>5</p> <ol style="list-style-type: none"> SELF SEALING, SELF ADHERING BITUMINOUS MEMBRANE APPLIED OVER SOLID BACKING FRAMING (SEE STRUCTURAL PLANS) APPROVED FLASHING MATERIAL (12" WIDE) CEMENTITIOUS TRIM, CUT TO FIT (SEE WINDOW TRIM DETAIL) WINDOW FRAME NON-HARDENING SEALANT TYPICAL (2) LAYERS WATER-RESISTANT PAPER (60 MINUTE, GRADE 'D' MINIMUM) <p>REFER TO DETAIL 4/D.2 FOR FLASHING MATERIALS, SEALANT, AND WATER-RESISTANT PAPER.</p>	<p>WINDOW JAMB AT EXTERIOR SIDING</p> <p>SCALE : 3" = 1'-0"</p> <p>2</p> <ol style="list-style-type: none"> WINDOW FRAME APPROVED FLASHING MATERIAL (2) LAYERS WATER-RESISTANT PAPER (60 MINUTE, GRADE 'D' MINIMUM) CEMENTITIOUS TRIM (SEE WINDOW TRIM DETAIL FOR SIZE) SEALANT, TYPICAL EXTERIOR V - RUSTIC' CEMENT BOARD SIDING. INSTALL PER MFR. NON-HARDENING SEALANT FRAMING (SEE STRUCTURAL PLANS) SELF SEALING, SELF ADHERING BITUMINOUS MEMBRANE APPLIED OVER SOLID BACKING <p>REFER TO DETAIL 4/D.2 FOR FLASHING MATERIALS, SEALANT AND WATER-RESISTANT PAPER.</p>
<p>WINDOW SILL AT EXTERIOR SIDING</p> <p>SCALE : 3" = 1'-0"</p> <p>3</p>	

Fortifiber Building Systems Group®
HIGH PERFORMANCE WINDOW FLASHING SYSTEM

This system from Fortifiber Building Systems Group raises the standard for flashing windows and doors. The system starts with your choice of one of two tried and true Fortifiber products, Moistop PF or Moistop next™. This base layer of flashing is mechanically attached (large-headed nails). Next, the window is installed using the proper fasteners and Moistop Sealant. Finally, the jambs and head flange are covered with Moistop E-Z Seal™, FortiFlash™ Waterproof Flashing, FortiFlash Commercial Waterproof Flashing or FortiFlash Butyl Waterproof Flashing. The High Performance Window Flashing System depends on this sequential installation for its success. Also, this system is just one of four proven methods for flashing windows. At www.fortifiber.com you can find detailed instructions for the remaining three methods (Method A, A1 and Method B). If you have any further questions, please call our Toll Free Technical Hotline at 800-773-4777.

Note: You can use FortiFlash, FortiFlash Commercial or FortiFlash Butyl in place of E-Z Seal.

Note: You can use Moistop next™ in place of Moistop PF in base flashing applications.

Listed below are the sizes and lengths available of these Fortifiber products:

- Mechanical flashing for base layer
 - Moistop next™ Flashing 6, 9 and 12 inch x 200' rolls
 - Moistop PF Flashing 6, 9, 12 and 18 inch x 300' rolls
- Self-adhesive flashing for the jambs and head flange
 - Moistop E-Z Seal Self Adhesive Flashing 6, 9 and 12 inch x 75' rolls
 - FortiFlash Waterproof Flashing 4, 6, 9, 12, 18 and 36 inch x 75' rolls
 - FortiFlash Commercial Waterproof Flashing 6, 9, 12 and 18 inch x 75' rolls
 - FortiFlash Butyl Waterproof Flashing 4, 6, 9 and 12 inch x 75' rolls

Sealant for window flange

- Moistop Sealant (Exceeds AAMA Standards)

1 SILL FLASHING

Once the rough opening is prepared, proceed by attaching Moistop PF Flashing (A) flush along the bottom of the rough opening extending the flashing beyond the jamb flashing to be applied later. Be sure not to fasten the lower edge of the flashing as that a Fortifiber weather-resistive barrier may be slipped up underneath the flashing in a weather-board fashion.

2 JAMB FLASHING

The jamb flashing should extend on each side of the Moistop E-Z Seal head flashing. The base layer of Moistop PF Flashing does not have head flashing. Extend jamb flashing beyond the sill flashing. Leave flashing free at bottom.

Cut a strip of Moistop PF Flashing long enough to extend beyond sill flashing already in place and above where the Moistop E-Z Seal head flashing will intersect. Next, attach the jamb flashing flush to the edge of the rough opening leaving the bottom free. Repeat above steps for the remaining jamb.

CONTINUED...

CONTINUED FROM FRONT...

3 WINDOW INSTALLATION

Before installing the window (C), apply a continuous 1/8" bead of Moistop Sealant to the perimeter of the rough opening or to the backside of the mounting flange (D) of the window. Install the window according to the window manufacturer's instructions.

4 SURFACE PREP

Wipe the window flange (D) and base Moistop PF Flashing (B) layer clean before applying Moistop E-Z Seal.

5 JAMB FLASHING

Use 6" Moistop E-Z Seal for jamb flashing.

Using a sharp knife, cut the desired length of Moistop E-Z Seal for the jamb (E) of the window, extending beyond the flange (3" minimum top and bottom). Place the Moistop E-Z Seal on top of the flange (D) and seal by applying pressure along the strip. Repeat for the other jamb.

6 HEAD FLASHING

Use 12" Moistop E-Z Seal for head installation.

Cut a strip of Moistop E-Z Seal for the head (F) of the window extending beyond the jamb flashing already in place. Place the Moistop E-Z Seal on top of the flange (D) of the window with the adhesive strip overlaying the flange and seal by applying pressure along the strip. If desired, staples or sealant may be used to secure the top corners of the head flashing in place.


OVERVIEW

Once the High Performance Window Flashing System is properly installed, apply a Fortifiber weather resistive barrier in a weather-board fashion.

Fortifiber recommends the use of a well integrated weather resistive barrier with all of its flashing systems.

Call 1-800-773-4777 for Technical Assistance
www.fortifiber.com

Fortifiber Building Systems Group®
Protective: Trade Dress: (see below) ®
NATIONAL SALES OFFICE - Fenley, NV





Bassenian | Lagoni
ARCHITECTURE • PLANNING • INTERIORS

Copyright 2022 Bassenian | Lagoni Architects

2031 Orchard Drive, Suite 100
Newport Beach, CA USA 92660
tel. +1 949 553 9100
fax +1 949 553 0548

PROPOSED RENDERING



311 HAWTHORNE AVE

Los Altos, Ca

918.21372

A6.0

10.18.22





PROPOSED STREET SCENE


311 HAWTHORNE AVE


Los Altos, Ca

918.21372

A6.1

10.18.22





CONCEPTUAL STREET SCENE


311 HAWTHORNE AVE


Los Altos, Ca

918.21372
B38A - TS

A7.0

11.07.22





MATERIALS LEGEND

- S1 VEHICULAR CONCRETE PAVEMENT
STANDARD GRAY CONCRETE WITH ACID ETCH FINISH
TOP CAST #05 SURFACE RETARDANT MANUFACTURED BY GRACE PRODUCTS. TOOLED SCORE JOINTS AS SHOWN ON PLANS.
- S2 CONCRETE PAVEMENT
STANDARD GRAY CONCRETE WITH ACID ETCH FINISH
TOP CAST #05 SURFACE RETARDANT MANUFACTURED BY GRACE PRODUCTS. TOOLED SCORE JOINTS AS SHOWN ON PLANS.
- S3 CONCRETE PAVERS
STANDARD GRAY CONCRETE WITH ACID ETCH FINISH
TOP CAST #01 SURFACE RETARDANT MANUFACTURED BY GRACE PRODUCTS. FILL GAPS WITH 3/8" 'DESERT GOLD' CRUSHED AGGREGATE BY LYNGSO.
- S4 CONCRETE PAVERS (MULCHED GAPS)
STANDARD GRAY CONCRETE WITH ACID ETCH FINISH
TOP CAST #01 SURFACE RETARDANT MANUFACTURED BY GRACE PRODUCTS. FILL GAPS WITH WOOD MULCH.
- S5 DECORATIVE GRAVEL
3/8" 'YOSEMITE TAN' CRUSHED AGGREGATE BY LYNGSO
2" OVER COMPACTED SUBGRADE OVER FILTER FABRIC. WITH 8" GALVANIZED WIRE STAPLES.
- S6 STEEL HEADER
- S7 6'-0" HIGH WOOD FENCE
- S8 GATE

LAYOUT LEGEND

- VIEW DETAIL CALLOUT
- SHEET NUMBER
- DIMENSION
- CENTERLINE
- ALIGN
- CONTROL JOINT
- EXPANSION JOINT (DOWELED)
- EXPANSION JOINT (NO DOWEL)
- (E) TREE TO REMAIN, TYP.
- (E) TREE TO BE REMOVED, TYP.
- (E) NEIGHBORING TREE, TYP.

ABBREVIATIONS

- ADJ. ADJACENT
- AVG. AVERAGE
- C.L. CENTER LINE
- CLR. CLEAR
- CONC. CONCRETE
- (E) EXISTING
- E.W. EACH WAY
- EQ. EQUAL SPACES
- EQPT. EQUIPMENT
- F.G. FINISH GRADE
- F.S. FINISH SURFACE
- F.T. FLUSH TREAD
- HORIZ. HORIZONTAL
- HT. HEIGHT
- JT. JOINT(S)
- MAX. MAXIMUM
- MECH. MECHANICAL
- MIN. MINIMUM
- (N) NEW
- O.C. ON CENTER
- (P) PROPOSED
- P.A. PLANTING AREA
- P.O.B. POINT OF BEGINNING
- PVMT. PAVEMENT
- R. RADIUS
- RS. RISER
- SIM. SIMILAR
- SP. SPACES
- T.B.D. TO BE DETERMINED
- TR. TREAD
- TYP. TYPICAL
- U. UNIT(S)
- VERT. VERTICAL
- V.I.F. VERIFY IN FIELD

TREE PROTECTION CHART

Keynote	Tag #	Protected	Offsite	Common Name	Botanical Name	DBH (inches)	Status	Note
1	9543	Y	N	Coast Redwood	Sequoia sempervirens	51	Retain and Protect	
2	9544	Y	N	Coast Redwood	Sequoia sempervirens	52	Remove	Poor Condition (See Arborist Report)
3	9545	Y	N	Italian Cypress	Cupressus sempervirens	15	Remove	
4	9546	Y	N	Italian Cypress	Cupressus sempervirens	17	Remove	
5	9547	N	N	Italian Cypress	Cupressus sempervirens	11	Remove	
6	9548	N	N	Sweetgum	Liquidambar	10	Retain and Protect	
7	9549	N	N	Sweetgum	Liquidambar	9	Retain and Protect	



GENERAL NOTES

- 1. DRAWINGS**
The drawings are for information only. The Contractor shall check and verify all dimensions, and existing conditions including structures, surface and subsurface utilities, pavements, and landscaping at site prior to commencement of the work. Any discrepancies in drawings shall be brought to the attention of the Owner's Representative and Landscape Architect. No work shall proceed until a resolution has been agreed upon to the satisfaction of the Owner's Representative.
- 2. SITE ACCEPTANCE**
The Contractor shall review the project site to verify that conditions are suitable to receive work and that no defects or errors are present which would cause defective installation of products or cause latent defects in workmanship and function. Any discrepancies shall be brought to the attention of the Owner's Representative in writing. Commencement of work constitutes the Contractor's acceptance of the site conditions.
- 3. CODES AND ORDINANCES**
All work and materials shall be in full accordance with all applicable federal, state, and local laws or codes and the applicable requirements of all regulatory agencies.
- 4. UTILITIES**
Contact Common Ground Alliance (C.G.A.) at 811, at least two working days in advance of work (per CA GOV. CODE 4216). Protect existing features and utilities to remain during construction until final completion. If live utilities are encountered which were not indicated previously, protect the same from damage and immediately notify the owner's representative and affected utility provider. Do not proceed until further instructions are received from the owner's representative. The contractor is solely responsible and shall pay for repairs to damaged utilities due to the contractor's operations.
- 5. EXISTING CONSTRUCTION**
The project involves construction within existing infrastructure systems and adjacent to existing facilities which are to remain operational and accessible at all times. All existing construction to remain shall be protected. New work shall meet existing construction level, plumb, and consistent. Any existing construction damaged by Contractor shall be replaced at Contractor's expense. Any disturbed areas outside project limit of work are to be restored to original conditions at Contractor's expense.
- 6. CONSTRUCTION MEANS AND COORDINATION**
The Contractor:
- Shall be solely responsible for and have control over construction means, methods, techniques, sequences, and procedures and for coordinating all portions of work under the contract.
- Shall supervise and direct the work, using the Contractor's best skill and attention.
- Shall coordinate the location and installation of all site work.
- Shall coordinate all trades. Any work that must be removed or relocated due to lack of coordination of the trades is solely the Contractor's responsibility. Lack of specific details shall not be an excuse for improper installation of any material, device, or system.
- Shall maintain a secure site throughout the construction process.
- 7. LAYOUT NOTES**
Written dimensions take precedence over scaled dimensions. Dimensions indicated on plans for horizontal control are accurate if measured on a level line. Measure horizontal control dimensions on a level line, not parallel with ground slope. Dimensions are to face of finish unless otherwise noted. Where dimensions are noted to be verified in field (VIF) the dimension shown is the design basis but may differ from actual conditions. Contractor shall verify these dimensions while laying out the work and report any discrepancies between the design basis and actual dimensions to the owner's representative prior to proceeding with the work. Where dimensions are noted "+/-" field dimensions may vary from the noted dimensions by minor amounts.
- 8. VERTICAL CONSTRUCTION**
All vertical construction shall be installed true and plumb. All unit coursing, tops of walls, fences, and other vertical elements, shall be level unless otherwise noted. All curves shall be continuous and consistent tangential arcs, with no breaks or angles at points of tangency or formwork jointing.
- 9. FENCING**
Fence locations and heights shown are diagrammatic. Final locations and heights are to be coordinated in the field by the landscape contractor.

I HAVE COMPLIED WITH THE CRITERIA OF THE WATER CONSERVATION IN LANDSCAPE ORDINANCE AND HAVE APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE LANDSCAPE AND IRRIGATION DESIGN.


Jorge Daniel Abich
JORGE DANIEL ABICH, P.L.A. (CA #5899)

SEE SHEET L1.2 FOR CONSTRUCTION DETAILS



ABICH LANDSCAPE ARCHITECTURE
CONSULTING + CONSTRUCTION
2043 San Pablo Avenue
Berkeley, CA 94702
abichlandarch@gmail.com
(510) 905-7444

LANDSCAPE IMPROVEMENTS
311 HAWTHORNE AVE.
LOS ALTOS, CA 94022



Date	No.	Revision Notes


Issue No.	PERMIT SET	Project ID	2204-01
Drawn By	D1	Reviewed By	P1
Date	12/15/2022	CAD File Name	311 Hawthorne.vwx

LAYOUT AND MATERIALS

L1.1

NOTE:


1. GEOTECHNICAL REPORT RECOMMENDATIONS SHALL SUPERCEDE PAVEMENT DESIGN REQUIREMENTS IN THIS DETAIL, IF AND WHEN AVAILABLE.



1 CONCRETE PAVEMENT (VEHICULAR)
SCALE: 1 1/2" = 1'-0"

NOTE:


1. GEOTECHNICAL REPORT RECOMMENDATIONS SHALL SUPERCEDE PAVEMENT DESIGN REQUIREMENTS IN THIS DETAIL, IF AND WHEN AVAILABLE.



2 CONCRETE PAVEMENT (PEDESTRIAN)
SCALE: 1 1/2" = 1'-0"

NOTE:


1. GEOTECHNICAL REPORT RECOMMENDATIONS SHALL SUPERCEDE PAVEMENT DESIGN REQUIREMENTS IN THIS DETAIL, IF AND WHEN AVAILABLE.



3 CONCRETE PAVERS
SCALE: 1 1/2" = 1'-0"

NOTE


1. BLACK ENAMEL PAINTED FINISH, TYP. U.O.N.





4 STEEL HEADER
SCALE: 1 1/2" = 1'-0"

NOTE

1. DO NOT COMPACT SOIL IN TREE DRILINES OR AREAS OF UNDISTURBED SUBGRADING






5 DECORATIVE GRAVEL
SCALE: 2" = 1'-0"



6 FENCE
SCALE: 3/4" = 1'-0"

NOTES:

- ALL FASTENERS SHALL BE GALVANIZED
- ALL WOOD SHALL BE CONSTRUCTION COMMON REDWOOD OR BETTER U.O.N.
- STEP FENCE AT POSTS, FOR GRADES 1-6 (17%) OR GREATER, SLOPE PANELS WITH GRADE
- STAIN HOMEOWNER SIDE WITH SEMI-TRANSPARENT EXT. STAIN COLOR PER BUILDER (SEE COLOR SAMPLES)



7 GATE
SCALE: 3/4" = 1'-0"

NOTES:


- ALL FASTENERS SHALL BE GALVANIZED
- ALL WOOD SHALL BE CONSTRUCTION COMMON REDWOOD OR BETTER U.O.N.
- STAIN BOTH SIDES WITH SEMI-TRANSPARENT EXT. STAIN COLOR PER BUILDER (SEE COLOR SAMPLES)

REPRESENTATIVE STAIN COLORS



THOMAS JAMES HOMES
 ABICH LANDSCAPE ARCHITECTURE CONSULTING
 2043 San Pablo Avenue
 Berkeley, CA 94702
 abichlandarch@gmail.com
 (510) 905-7444

LANDSCAPE IMPROVEMENTS
 311 HAWTHORNE AVE.
 LOS ALTOS, CA 94022




Date	No.	Revision Notes

Issue No:	PERMIT SET	Project ID:	2204-01
Drawn By:	D1	Reviewed By:	P1
Date:	12/15/2022	CAD File Name:	311 Hawthorne.vwx

CONSTRUCTION DETAILS

L1.2



IRRIGATION LEGEND

CONTROLLER

Symbol	Manufacturer	Series	Model	Quantity	Note
C	Hunter Industries(R)	Pro-HC	PHC-1200	1	Locate controller as directed by builder. Controller shown at approximate location only. Coordinate with builder for all required penetrations and 120v power. 12 station controller.

VALVES

Symbol	Manufacturer	Series	Model	Type	Zone ID	Size	Design Flow	Note (*)
⊙	Toro(R)	EZ-Fl(R) Plus Jar-Top Series	EZF-29-03	Control / Zone	A1	0.75	5.00	F Series Y Filter and 40PSI Pressure Regulator
⊙	Toro(R)	EZ-Fl(R) Plus Jar-Top Series	EZF-29-03	Control / Zone	A2	0.75	11.66	F Series Y Filter and 40PSI Pressure Regulator
⊙	Toro(R)	EZ-Fl(R) Plus Jar-Top Series	EZF-29-03	Control / Zone	A3	0.75	17.00	F Series Y Filter and 40PSI Pressure Regulator
⊙	Toro(R)	EZ-Fl(R) Plus Jar-Top Series	EZF-29-03	Control / Zone	A4	0.75	11.24	F Series Y Filter and 40PSI Pressure Regulator
⊙	Toro(R)	EZ-Fl(R) Plus Jar-Top Series	EZF-29-03	Control / Zone	A5	0.75	4.33	F Series Y Filter and 40PSI Pressure Regulator
⊘	Nibco	Gate Valves	T-113	Isolation / Shut Off			0.00	

SYSTEM COMPONENTS

Symbol	Manufacturer	Series	Model	Type	Qty	Note
WS	Hunter Industries(R)	Rain Sensor	MINI-CLK(R)	Environmental Sensor / Station	1	Place on gutter in inconspicuous area.
⬢	Hunter Industries(R)	Flow Meter	HC-100-FLOW	Flow Sensor	1	Per Detail 5/L2.2
⊕	Hunter Industries(R)	Automatic Flush Valve	AFV-B	Blow Out Connection	12	Per Detail 10/L2.2
⬢	Rain Bird(R)	Drip System Operation Indicator	OPERIND	Other	12	Per Detail 12/L2.2

IRRIGATION SPRAY AND BUBBLER HEADS

Symbol	Manufacturer	Series (Body)	Model	Series (Nozzles)	Model	Quantity	Pattern	Arc	Radius
⊙	Toro(R)	1/2 in MPT Adapter 17 mm barb	i560-M50	Flood Bubbler	570	44	Radial		2'0"
⊙	Hunter Industries(R)	570Z Series	570Z-6P	MP Rotator(R)	MP1000-360	3	Radial	360°	10'0"
⊙	Hunter Industries(R)	570Z Series	570Z-6P	MP Rotator(R)	MP1000-90	1	Radial	180°	10'0"
⊙	Hunter Industries(R)	570Z Series	570Z-6P	MP Rotator(R)	MP1000-90	1	Radial	180°	10'0"
⊙	Hunter Industries(R)	570Z Series	570Z-6P	MP Rotator(R)	MP1000-90	4	Radial	90°	10'0"
⊙	Hunter Industries(R)	570Z Series	570Z-6P	MP Rotator(R)	MP1000-90	6	Radial	180°	10'0"


DRIP LINE

Symbol	Manufacturer	Series	Model	Area	Row Spacing	Estimated Length	Note
▨	Toro(R)	DL2000(TM) Series	RGP-218	5696 sq ft	1'6"	3798'0 1/4"	Triangulate Emitters

MAINLINE AND LATERAL PIPING

	Type	Diameter	Total Length
SLEEVE	PVC Schedule 80	1 1/4"	40'4 1/2"
	PVC Schedule 40	1 1/4"	76'4 1/4"
MAINLINE	PVC Schedule 40	1"	238'9 1/2"
	PVC Schedule 40	3/4"	542'2 3/4"
LATERAL	PVC Schedule 40	1/2"	414'0 1/8"
	Polyethylene Tubing	1/2"	262'6 5/8"

TAG/LABEL LEGEND



IRRIGATION NOTES


- CODES AND ORDINANCES**
The irrigation system shall be installed in conformance with all applicable state and local codes and ordinances by licensed contractors and experienced workmen. Contractor shall obtain and pay for all required permits and fees relating to their work.
- DIAGRAMMATIC PLANS**
This design is diagrammatic. All piping, valves, etc. shown within paved areas is for design clarification only and shall be installed in planting areas where possible. Avoid any conflicts between the sprinkler system, planting and architectural features. Parallel pipes may be installed in common trench. Pipes are not to be installed directly above one another. Valve locations shown are diagrammatic. Install in ground cover/shrub areas where possible (not in lawn area).
- ELECTRICAL CONNECTIONS**
Electrical contractor to supply 120 VAC (2.5 amp) GFCI Receptacle service to controller location. Irrigation contractor to make final connection from electrical stub-out to controller. Irrigation control wire shall be #16, U.L. approved for direct burial. Common wire shall be #14 U.L. approved and shall be white in color. Wiring to individual remote control valves shall be color other than white.
- FIELD OBSTRUCTIONS**
Do not willfully install the sprinkler system as shown on the drawings when it is obvious in the field that obstructions, grade differences or differences in the area dimensions exist that might not have been considered in the engineering. Such obstructions or differences should be brought to the attention of the owner's representative. If this notification is not performed, the irrigation Contractor shall assume full responsibility for any revisions necessary at no cost to the Owner. When vertical obstructions (street lights, trees, fire hydrants, etc.) interfere with the spray pattern of the heads so as to prevent proper coverage, the irrigation contractor shall field adjust the sprinkler system by installing a quarter, third, or half circle head at the sides of the obstruction so as to provide proper coverage. All adjustments shall be made at no additional cost to the Owner.
- FIELD COORDINATION**
It is the responsibility of the irrigation Contractor to familiarize himself with all grade differences, location of walls, retaining walls, etc. The Contractor shall coordinate their work with the general Contractor and other Subcontractors for the location and the installation of pipe sleeves through walls, under paving, structures, etc. Contractor to verify the location of existing underground utilities and structures prior to the excavation of trenches. Contractor is to repair any damage caused by his work at no additional cost to the Owner.
- FLOW AND OPERATING PRESSURE**
The sprinkler system design is based on a 50 psi minimum operating pressure. The irrigation Contractor

- shall verify water pressure prior to construction. Report any difference between the water pressure indicated on the drawings and the actual pressure reading at the irrigation point of connection to the Owner's Representative.
- EXCAVATIONS AND TRENCHING**
All excavations are to be filled with compacted backfill. Contractor to repair all settled trenches promptly, for a period of 1 year after completion of work. Additionally, Contractor shall warrant that the irrigation system will be free from defects in materials and workmanship for a period of 1 year after final acceptance of work.
- SLEEVE AND CONDUITS**
In addition to the sleeves and conduits shown on the drawings, the irrigation contractor shall be responsible for coordinating the installation of sleeves and conduits of sufficient size under all paved areas.
- CONTROL WIRE CONNECTIONS**
Remote control valves shall be wired to controller in sequence as shown on plans. Run wire from each RCV to the controller. Splicing wires together outside of valve boxes will not be permitted. Splicing of 24-volt wires will not be permitted except in valve boxes. Leave a 36" coil of excess wire at each splice and 100 feet on center along wire run. Tape wire in bundles 10 feet on center. No taping permitted inside sleeves.
- SPARE CONTROL WIRE**
Install two (2) spare control wire for every 6 (six) stations on the controller along the entire main line. Spare wires shall be the same color (one with a white stripe) and of a different color than other control wires. Loop 36" excess wire into each single valve box and into one valve box in each group of valves.
- PRESSURE REGULATION AND FLUSHING**
The irrigation contractor shall adjust pressure regulating module at each valve to obtain the optimum operating pressure for each system. All main lines shall be flushed prior to the installation of irrigation dripline and bubblers. At 30 days after installation each system shall be flushed to eliminate glue and dirt particles from the lines.
- IRRIGATION COVERAGE**
Notify Owner's Representative of any aspects of layout that will provide incomplete or insufficient water coverage of plant material and do not proceed until instructions are obtained.
- SPRINKLER ORIENTATION**
All sprinkler heads shall be set perpendicular to finish grade of the area to be irrigated unless otherwise designated on the plans.
- CHECK VALVES**
In locations where low head drainage will cause erosion and excess water, install King Bros. CV series check valves in lateral lines for every 5' of elevation change.

I HAVE COMPLIED WITH THE CRITERIA OF THE WATER CONSERVATION IN LANDSCAPE ORDINANCE AND HAVE APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE LANDSCAPE AND IRRIGATION DESIGN.

Jorge Daniel Abich
JORGE DANIEL ABICH, PLA (CA #5899)

SEE SHEET L2.2 FOR IRRIGATION DETAILS



S. GORDON WAY



2043 San Pablo Avenue
Berkeley, CA 94702
abichlandarch@gmail.com
(510) 905-7444

LANDSCAPE IMPROVEMENTS
311 HAWTHORNE AVE.
LOS ALTOS, CA 94022



Date No. Revision Notes

Issue Note	PERMIT SET	Project ID	2204-01
Drawn By	D1	Reviewed By	P1
Date	12/15/2022	CAD File Name	311 Hawthorne.vwx


IRRIGATION PLAN

Sheet No.

L2.1

POINT OF CONNECTION NOTES:


1. ALL THREADED CONNECTIONS TO BE WRAPPED WITH PTFE WHITE TEFLON TAPE. 2 FULL WRAPS MIN. CLOCKWISE DIRECTION.
2. COORDINATE PIPE WRAPPING OR PAINTING WITH GENERAL CONTRACTOR.



1 IRRIGATION POINT OF CONNECTION
SCALE: NTS

CONTROLLER NOTES:


1. FOLLOW NEC AND ALL LOCAL REQUIREMENTS FOR ASSOCIATED ELECTRICAL WORK.
2. VERIFY THE LOCATION AND CLEARANCES TO CONTROLLER WITH GENERAL CONTRACTOR PRIOR TO INSTALLATION.
3. PROVIDE A CLEARLY WRITTEN SCHEDULE WITH CONTROLLER STATION ASSIGNMENTS ON MANUFACTURER PROVIDED SCHEDULE CARD. PLACE SCHEDULE AND PRODUCT LITERATURE IN WEATHER PROOF ZIPLOC STYLE BAG. COORDINATE STORAGE OF THESE MATERIALS WITH GENERAL CONTRACTOR.



2 WALL MOUNT IRRIGATION CONTROLLER
SCALE: NTS

VALVE NOTES:


1. ALL THREADED CONNECTIONS TO BE WRAPPED WITH PTFE WHITE TEFLON TAPE. 2 FULL WRAPS MIN. CLOCKWISE DIRECTION.
2. COORDINATE VALVE STATION TAG WITH CONTROLLER STATION ASSIGNMENT PER CONTROLLER NOTES.
3. EXTEND MAINLINE 12" MIN. BEYOND LAST VALVE. CAP FOR FUTURE CONNECTION
4. VALVES ARE TO BE LOCATED IN AN INCONSPICUOUS LOCATION IN PLANTING AREAS OR BEHIND LANDSCAPE FEATURES. VALVES ARE TO BE ALIGNED ON CENTER AND SPACED 12" MIN. TO CENTERLINE OF EACH VALVE.




3 REMOTE CONTROL ANTI-SIPHON VALVE
SCALE: NTS

TIE DOWN NOTES

1. PLACE TIE DOWN STAKES EVERY THREE FEET IN SAND, FOUR FEET IN LOAM, AND FIVE FEET IN CLAY
2. AT FITTINGS WHERE THERE IS A CHANGE OF DIRECTION SUCH AS TEES OR ELBOWS, USE TIE DOWN STAKES ON EACH LEG OF THE CHANGE OF DIRECTION




4 DRIP IRRIGATION RISER CONNECTION
SCALE: NTS



5 GATE VALVE AND FLOW METER
SCALE: NTS

DRIP LAYOUT NOTES:


1. DISTANCE BETWEEN LATERAL ROWS AND EMITTER SPACING PER IRRIGATION SCHEDULE
2. LENGTH OF THE LONGEST DRIPLINE SHALL NOT EXCEED MANUFACTURER'S RECOMMENDATIONS



6 DRIP IRRIGATION END FEED LAYOUT
SCALE: NTS

DRIP LAYOUT NOTES:


1. DISTANCE BETWEEN LATERAL ROWS AND EMITTER SPACING PER IRRIGATION SCHEDULE
2. LENGTH OF THE LONGEST DRIPLINE SHALL NOT EXCEED MANUFACTURER'S RECOMMENDATIONS



7 DRIP IRRIGATION CENTER FEED LAYOUT
SCALE: NTS

DRIP LAYOUT NOTES:


1. DISTANCE BETWEEN LATERAL ROWS AND EMITTER SPACING PER IRRIGATION SCHEDULE
2. LENGTH OF THE LONGEST DRIPLINE SHALL NOT EXCEED MANUFACTURER'S RECOMMENDATIONS
3. MAINTAIN 18" MIN. SPACING BETWEEN TREE TRUNK AND TREE BUBBLERS
4. MAINTAIN 48" MIN. SPACING BETWEEN TREE TRUNK AND ADJACENT SHRUB DRIP EMITTER LINE




8 TREE BUBBLERS
SCALE: NTS

IRRIGATION TRENCHING NOTES:

1. INSTALL CONTROL WIRING WITHIN 4" OF MAINLINE BUT NOT DIRECTLY ABOVE MAINLINE.
2. DO NOT STACK PIPES. THREE PIPES MAXIMUM PER TRENCH.
3. EXTEND SLEEVES 12" BEYOND LIMIT OF PAVEMENTS.
4. INSTALL (1) ADDITIONAL SLEEVE FOR FUTURE EXPANSION AT ALL SLEEVE LOCATIONS.
5. SLEEVE DIAMETER TO BE 2X PIPE DIAMETER. 1 PIPE PER SLEEVE/WIRE BUNDLE.




9 IRRIGATION TRENCHING
SCALE: NTS




10 DRIP IRRIGATION AUTOFLUSH VALVE
SCALE: NTS

POP-UP SPRAY HEAD NOTES:

1. PLACE HEADS 2" CLR. FROM EDGES OF ALL PAVEMENTS.
2. DO NOT USE 'MARLEX' TYPE FITTINGS, ACETAL PLASTIC FITTINGS ARE ACCEPTABLE.
3. ALL THREADED CONNECTIONS TO BE WRAPPED WITH PTFE WHITE TEFLON TAPE. 2 FULL WRAPS MIN. CLOCKWISE DIRECTION.



11 POP-UP SPRAY HEAD
SCALE: NTS



- DRIP INDICATOR NOTES**
1. PLACE 2" CLR. FROM EDGES OF ALL PAVEMENTS.
 2. INSTALL NEARBY DRIP AUTOFLUSH VALVE BOX

12 DRIP ZONE OPERATION INDICATOR
SCALE: NTS




2043 San Pablo Avenue
Berkeley, CA 94702
abichlandarch@gmail.com
(510) 905-7444

Project Title:

LANDSCAPE IMPROVEMENTS
311 HAWTHORNE AVE.
LOS ALTOS, CA 94022

Stamp:



Date No. Revision Notes

Issue No. PERMIT SET Project ID 2204-01

Drawn By D1 Reviewed By P1


Date 12/15/2022 CAD File Name 311 Hawthorne.vwx

Sheet Title


IRRIGATION DETAILS

Sheet No.


L2.2




1 SOIL PREPARATION
SCALE: NTS




2 GROUND COVER PLANTING
SCALE: NTS



3 SHRUB PLANTING
SCALE: NTS



4 TREE PLANTING
SCALE: NTS



5 PLANT SPACING
SCALE: NTS

NOTE:
1. 'X' EQUALS PLANT SPACING. SEE PLANTING PLANS AND PLANT SCHEDULE.

PLANTING NOTES


- DRAWING CONFORMANCE**
All work shall conform to drawings and planting details. No deviations shall be accepted unless approved by the Owner's Representative.
- SITE PREPARATION**
Remove all vegetation and deleterious materials prior to rough grading operations. Test on-site soils for horticultural suitability and amendments. Preserve all horticulturally suitable topsoil by stockpiling on site. Topsoil shall be replaced in planting areas to achieve final finish grades. Rip and till areas to receive topsoil on the same day topsoil is relocated. Areas of contaminated soil shall be scraped to a depth of 24" and replaced with amended planting soil per soils analysis report.
- DRAINAGE**
All softscapes and hardscapes shall slope to drain away from buildings towards drainage appurtenances at a rate of .5% minimum to 1% maximum, unless otherwise noted.
- WORK IN RIGHT OF WAY**
Any work conducted within the right of way or to be maintained by local jurisdictional agencies shall be installed per the latest edition of the agency construction standards, and all other agency requirements.
- UTILITY CLEARANCE**
For all trees, a 5' minimum clearance shall be maintained from all water, electric and sanitary sewer utility lines. A 10' minimum clearance shall be maintained from all overhead utilities. All planting except low-growing groundcover shall be 3' clear of all fire appurtenances per NFPA 18.5.7
- SOIL TESTING**
Contractor shall submit soil samples to a certified soil testing laboratory for the determination of soil suitability and amendments. Contractor shall amend soils per the recommendations provided in the soil analysis report at the rates prescribed by the soil testing laboratory. All tree planting pits shall be backfilled with amended planting soil per the soil analysis report. Contractor shall submit a copy of the soil analysis report to the Landscape Architect for review of compliance with Water Efficient Landscape Ordinance.
- PLANT STANDARDS**
All plant material shall comply with ANSI Z60.1 "Standard For Nursery Stock," notes, and details on the drawings.

- SUBSTITUTIONS**
Planting substitutions, if necessary, shall be submitted to the Landscape Architect for approval. Any substitutions made without the approval of the Landscape Architect shall be rejected. Substitutions shall be made at no additional cost to the owner.
- TREE PLANTING**
All planting pits shall be bermed to allow for appropriate drainage. In soils with slow percolation rates, planting pits shall be augured 12" dia. X 8' depth and filled with drain rock to prevent ponding. All planting pits shall drain completely within a time frame of 2 hours.
- ROOT BARRIERS**
Root control barriers shall be utilized at any sidewalks, curbs, or hardscapes that are within 5 feet of trees. Root barrier panels shall be 18" deep and span 10' feet to each side of the centerline of the tree.
- TURF INSTALLATION**
 - Roto till or spade the area to a depth of 4 to 6 inches. Rake and smooth the soil, removing rocks, roots, and large clods
 - Ensure proper soil compaction of no more than 85% relative density.
 - Roll the area lightly with a lawn roller 1/3 full of water, maintaining the finish grade of soil 1 inch below adjacent paving.
 - Water the prepared area to settle the soil and provide a moist base for turf. Moisten the soil to a depth of 6 inches minimum.
 - Install turf immediately upon delivery. In hot weather, protect unlaidd turf by placing stacks in shade, covering with moist burlap sacking, and/or sprinkling.
 - Begin installing turf along the longest straight line, such as a driveway or sidewalk. Butt and push edges and ends against each other tightly, without stretching. Avoid gaps or overlaps. Stagger the joints in each row in a brick-like fashion at a minimum overlap of 2'. Avoid leaving small strips at outer edges as they will not retain moisture. On slopes, place the turf pieces across the slope.
 - Begin watering turf within 30 minutes of installation. To avoid causing indentations or air pockets, avoid repeated walking or kneeling on the turf while it is being installed or just after watering.
 - After installation, roll the entire area to improve turf/soil contact and remove air pockets.

- MULCHING**
All planting areas are to receive a 3" layer of bark mulch. Contractor shall submit a sample of proposed mulch material to Landscape Architect for review. All areas to receive mulch shall be treated with an organic pre-emergent herbicide to control weed growth.


- CERTIFICATE OF COMPLETION**
A Certificate of Completion shall be certified by the Landscape Contractor upon completion and final review of landscape installation and provided to the Owner's Representative for submittal to the local governing jurisdiction.

- ESTABLISHMENT PERIOD**
The establishment period shall be a minimum of 60 calendar days commencing upon written verification of substantial completion by the Owner's Representative. Contractor shall observe and maintain planting material to ensure planting material is acclimatized and displays healthy and vigorous growth. Any planting in need of replacement shall trigger an additional establishment period of 60 calendar days commencing on the date of replacement.



Notes:
1- Aspect ratio shall be less than 0.66 on all branch unions. Aspect ratio is the diameter of branch (B) divided by the diameter of the trunk (A) as measured 1" above the top of the branch union.
2- Any tree not meeting the crown observations detail may be rejected.

6 TREE BRANCHING STRUCTURE
SCALE: NTS



Notes:
1- Observations of roots shall occur prior to acceptance. Roots and substrate may be removed during the observation process; substrate/soil shall be replaced after observation has been completed.
2- Small roots (1/4" or less) that grow around, up, or down the root ball periphery are considered a normal condition in container production and are acceptable however they should be eliminated at the time of planting. Roots on the periphery can be removed at the time of planting.
3- See specifications for observation process and requirements.

7 ROOT CONTAINER STRUCTURE
SCALE: NTS



2043 San Pablo Avenue
Berkeley, CA 94702
abichlandarch@gmail.com
(510) 905-7444


LANDSCAPE IMPROVEMENTS
311 HAWTHORNE AVE.
LOS ALTOS, CA 94022








Issue Note	PERMIT SET	Project ID	2204-01
Drawn By	D1	Reviewed By	P1
Date	12/15/2022	CAD File Name	311 Hawthorne.vwx

PLANTING DETAILS AND NOTES

L3.2



TREE PROTECTION LEGEND

-  (E) TREE TO REMAIN
 -  (E) TREE TO BE REMOVED, TYP.
 -  (E) NEIGHBORING TREE, TYP.
 -  'NOT PROTECTED' DESIGNATION PER ARBORIST REPORT
 -  TREE PROTECTION FENCING
- ALL TREE PROTECTION FENCING SHALL BE CHAIN LINK AND A MINIMUM OF FIVE FEET IN HEIGHT WITH POSTS DRIVEN INTO THE GROUND

TREE PROTECTION NOTES


1. Refer to the arborist report "ARBORIST REPORT AND TREE INVENTORY, June 1st, 2022" prepared by "CALTLIC"
2. Trees and shrubs not identified within the arborist report, but as included in survey drawings, are included for reference only.
3. Protect all existing items that are not noted for removal.
4. Existing trees to remain unless noted otherwise. Do not stockpile, drive over, or otherwise disturb soil under driplines of existing trees, except as required for planting operations.
5. Use hand tools only for work under driplines of existing trees to remain.
6. Trees noted to be removed shall be completely removed, including stump and root mass. Refer to arborist report for instructions on removing tree stumps within protected tree root zones.
7. No roots over 2" in diameter shall be cut except under the direction of an arborist. All cut roots shall be covered with burlap or straw and shall remain moist until re-buried in soil.
8. Contractor to refer to final arborist report for tree protection fencing locations.

TREE PROTECTION CHART

Keynote	Tag #	Protected	Offsite	Common Name	Botanical Name	DBH (inches)	Status	Note
1	9543	Y	N	Coast Redwood	Sequoia sempervirens	51	Retain and Protect	
2	9544	Y	N	Coast Redwood	Sequoia sempervirens	52	Remove	Poor Condition (See Arborist Report)
3	9545	Y	N	Italian Cypress	Cupressus sempervirens	15	Remove	
4	9546	Y	N	Italian Cypress	Cupressus sempervirens	17	Remove	
5	9547	N	N	Italian Cypress	Cupressus sempervirens	11	Remove	
6	9548	N	N	Sweetgum	Liquidambar	10	Retain and Protect	
7	9549	N	N	Sweetgum	Liquidambar	9	Retain and Protect	

NOTES


1. See arborist report for additional protection requirements. Comply with all tree protection requirements per jurisdiction.
2. Irrigate as needed to maintain health of tree.
3. Keep exposed roots moist.
4. No pruning shall be performed except under the direction of approved arborist.
5. No equipment shall operate inside the protective fencing including during fence installation and removal.
6. No materials shall be stored inside fence.



1 TREE PROTECTION FENCING
SCALE: NTS

I HAVE COMPLIED WITH THE CRITERIA OF THE WATER CONSERVATION IN LANDSCAPE ORDINANCE AND HAVE APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE LANDSCAPE AND IRRIGATION DESIGN.

J. Abich
JORGE DANIEL ABICH, PLA (CA #5899)



2043 San Pablo Avenue
Berkeley, CA 94702
abichlandarch@gmail.com
(510) 905-7444

LANDSCAPE IMPROVEMENTS


311 HAWTHORNE AVE.
LOS ALTOS, CA 94022



Issue No:	PERMIT SET	Project ID:	2204-01
Drawn By:	D1	Reviewed By:	P1
Date:	12/15/2022	CAD File Name:	311 Hawthorne.vwx

TREE PROTECTION PLAN

L3.3



VICINITY MAP
NOT TO SCALE

GENERAL NOTES

- SITE ADDRESS: 311 HAWTHORNE AVENUE, LOS ALTOS, CA 94024
- DEVELOPER: THOMAS JAMES HOMES, 255 SHORELINE DRIVE, SUITE 428, REDWOOD CITY, CA 94065, (650) 434-7966, KEN KING
- CIVIL ENGINEER: CARLSON, BARBEE & GIBSON, INC., 2633 CAMINO RAMON, SUITE 350, SAN RAMON, CA 94583, (925) 866-0322, JUSTIN R. DEKNOBLOUGH, R.C.E. 79604
- SOILS ENGINEER: ROMIG ENGINEERS, 1390 EL CAMINO REAL, 2ND FLOOR, SAN CARLOS, CA 94070, (650) 591-5224, JONATHAN J. FONE, R.C.E. 80875
- ARCHITECT: BASSENIAN LAGONI, 2031 ORCHARD DRIVE, SUITE 100, NEWPORT BEACH, CA 92660, (949) 533-9100, SOPHIA BRAVERMAN
- LANDSCAPE ARCHITECT: ABICH LANDSCAPE ARCHITECTURE & CONSULTING, 1136 HEARST AVENUE, UNIT A, BERKELEY, CA 94702, (510) 905-7444, JORGE ABICH
- CONTRACTOR SHALL COMPLY WITH ALL STATE, COUNTY AND CITY LAWS AND ORDINANCES, AND REGULATIONS OF THE DEPARTMENT OF INDUSTRIAL RELATIONS, OSHA, AND INDUSTRIAL ACCIDENT COMMISSION RELATING TO THE SAFETY AND CHARACTER OF WORK, EQUIPMENT, AND LABOR PERSONNEL.
- THE CONTRACTOR SHALL CONTACT CARLSON, BARBEE AND GIBSON, INC. AT (925) 866-0322 IF DISCREPANCIES EXIST ON THESE PLANS OR IF THE WORK TO BE DONE, OR ANY MATTER RELATED THERETO, IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS.
- THE GEOTECHNICAL REPORT, NAMED GEOTECHNICAL INVESTIGATION (ROMIG PROJECT NO. 5366-60) JANUARY 24, 2022, SHALL BE RETAINED ON THE CONSTRUCTION SITE.
- EARTHWORK, SLAB AND FOUNDATION CONSTRUCTION, SLAB SUBGRADE AND NON-EXPANSIVE FILL PREPARATION, UTILITY TRENCH BACKFILL, PAVEMENT CONSTRUCTION, AND SITE DRAINAGE SHOULD BE PERFORMED IN ACCORDANCE WITH THE GEOTECHNICAL REPORT PREPARED BY ROMIG ENGINEERS, INC., DATED JANUARY 24, 2022. ROMIG ENGINEERS SHOULD BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE OF ANY EARTHWORK AND SHOULD OBSERVE AND TEST DURING EARTHWORK AND FOUNDATION CONSTRUCTION AS RECOMMENDED IN THE GEOTECHNICAL REPORT. ROMIG ENGINEERS SHOULD BE NOTIFIED AT LEAST 5 DAYS PRIOR TO EARTHWORK, TRENCH BACKFILL AND SUBGRADE PREPARATION WORK TO ALLOW TIME FOR SAMPLING OF ON-SITE SOIL AND LABORATORY COMPACTION CURVE TESTING TO BE PERFORMED PRIOR TO ON-SITE COMPACTION DENSITY TESTING.
- ON-SITE SLOPES, AWAY FROM THE STRUCTURE, OF AT LEAST 2 PERCENT ARE RECOMMENDED FOR FLATWORK AND PAVEMENT AREAS WITH 5 PERCENT PREFERRED IN LANDSCAPE AREAS WITHIN 8 FEET OF THE STRUCTURES, WHERE POSSIBLE, AS DESCRIBED IN THE PROJECT GEOTECHNICAL INVESTIGATION REPORT.
- CONTRACTOR SHALL FOLLOW ALL PROJECT ARBORIST RECOMMENDATIONS FOR GRADING WITHIN TREE PROTECTION AREAS.

UTILITY NOTES


- EXISTING WATER SERVICE LATERAL AND METER TO REMAIN. IF EXISTING METER IS LESS THAN 1" METER, EXISTING METER IS TO BE REMOVED AND REPLACED WITH 1" WATER METER PER CALIFORNIA WATER SERVICE STANDARD DRAWING CW-555R14. WATER PROVIDER TO DETERMINE IF EXISTING WATER LATERAL IS SUITABLE FOR PROJECT FLOWS. IF WATER METER IS WITHIN DRIVEWAY OR AC PARKING STRIP, THE METER BOX AND LID MUST BE UPGRADED TO A TRAFFIC RATED BOX AND LID. LAYOUT OF WATER SERVICE FROM BACK OF WATER METER TO THE HOUSE IS SHOWN FOR REFERENCE ONLY. SAID LINE SHALL BE CONSTRUCTED PER APPROVED PLUMBING PLANS BY GOUVIS ENGINEERING.
- EXISTING SANITARY SEWER LATERAL TO BE REMOVED AND REPLACED. A NEW PROPERTY LINE CLEANOUT SHALL BE INSTALLED PER CITY OF LOS ALTOS STANDARD DETAIL SS-6. A NEW 4" SEWER LATERAL SHALL BE INSTALLED PER CITY OF LOS ALTOS STANDARD DETAIL SS-5. LAYOUT OF THE BUILDING SEWER LATERAL, FROM THE PROPERTY LINE CLEANOUT TO THE HOUSE, IS SHOWN FOR REFERENCE ONLY. LAYOUT AND CONSTRUCTION OF BUILDING SEWER SHALL FOLLOW APPROVED PLUMBING PLANS BY GOUVIS ENGINEERING.
- THE EXISTING GAS SERVICE LATERAL WILL BE ABANDONED. THE LOCATION OF THE EXISTING GAS MAIN IS UNKNOWN AND SHALL BE VERIFIED PRIOR TO ANY WORK AFFECTING SAID LINE. THIS PLAN DOES NOT COVER ABANDONMENT OF THE EXISTING GAS LATERAL.
- NEW DRY UTILITY SERVICE CONNECTIONS TO FOLLOW PLAN BY DRY UTILITY CONSULTANT.
- THE LOCATIONS OF THE UTILITIES SHOWN ON THIS PLAN ARE APPROXIMATE AND FOR REFERENCE ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY WORK AFFECTING EXISTING UTILITY LINES TO DETERMINE IF CONFLICTS EXIST.

SHEET INDEX

SHEET NO.	SHEET TITLE
GP-1	NOTES, LEGEND, ABBREVIATIONS, AND SITE PLAN
GP-2	CITY STANDARD DETAILS
GP-3	CLEAN BAY BLUEPRINT
ECP-1	EROSION CONTROL NOTES & SITE PLAN
ECP-2	EROSION CONTROL DETAILS

319 HAWTHORNE WAY
APN 170-28-044

249 S. GORDON WAY
APN 170-28-047




CAUTION:
EXISTING OVERHEAD WIRES TO REMAIN. USE EXTREME CAUTION WHEN WORKING NEAR OVERHEAD WIRES.

LEGEND


EXISTING	PROPOSED	DESCRIPTION
---	---	PROPERTY LINE (PROJECT)
---	---	PROPERTY LINE (ADJOINER)
---	---	RIGHT OF WAY LINE
---	---	CENTER LINE
---	---	SAW-CUT LINE
---	---	STRUCTURE
---	---	4" AREA DRAIN PIPE
---	---	SANITARY SEWER PIPE OR LATERAL
---	---	WATER PIPE
---	---	FENCE
---	---	SPOT ELEVATION
---	---	DOWNSPOUT (PER ARCHITECTURE)
---	---	AREA DRAIN
---	---	PROPOSED INFILTRATION DEVICE
---	---	SANITARY SEWER CLEANOUT
---	---	SANITARY SEWER MANHOLE
---	---	WATER METER
---	---	ELECTRIC METER (PER ARCHITECTURE)
---	---	GAS METER (PER ARCHITECTURE)
---	---	TREE (SEE LANDSCAPE PLANS)
---	---	STRUCTURAL CONCRETE
---	---	CONCRETE PAVEMENT
---	---	ASPHALT CONCRETE
---	---	DECORATIVE GRAVEL
---	---	TURF

ABBREVIATIONS

AC	AIR CONDITIONER	LS	LANDSCAPE
AD	AREA DRAIN	MAX	MAXIMUM
APN	ACCESSORS PARCEL NUMBER	MIN	MINIMUM
DW	DRIVEWAY	OHW	OVERHEAD WIRES
DWS	DOMESTIC WATER SERVICE	S	SLOPE
EX	EXISTING	SD	SUBDRAIN
FF	FINISHED FLOOR	SDFI	STORM DRAIN FIELD INLET
FL	FLOW LINE	SDMH	STORM DRAIN MANHOLE
GLIP	GARAGE LIP	SS	SANITARY SEWER
GB	GRADE BREAK	SSCO	SANITARY SEWER CLEANOUT
GPAD	GARAGE PAD	SSMH	SANITARY SEWER MANHOLE
HP	HIGH POINT	SW	SIDEWALK
ID	INFILTRATION DEVICE	TC	TOP OF CURB
INV	INVERT	TYP.	TYPICAL
JT	JOINT TRENCH	W	WATER
L	LENGTH	WM	WATER METER
LAT	LATERAL	WS	WATER SERVICE




1 AREA DRAIN
NOT TO SCALE



2 INFILTRATION DEVICE
NOT TO SCALE

ROUGH EARTHWORK SUMMARY

CUT	30± CY
FILL	70± CY
NET	40± CY



PRELIMINARY PLANS
NOT FOR CONSTRUCTION

DATE: DEC 2022
DRAWN BY: SLC
PROJ. ENGR: REN
PROJ. MGR: JFD

REGISTERED PROFESSIONAL CIVIL ENGINEER
SAN RAMON
ROSEVILLE
EXP. 9-30-24
WWW.CBANG.COM


311 HAWTHORNE AVENUE
CALIFORNIA

THOMAS JAMES HOMES
CITY OF LOS ALTOS


GRADING AND DRAINAGE PLAN
NOTES, LEGEND, ABBREVIATIONS, SITE PLAN

SHEET NUMBER
GP-1
1 OF 5
JOB NUMBER
3085-00

F:\3085-00\LOS ALTOS\311 HAWTHORNE AVE\CAD\GP\GP01.DWG




Approved: Date: 1/4/10
City Engineer




REVISION	
Description	Date

ENGINEERING DIVISION	
SEWER LATERAL AND SEWER RISER	SS-5

STANDARD DETAILS MAY 2010



Approved: Date: 1/4/10
City Engineer




REVISION	
Description	Date
Changed Detail Title	02/16/12

ENGINEERING DIVISION	
SEWER LATERAL CLEAN-OUT	SS-6


STANDARD DETAILS MAY 2010

PRELIMINARY PLANS
NOT FOR CONSTRUCTION

DATE	DEC 2022
DRAWN BY	SILC
PROJ. ENGR.	REN
PROJ. MGR.	JFD



SAN RAMON • (925) 866-0322
ROSEVILLE • (916) 786-4456
WWW.CBAG.COM
CIVIL ENGINEERS • SURVEYORS • PLANNERS



311 HAWTHORNE AVENUE
CALIFORNIA


GRADING AND DRAINAGE PLAN
CITY STANDARD DETAILS

THOMAS JAMES HOMES
CITY OF LOS ALTOS

SHEET NUMBER
GP-2
2 OF 5
JOB NUMBER
3085-00

Heavy Equipment Operation

Best Management Practices for the Construction Industry



Best Management Practices for the

- Vehicle and equipment operators
- Site supervisors
- General contractors
- Home builders
- Developers

Doing The Job Right

General Business Practices

- Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks.
- Perform major maintenance, repair jobs, and vehicle and equipment washing off site where cleanup is easier.
- If you must drain and replace motor oil, radiator coolant, or other fluids on site, use drip pans or drop cloths to catch drips and spills. Collect all spent fluids, store in separate containers, and properly dispose as hazardous waste (recycle whenever possible).
- Do not use diesel oil to lubricate equipment parts, or clean equipment. Use only water for any site cleaning.
- Cover exposed fifth wheel hitch and other oily or greasy equipment during rain events.

Storm water Pollution from Heavy Equipment on Construction Sites

Poorly maintained vehicles and heavy equipment that leak fuel, oil, antifreeze or other fluids on the construction site are common sources of storm drain pollution. Prevent spills and leaks by isolating equipment from runoff channels, and by watching for leaks and other maintenance problems. Remove construction equipment from the site as soon as possible.

Spill Cleanup

- Clean up spills immediately when they happen.
- Never hose down "dirty" pavement or impermeable surfaces where fluids have leaked. Use dry cleanup methods (absorbent materials, cat litter, and/or rags) whenever possible and properly dispose of absorbent materials.
- Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- Use as little water as possible for dust control. Ensure water used doesn't leave silt or discharge to storm drains.
- Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- Report significant spills to the appropriate local spill response agencies immediately.
- If the spill poses a significant hazard to human health and safety, property or the environment, you must also report it to the State Office of Emergency Services.

Roadwork and Paving

Best Management Practices for the Construction Industry



Best Management Practices for the

- Road crews
- Driveway/sidewalk/parking lot construction crews
- Seal coat contractors
- Operators of grading equipment, paving machines, dump trucks, concrete mixers
- Construction inspectors
- General contractors
- Home builders
- Developers

Doing The Job Right

General Business Practices

- Develop and implement erosion/sediment control plans for roadway embankments.
- Schedule excavation and grading work during dry weather.
- Check for and repair leaking equipment.
- Perform major equipment repairs at designated areas in your maintenance yard, where cleanup is easier. Avoid performing equipment repairs at construction sites.
- When refueling or when vehicle/equipment maintenance must be done on site, designate a location away from storm drains and creeks.
- Do not use diesel oil to lubricate equipment parts or clean equipment.
- Recycle used oil, concrete, broken asphalt, etc. whenever possible, or dispose of properly.

During Construction

- Avoid paving and seal coating in wet weather, or when rain is forecast, to prevent fresh materials from contacting stormwater runoff.
- Cover and seal catch basins and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- Protect drainage ways by using earth dikes, sand bags, or other controls to divert or trap and filter runoff.

Storm Drain Pollution from Roadwork

Road paving, surfacing, and pavement removal happen right at the curb, where there are numerous opportunities for asphalt, saw-cut slurry, or excavated material to illegally enter storm drains. Extra planning is required to store and dispose of materials properly and guard against pollution of storm drains, creeks, and the Bay.

Doing The Job Right

General Business Practices

- Never wash excess material from exposed aggregate concrete or similar treatments into a street or storm drain. Collect and recycle, or dispose to dirt area.
- Cover stockpiles (asphalt, sand, etc.) and other construction materials with plastic tarps. Protect from rainfall and prevent runoff with temporary roofs or plastic sheets and berms.
- Park paving machines over drip pans or absorbent material (oath, rags, etc.) to catch drips when not in use.
- Clean up all spills and leaks using "dry" methods (with absorbent materials and/or rags), or dig up, remove, and properly dispose of contaminated soil.
- Collect and recycle or appropriately dispose of excess abrasive gravel or sand.
- Avoid over-application by water trucks for dust control.

Asphalt/Concrete Removal

- Avoid creating excess dust when breaking asphalt or concrete.
- After breaking up old pavement, be sure to remove all chunks and pieces. Make sure broken pavement does not come in contact with rainfall or runoff.
- When making saw cuts, use as little water as possible. Shovel or vacuum saw-cut slurry and remove from the site. Cover or protect storm drain inlets during saw-cutting. Sweep up, and properly dispose of, all residues.
- Sweep, never hose down streets to clean up tracked dirt. Use a street sweeper or vacuum truck. Do not dump vacuumed liquor in storm drains.

Fresh Concrete and Mortar Application

Best Management Practices for the Construction Industry



Best Management Practices for the

- Masons and bricklayers
- Sidewalk construction crews
- Patio construction workers
- Construction inspectors
- General contractors
- Home builders
- Developers
- Concrete delivery/pumping workers

Doing The Job Right

General Business Practices

- Wash out concrete mixers only in designated wash-out areas in your yard, away from storm drains and waterways, where the water will flow into a temporary waste pit in a dirt area. Let water percolate through soil and dispose of settled, hardened concrete as garbage. Whenever possible, recycle washout by pumping back into mixers for reuse.
- Wash out chutes onto dirt areas at site that do not flow to streets or drains.
- Always store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Protect dry materials from wind.
- Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from streets, gutters, storm drains, rainfall, and runoff.
- Do not use diesel fuel as a lubricant on concrete forms, tools, or trailers.

Storm Drain Pollution from Fresh Concrete and Mortar Applications

Fresh concrete and cement-related mortars that wash into lakes, streams, or estuaries are toxic to fish and the aquatic environment. Disposal of these materials to the storm drains or creeks can block storm drains, cause serious problems, and is prohibited by law.

During Construction

- Don't mix up more fresh concrete or cement than you will use in a two-hour period.
- Set up and operate small mixers on tarps or heavy plastic drop cloths.
- When cleaning up after driveway or sidewalk construction, wash fines onto dirt areas, not down the driveway or into the street or storm drain.
- Protect applications of fresh concrete and mortar from rainfall and runoff until the material has dried.
- Wash down exposed aggregate concrete only when the wash water can (1) flow into a dirt area, (2) drain onto a bermed surface from which it can be vacuumed from a catchment created by blocking a storm drain inlet. If necessary, divert runoff with temporary berms. Make sure runoff does not reach gutters or storm drains.
- When breaking up pavement, be sure to pick up all the pieces and dispose of properly. Recycle large chunks of broken concrete at a landfill.
- Never bury waste material. Dispose of small amounts of excess dry concrete, grout, and mortar in the trash.
- Never dispose of washout into the street, storm drains, drainage ditches, or streams.

Preventing Pollution: It's Up to Us

In the Santa Clara Valley, storm drains transport water directly to local creeks and San Francisco Bay without treatment. Storm water pollution is a serious problem for wildlife dependent on our waterways and for the people who live near polluted streams or bay lands. Some common sources of this pollution include spilled oil, fuel, and fluids from vehicles and heavy equipment; construction debris; sediment created by erosion; landscaping runoff containing pesticides or weed killers; and materials such as used motor oil, antifreeze, and paint products that people pour or spill into a street or storm drain.

Thirteen valley municipalities have joined together with Santa Clara County and the Santa Clara Valley Water District to educate local residents and businesses and fight storm water pollution. TO comply with this program, contractors most comply with the practices described in this drawing sheet.

Spill Response Agencies

DIAL 9-1-1
State Office of Emergency Services Warning Center (24 hours): 800-852-7550
Santa Clara County Environmental Health Services: (408) 299-6930

Local Pollution Control Agencies

County of Santa Clara Pollution Prevention Program: (408) 441-1195
County of Santa Clara Integrated Waste Management Program: (408) 441-1198
County of Santa Clara District Attorney Environmental Crimes Hotline: (408) 299-TIPS
Santa Clara County Recycling Hotline: 1-800-533-8414
Santa Clara Valley Water District: (408) 265-2600
Santa Clara Valley Water District Pollution Hotline: 1-888-510-5151
Regional Water Quality Control Board San Francisco Bay Region: (510) 622-2300
Palo Alto Regional Water Quality Control Plant: (650) 329-2598
Serving East Palo Alto Sanitary District, Los Altos, Los Altos Hills, Mountain View, Palo Alto, Stanford

City of Los Altos
Building Department: (650) 947-2752
Engineering Department: (650) 947-2780

Landscaping, Gardening, and Pool Maintenance

Best Management Practices for the Construction Industry



Best Management Practices for the

- Landscapers
- Gardeners
- Swimming pool/spa service and repair workers
- General contractors
- Home builders
- Developers
- Homeowners

Doing The Right Job

General Business Practices

- Protect stockpiles and landscaping materials from wind and rain by storing them under tarps or secured plastic sheeting.
- Store pesticides, fertilizers, and other chemicals indoors or in a shed or storage cabinet.
- Schedule grading and excavation projects during dry weather.
- Use temporary check dams or ditches to divert runoff away from storm drains.
- Protect storm drains with sandbags or other sediment controls.
- Re-vegetation is an excellent form of erosion control for any site.

Storm Drain Pollution from Landscaping and Swimming Pool Maintenance

Many landscaping activities expose soils and increase the likelihood that earth and garden chemicals will run off into the storm drains during irrigation or when it rains. Swimming pool water containing chlorine and copper-based algaecides should never be discharged to storm drains. These chemicals are toxic to aquatic life.

Landscaping/Garden Maintenance

- Use pesticides sparingly according to instructions on the label. Rinse empty containers, and use rinse water as product. Dispose of rinsed, empty containers in the trash. Dispose of unused pesticides as hazardous waste.
- Collect lawn and garden clippings, pruning waste, and tree trimmings. Chip if necessary, and compost.
- Communicate with curbside pick-up of the curb in approved bags or containers. Or take to a landfill that accepts yard waste. No curbside pickup of yard waste is available for commercial properties.

Painting and Application of Solvents and Adhesives

Best Management Practices for the Construction Industry



Best Management Practices for the

- Homeowners
- Painters
- Pipefitters
- Plasterers
- Graphic artists
- Dry wall crews
- Floor covering installers
- General contractors
- Home builders
- Developers

Doing The Job Right

Handling Paint Products

- Keep all liquid paint products and wastes away from the gutter, street, and storm drains. Liquid residues from paints, thinners, solvents, glues, and cleaning fluids are hazardous waste and must be disposed of at a hazardous waste collection facility (contact your local stormwater program listed on the back of this brochure).
- When thinning dry, empty paint cans, used brushes, rags, and drop cloths may be disposed of as garbage in a sanitary landfill. Empty dry paint cans also may be recycled as metal.
- Wash water from painted buildings constructed before 1978 can contain lead amounts of lead, even if paint chips are not present. Before you begin stripping paint or cleaning pre-1978 building exteriors with water under high pressure, test paint for lead by taking paint scrapings to a local laboratory. See Yellow Pages for a state-certified laboratory.
- If there is loose paint on the building, or if the paint tests positive for lead, block storm drains. Check with the wastewater treatment plant to determine whether you may discharge water to the sanitary sewer, or if you must send it offsite for disposal as hazardous waste.

Storm Drain Pollution from Paints, Solvents, and Adhesives

All paints, solvents, and adhesives contain chemicals that are harmful to wildlife in local creeks, San Francisco Bay, and the Pacific Ocean. Toxic chemicals may come from liquid or solid products or from cleaning residues or rags. Paint material and solvents, adhesives and cleaning fluids should be recycled when possible, or disposed of properly to prevent these materials from flowing into storm drains and watercourses.

Painting Cleanup

- Never clean brushes or rinse paint containers into a street, gutter, storm drain, French drain, or stream.
- For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to a sanitary sewer. Never pour paint down a storm drain.
- For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids and residue as hazardous waste.
- Paint Removal
Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury or tributyl tin must be disposed of as hazardous waste. Lead based paint removal requires a state-certified contractor.
- When stripping or cleaning building exteriors with high-pressure water, block storm drains. Direct wash water onto a dirt area and spade into soil. Or, check with the local wastewater treatment authority to find out if you can collect (no vacuum) building cleaning water and dispose to the sanitary sewer. Sampling of the water may be required to assist the wastewater treatment authority in making its decision.
- Recycle/Reuse Latex/Paints
Whenever Possible
□ Recycle or donate excess water-based (latex) paint, or return to supplier.
□ Reuse leftover oil-based paint. Dispose of non-recyclable thinners, sludge and unwanted paint, as hazardous waste.
- Unopened cans of paint may be able to be returned to the paint vendor. Check with the vendor regarding its "buy-back" policy.

Los Altos Municipal Code Requirements

Los Altos Municipal Code Chapter 10.08.390 Non-storm water discharges

- Unlawful discharges. It shall be unlawful to discharge any domestic waste or industrial waste into storm drains, gutters, creeks, or San Francisco Bay. Unlawful discharges to storm drains shall include, but not be limited to, discharge from toilets; sinks; industrial processes; cooling systems; boilers; fabric cleaning; equipment cleaning; vehicle cleaning; construction activities, including, but not limited to, painting, paving, concrete placement, saw cutting and grading; swimming pools; spas; and fountains, unless specifically permitted by a discharge permit or unless exempted pursuant to guidelines published by the superintendent.
- Threatened discharges. It shall be unlawful to cause hazardous materials, domestic waste, or industrial waste to be deposited in such a manner or location as to constitute a threatened discharge into storm drains, gutters, creeks or San Francisco Bay. A "threatened discharge" is a condition creating a substantial probability of harm, when the probability and potential extent of harm make it reasonably necessary to take immediate action to prevent, reduce or mitigate damages to persons, property or natural resources. Domestic or industrial wastes that are no longer contained in a pipe, tank or other container are considered to be threatened discharges unless they are actively being cleaned up.


Los Altos Municipal Code Section 10.08.430 Requirements for construction operations.

- A spill response plan for hazardous waste, hazardous materials and uncontained construction materials shall be prepared and available at the construction sites for all projects where one acre or disturbed soil and for any other projects for which the city engineer determines is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer.
- A storm water pollution prevention plan shall be prepared and available at the construction sites for all projects greater than one acre of disturbed soil and for any other projects for which the city engineer determines that a storm water management plan is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer.
- Prior approval shall be obtained from the city engineer or designee to discharge water pumped from construction sites to the storm drain. The city engineer or designee may require gravity settling and filtration upon a determination that either or both would improve the water quality of the discharge. Contaminated groundwater or water that exceeds state or federal requirements for discharge to navigable waters may not be discharged to the storm drain. Such water may be discharged to the sewer, provided that the requirements of Section 10.08.240 are met and the approval of the superintendent is obtained prior to discharge.
- No cleanup of construction debris from the streets shall result in the discharge of water to the storm drain system; nor shall any construction debris be deposited or allowed to be deposited in the storm drain system. (Prior code § 6-5.643)

Criminal and judicial penalties can be assessed for non-compliance.

General Construction And Site Supervision

Best Management Practices For Construction



Best Management Practices for the

- General contractors
- Site supervisors
- Inspectors
- Home builders
- Developers

Doing The Job Right

General Principals

- Keep an orderly site and ensure good housekeeping practices are used.
- Maintain equipment properly.
- Cover materials when they are not in use.
- Keep materials away from streets, storm drains and drainage channels.
- Ensure dust control water doesn't leave site or discharge to storm drains.

Advancing Planning To Prevent Pollution

- Schedule excavation and grading activities for dry weather periods. To reduce soil erosion, plant temporary vegetation or place other erosion controls before rain begins. Use the Erosion and Sediment Control Manual available from the Regional Water Quality Control Board, as a reference.
- Control the amount of runoff crossing your site (especially during excavation) by using berms or temporary or permanent drainage ditches to divert water flow around the site. Reduce storm water runoff velocities by constructing temporary check dams or berms where appropriate.
- Train your employees and subcontractors. Make these best management practices available to everyone who works on the construction site. Inform subcontractors about the storm water requirements and their own responsibilities.

Good Housekeeping Practices

- Designate one area of the site for auto parking, vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets, bermed if necessary. Make major repairs off site.
- Keep materials out of the rain - prevent runoff contamination at the source. Cover exposed piles of soil or construction materials with plastic sheeting or temporary roofs. Before it rains, sweep and remove materials from surfaces that drain to storm drains, creeks, or channels.
- Keep pollutants off exposed surfaces. Place trashcans and recycling receptacles around the site to minimize litter.

Clean up leaks, drips and other spills immediately so they do not contaminate soil or groundwater or leave residue on paved surfaces. Use dry cleanup methods whenever possible. If you must use water, use just enough to keep the dust down.


- When refueling or vehicle/equipment maintenance must be done on site, designate a location away from storm drains.
- Do not use diesel oil to lubricate equipment parts, or clean equipment.
- Practices During Construction
□ Remove existing vegetation only when absolutely necessary. Plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- Protect down slope drainage courses, streams, and storm drains with wattles, or temporary drainage swales. Use check dams or ditches to divert runoff around excavations. Refer to the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control measures.

Materials/Waste Handling

- Practice Source Reduction - minimize waste when you order materials. Order only the amount you need to finish the job.
- Use recyclable materials whenever possible. Arrange for pick-up of recyclable materials such as concrete, asphalt, scrap metal, solvents, degreasers, cleaned vegetation, paper, rock, and vehicle maintenance materials such as used oil, antifreeze, batteries, and tires.
- Dispose of all wastes properly. Many construction materials and wastes, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation can be recycled. Materials that cannot be recycled must be taken to an appropriate landfill or disposed of as hazardous waste. Never bury waste materials or leave them in the street or near a creek or stream bed.
- Permits
□ In addition to local building permits, you will need to obtain coverage under the State's General Construction Activity Storm Water Permit if your construction site disturbs one acre or more. Obtain information from the Regional Water Quality Control Board.

Earth-Moving And Dewatering Activities

Best Management Practices for the Construction Industry



Best Management Practices for the

- Bulldozer, back hoe, and grading machine operators
- Dump truck drivers
- Site supervisors
- General contractors
- Home builders
- Developers

Doing The Job Right

General Business Practices

- Schedule excavation and grading work during dry weather.
- Perform major equipment repairs away from the job site.
- When refueling or vehicle/equipment maintenance must be done on site, designate a location away from storm drains.
- Do not use diesel oil to lubricate equipment parts, or clean equipment.
- Practices During Construction
□ Remove existing vegetation only when absolutely necessary. Plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- Protect down slope drainage courses, streams, and storm drains with wattles, or temporary drainage swales. Use check dams or ditches to divert runoff around excavations. Refer to the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control measures.

Storm Drain Pollution from Earth-Moving Activities and Dewatering

Soil excavation and grading operations loosen large amounts of soil that can flow or blow into storm drains when handled improperly. Sediments in runoff can clog storm drains, smother aquatic life, and destroy habitats in creeks and the Bay. Effective erosion control practices reduce the amount of runoff crossing a site and slow the flow with check dams or roughened ground surfaces.

Contaminated groundwater is a common problem in the Santa Clara Valley. Depending on soil types and site history, groundwater pumped from construction sites may be contaminated with toxics (such as oil or solvents) or laden with sediments. Any of these pollutants can harm wildlife in creeks or the Bay, or interfere with wastewater treatment plant operation. Discharging sediment-laden water from a dewatering site into any water of the state without treatment is prohibited.

Cover stockpiles and excavated soil with secured tarps or plastic sheeting.

Dewatering Operations

- Check for Toxic Pollutants**
□ Check for odors, discoloration, or an oily sheen on groundwater.
□ Call your local wastewater treatment agency and ask whether the groundwater must be tested.
□ If contamination is suspected, have the water tested by a certified laboratory.
□ Depending on the test results, you may be allowed to discharge pumped groundwater to the storm drain (if no sediments present) or sanitary sewer. OR, you may be required to collect and haul pumped groundwater offsite for treatment and disposal at an appropriate treatment facility.
- Check for Sediment Levels**
□ If the water is clear, the pumping time is less than 24 hours, and the flow rate is less than 20 gallons per minute, you may pump water to the street or storm drain.
□ If the pumping time is more than 24 hours and the flow rate greater than 20 gpm, call your local wastewater treatment plant for guidance.
□ If the water is not clear, solids must be filtered or settled out by pumping to a settling tank prior to discharge. Options for filtering include:
- Pumping through a perforated pipe sunk part way into a small pit filled with gravel.
- Pumping from a bucket placed below water level using a submersible pump;
- Pumping through a filtering device such as a swimming pool filter or filter fabric wrapped around end of suction pipe.
□ When discharging to a storm drain, protect the inlet using a barrier of burlap bags filled with drain rock, or cover inlet with filter fabric anchored under the grate. OR pump water through a grassy swale prior to discharge.


Blueprint for a Clean Bay

Remember: The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site. You may be held responsible for any environmental damage caused by your subcontractors or employees.

Best Management Practices for the Construction Industry



Santa Clara Urban Runoff Pollution Prevention Program



DESIGNED BY: LARRY LIND	APPROVED BY: <i>[Signature]</i>	CITY OF LOS ALTOS	DATE: OCTOBER, 2003
DRAWN BY: VICTOR CHEN	CITY ENGINEER	48056	SCALE: N.T.S.
CHECKED BY: JIM GUSTAFSON	SHEET	OF	SHEETS
			DRAWING NO.:





GENERAL NOTES

- SITE ADDRESS: 311 HAWTHORNE AVENUE
LOS ALTOS, CA 94024
- OWNER/DEVELOPER (DISCHARGER): THOMAS JAMES HOMES, LLC
255 SHORELINE DRIVE SUITE 428
REDWOOD CITY, CA 94065
(650) 434-7966
KEN KING
- CIVIL ENGINEER: CARLSON, BARBEE & GIBSON, INC.
2633 CAMINO RAMON, SUITE 350
SAN RAMON, CA 94583
(925) 866-0322
JUSTIN R. DEKNOBLOUGH, R.C.E. 79604

BEST MANAGEMENT PRACTICE NOTES

- IT SHALL BE THE OWNER'S DUTY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO ENSURE THE ENTIRE SITE IS IN COMPLIANCE WITH LOCAL ORDINANCES PROTECTING THE CASQA CONSTRUCTION BMP GUIDANCE HANDBOOK.
- THIS PLAN IS INTENDED TO BE UTILIZED FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY AND IS NOT TO BE UTILIZED FOR FINAL ELEVATIONS OR PERMANENT IMPROVEMENTS.
- THIS PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN AS NECESSARY IN THE FIELD. DOCUMENT AND REPORT ANY FIELD CHANGES AND NOTIFY THE CITY OR COUNTY REPRESENTATIVE OF THE FIELD CHANGES.
- ALL MAINTENANCE AND OPERATION REQUIREMENTS SHALL FOLLOW THE CASQA CONSTRUCTION BMP GUIDANCE HANDBOOK.
- THE CONTRACTOR OR OWNER SHALL EFFECT AND MAINTAIN PRECAUTIONARY MEASURES NECESSARY TO PROTECT ADJACENT WATERCOURSES AND PUBLIC OR PRIVATE PROPERTY FROM DAMAGE BY EROSION, FLOODING AND DEPOSITION OF MUD OR DEBRIS ORIGINATING FROM THE SITE.
- THE CONTRACTOR OR OWNER IS RESPONSIBLE FOR ALL ASPECTS OF EROSION CONTROL FOR THE PROJECT AND SHALL INSTALL AND MAINTAIN ANY DEVICES AND MEASURES NECESSARY TO THE SATISFACTION OF THE CITY OR COUNTY ENGINEER.
- THE CONTRACTOR OR OWNER SHALL ESTABLISH AND MAINTAIN EFFECTIVE BMP PERIMETER CONTROLS AND STABILIZED ALL CONSTRUCTION ENTRANCES AND EXITS TO SUFFICIENTLY CONTROL EROSION AND SEDIMENT DISCHARGES FROM THE SITE YEAR-ROUND.
- EROSION CONTROL MEASURES WILL BE PROPERLY IN PLACE YEAR-ROUND. ALL REMOVABLE PROTECTIVE DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE FIVE DAY RAIN PROBABILITY EXCEEDS 50 PERCENT.
- INSPECTIONS AND OBSERVATIONS SHALL OCCUR WEEKLY, AND AT LEAST ONCE EACH 24-HOUR PERIOD DURING EXTENDED STORM EVENTS, TO IDENTIFY AND RECORD BMPs THAT NEED MAINTENANCE TO OPERATE EFFECTIVELY, THAT HAVE FAILED OR THAT COULD FAIL TO OPERATE AS INTENDED.
- DISCHARGERS SHALL IMPLEMENT MEASURES TO CONTROL ALL NON-STORMWATER DISCHARGES DURING CONSTRUCTION.
- DISCHARGERS SHALL IMPLEMENT EFFECTIVE WIND EROSION CONTROL.
- STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF SITE WORK. ALL CONSTRUCTION TRAFFIC ENTERING THE PAVED ROAD MUST CROSS THE ENTRANCE. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY.
- APPLY GRAVEL CONSTRUCTION ENTRANCE MATERIAL WITHIN MATERIAL STORAGE AREA.
- APPLY GRAVEL CONSTRUCTION ENTRANCE MATERIAL WITHIN THE VEHICLE STORAGE AREA.
- PLACE ALL EQUIPMENT OR VEHICLES, WHICH ARE TO BE FUELED, MAINTAINED AND STORED IN A DESIGNATED AREA FITTED WITH APPROPRIATE BMPs.
- IMPLEMENT BMPs TO PREVENT THE OFF-SITE TRACKING OF LOOSE CONSTRUCTION AND LANDSCAPE MATERIALS.
- PAVED STREETS WILL BE MONITORED DAILY AND FREQUENTLY CLEANED. STREETS WILL ALSO BE SWEEPED ON AT LEAST A WEEKLY BASIS OR MORE OFTEN, AS NEEDED, TO MAINTAIN CONTINUOUS LITTER AND TRACKING CONTROL. STREET WASHING WILL NOT BE DONE.
- TRASH RECEPTACLES WILL BE PROVIDED THROUGHOUT THE SITE AND UTILIZED BY ALL WORKERS FOR MISCELLANEOUS TRASH. SITE REFUSE WILL BE PICKED UP ON A WEEKLY BASIS OR AS OFTEN AS NECESSARY IN ORDER TO KEEP THE SITE CLEAN.
- COVER AND BERM LOOSE STOCKPILED CONSTRUCTION MATERIALS THAT ARE NOT ACTIVELY BEING USED (I.E. SOIL, SPOILS, AGGREGATE, FLY-ASH, STUCCO, HYDRATED LIME, ETC.).
- CONTAIN AND SECURELY PROTECT STOCKPILED WASTE MATERIAL FROM WIND AND RAIN AT ALL TIMES UNLESS ACTIVELY BEING USED.
- EXCAVATING, FILLING, BACKFILLING AND GRADING WORK SHALL NOT BE PERFORMED DURING UNFAVORABLE WEATHER CONDITIONS.
- DISCHARGERS SHALL PROVIDE EFFECTIVE SOIL COVER FOR INACTIVE AREAS AND ALL FINISHED SLOPES, OPEN SPACE, UTILITY BACKFILL AND COMPLETED LOTS. INACTIVE AREAS OF CONSTRUCTION ARE AREAS OF CONSTRUCTION ACTIVITY THAT HAVE BEEN DISTURBED AND ARE NOT SCHEDULED TO BE RE-DISTURBED FOR AT LEAST 14 DAYS.
- SLOPES WILL BE GRADED SO THAT WATER IS DIRECTED AWAY FROM THE SLOPE FACES AT THE END OF EACH WORKING DAY WHEN A CHANCE OF RAIN IS FORECAST.
- ALL RILLS, GULLIES, ETC. WILL BE PROMPTLY REPAIRED AS PRACTICAL BY REGRADING OR INSTALLATION OF SOIL, GRAVEL OR SANDBAGS.
- ALL DRAIN INLETS WILL BE PROTECTED AS THEY ARE COMPLETED, DURING THE ENTIRE COURSE OF CONSTRUCTION.
- IF SEDIMENT BASINS ARE TO BE USED, DISCHARGERS SHALL, AT A MINIMUM DESIGN SEDIMENT BASINS ACCORDING TO THE METHOD PROVIDED IN CASQA'S CONSTRUCTION BMP GUIDANCE HANDBOOK.
- AFTER EACH RAINSTORM, SILT AND DEBRIS SHALL BE REMOVED FROM CHECK DAMS, FIBER ROLLS, SILT FENCES AND SILT SACKS. SEDIMENT TRAPS/BASINS SHOULD ALSO BE OBSERVED AND PUMPED DRY AS NECESSARY TO ASSURE PROPER FUNCTION AND CAPACITY.
- INTERIOR FIBER ROLLS MAY BE REMOVED AS THE AREA COMES UNDER CONSTRUCTION FOR FINISH GRADING AND LANDSCAPING INSTALLATION. PERIMETER PROTECTION SHOULD BE LEFT IN PLACE YEAR-ROUND DURING CONSTRUCTION OR DEMOLITION.
- AT A MINIMUM, TREE PROTECTION FENCING IS TO BE ORANGE CONSTRUCTION FENCING AND PLACED AROUND TREE TO CREATE A TREE PROTECTION ZONE AND SHALL BE INSTALLED AROUND TREES THAT ARE TO REMAIN. IF PROJECT ARBORIST REQUIRES ADDITIONAL PROTECTIONS, THE CONTRACTOR SHALL FOLLOW AND INSTALL SAID PROTECTIONS.



- LEGEND**
- PROPERTY BOUNDARY
 - ADJONER PROPERTY LINE
 - EXISTING FENCE
 - TREE PROTECTION FENCE
 - TEMPORARY TREE PROTECTION FENCE DURING DEMOLITION
 - FIBER ROLL - (EC-1 & EC-4)
 - TREE NUMBER PER ARBORIST REPORT (RETAINED)
 - TREE NUMBER PER ARBORIST REPORT (REMOVE)
 - STABILIZED CONSTRUCTION ENTRANCE/EXIT - (EC-2)
 - DIRECTION OF EXISTING RUNOFF FLOW

- PROJECT SUPERINTENDENT TO MARK KNOWN LOCATIONS***
- MATERIALS AND EQUIPMENT STORAGE AREA (WM-1 - WM-3**)
 - SANITARY FACILITY (WM-9**)
 - CONCRETE/WASTE WASHOUT (WM-8)

NOTE:

- * THE MATERIALS AND EQUIPMENT STORAGE AREA AND SANITARY FACILITY WILL BE PLACED AT THE PROJECT SUPERINTENDENT'S DISCRETION AND ARE SUBJECT TO CHANGE.
- ** DENOTES SECTION RELATED TO BMP IN THE CASQA BMP HANDBOOK.

- CURRENT CASQA STORMWATER BMP CONSTRUCTION HANDBOOK DETAILS**
- EC-1 SCHEDULING
 - NS-1 WATER CONSERVATION PRACTICES
 - NS-8 VEHICLE & EQUIPMENT CLEANING
 - NS-9 VEHICLE & EQUIPMENT FUELING
 - NS-10 VEHICLE & EQUIPMENT MAINTENANCE
 - NS-12 CONCRETE DURING
 - NS-13 CONCRETE FINISHING
 - SE-1 SILT FENCE
 - SE-5 FIBER ROLLS
 - SE-8 SANDBAG BARRIER
 - SE-10 STORM DRAIN INLET PROTECTION
 - TC-1 STABILIZED CONSTRUCTION ENTRANCE/EXIT
 - WE-1 WIND EROSION CONTROL
 - WM-1 MATERIAL DELIVERY & STORAGE
 - WM-2 MATERIAL USE
 - WM-3 STOCKPILE MANAGEMENT
 - WM-8 CONCRETE WASTE MANAGEMENT
 - WM-9 SANITARY/SEPTIC WASTE MANAGEMENT


- SHEET INDEX**
- EC-1 EROSION CONTROL PLAN
 - EC-2 EROSION CONTROL NOTES & DETAILS

EXISTING TREES TO BE RETAINED

TREE NUMBER	COMMON NAME	DBH (IN)
1	COAST REDWOOD	51
6	SWEETGUM	10
7	SWEETGUM	9

EXISTING TREES TO BE REMOVED

TREE NUMBER	COMMON NAME	DBH (IN)
2	COAST REDWOOD	18
3	ITALIAN CYPRESS	15
4	ITALIAN CYPRESS	17
5	ITALIAN CYPRESS	11



**PRELIMINARY PLANS
NOT FOR CONSTRUCTION**

DATE: DEC 2022
DRAWN BY: SLC
PROJ. ENGR.: REN
PROJ. MGR.: JRD



JUSTIN R. DEKNOBLOUGH, R.C.E.
CIVIL ENGINEER
EXP. 9-30-24

SAN RAMON • (925) 866-0322
ROSEVILLE • (916) 788-4456
WWW.CBGO.COM



cbg
CIVIL ENGINEERS • SURVEYORS • PLANNERS

311 HAWTHORNE AVENUE
GRADING AND DRAINAGE PLAN
EROSION CONTROL NOTES & SITE PLAN
CITY OF LOS ALTOS

SHEET NUMBER
ECP-1
4 OF 5
JOB NUMBER
3085-00



Concrete Waste Management WM-8



PRELIMINARY PLANS
NOT FOR CONSTRUCTION

DATE: DEC 2022
 DRAWN BY: SLC
 PROJ. ENGR: REN
 PROJ. MGR: JFD

REGISTERED PROFESSIONAL ENGINEER
 JUSTIN K. DEANBORN
 7864
 EXP. 9-30-24
 CIVIL
 STATE OF CALIFORNIA

SAN RAMON • (925) 866-0322
 ROSEVILLE • (916) 786-4456
 WWW.CBAG.COM

CIVIL ENGINEERS • SURVEYORS • PLANNERS

cbg
 CIVIL ENGINEERS

311 HAWTHORNE AVENUE
 THOMAS JAMES HOMES
 CALIFORNIA

GRADING AND DRAINAGE PLAN
 EROSION CONTROL DETAILS

SHEET NUMBER
ECP-2
 5 OF 5

JOB NUMBER
 3085-00