
Desphande Residence NEW RESIDENCE - DESIGN REVIEW

	_	GENERAL NOTI	
GENERAL	CODES	GREEN BUILDING CODE	Best Management Practic
 A. Permits: All permits and fees shall be secured and paid for by the Contractor. B. Substitutions: No substitutions shall be made 	A. All construction shall conform to the California Building Standards Code, California Code of Regulations, Title 24 (CCR, T-24) incorporating the latest approved edition of model codes:	A. Automatic irrigation system controllers installed at time of final inspection shall be provided with integral rain sensors or soil moisture	BASIC CONSTRUCTION PRACTIC 1. All exposed surfaces (e.g. parking areas, stagi
 c, Intent: The Intent of the drawings is to 	2019 California Building Code (CBC) 2019 California Residential Code (CRC) 2019 California Mechanical Code (CMC)	sensors that adjust irrigation in response to changes in watering needs as weather conditions change.	areas, soil piles, graded areas, and unpaveded roads) shall be watered two times per day. 2. All haul trucks transporting soil, sand, or othe
 c, intent: The intent of the drawings is to include all labor, materials, equipment, and transportation necessary for complete and proper execution of the Work. D. Changes: The Owner may order extra Work or 	2019 California Mechanical Code (CMC) 2019 California Electrical Code (CEC) 2019 California Fire Code (CEC) 2019 California Energy Standards (CES) 2019 California Green Building Code (CGBC)	B. Annular spaces around pipes, electrical cables, conduits, or other openings in plates at exterior walls shall be protected against the passage of rodents by closing such openings with cement mortar, concrete masonry, or similar accepted	 loose material off-site shall be covered. All visible mud, or dirt tracked-out onto adjac public roads shall be removed using wet powe vacuum street sweepers at least once per da The use of dry power sweeping is prohibited. All vehicle speeds on unpaved roads shall be
make changes by altering, adding to, or deducting from the Work, The Contract sum being adjusted accordingly. E. Cutting and Patching: All trades shall do their	B. All construction shall conform to local government ammendments to the Building Standards contained in CCR T-24 as filed with the Building Standards Commision (per Bulletin	method. C. A minimum of 65 percent of the construction waste generated at the site shall be divered to recycle or salvage.	 limited to 15 miles per hour. All roadways, driveways, and sidewalks to be to be completed as soon as possible. Building pads shall be laid as soon as possible after grading unless seeding or soil binders are
own cutting, fitting, patching, etc. to make the several parts come together properly and fit it to receive or be be received by the Work of other Trades.	99-01). C. All construction shall conform to all local government laws, ordinances, regulations, and interpretations as applicable to this Project.	D. An operation and maintenance manual shall be provided by the Contractor prior to final inspection.	7. Idling times shall be minimized either by shut equipment off when not in use or reducing the maximum ilding time to 5 minutes. Clear sign shall be provided for construction works at al
F. Scope: All Trades shall furnish all equipment, labor, materials, and perform all Work indicated, necessary, reasonably inferred, or required by any Code with jurisdiction to complete their	D. Approval by a Building Department Inspector does not constitute approval from any of the above.	E. Gas fireplaces shall be direct-vent sealed- combustion type. Wood/pellet stoves shall comply with U.S. E.P.A. Phase II emission limits.	access points. 8. All construction equipment shall be maintained properly tuned in accordance with manufacture specifications. All equipment shall be checked a certified visible emissions evaluator.
Scope of Work for a complete and properly finished Job.	CONSTRUCTION WASTE MANAGEMENT	F. Duct and vent openings shall be covered during construction.	9. Post a publicly visilbe sign with the telephone number and person to contact at the lead age regarding dust complaints. This person shall b
G. Clean-up: All Trades shall at all times keep the premises free from accumulation of waste materials or rubbish caused by their Work.	A. Recycle and/or salvage for reuse of non- hazardous construction and demolition debris shall	G. Adhesives, sealants, and caulks shall be compliant with V.O.C. and other toxic compound limits.	and take corrective action within 48 bhours. Air District's telephone number shall be visible ensure compliance with applicable regulations.
H. Temporary Toilets: The Contractor shall provide temporary sanitary facilities for all Trades until completion of the Work.	comply with City of Los Altos "Collection, Recycling and Disposal of Waste Generated from Construction and Renovation Projects within the City of Los Altos" ordinance - Los Altos	H. Paint, stains, and other coatings shall be compliant with V.O.C. and other toxic compound limits.	ADDITIONAL CONSTRUCTION PRACT
I. Lines and Level: The Contractor shall be responsible for the accuracy of the Building Lines and Levels. The Contractor shall carefully compare the Lines and Levels shown on the	Municipal Code, Title 6, Chapter 6.14 and/or LEED residential requirements for Silver Level. B. Documentation shall be prepared by the	I. Aerosol paints and coatings shall be compliant with product weighted M.I.R. limits for V.O.C. and other toxic compounds.	1. All exposed surface shall be watered at a free adequate to maintain minimum soil moisture of percent. Moisture content can be verified by samples or moisture probe.
Drawings with existing levels for location and construction of the Work and shall call to the attention of the Architect any differences before proceeding with the Work.	Contractor (Waste Management Plan) to demostrate compliance with the ordinance and	J. Documentation shall be provided to verify that compliant V.O.C. limited finish materials have been used.	 All excavation, grading, and/or demolition actives shall be suspended when average wind speed exceeds 20 miles per hour. Wind breaks (e.g. trees, fences) shall be instant on the windward side(s) of actively disturbed
J. On-site verification of all dimensions and conditions shall be the responsibility of the Contractor. Noted dimensions shall take	C. Mixed construction and demolition debris processors can be located at the California Department of Resources Recycling and Recovery	 K. Carpet and carpet systems shall be compliant with V.O.C. limits. L. 80 percent of floor area receiving resilient 	of construction. Wind breaks should have a maximum of 50 percent air porosity. 4. Vegetative ground cover (e.g. fast-germinating
precedence and measurements shall not be scaled from the Drawings. Contractor shall report to Architect all conditions that prevent	(CalRecycle).	flooring shall be compliant with V.O.C. limits. M. Partical board, medium density fiberboard, and	grass seed) shall be planted in disturbed areas soon as possible and watered appropriately un vegetation is established. 5. The simultanrous occurence of excavation, grav
the proper execution of the Work. K. The Architect shall be notified immediately by	FIRE SPRINKLER SYSTEM	hardwood plywood used in interior finish systems shall comply with low formaldehyde emission standards.	and ground-disturbing construction activities on same area at any one time shall be limited. Activities shall be phased to reduce the amou
the Contractor should any discrepancy or other questions arise pertaining to the Drawings and/ or Specifications. L. The Contractor shall insure that all Work is	A. Fire sprinkler system design shall be a deferred submittal (where allowed). Contractor shall submit shop drawings and any required calculations to building department for review and approval a minimum of two (2) weeks prior to installation.	N. Moisture content of building materials used in enclosed wall and floor framing is checked before enclosure and shall not exceed 19 percent.	disturbed surfaces at any one time. 6. All trucks and equipment, including their tires, be washed off prior to leaving the site. 7. Site access to a distance of 100 feet from
done in a professional and workmanlike manner by skilled mechanics and shall replace any material or items damaged by a Subcontractor's performance. Subcontractors and Suppliers are	B. An Owner's manual for the fire sprinkler system shall be provided to the Owner. A sign or valve tag shall be installed at the main shutoff	O. Whole house exhaust fans shall have insulated louvers or covers which close when the fan is off. Covers or louvers shall have a mimimum insulation value of R-4.2.	paved road shall be treated with a 6 to 12 compacted layer of wood chips, mulch, or gra 8. Sandbags or other erosion control measures sh installed to prvent silt runoff to public roadwa from sites with a slope greater than 1 percen
hereby notified that they are to confer and cooperate fully with each other during the course of construction to determine their exact extent and overlap of each other's Work and to successfully complete the execution of the	valve to the water distribution system stating the following: "WARNING: The water system for this home supplies fire sprinklers that require certain flows and pressure to fight a fire. Devices	P. HVAC system installers shall be trained and certified in the proper installation of the HVAC systems.	 9. Minimize the idling time of diesel powered equato 2 minutes. 10. The project shall develop a plan demonstrating the off-road equipment (more than 50 H.P.) to used in the project (i.e. example leaged and and and and and and and and and an
Work. M. Refer to the Structural Calculations for any	that restrict the flow, decreases the pressure, or automatically shuts off the water to the fire sprinkler system, such as water softeners,	SHOP DRAWINGS AND WALK-THROUGH APPROVAL	used in the project (i.e. owned, leased, and s contractor vehicles) would achieve a project-w fleet average 20 percent NOX reduction and 4 percent PM reduction compared to the most re
questions regarding lumber grade, beam and header sizes, footings and shear requirments. No deviation from structural details shall be made without the written approval of the Structural Engineer. Approval by a Building Department Inspector does not constitute	filtration systems, or automatic shutoff valves shall not be added to this system without a review of the fire sprinkler system by a fire protection specialist. DO NOT REMOVE THIS SIGN"	A, Shop drawings shall be prepared and submitted to the Architect for approval prior to the ordering, fabrication, or installation of the following: CASEWORK, DOORS, WINDOWS, FIRE SPRINKLERS, METAL FABRICATIONS, CUSTOM	ARB fleet average. Acceptable options for re emissions include the use of late-model engine emission diesel products, alternative fuels, engi retrofit technology, after-treatment products, a devices such as particulate filters, and/or othe options as such become available.
authority to deviate from Drawings or Specifications. N. Specifications take precedence over the	CONSTRUCTION HOURS	OR SPECIALIZED MATERIALS OR ASSEMBLIES, or any other item(s) or assembly(ies) that may be identified elsewhere in the drawings.	 Use low VOC (i.e. ROG) coatings beyond the lo requirments. Require that all construction equipment, diesel
information on the Drawings. The Architect shall be notified at once in cases of conflict.	7:00 am - 5:30 pm MONDAY-FRIDAY 9:00 am - 3:00 SATURDAY NO CONSTRUCTION ALLOWED ON SUNDAY OR CITY OBSERVED HOLIDAYS	B. Contractor shall arrange walk-through with the Owner and Architect for layout approval prior to the following: INTERIOR WALL FRAMING (chalk lines must be in place) and ELECTRICAL ROUGH-IN.	 and generators be equiped with best available control technology for emission reductions of N and PM. 13. Require all contractors use equipment that mee CARB's most recent certification standards for

OR CITY OBSERVED HOLIDAYS

3. Require all contractors use equipment that i CARB's most recent certification standards road heavy duty diesel engines.

658 SPARGUR DRIVE LOS ALTOS, CALIFORNIA 94022



e. owned, leased, and sub- uld achieve a project-wide		FROJECT DIRECTORT										
nt NOX reduction and 45 compared to the most recent	OWNER/APPLICANT	ARCHITECT	STRUCTURAL ENGINEER	CIVIL ENGINEER	LANDSCAPE							
cceptable options for reducing use of late-model engines, low- s, alternative fuels, engine er-treatment products, add-on ulate filters, and/or other e available. coatings beyond the local	Pawan and Smita Deshpande 658 SPARGUR DRIVE LOS ALTOS, CA 94022	SCHWANKE ARCHITECTURE 1100 BAY LAUREL DR. MENLO PARK, CA 94025 (650) 321-4348	XL ENGINEERING 1320 LINCOLN WAY AUBURN, CA 95630 (925) 803-9756	CLARK CIVIL ENGINEERING 5500 NICASIO ROAD NICASIO, CA 94946 (510) 295-4450	W. JEFFREY HEID 6179 ONEIDA DRIVE SAN JOSE, CA 95123 (408) 691-5207							
nction equipment, diesel trucks, iped with best available emission reductions of NOX use equipment that meets ertification standards for off- l engines.		steve@sschwanke-aia.com	leifl@xl-engineering.net Project No.: (STRUCTURAL ENGINEERING NOT INCLUDED IN PLANNING SUBMITTAL)	wclark@clarkcivil.com Project No.: 222004 Date: 02/10/2022	wjheidasla@gmail.com Project No.: Date:							



PROJECT SUMMARY TABLE

ZONING COMPLIANCE

-				
	Existing	Proposed	Allowed/Required	
	3,855 square feet	3,543 square feet	4,047 square feet	
	28.6%	26.3%	30 %	
t Floor:	3,585 square feet	2,804 square feet		
d Floor:	N/A square feet	1,290 square feet		
tal:	3,585 square feet	4,094 square feet	4,099 square feet	
A.R. Percentage	26.6 %	30.3 %	30.4 %	
ont	28.16 feet	25.33 feet		
ar	33.60 feet	30.01 feet		
ght side - 1st (2nd)	18.45 (N/A) feet	19.19 (28.19) feet	10 (17.5) feet	
ft side - 1st (2nd)	10.34 (N/A) feet	18.15 (25.15) feet	10 (17.5) feet	
	19.32 feet	_26.78 feet		

SQUARE FOOTAGE BREAKDOWN

	Existing	Change in	Total Proposed		
AREA: ment	3,086 square feet	3,052 square feet	6,138 square feet		
PEA: porches or open structures	499 square feet	_ -146 square feet			

LOT CALCUATIONS

		13,493 square feet		
DSCAPE AREA: t yard setback shall not exceed 50	1,080 square feet	43	%	
	Total hardscape	area (proposed):	5,165	square feet
AKDOWN: Id equal the site's net lot area.	Existing softsca	pe (undisturbed) area:	6,938	square feet
a oquar allo ono o hot fot alba.	New softscape area:		1,390	square feet

W.E.LO. DECLARATIONS

LANDSCAPE DESIGNER

I have complied with the criteria of the Model Water Efficient Landscape Ordinance and applied them for the effcient use of water in the landscape and irrigation design plan(s).

OWNER/APPLICANT

I agree to comply with the criteria of the Model Water Efficient Landscape Ordinance and submit a complete Landscape Documentation Package:


GEOTECHNICAL ARBORIST ROMIG ENGINEERS, INC. KIELTY ARBORIST SERVICE 1390 EL CAMINO REAL P.O. Box 6187 SAN MATEO, CA 94403 SAN CARLOS, CA 94070 (650) 591-5224 (650) 532-4418 Project No.: Project No.: 658 Spargur Date: Date: 02/11/2022

SHEET INDEX

		COVER SHEET RENDERING/MATERIAL EXAMPLES/ STREETSCAPE
		NEIGHBORHOOD CONTEXT MAP WITH PHOTOGRAPHS
AS.Ø1	-	PROPOSED SITE PLAN
EP.Ø1	-	EXISTING SITE PLAN EXISTING FLOOR PLAN EXISTING EXTERIOR ELEVATIONS
AP.Ø1 AP.Ø2	-	AREA BLOCK DIAGRAMS BASEMENT FLOOR PLAN LOWER FLOOR PLAN UPPER FLOOR PLAN
		LOWER ROOF PLAN UPPER ROOF PLAN
AE.Ø2	-	EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS
		BUILDING SECTIONS BUILDING SECTIONS
	FN	IGINEERING
		TOPOGRAPHIC SURVEY
		TITLE SHEET GRADING SPECIFICATIONS
		GRADING AND DRAINAGE PLAN
		DETAILS DETAILS
		EROSION CONTROL PLAN
		EROSION CONTROL DETAILS BEST MANAGEMENT PRACTICES
LANDS	CAF	PING
L1	-	LANDSCAPE MASTER PLAN
		HYDROZONE PLAN IRRIGATION PLAN



05/31/2022 Planning Application Completeness Comments













TREE SCHEDULE									
No.	SPECIES	DIA.	N	H	P	R	* - ESTIMATED TREE DIAMETER		-
1	Weeping cherry	5″				X	N - TREE ON ADJACENT PROPERTY H - HERITAGE TREE PROTECTED BY ORDINANCE		
2	Japanese maple	3.4"					P - TREE PROTECTION REQUIRED R - TREE TO BE REMOVED (See note 'C' below)		1.5' ASPHALTIC CONCRETE PLUG (CROSSHATCHED) TO MATCH AND
3	Coast live oak Redwood	38.4" 15" *	X	Х Х	X X		^ - TREE TO BE RELOCATED NOTES:		WITH EXISTING STREET PAVING
4 5	Redwood Redwood	15" *	Х Х	X X	Х Х	$\left \right $	A. TREE SCHEDULE BASE ON Kielty Aborist Services,		PERMABLE DRAINAGE SWALE
6	Redwood	15″ *	X	X	X		DATED February 11, 2022 B. REFER TO ARBORIST REPORT FOR ADDITIONAL		
7	Redwood	15″ *	X	X	X		INFORMATION REGARDING PROTECTION, PRUNING, AND MAINTENACE OF TREES DURING CONSTRUCTION.	CONCRU	TE CURB EACH SIDE OF SWALE
8	Japanese maple	2"					C. NON-HERITAGE TREES MARKED AS "RETAIN" and "PROTECT" MAY NOT BE REMOVED WITHOUT A		EXISTING JOINT POLE WITH
9	Marina madrone	8″ 3″	X			X^	TREE REMOVAL PERMIT FROM THE COMMUNITY DEVELOPMENT DIRECTOR.	EDGE OF	UNDERGROUND ELECTRICAL DROP EXISTING PAVING
1	Avacado	2"				X^	D. CITY APPROVDED TREE PROTECTION WARNING SIGNS ARE REQUIRED TO BE INSTALLED AND	OH	
12	Plum	2″				χ^	MAINTAINED AT ALL TIMES UNTIL ALL		
3	Cherry laurel	2"					CONSTRUCTION ACTIVITIES ARE COMPLETE. E. REQUIRED TREE PROTECTION SHALL REMAIN IN		x
4 5	Cherry laurel Cherry laurel	2" 2"					PLACE UNTIL ALL CONSTRUCTION ACTIVITIES ARE COMPLETE. NO CHANGES TO TREE PROTECTION CAN		
6	Orange	2"					BE MADE UNTIL A REVISED TREE PROTECTION PLAN IS SUBMITTED AND APPROVED BY THE TOWN		EXISTING SANITARY
7	Orange	3″				X^	ARBORIST. F. FAILURE TO INSTALL AND MAINTAIN REQUIRED		SEWER P.O.C.
3	Xylosma	12" *	X				TREE PROTECTION WILL RESULT IN ISSUANCE OF STOP WORK ORDER AND IMPLEMENTATION		
9	Redwood	18″ *	X	X	X		OF A CORRECTIVE ACTION PLAN.	ú	
+							G. ANY DIGGING WITHIN THE TREE PROTECTION ZONE (TPZ) SHALL BE DONE BY HAND (AIR-SPADE OR	26.5′	
_							VACUUM SYSTEM) UNDER THE DIRECT SUPERVISION OF A CERTIFIED ARBORIST.	35 5, 25	4' REDWOOD SCREEN
							H. TREES IDENTIFIED TO BE REMOVED AND RELOCATED SHALL BE REMOVED AND RELOCATED PRIOR TO		FENCE AT BIN AREA
_							DEMOLITION (REFER TO LANDSCAPE PLAN FOR PROPOSED LOCATIONS).		WHEELIE BIN AREA
									UTILITIES IN JOINT TRENCH
									CONCRETE SERVICE AREA
									POINT OF EVALUATION FOR
									CONDENSING UNITS: COMBINED
								(UEVEL= +/- 49 dB(A) 0 dB(A) MAX. PER L.A.M.C. 6.16)
								()	U UD(A) MAA. FER L.A.M.C. 0.10
									CONDENSING UNIT, TYPICAL
								EXISTING	118. D.P. R
								ADJACENT RESIDENCE	
								64.17	
									ROOF OVERHANG (DASHED), TYPICAL
									EXISTING FRUIT TREES
									IN THIS AREA TO BE RELOCATED - PLANTING
									LOCATION TO BE DETERMINED
								4.25'	PROPOSED EVERGREEN SCREEN
								4.	TREE TO OBSCURE FIELD OF VISION - SPECIES TO BE
								655 4.3'	DETERMINED - REFER TO
									,
								K	
								, veor	
								30.01	
								× ·	
								۲,	
								\	














BASEMENT FLOOR PLAN









LOWER FLOOR PLAN


(SA)



EXISTING FLOOR AREA E1 7.83' x 1Ø.62' = 83.16 S.F. 25.33' x 3Ø.87' = 781.94 S.F. E2 16.33' x 16.00' = 261.28 S.F. E3 11.83' x 12.38' = 146.46 S.F. E4 18.83' x 30.08' = 566.41 S.F. E5 10.00' x 6.04' = 60.40 S.F. E6 E7 15.00' x 1.50' = 22.50 S.F. E8 19.00' x 42.21' = 801.99 S.F. E9 19.67' x 21.67' = 361.24 S.F. EXISTING GARAGE AREA 21.33' x 23.38' = 498.7Ø S.F. EG ADDITIONAL COVERAGE AREAS P1 (porch) 20.67' x 6.04' = 124.85 S.F. 9.00' x 16.00' = 144.00 S.F. P2 (porch) EF (fireplace) 4.00' x 0.33' = 1.32 S.F. SA (shed) 7.30' x 12.22' = 87.13 S.F. 11.20' x 8.14' = 91.17 S.F. SB (shed) TOTAL EXISTING FLOOR AREA: 3584.Ø8 S.F. 4Ø32.55 S.F. TOTAL EXISTING COVERAGE:



UPPER FLOOR PLAN



16'

V

24

D

日

2

OF CALIFO

Steven A.

C-17497 10/23 NSED ARCH

 \square

U U

 $\mathbf{A} \sim$

 \mathbf{O}

Q

R R

shpa

Ш Ш

 Δz

Block

Area


AP.00


DATE:


S


E


BLOCK AREA DIAGRAMS



















RI	GHT	SID
	— — — —	~














658 SPARGUR DRIVE LOS ALTOS, CA. 94022



<u>EXISTING</u>

 $\sim \sim >$


LEGEND DDADACED


- · · · ·	— · — ·
SD	
SS	
W	
G {	
P	
·	
JT	
	· · · · · ·
	· ~~ ·
ШШ СВ	
JB	
AD	
AD	
⊖ _{sdmh}	
ж.	
SSMH	
٩ 222.57	
SSMH 222.57 × INV	
L	
\bullet	
200	
200	
FERCER	
XX TREE	

	PROP	<u>DSED</u>
		·
	<u> </u>	
	— JT —	
_		
~~~ ·	~~~~~} ·	
~~~ ·	~~~ `	
		Ш св
		IIII JB
		AD
		AD
		¥
		52M⊓ ∲
		× 1NV
		←
	200-	+
	200- & 1	
	- AN	SCAT
	XX	
		-

DESCRIPTION

BOUNDARY PROPERTY LINE **RETAINING WALL** LANDSCAPE RETAINING WALL SUBDRAIN LINE TIGHTLINE STORM DRAIN LINE SANITARY SEWER LINE WATER LINE GAS LINE PRESSURE LINE JOINT TRENCH SET BACK LINE CONCRETE VALLEY GUTTER SWALE FLOW DIRECTION CATCH BASIN JUNCTION BOX AREA DRAIN SQUARE AREA DRAIN CURB INLET STORM DRAIN MANHOLE FIRE HYDRANT SANITARY SEWER MANHOLE STREET SIGN SPOT ELEVATION FLOW DIRECTION BENCHMARK CONTOURS TREE TO BE REMOVED






KEY MAP 1" = 20'

ABBREVIATIONS

AGGREGATE BASE	LF	LINEAL FEET
ASPHALT CONCRETE	MAX	MAXIMUM
ACCESSIBLE	MH	MANHOLE
AREA DRAIN	MIN	MINIMUM
ACCESSIBLE AREA DRAIN BEGINNING OF CURVE BEARING & DISTANCE	MON.	MONUMENT
BEARING & DISTANCE	(N)	NEW
BENCHMARK		NUMBER
BOTTOM OF WALL/FINISH GRADE	NO. NTS O.C.	NOT TO SCALE
CATCH BASIN		ON CENTER
	0.0.	
CURB AND GUTTER	0/	OVER
CENTER LINE	(PA)	PLANTING AREA
CORRUGATED PLASTIC PIPE	PED	PEDESTRIAN
(SMOOTH INTERIOR) CLEANOUT CONCRETE CONSTRUCT or -TION CONCRETE CORNER	PIV	
ČLEANOUT	PSS	PUBLIC SERVICES EASEMENT
CONCRETE	ዊ	
CONSTRUCT or -TION	PP	POWER POLE
CONCRETE CORNER	PUC	
	PVC	POLYVINYL CHLORIDE
DIAMETER	R	RADIUS
CONCRETE CORNER CUBIC YARD DIAMETER DROP INLET	RCP	
DUCTILE IRON PIPE	RIM	
		RIM ELEVATION
	RW	
END OF CURVE	R/W	RIGHT OF WAY
EXISTING GRADE ELEVATIONS	S	SLOPE
ELEVATIONS	S.A.D.	SEE ARCHITECTURAL DRAWINGS
EDGE OF PAVEMENT	SAN	SANITARY
EDGE OF PAVEMENT EQUIPMENT EACH WAY EXISTING FACE OF CURB FINISHED FLOOR FINISHED GRADE FIRE HYDRANT FLOW LINE FINISHED SURFACE GAS	SD	STORM DRAIN
EACH WAY	SD SDMH SHT S.L.D. SPEC	STORM DRAIN MANHOLE
EXISTING	SHT	SHEET
FACE OF CURB	S.L.D.	SEE LANDSCAPE DRAWINGS
FINISHED FLOOR	SPFC	SPECIFICATION
FINISHED GRADE	SS	SANITARY SEWER
FIRE HYDRANT	SS SSMH	SANITARY SEWER MANHOLE
	ST.	STREET
	STA	STATION
CAS	STD	STANDARD
GAGE OR GAUGE		
GRADE BREAK	STRUCT	STRUCTURAL
	T	TELEPHONE
HIGH DENSITY CORRUGATED	TC	TOP OF CURB
	TEMP	TEMPORARY
HORIZONTAL	TP	TOP OF PAVEMENT
HIGH POINT	TW/FG	TOP OF WALL/FINISH GRADE
HUB & TACK	TYṔ	TYPICAL
INSIDE DIAMETER	VC	VERTICAL CURVE
INVERT ELEVATION	VCP	VITRIFIED CLAY PIPE
JUNCTION BOX	VERT	VERTICAL
JOINT TRENCH	W/	WITH
JOINT UTILITY POLE	Ŵ, WL	WATER LINE
LENGTH	WM	WATER METER
LANDING		
	WWF	WELDED WIRE FABRIC



NTS

REFERENCES

THIS GRADING AND DRAINAGE PLAN IS SUPPLEMENTAL TO: 1. TOPOGRAPHIC SURVEY CLARK CIVIL ENGINEERING 2. ARCHITECTURAL PLAN BY ARCHIT STUDIO, LLP

THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM.


ON-SITE IMPERVIOUS AREA


	EXISTING	PROPOSED
HOUSE	3585 S.F.	2810 S.F.
DRIVEWAY AND PATIO	2855 S.F.	3180 S.F.
NET DECREASE IN IMPERVIOUS SURFACE		450 S.F.

ESTIMATED EARTHWORK QUANTITIES

FILL 0 C.Y. CUT 1,175 C.Y. EXPORT 1,175 C.Y.

NOTE: GRADING QUANTITIES REPRESENT BANK YARDAGE. IT DOES NOT INCLUDE ANY SWELLING OR SHRINKAGE FACTORS AND IS INTENDED TO REPRESENT IN-SITU CONDITIONS. QUANTITIES DO NOT INCLUDE OVER-EXCAVATION, TRENCHING, STRUCTURAL FOUNDATIONS OR PIERS, OR POOL EXCAVATION (IF ANY). NOTE ADDITIONAL EARTHWORKS, SUCH AS KEYWAYS OR BENCHING MAY BE REQUIRED BY THE GEOTECHNICAL ENGINEER IN THE FIELD AT TIME OF CONSTRUCTION. CONTRACTOR TO VERIFY QUANTITIES





G	ENERAL SITE NOTES:	SITE MAINTEN
1.	CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING ON THIS WORK AND CONSIDER THE EXISTING CONDITIONS AND SITE CONSTRAINTS IN THE BID. CONTRACTOR SHALL BE IN THE POSSESSION OF AND FAMILIAR WITH ALL APPLICABLE GOVERNING AGENCIES STANDARD DETAILS AND SPECIFICATIONS PRIOR TO SUBMITTING OF A BID.	1. REMOVE ALL DIRT, GRAVE STREET PAVEMENT AND S CONSTRUCTION ACCESS R AT THESE LOCATIONS. DO PAVED OR GRAVELED ARE
	ALL WORK IN THE PUBLIC RIGHT-OF-WAY SHALL CONFORM TO ALL APPLICABLE GOVERNING AGENCIES STANDARD DETAILS & SPECIFICATIONS.	SWEEPING. CORNERS AND
3.	PRIOR TO BEGINNING WORK, AND AFTER INITIAL HORIZONTAL CONTROL STAKING, CONTRACTOR SHALL FIELD CHECK ALL ELEVATIONS MARKED WITH (E) AND REPORT ANY DISCREPANCIES GREATER THAN 0.05' TO OWNER'S PROJECT MANAGER AND CIVIL ENGINEER.	3. CONTRACTOR SHALL: GAT BASIS AND PLACE IT IN A EMPTIED OR REMOVED ON TARPS ON THE GROUND COULD CONTRIBUTE TO S
	DAMAGE TO ANY EXISTING SITE IMPROVEMENTS, UTILITIES AND/OR SERVICES TO REMAIN SHALL BE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR SHALL REPAIR AND/OR REPLACE IN KIND. CONTRACTOR SHALL REPLACE ALL STRUCTURES AND GRATE LIDS	4. IF THE STREET, SIDEWALK WASHED, DEBRIS MUST BE INTO THE STORM DRAIN S
	CONTRACTOR SHALL REPLACE ALL STRUCTURES AND GRATE LIDS FOR VAULTS, CATCH BASINS, ETC, WITH VEHICULAR-RATED STRUCTURES IN ALL TRAFFIC ACCESSIBLE AREAS WITHIN NEW CONSTRUCTION AREA UNLESS OTHERWISE NOTED.	
0.	THE CONTRACTOR SHALL ADJUST TO FINAL GRADE ALL EXISTING AND/OR NEW MANHOLES, CURB INLETS, CATCH BASIN, VALVES, MONUMENT COVERS, AND OTHER CASTINGS WITHIN THE CONSTRUCTION AREA TO FINAL GRADE IN PAVEMENT AND LANDSCAPE AREAS UNLESS OTHERWISE NOTED.	
7.	CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND	6. NEVER CLEAN MACHINERY OR STORM DRAIN.
	COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT INCLUDING SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT TO BE LIMITED TO NORMAL WORKING HOURS AND THAT THE CONTRACTOR SHALL DEFEND	7. ENSURE THAT CEMENT TR CONTRACTORS DO NOT DI OR RINSE CONTAINERS IN
	COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT INCLUDING SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT TO BE LIMITED TO NORMAL WORKING HOURS AND THAT THE CONTRACTOR SHALL DEFEND INDEMNIFY AND HOLD THE OWNER, THE CONSULTING ENGINEER AND THE CITY HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE CONSULTING ENGINEER.	8. THE ON-SITE STORM DRA TWICE A YEAR AS FOLLOV ONCE IN JANUARY. ADDIT NECESSARY BY THE INSPI FOR COST ASSOCIATED W
	EXISTING PEDESTRIAN WALKWAYS. BIKE PATHS AND ACCESSIBLE PATHWAYS SHALL BE MAINTAINED, WHERE FEASIBLE, DURING CONSTRUCTION.	SHEET.
	IF A CONFLICT ARISES BETWEEN THE SPECIFICATIONS AND THE PLANS NOTES, THE MORE STRINGENT REQUIREMENT SHALL GOVERN.	
	D. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY REQUIRED PERMITS AND COSTS ASSOCIATED WITH SAID PERMITS	11. MAINTAIN EXISTING TREES REQUIRED BY THE TREE A
	REE/PLANT PROTECTION NOTES:	STORMWATER POL
1.	PRIOR TO BEGINNING CONSTRUCTION ON SITE, CONTRACTOR SHALL IDENTIFY, CONFIRM WITH OWNER AND PROTECT EXISTING TREES AND PLANTS DESIGNATED AS TO REMAIN.	1. STORE, HANDLE, AND DISPO PROPERLY, SO AS TO PREV
	PROVIDE 5 FOOT TALL TREE PROTECTION FENCE WITH DISTINCTIVE MARKING VISIBLE TO CONSTRUCTION EQUIPMENT, ENCLOSING DRIP LINES OF TREES DESIGNATED TO REMAIN.	2. CONTROL AND PREVENT THE INCLUDING SOLID WASTES, F CHEMICALS, WASHWATER OF TO STORM DRAINS AND WA
3.	WORK REQUIRED WITHIN FENCE LINE SHALL BE HELD TO A MINIMUM, AVOID UNNECESSARY MOVEMENT OF HEAVY EQUIPMENT WITHIN FENCED AREA AND DO NOT PARK ANY VEHICLES UNDER DRIP LINE OR TREES. DO NOT STORE EQUIPMENT OR MATERIALS WITHIN FENCE LINE.	 USE SEDIMENT CONTROL OF DEWATERING EFFLUENT. AVOID CLEANING, FUELING,
4.	PRIOR TO REMOVING ROOTS AND BRANCHES LARGER THAN 2" IN DIAMETER OF TREES OR PLANTS THAT ARE TO REMAIN, CONSULT WITH THE OWNER'S PROJECT MANAGER.	DESIGNATED AREA IN WHICH 5. DELINEATE CLEARING LIMITS AREAS, BUFFER ZONES, TRI MARKERS.
5.	ANY GRADE CHANGES GREATER THAN 6" WITHIN THE DRIPLINE OF EXISTING TREES SHALL NOT BE MADE WITHOUT FIRST CONSULTING THE ARCHITECT / CIVIL ENGINEER.	6. PROTECT ADJACENT PROPE CONSTRUCTION IMPACTS US BARRIERS OF FILTERS, DIKE APPROPRIATE.
6.	PROTECT EXISTING TREES TO REMAIN FROM SPILLED CHEMICALS, FUEL OIL, MOTOR OIL, GASOLINE AND ALL OTHER CHEMICALLY INJURIOUS MATERIALS; AS WELL AS FROM PUDDLING OR CONTINUOUSLY RUNNING WATER. SHOULD A SPILL OCCUR, STOP WORK IN THAT AREA AND	7. PERFORM CLEARING AND EA THE MAXIMUM EXTENT PRAC
	CONTACT THE INSPECTOR IMMEDIATELY. CONTRACTOR SHALL BE RESPONSIBLE TO MITIGATE DAMAGE FROM SPILLED MATERIAL AS WELL AS MATERIAL CLEAN UP.	 8. LIMIT AND TIME APPLICATIO POLLUTED RUNOFF. 9. LIMIT CONSTRUCTION ACCES
7.	PROVIDE TEMPORARY IRRIGATION TO ALL TREES AND PLANTS THAT ARE IN OR ADJACENT TO CONSTRUCTION AREAS WHERE EXISTING IRRIGATION SYSTEMS MAY BE AFFECTED BY THE CONSTRUCTION. ALSO PROVIDE TEMPORARY IRRIGATION TO RELOCATE TREES.	9. LIMIT CONSTRUCTION ACCES POINTS. 10. AVOID TRACKING DIRT OR M AREAS AND SIDEWALKS USI
8.	CONTRACTOR SHALL BE RESPONSIBLE FOR ONGOING MAINTENANCE OF ALL TREES AND PLANTS DESIGNATED TO REMAIN AND FOR MAINTENANCE OF RELOCATED TREES STOCKPILED DURING CONSTRUCTION. CONTRACTOR	EXTENT PRACTICAL. SUPPLEMENTAL MEASURES
9.	WILL BE REQUIRED TO REPLACE TREES OR PLANTS THAT DIE DUE TO LACK OF MAINTENANCE. TREE PROTECTION ZONES NEED TO BE SET UP WITH FENCING AROUND TREES TO A MINIMUM DISTANCE OF 10 FEET FROM THE BUTTRESS FLAIR.	A. THE PHRASE "NO DUMPING PHRASE MUST BE LABELED BRANDING, OR PLAQUES) TO STORM WATER AND TO PRE THE STORM DRAIN.
	NO EQUIPMENT, MATERIALS STORAGE, OR DIGGING IS ALLOWED WITHIN THE TREE PROTECTION ZONE WITHOUT WRITTEN AUTHORIZATION FROM THE PROJECT ARBOHIST, ARBOHIST SUPERVISOR OR AUTHORIZED	B. USING FILTRATION MATERIAL SEDIMENT FROM DEWATERIN
	DESIGNATE. ANY AUTHORIZED DIGGING WITHIN THE TREE PROTECTION ZONE MUST BE DONE BY HAND; I.E. PICK AND SHOVEL: CARE MUST BE TAKEN TO AVOID SEVERING ANY STRUCTURAL ROOTS. ANY ROOTS	C. STABILIZING ALL DENUDED A MEASURES CONTINUOUSLY F
	GREATER THAN 2" IN DIAMETER INCIDENTALLY SEVERED, WHETHER INSIDE OR OUTSIDE OF THE TREE PROTECTION ZONE, WILL NEED TO BE BROUGHT TO THE ATTENTION OF AND INSPECTED BY THE PROJECT ARBOHIST, ARBOHIST SUPERVISOR OR AUTHORIZED DESIGNATE; WHO WILL	D. REMOVING SPOILS PROMPTL WHEN RAIN IS FORECAST. OTHER MATERIALS SHALL B MATERIAL.
	EVALUATE THE TREE IN QUESTION FOR IMPACTS TO BOTH LONG TERM HEALTH AND STABILITY. ANY ROOT SEVERANCE CONCLUDED TO COMPROMISE TREE STABILITY/SAFETY MAY RESULT IN TREE REMOVAL. ANY COSTS RESULTING FROM TREE REMOVALS WILL BE CHARGED TO THE PROJECT IN QUESTION. ANY COSTS FROM TREE REMOVALS RESULTING	E. STORING, HANDLING, AND D WASTES SO AS TO AVOID 1 WATER BODY.
	PROJECT IN QUESTION. ANY COSTS FROM TREE REMOVALS RESULTING FROM VIOLATIONS OF THE COUNTY CODES WILL BE ABSORBED BY THE CONTRACTOR UP TO AND INCLUDING ANY FINES LEVIED BY THE COUNTY.	F. AVOIDING CLEANING, FUELIN AN AREA DESIGNATED TO C
		G. LIMITING AND TIMING APPLIC POLLUTING RUNOFF.

SITE MAINTENANCE:

LICATIONS OF PESTICIDES AND FERTILIZER TO AVOID POLLUTING RUNOFF

CENERAL SITE NOTES.

- VEL, RUBBISH, REFUSE, AND GREEN WASTE FROM STORM DRAINS ADJOINING THE SITE. LIMIT ROUTES ONTO THE SITE AND PLACE GRAVEL PADS DO NOT DRIVE VEHICLES AND EQUIPMENT OFF THE REAS DURING WET WEATHER.
- STREET PAVEMENT AND SIDEWALKS ADJOINING THE ON-SITE PAVED AREAS ON A DAILY BASIS. D AND DIRT FROM THESE AREAS BEFORE ND HARD TO REACH AREAS SHALL BE SWEPT
- ATHER ALL CONSTRUCTION DEBRIS ON A REGULAR A DUMPSTER OR OTHER CONTAINER WHICH IS ON A REGULAR BASIS. WHEN APPROPRIATE, USE TO COLLECT FALLEN DEBRIS OR SPLATTERS THAT STORM WATER RUNOFF POLLUTION.
- _KS AND/OR PARKING LOT ARE PRESSURE BE TRAPPED AND COLLECTED TO PREVENT ENTRY SYSTEM. NO CLEANING AGENT MAY BE STORM DRAIN. IF ANY CLEANING AGENT OR ASHED WATER MUST BE COLLECTED AND ANITARY SEWER, SUBJECT TO THE APPROVAL OF MANAGER, OR OTHERWISE DISPOSED OF THROUGH ETHODS.
- ND COVERED AREA ON THE SITE FOR THE IENT, PAINTS, OILS, FERTILIZERS, PESTICIDES, OR ON THE SITE THAT HAVE THE POTENTIAL OF IN THE EVENT OF A MATERIAL SPILL.
- RY, EQUIPMENT OR TOOLS INTO A STREET, GUTTER
- TRUCKS, PAINTERS, OR STUCCO/PLASTER FINISHING DISCHARGE WASH WATER FROM EQUIPMENT, TOOLS INTO GUTTERS OR DRAINS.
- RAIN FACILITIES SHALL BE CLEANED A MINIMUM OF OWS: IMMEDIATELY PRIOR TO OCTOBER 15TH AND ITIONAL CLEANING MAY BE REQUIRED IF FOUND PECTOR. CONTRACTOR SHALL BE RESPONSIBLE WITH CLEANING.
- EAVING THE SITE AND ACCUMULATING ON EQUIRED IN THE DUST CONTROL NOTES ON THIS
- EN STORM RUN-OFF FROM LEAVING THE SITE OR OR SANITARY SEWER SYSTEMS AS REQUIRED IN MENTATION CONTROL NOTES ON THIS SHEET.
- IS AND PLANTS THAT ARE TO REMAIN AS AND PLANT PROTECTION NOTES ON THE SHEET.

DESTIGATION PREVENTION NOTES:

- POSE OF CONSTRUCTION MATERIALS AND WASTES EVENT THEIR CONTACT WITH STORMWATER.
- THE DISCHARGE OF ALL POTENTIAL POLLUTANTS, PAINTS, CONCRETE, PETROLEUM PRODUCTS, OR SEDIMENT, AND NON-STORMWATER DISCHARGES ATER COURSES.
- OR FILTRATION TO REMOVE SEDIMENT FROM
- , OR MAINTAINING VEHICLES ON SITE, EXCEPT IN A ICH RUNOFF IS CONTAINED AND TREATED.
- TS, EASEMENTS, SETBACKS, SENSITIVE OR CRITICAL REES AND DISCHARGE COURSE WITH FIELD
- PERTIES AND UNDISTURBED AREAS FROM JSING VEGETATIVE BUFFER STRIPS, SEDIMENT KES, MULCHING, OR OTHER MEASURES AS
- EARTH MOVING ACTIVITIES DURING DRY WEATHER TO ACTICAL.
- IONS OF PESTICIDES AND FERTILIZERS TO PREVENT
- ESS ROUTES AND STABILIZE DESIGNATED ACCESS

MATERIALS OFF-SITE; CLEAN OFF-SITE PAVED SING DRY SWEEPING METHODS TO THE MAXIMUM

- NG DRAINS TO BAY" OR EQUALLY EFFECTIVE ED ON STORM DRAIN INLETS (BY STENCILING, TO ALERT THE PUBLIC TO THE DESTINATION OF REVENT DIRECT DISCHARGE OF POLLUTANTS INTO
- ALS ON STORM DRAIN COVERS TO REMOVE ING EFFLUENT.
- AREAS AND MAINTAINING EROSION CONTROL FROM OCTOBER 15 AND APRIL 15.
- TLY, AND AVOID STOCKPILING OF FILL MATERIALS, IF RAIN THREATENS. STOCKPILED SOILS AND BE COVERED WITH A TARP OR OTHER WATERPROOF
- DISPOSING OF CONSTRUCTION MATERIALS AND THEIR ENTRY TO THE STORM DRAIN SYSTEMS OR
- ING. OR MAINTAINING VEHICLES ON-SITE. EXCEPT IN CONTAIN AND TREAT RUNOFF.

WATER SYSTEM NOTES:

- 1. WHERE WATER LINES HAVE TO CROSS SANITARY SEWER LINES, DO SO AT A 90 DEGREE ANGLE AND WATER LINES SHALL BE MINIMUM OF 12" ABOVE THE TOP OF THE SANITARY SEWER LINES.
- 2. WATER LINES ARE SHOWN SCHEMATICALLY; CONTRACTOR SHALL IDENTIFY EACH ANGLE AND / OR BEND THAT MAY BE REQUIRED TO ACCOMPLISH THE INTENDED DESIGN.
- 3. USE DETECTABLE METALIZED WARNING TAPE APPROXIMATELY 6" BELOW THE SURFACE, TAPE SHALL BE A BRIGHT COLOR AND IMPRINTED WITH "CAUTION-WATER LINE BELOW", CALPICO TYPE 2 OR EQUAL.
- 4. ALL WATER SERVICE CONNECTIONS SHALL BE INSTALLED IN ACCORDANCE WITH THE CITY OR APPLICABLE WATER DISTRICT STANDARDS.
- 5. PUBLIC AND PRIVATE WATER MAIN AND WATER SERVICE LINE 4-INCH THROUGH 12-INCH SHALL BE POLYVINYL CHLORIDE (PVC) AND SHALL MEET AWWA C900, RATED FOR 200 PSI CLASS PIPE WITH EPOXY COATED DUCTILE IRON FITTINGS AND FUSION EPOXY COATED GATE VALVES. ALL JOINTS SHALL FACTORY MANUFACTURED WITH BELL AND SPIGOT ENDS AND RUBBER GASKETS. NONMETALLIC WATER LINES HAVE TRACER WIRE INSTALLED.
- 6. CONNECTION TO THE EXISTING WATER MAIN SHALL BE APPROVED BY WATER COMPANY. THE DISTRICT SHALL PAY THE ACTUAL COSTS OF CONSTRUCTION. THE CONTRACTOR SHALL PERFORM ALL EXCAVATION PREPARE THE SITE, FURNISH ALL MATERIALS, INSTALL TAPPING TEE VALVE AND ALL THRUST BLOCKS. BACKFILL, RESTORE THE SURFACE, AND CLEANUP. ALL WET TAPS SHALL BE APPROVED BY THE CITY OR APPLICABLE WATER DISTRICT. NONMETALLIC WATER LINES SHALL HAVE TRACER WIRES INSTALLED.
- 7. ALL WATER LINES 3" OR SMALLER SHALL BE TYPE K COPPER WITH SILVER BRAZED JOINTS. POLYETHYLENE PIPE MAY BE SUBSTITUTED, CONTRACTOR SHOULD SEEK APPROVAL FROM DISTRICT BEFORE MAKING SUBSITUTION. CONTRACTOR TO VERIFY PRESSURES FROM EXISTING LINES ARE ADEQUATE TO SERVICE BUILDINGS AS SPECIFIED BY THE PLUMBING PLANS.
- 8. ALL WATER LINES SHALL BE INSTALLED WITH 3' MINIMUM COVER.
- 9. ALL WATER VALVES SHALL BE PER CITY STANDARD.
- 10. ALL TEMPORARY AND/OR PERMANENT AIR-RELEASE AND BLOW-OFF VALVES SHALL BE PER CITY STANDARD AND AS DIRECTED BY THE CITY ENGINEER.
- 11. CONCRETE THRUST BLOCKS SHALL BE INSTALLED AT ALL TEES, CROSSINGS, BENDS (HORIZONTAL AND VERTICAL), AT SIZE CHANGES AND AT FIRE HYDRANTS PER CITY STANDARD. AWWA C600, SECTION 3.8 UNLESS NOTED OTHERWISE.
- 12. MECHANICALLY RESTRAINED JOINTS SHALL BE INSTALLED AT VERTICAL BENDS IN ACCORDANCE WITH CITY STANDARDS AND AS APPROVED BY THE CITY ENGINEER.
- 13. ALL WATER VALVES SHALL BE CLUSTERED, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER.

STORM DRAIN NOTES:


- 1. ALL STORM DRAIN PIPE SHALL BE PVC PER SECTION 02630, SLOPED AT 2% UNLESS OTHERWISE SPECIFIED ON THE PLANS. PIPE SHALL BE SIZED AS SPECIFIED ON THE PLANS. ALL DIRECTION CHANGES SHALL BE MADE WITH A Y CONNECTION OR LONG SWEEP ELBOWS, REGULAR ELBOWS, AND TEE'S SHOULD BE AVOIDED.
- 2. USE DETECTABLE METALIZED WARNING TAPE APPROXIMATE 6" BELOW THE SURFACE. TAPE SHALL BE A BRIGHT COLOR AND IMPRINTED WITH "CAUTION- STORM DRAIN LINE BELOW". CALPICO TYPE 2 OR EQUAL.
- 3. PAINT THE TOP OF THE CURBS ADJACENT TO EACH CATCH BASIN INSTALLED UNDER THE WORK OR ADJACENT TO THIS SITE WITH THE WORDS "NO DUMPING". WORDING TO BE BLUE 4" HIGH LETTERS ON A PAINTED WHITE BACKGROUND. A " NO DUMPING"
- 4. ALL AREA DRAINS AND CATCH BASINS GRATES WITHIN PEDESTRIAN ACCESSIBLE AREAS SHALL MEET ADA REQUIREMENTS AND HAVE BOLT DOWN GRATES.
- 5. ALL TRENCHES SHALL BE BACKFILLED PER THE SPECIFICATIONS OF THE CIVIL ENGINEER TO VERIFY COMPACTION VALUES.
- 6. FOR GRAVITY FLOW SYSTEMS CONTRACTOR SHALL VERIFY (POTHOLE IF NECESSARY) SIZE, MATERIAL, LOCATION AND DEPTH OF ALL SYSTEMS THAT ARE TO BE CONNECTED TO OR CROSSED PRIOR TO TRENCH OR INSTALLATION OF ANY GRAVITY FLOW SYSTEM.
- 7. COMPLETE SYSTEMS: ALL UTILITY SYSTEMS ARE DELINEATED IN SCHEMATIC MANNER ON THESE PLANS. CONTRACTOR IS TO PROVIDE ALL FITTINGS. ACCESSORIES. AND WORK NECESSARY TO COMPLETE THE UTILITY SYSTEM SO THAT IT IS FULLY FUNCTIONING FOR THE PURPOSE INTENDED.


SANITARY SEWER NOTES:

- 1. INSTALL DETECTABLE METALIZED WARNING TAPE APPROXIMATELY 6"-12" BELOW THE SURFACE IN NON-PAVED AREAS, AND AT THE BOTTOM OF BASEROCK FOR PAVED AREAS. GREEN IMPRINTED WITH "CAUTION-SANITARY SEWER LINE BELOW", CALPICO TYPE 2 OR EQUAL.
- 2. ALL SEWER WORK SHALL BE IN CONFORMANCE WITH THE CITY OR APPROPRIATE SANITARY SEWER DISTRICT.
- 3. PUBLIC AND PRIVATE SANITARY SEWER MAIN AND SERVICE LINE 4-INCH THROUGH 8-INCH SHALL BE POLYVINYL CHLORIDE (PVC) SDR 26 GREEN SEWER PIPE AND SHALL CONFORM TO THE REQUIREMENTS OF ASTM DESIGNATION D 3034-08 WITH GLUED JOINTS.

DEMOLITION NOTES:

- 1. CONTRACTOR IS TO COMPLY WITH ALL GENERAL AND STATE REQUIREMENTS INVOLVING THE REMOVAL AND DISPOSAL OF HAZARDOUS MATERIAL(S).
- 2. THE CONTRACTOR SHALL LOCATE AND CLEARLY MARK (AND THEN PRESERVE THESE MARKERS) FOR THE DURATION OF CONSTRUCTION OF ALL TELÉPHONE, DATA, STREET LIGHT, SIGNAL LIGHT AND POWER FACILITIES THAT ARE IN OR NEAR THE AREA OF CONSTRUCTION.
- 3. CONTRACTOR'S BID IS TO INCLUDE ALL VISIBLE SURFACE AND ALL SUBSURFACE FEATURES IDENTIFIED TO BE REMOVED OR ABANDONED IN THESE DOCUMENTS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR A SITE INSPECTION TO FULLY ACKNOWLEDGE THE EXTENT OF THE DEMOLITION WORK.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS NECESSARY FOR ENCROACHMENT, GRADING, DEMOLITION. AND STATE JURISDICTIONS. THE CONTRACTOR SHALL PAY ALL FEES ASSOCIATED CONTRACTOR SHALL PAY DISPOSAL FFFS.
- 6. CONTRACTOR SHALL PAY DISPOSAL FEES.
- 7. BACKFILL ALL DEPRESSIONS AND TRENCHES FROM DEMOLITION OF FOUNDATIONS & UTILITIES.
- 8. WITHIN LIMITS OF WORK, REMOVE CURBS, GUTTERS, LANDSCAPING, SIGNAGE, TREES, SCRUBS, ASPHALT, UNDERGROUND PIPES, ETC. AS INDICATED ON THE PLANS AND SPECS.
- 9. REMOVAL OF LANDSCAPING SHALL INCLUDE ROOTS AND ORGANIC MATERIALS.
- 10. PRIOR TO BEGINNING DEMOLITION WORK ACTIVITIES. CONTRACTOR SHALL INSTALL EROSION CONTROL MEASURES OUTLINED IN THE EROSION & SEDIMENTATION CONTROL PLAN & DETAILS.
- 11. CONTRACTOR SHALL BE RESPONSIBLE FOR DISPOSING ALL DEMOLITION MATERIALS, OR STORING SELECTED ITEMS BY OWNER'S REPRESENTATIVE AT DESIGNATED LOCATIONS.
- 12. THE CONTRACTOR SHALL MAINTAIN ALL SAFETY DEVICES, AND SHALL BE RESPONSIBLE FOR CONFORMANCE TO ALL LOCAL, STATE AND FEDERAL SAFETY AND HEALTH STANDARDS LAWS AND REGULATIONS.
- 13. THE CONTRACTOR SHALL PROTECT FROM DAMAGE ALL EXISTING IMPROVEMENTS FACILITIES AND STRUCTURES WHICH ARE TO REMAIN. ANY ITEMS DAMAGED BY THE CONTRACTOR OR HIS AGENTS OF ANY ITEMS REMOVED FOR HIS USE SHALL BE REPLACED IN EQUAL OR BETTER CONDITION AS APPROVED BY THE ARCHITECT OR OWNER'S REPRESENTATIVE.
- 14. COORDINATE WITH ELECTRICAL. MECHANICAL. FIRE PROTECTION AND ARCHITECTURAL DRAWINGS FOR UTILITY SHUT-DOWN / DISCONNECT LOCATIONS. CONTRACTOR IS TO SHUT OFF ALL UTILITIES AS NECESSARY PRIOR TO DEMOLITION. CONTRACTOR IS TO COORDINATE SERVICE INTERRUPTIONS WITH THE OWNER. DO NOT INTERRUPT SERVICES ADJACENT OFF-SITE OWNERS. ALSO SEE ARCHITECTURAL PLANS FOR ADDITIONAL SCOPE OF WORK.
- 15. DEMOLITION INCLUDES REMOVAL OF ALL ITEMS ASSOCIATED WITH THE UTILITIES AND SHALL INCLUDE PREPARING THE SITE FOR NEW UTILITIES, BUILDINGS, RETAINING WALLS, ETC.
- 16. ALL MATERIALS TO BE DEMOLISHED AND REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE LAWFULLY DISPOSED OF OFF-SITE.
- 17. THE PLAN IS NOT INTENDED TO BE A COMPLETE CATALOGUE OF ALL EXISTING STRUCTURES AND UTILITIES. THIS PLAN INTENDS TO DISCLOSE GENERAL INFORMATION KNOWN BY THE ENGINEER AND TO SHOW THE LIMITS OF THE AREA WHERE WORK WILL BE PERFORMED. THIS PLAN SHOWS THE EXISTING FEATURES TAKEN FROM A FIELD SURVEY, FIELD INVESTIGATIONS AND AVAILABLE INFORMATION. THIS PLAN MAY OR MAY NOT ACCURATELY REFLECT THE TYPE OR EXTENT OF THE ITEMS TO BE ENCOUNTERED AS THEY ACTUALLY EXIST. WHERE EXISTING FEATURES ARE NOT SHOWN, IT IS IMPLIED THAT THEY ARE NOT TO BE DEMOLISHED OR REMOVED. THE CONTRACTOR SHALL PERFORM A THOROUGH FIELD INVESTIGATION AND REVIEW OF THE SITE WITHIN THE LIMIT OF WORK SHOWN IN THIS PLAN SET TO DETERMINE THE TYPE, QUANTITY AND EXTENT OF ANY AND ALL ITEMS. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR DETERMINING THE EXTENT OF EXISTING STRUCTURES AND UTILITIES AND QUANTITY OR WORK INVOLVED IN REMOVING THESE ITEMS FROM THE SITE.





GRADING NOTES:

IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IDENTIFY, LOCATE AND PROTECT ALL UNDERGROUND FACILITIES. UNDERGROUND FACILITIES DAMAGED DURING GRADING SHALL BE REPAIRED AND/OR REPLACED TO LIKE NEW CONDITION AT NO ADDITIONAL COST TO CONTRACT. REFER TO TOPOGRAPHIC SURVEY AND UTILITY SURVEY FOR ADDITIONAL INFORMATION.

THE CONTRACTOR SHALL MAINTAIN THE STREETS, SIDEWALKS AND ALL OTHER PUBLIC RIGHT-OF-WAY IN A CLEAN, SAFE AND USABLE CONDITION. ALL SPILLS OF SOIL, ROCK OR CONSTRUCTION DEBRIS SHALL BE REMOVED FROM THE PUBLICLY OWNED PROPERTY DURING CONSTRUCTION AND UPON COMPLETION OF THE PROJECT. ALL ADJACENT PROPERTY, PRIVATE OR PUBLIC SHALL BE MAINTAINED IN A CLEAN, SAFE AND USABLE CONDITION.

ALL GRADING SHALL BE PERFORMED IN SUCH A MANNER AS TO COMPLY WITH THE STANDARDS ESTABLISHED BY THE AIR QUALITY MANAGEMENT DISTRICT FOR AIRBORNE PARTICULATES.

STANDARD TRUST ARCHAEOLOGICAL PROTOCOLS ISSUED THROUGH EXCAVATION CLEARANCE APPLICATION AND MONITORING WILL BE REQUIRED

CONTRACTOR VERIFY EXISTING UTILITY STUB LOCATIONS AND DEPTHS PRIOR TO COMMENCING CONSTRUCTION.

FINISHED GRADES SHALL BE SLOPED TOWARD INLETS OR POSITIVE RELEASE AT 0.5% MIN. FOR CONCRETE AND 1% MIN FOR ASPHALT AREAS.

REFER TO ARCHITECTURAL AND/OR LANDSCAPE PLANS FOR ADDITIONAL INFORMATION ON FLAT WORK, PAVING TYPE AND SCORING.

REFER TO ARCHITECTURAL PLANS FOR ACCESSIBLE PATH OF TRAVEL. GRADES SHALL BE DONE PER FEDERAL AND STATE ACCESSIBILITY REQUIREMENTS. IF CONTRACTOR BECOMES AWARE OF GRADES THAT ARE NOT CONFORMING TO ACCESSIBILITY REQUIREMENTS, HE SHALL BRING THIS TO THE ATTENTION OF THE ARCHITECT AND THE ENGINEER.

CUT AND FILL SLOPES AND GRADING TRANSITIONS AT THE OUTER EDGES OF THE PROPOSED IMPROVEMENTS ARE TO BE CONSTRUCTED AT THREE HORIZONTAL TO ONE VERTICAL (3:1) UNLESS OTHERWISE NOTED.

UTILITY NOTES:

STORM DRAIN PIPING SHALL BE PVC SDR-35 OR BETTER OR DOUBLE WALLED HDPE PIPING ADS N-12 OR APPROVED EQUAL. 6" MIN U.O.N.

CONTRACTOR SHALL VERIFY BUILDING CONNECTIONS AND ELEVATION. THIS INCLUDES RAIN WATER LEADER, SEWER CONNECTION AND WATER CONNECTION. NOTIFY ENGINEER OF ANY CONFLICTS.

DIMENSIONED & PIPE LENGTHS SHOWN ARE NOT MEANT TO PROVIDE BID QUANTITIES FOR CONTRACTOR, SHOWN FOR INFORMATIONAL PURPOSES ONLY.

PROPOSED GRADES SHALL MEET EXISTING GRADES WITH A SMOOTH AND CONTINUOUS TRANSITION SO AS TO AVOID TRAPPING WATER. CONTRACTOR SHALL NOTIFY PROJECT REPRESENTATIVE IF PUDDLING IS SUSPECTED AND REDIRECT WORK SO AS TO AVOID DELAY WHILE AWAITING RESPONSE.

ALL EXISTING DRAINAGE STRUCTURES, BOXES, UTILITY VAULTS ETC. SHALL BE BROUGHT TO FINAL FINISH GRADE PRIOR TO FINAL SURFACE TREATMENT, UNLESS NOTED OTHERWISE.

COORDINATE ALL EXISTING AND PROPOSED DRAINAGE SLEEVES, AND UTILITY LOCATIONS AS SHOWN ON THE PLANS AND DETAILS CONTAINED WITHIN THESE CONTRACT DOCUMENTS.

THE CONTRACTOR IS TO ENSURE THAT ALL REMAINING ACTIVE AND NEW DRAINAGE AND UTILITY LINES ARE PROTECTED AND UNDAMAGED FROM TRENCHING AND FOOTING EXCAVATIONS FOR NEW FOOTINGS, PARTICULARLY FOR NEW FENCING AND WALLS.

CONTRACTOR IS TO ENSURE THAT ALL AREAS ARE GRADED TO PROVIDE POSITIVE DRAINAGE TO IDENTIFIED EXISTING AND PROPOSED DRAIN INLETS.

AREAS OF TRENCHING SHALL BE PATCHED TO MATCH EXISTING CONDITIONS TO LIKE NEW CONDITIONS, INCLUDING BUT NOT LIMITED TO SOD, CONCRETE AND ASPHALT

SITE ANNOTATION KEYS

FINISHED GRADES AT BUILDING PERIMETER SHALL BE SLOPED AT A MIN. OF 5% FOR THE FIRST 10 FT. AWAY FROM THE BUILDING AND THEN SHALL CONTINUE TO SLOPE TO TOWARDS POSITIVE OUTFALL. MAINTAIN 8" CLEARANCE BETWEEN FINISH EARTHEN GRADE AND BOTTOM OF MUD SILL AT ALL TIMES (PER CBC), U.O.N. -TYP.

PROVIDE 2% (WITHIN 10 FOOT OF BUILDING) SLOPE ACROSS FLATWORK AND/OR PAVING AND SLOPE TO DAYLIGHT. REFER TO ARCHITECT'S PLANS FOR PAVEMENT TYPE, LAYOUT, AND FINISH. - TYP.

DEMOLISH (E) IMPROVEMENTS AS NECESSARY TO ACCOMMODATE (N) CONSTRUCTIÓN. NO DEMOLITION SHALL COMMENCE WITHOUT REQUIRÉD DEMOLITION CITY PERMIT. SEE DEMOLITION PLAN.

PROVIDE TREE PROTECTION AROUND DRIP LINES OF (E) TREES. SEE LANDSCAPE AND/OR SEPARATE TREE PROTECTION PLANS FOR TREE PROTECTION DETAILS. CONTRACTOR TO USE EXTREME CARE WHEN EXCAVATING UNDER TREE CANOPY. HAND DIGGING MAY BE REQUIRED.

DIRECT ROOF DOWNSPOUT (DS) LEADERS TO SPLASH BLOCKS, PROVIDE 2' LONG SPLASH BLOCKS TO BE USED BELOW RAIN WATER LEADERS IN PERVIOUS AREAS.

INSTALL (N) WATER LATERAL & METER AS REQUIRED BY LOCAL UTILITIES. CONTRACTÓR SHALL LOCATE PRIOR TO CONSTRUCTION PER UTILITY COMPANY STANDARDS.

CONNECT/RECONNECT TO (E) SEWER LATERAL AS REQUIRED. CONTRACTOR TO LOCATE PRIOR TO CONSTRUCTION AND VERIFY ADEQUACY OF SYSTEM VIA VIDEOTAPED INSPECTION. IF NEEDED, INSTALL (N) LATERAL MINIMUM 4" PVC (SDR-35 OR BETTER). SLOPED AT 2% MINIMUM. CONTRACTOR TO VERIFY INVERTS AND/OR LOCATION OF (E) UTILITIES PRIOR TO CONSTRUCTION AND INFORM ENGINEER OF ANY DISCREPANCIES. REROUTE AS REQUIRED FOR NEW CONSTRUCTION.


REMOVE (E) GAS METER AND UPGRADE (N) GAS LINE AND SERVICE AS REQUIRED PER UTILITY COMPANY STANDARDS. CONTRACTOR TO VERIFY INVERTS AND/OR LOCATION OF (E) UTILITIES PRIOR TO CONSTRUCTION AND INFORM ENGINEER OF ANY DISCREPANCIES.


CONSTRUCT (N) GRASSY SWALE. SWALE SHALL BE 12-INCHES WIDE AND 3-INCHES DEEP MIN. SLOPE @ 1% TYPICAL (0.5% MIN). DIRECT TOWARDS DAYLIGHT. HAND DIGGING MAY BE REQUIRED UNDER THE TREE CANOPY. SEE DETAIL


(N) DEDICATED LIGHTWELL SUMP PUMP PROVIDE 1/3 HP PUMP. PROVIDE HIGHWATER ALARM AND BACKUP POWER RECOMMENDED.


(N) LIGHTWELL DRAIN (SEE DETAIL C3) TO BE CONNECTED TO SUMP PUMP VIA DEDICATED 4" PCV STORM DRAIN LINE O 0.5% MIN

(N) DEDICATED SUMP PUMP FOR SUBDRAINAGE ONLY PROVIDE 1/3 HP PUMP. PROVIDE HIGHWATER ALARM AND BACKUP POWER RECOMMENDED.





















ËACH WAY



-3" ASPHALT CONCRETE

8" CALTRANS CLASS II BASE ROCK





EROSION CONTROL MEASURES:

- 1. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 1ST TO APRIL 30. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 1ST OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- 2. SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- 3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- 4. ALL EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE-STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
- 5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- 6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF CLARK CIVIL ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY CLARK CIVIL ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- 7. THE EROSION CONTROL MEASURES SHALL CONFORM TO THE COUNTY STANDARDS AND THE APPROVAL OF THE COUNTY'S ENGINEERING DEPARTMENT.
- 8. STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWNSLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY ENDBUTTED. CONTRACTOR SHALL REFER TO MANUFACTURES SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

REFERENCES:

- 1. CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- 2. CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

PURPOSE:

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. CLARK CIVIL ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.

EROSION CONTROL LEGEND

GRAVEL BAG



INLET PROTECTION



CONCRETE WASHOUT







STRAW ROLL

____x _____x ____

SILT FENCE






EROSION CONTROL NOTES:

- 1. IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- 2. THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
- 3. OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- 4. SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 5. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- 6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- 7. CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- 8. ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 1ST.
- 9. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 1ST THROUGH APRIL 30, WHICHEVER IS LONGER.
- 10. IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- 12. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY COUNTY'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- 13. MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- 14. EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 30
- ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER 15 THRU APRIL 30, WHICHEVER IS GREATER.


PERIODIC MAINTENANCE:

- 1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
- A. DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
- B. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
- C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
- D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
- E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE. F. RILLS AND GULLIES MUST BE REPAIRED.
- 2. GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- 3. STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- 4. SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- 5. CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- 6. ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION



Construction Best Management Practices (BMPs)

Materials & Waste Management



Non-Hazardous Materials

- Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- Use (but don't overuse) reclaimed water for dust control.

Hazardous Materials

- Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- □ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- □ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- □ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

Construction Entrances and Perimeter

- Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- □ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control



Maintenance and Parking

- Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage. □ Perform major maintenance, repair jobs, and vehicle
- and equipment washing off site.
- □ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- □ If vehicle or equipment cleaning must be done onsite. clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- Do not clean vehicle or equipment onsite using soaps solvents, degreasers, steam cleaning equipment, etc.

Spill Prevention and Control


- Keep spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- □ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- □ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them. □ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- □ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).



Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.



Earthwork & Contaminated Soils



Erosion Control

- □ Schedule grading and excavation work for dry weather only.
- □ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- □ Seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.

Sediment Control

- □ Protect storm drain inlets, gutters, ditches. and drainage courses with appropriate BMPs, such as gravel bags, fiber rolls, berms, etc.
- □ Prevent sediment from migrating offsite by installing and maintaining sediment controls, such as fiber rolls, silt fences, or sediment basins.
- □ Keep excavated soil on the site where it will not collect into the street.
- Transfer excavated materials to dump trucks on the site, not in the street.
- □ Contaminated Soils
- □ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash.

Paving/Asphalt Work


Concrete, Grout & Mortar Application




- Avoid paving and seal coating in wet weather, or when rain is forecast before fresh pavement will have time to cure.
- Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- □ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- Do not use water to wash down fresh asphalt concrete pavement.

Sawcutting & Asphalt/Concrete Removal

- Completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- □ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- □ If sawcut slurry enters a catch basin, clean it up immediately.



- storm drain.
- □ Wash out concrete equipment/trucks harden and dispose of as garbage.
- □ Collect the wash water from washing for appropriate disposal offsite.



- Effectively manage all run-on, all
- □ When dewatering, notify and obtain may be required.
- off-site for proper disposal.

Storm drain polluters may be liable for fines of up to \$10,000 per day!

□ Store concrete, grout and mortar under cover, on pallets and away from drainage areas. These materials must never reach a

offsite or in a contained area, so there is no discharge into the underlying soil or onto surrounding areas. Let concrete

exposed aggregate concrete and remove it


Dewatering

runoff within the site, and all runoff that discharges from the site. Divert run-on water from offsite away from all disturbed areas or otherwise ensure compliance. approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap

□ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the Engineer to determine whether testing is required and how to interpret results. Contaminated groundwater must be treated or hauled



Painting & Paint Removal



Painting cleanup

- □ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or surface waters.
- □ For water-based paints, paint out brushes to the extent possible. Rinse to the sanitary sewer once you have gained permission from the local wastewater treatment authority. Never pour paint down a drain.
- □ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of residue and unusable thinner/solvents as hazardous waste.


Paint removal

- □ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead or tributyltin must be disposed of as hazardous waste.
- □ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.


Landscape Materials





- Contain stockpiled landscaping materials by storing them under tarps when they are not actively being used.
- □ Stack erodible landscape material on pallets. Cover or store these materials when they are not actively being used or applied.
- Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



Symbol	Species	Size Water	PROPOSED/EXISTING PLANT
	Rosa white carpet rose @ 30'' oc	l qallon low	
	Sedum qold @ 18'' oc	l qallon low	Proposed pla
	Dianella variqata @ 1811 oc	l qallon low	
	Gazania mitsuwa yellow @ 1811 oc	l qallon low	Proposed pla
А	Chondropetalum tectorum/Cape Rush	5 qallon low	T oposcu pia
В	Loropetalum Jazz Hands	5 qallon low	
С	Prunus caroliana Compacta/Carolina Laurel mature size 12'-15' tall - 2'-3' per year growth	24" box low	Existing plant
D	Cotinus Golden Spirit/Smoke Tree	15 gallon low	
E	Lavandula Munstead/Lavendar	5 qallon low	
F	Phormium Apricot Queen/Flax	5 qallon low	
G	Lomandra Baby Breeze	5 qallon low	
И	Pittosporum tenufolium Silver Sheen mature size 15'-20' tall - 2'-3' per year growth	24'' box low	
1I	Lagerstroemia Tuscorora std./Crape Myrtle mature height 15' - 2' per year growth	24" box low	
12	Olea europa Swan Hill/Fruitless Olive multi trunk mature size 25' tall - 2'-3' per year growth.	36" box low	
13	Acer palmatum Bloodqood/Japanese Maple	24" box low	
<i>ч</i> Л		24111	







<u> </u>			Efficient La			4° - 1	
Reference Evapotranspir		43	-	ect ⊺ype			0.55
Hydrozone # / Planting	Plant	Irrigation	Irrigation	ETAF	Landscape	ETAF x	
Description ^a	Factor (PF)	Method ^b	Efficiency	(PF/IE)	Area (Sq. Ft.)	Area	Water Use
			(IE) ^c				(ETWU) ^d
Regular Landscape		1		ı	1	r	1
#1 low water	0.3	Drip	0.81	0.37	355	131	3505
#2 low water	0.3	Drip	0.81	0.37	1185	439	11701
#3 low water	0.3	Drip	0.81	0.37	260	96	2567
#4 medium water	0.5	Drip	0.81	0.62	150		
#5 low water	0.3	Drip	0.81	0.37	360	133	3555
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75			0	
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75	0.00		0	0
			0.75			0	
			0.75			0	
			0.75	0.00		0	
			0.75	0.00		0	0
			0.75			0	
			0.75			0	
			•//•	Totals	2310	893	23797
Special Landscape	Areas						
				1		0	0
				1	1	0	
				1		0	
				1		0	0
				Totals	0	0	0
					ETV	, U Total	23797
		Ma	aximum Allow	ed Wate	r Allowance (I		33872

- a Hydrozone # / Planting Description e.g.
 1.) Front lawn
 2.) Low water use planting
- 3.) Medium water use planting
- ^b Irrigation Method
- 1.) Overhead Spray
 2.) Drip

Irrigation Efficiency
1.) 0.75 for Overhead Spray
2.) 0.81 for Drip

- ^d ETWU (Annual Gallons Required) =
 Eto x 0.62 x ETAF x Area
 Where 0.62 is a conversion factor to change acre-inches per acre per year to gallons per square foot per year
- MAWA (Annual Gallons Allowed) =

 (Eto) (0.62) [(ETAF x LA) + ((1-ETAF) x SLA)]

 Where 0.62 is a conversion factor to change acre-inches
 per acre per year to gallons per square foot per year, LA is
 the total regular landscape area in square feet, SLA is the
 total special landscape area in square feet, and ETAF is
 0.55 for residential areas and 0.45 for non-residential
 areas

0.45	Non-Residential
0.55	Residential
0.81	Drip
0.75	Overhead


ETAF Calculations


Regular Landscape Areas		
Total ETAF x Area	893	
Total Area	2310	
Average ETAF	0.39	

All Landscape Areas	
Total ETAF x Area	893
Total Area	2310
Average ETAF	0.39

Average ETAF for Regular Landscape Areas must be 0.55 or

below for residential areas, and 0.45 or below for non-residential





WILL OCCUR. 3. RAIN BIRD XERI-BUG BARB X BARB EMITTERS ARE AVAILABLE IN THE FOLLOWING MODELS: XB-05PC 0.5 GPH XB-10PC 1.0 GPH XB-20PC 2.0 GPH

BARB CONNECTOR INTO 1/2" TUBING

OPTION 3

N.T.S.

WITH 1/4" TUBING, STAKE AND XERI-BUG

OUTLET EMITTER:

RAIN BIRD TS-025

RAIN BIRD XQ TUBING (LENGTH AS REQUIRED)

RAIN BIRD SPB-025


RAIN BIRD XERI-BUG EMITTER

RAIN BIRD XF SERIES TUBING OR


RAIN BIRD XT-700 XERI-TUBE OR

1-18-10

RAIN BIRD XBS BLACK STRIPE TUBING



XB-05PC 0.5 GPH XB-10PC 1.0 GPH XB-20PC 2.0 GPH




W. Jeffrey Heid Landscape Architect c-2235

6179 Oneida Drive San Jose, California 95123

tel 408 691-5207 fax 408 226-6085 email wyheidasla@comcast.net

OWNERSHIP AND USE OF DRAWINGS

Il drawings, specifications and copies thereof furnished b I. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Project and are not to be used on any other project. Submission or distribution to meet official regulatory equirements or for other purposes in connection with he Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect , common law, copyright or other reserved rights.






DES	HPAN	JDE
RÉS	ÍDÉŇ	ĈĔ

for: SMITA AND PAWAN DESHPANDE 658 SPARGUR DRIVE LOS ALTOS, CA. 95020

IRRIGATION PLAN

date: 3/14/22 NOTED scale WJH drawn by: 202207 job no. sheet

of



shts