2. ALL CODES HAVING JURISDICTION ARE HEREBY MADE A PART OF THIS DOCUMENT AND ARE TO BE STRICTLY OBSERVED BY THE CONTRACTOR IN THE CONSTRUCTION OF THE PROJECT. IN THE EVENT OF CONFLICT BETWEEN THESE DOCUMENT AND THE CODE, THE CODE SHALL PREVAIL. ANY CONFLICT OR DISCREPANCY SHALL IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE ARCHITECT

3. ALL WORK, TO BE ACCEPTABLE, MUST BE IN COMPLIANCE WITH THESE DRAWINGS AND SPECIFICATIONS, AND MUST BE OF A QUALITY EQUAL OR BETTER THAN THE STANDARD OF THE TRADE. FINISHED WORK SHALL BE FIRM, WELL-ANCHORED, IN TRUE ALIGNMENT, PLUMB, LEVEL, WITH SMOOTH, CLEAN, UNIFORM APPEARANCE.

4. CONTRACTOR SHALL AT ALL TIMES PROVIDE PROTECTION AGAINST WEATHER, RAIN, WINDSTORMS, OR HEAT SO AS TO MAINTAIN ALL WORK, MATERIALS, EQUIPMENT AND APPARATUS FREE FROM INJURY OR DAMAGE.

5. CONTRACTOR SHALL VISIT THE SITE OF THE PROJECT, EXAMINE FOR HIMSELF/HERSELF THE NATURE OF THE EXISTING CONDITIONS AND ALL OTHER CONDITIONS RELEVANT TO THE SATISFACTORY COMPLETION OF THE PROJECT. SUBMISSION OF A BID FOR CONSTRUCTION SHALL BE CONSIDERED EVIDENCE OF SUCH

6. BEFORE ORDERING MATERIAL OR COMMENCING WORK WHICH IS DEPENDENT FOR THE PROPER SIZE AND INSTALLATION UPON COORDINATION WITH CONDITIONS IN THE BUILDING. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND SHALL BE RESPONSIBLE FOR THE CORRECTNESS. ANY DISCREPANCIES BETWEEN THE DOCUMENTS AND THE EXISTING CONDITIONS SHALL BE REFERRED TO THE ARCHITECT FOR ADJUSTMENTS BEFORE ANY WORK BEGINS OR MATERIALS ARE PURCHASED.

7. MATERIALS, PRODUCTS AND EQUIPMENT SHALL ALL BE NEW, EXCEPT AS

8. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL DEBRIS IN A LOCATION OF THE PROPERTY APPROVED BY THE OWNER AND SHALL REMOVE SAME IN A TIMELY MANNER DURING THE COURSE OF WORK.

COMPLETION OF THE PROJECT, PROTECT FROM DAMAGE OR INJURY ALL EXISTING TREES, LANDSCAPING AND IMPROVEMENTS INDICATED BY THE ARCHITECT. 10. EXCAVATE ALL FOOTINGS AS INDICATED ON THE DRAWING TO REACH SOLID,

9. CONTRACTOR SHALL REMOVE FROM SITE ANY IMPROVEMENTS NECESSARY FOR

UNDISTURBED SOIL. BOTTOMS OF EXCAVATIONS SHALL BE LEVEL, CLEAN AND DRY AND AT THE ELEVATIONS INDICATED ON THE STRUCTURAL DRAWINGS. COORDINATE WITH

11. PROVIDE FINISH GRADES TO DRAIN AWAY FROM THE FOUNDATIONS ON ALL SIDES OF THE BUILDING. SEE CIVIL DRAWINGS

12. CONTRACTOR TO PRECISELY LOCATE ALL UTILITIES PRIOR TO ANY CONSTRUCTION

13. WORK HOURS: CONSTRUCTION, DELIVERIES, AND OR SERVICING OF ANY ITEM ON SITE SHALL BE PROHIBITED BEFORE 8:00 AM AND AFTER 5:00 PM, WEEKDAYS, ALL DAY SATURDAY, SUNDAY AND HOLIDAYS.

14. CONSTRUCTION PARKING IS PERMITTED ONLY ON THE SITE AND ONLY ON THE SIDE OF THE STREET FRONTING THE PROPERTY FOR WHICH THE PERMIT IS ISSUED.

15. SURVEYOR IS REQUIRED TO PROVIDE LETTERS VERIFYING THE STRUCTURE IS LOCATED AS APPROVED ON THE PLANS FOR SETBACKS PRIOR TO POURING ANY CONCRETE AND VERIFYING THE HEIGHT OF THE STRUCTURE IS AS SHOWN ON THE

SLABS-ON-GRADE, PLACEMENT AND COMPACTION OF ENGINEERED FILL, AND SURFACE GEOTECHNICAL REPORT PREPARED BY EARTH SYSTEMS PACIFIC DATED NOVEMBER 22 2019. EARTH SYSTEMS PACIFIC SHOULD BE PROVIDED AT LEAST 48 HOURS ADVANCE NOTIFICATION OF ANY EARTHWORK OPERATIONS AND SHOULD BE PRESENT TO OBSERVE AND TEST, AS NECESSARY, THE EARTHWORK AND FOUNDATION INSTALLATION PHASES OF THE PROJECT.

MTL./MET.

(N) or NEW

NO. or #

N.T.S.

P.E.N.

PERF

P.LAM.

P.T.D.

REINF.

REQ'D

RWD.

R.W.L.

SCHED

SPEC.

STD.

SUSP.

T.&B.

T.&G.

T.O.P./TP

T.O.W./TW

T.P.D.

U.O.N.

VERT

W.H.

W.W.F.

PLYWD.

MISCELLANEOUS

NOT IN CONTRACT

OUTSIDE DIAMETER

PLASTIC LAMINATE

PRESSURE TREATED

PREFABRICATED

PLYWOOD EDGE NAILING

PLATE OR PROPERTY LINE

PAPER TOWEL DISPENSER

EMAIL:

NOT TO SCALE

ON CENTER

PERFORATED

DOUGLAS FIR

ROOF DRAIN

REFERENCE

REINFORCE

REQUIRED

REDWOOD

SOLID CORE

SCHEDULE

SELECT

SHEET

SQUARE

STANDARD

STORAGE

TELEPHONE

TOP OF CURB

TOP OF WALL

TELEVISION

TYPICAL

NOTED

VERTICAL

WITHOUT

WOOD

TOP OF PAVEMENT

TOILET PAPER HOLDER

UNLESS OTHERWISE

VERTICAL GRAIN

WATER CLOSET

WATER HEATER

WELDED WIRE FABRIC

WATERPROOF

TOILET PAPER DISPENSER

THROUGH

STRUCT./STRL. STRUCTURAL

ROUGH OPENING

RAIN WATER LEADER

SURFACED 4 SIDES

SMOKE DETECTOR

SPECIFICATION(S)

STAINLESS STEEL

TOP AND BOTTOM

SYMBOL or SYMMETRICAL

TONGUE AND GROOVE

RISER

RADIUS

OPENING

PLYWOOD

METAL

NEW

NORTH

NUMBER

ABBREVIATIONS

DIAMETER or ROUND

ABOVE FINISHED FLOOR

CONCRETE MASONRY UNIT

CLEANOUT or CASED OPENING P.T.D.F.

ACOUTSTICAL

ADJUSTABLE

APPROXIMATE

BUII DING

BLOCKING

BFAM

CABINET

CEILING

CLOSET

COLUMN

DOUBLE

DFTAII

DOWN

EACH

FQUAL

ELECT./ELEC. ELECTRICAL

CONCRETE

COLLAR TIE

COLD WATER

DEPARTMENT

DOUGLAS FIR

DIMENSION

DOWNSPOUT

DRAWING

FNCLOSURE

EQUIPMENT

FXISTING

GYPSUM

OWE. HARDWARE

HEIGHT

HFATER

HOSE BIB

EXPANSION

GYPSUM BOARD

HOLLOW CORE

HOLLOW META

HORIZONTAL

HOT WATER

HARDWOOD

INSULATION

INTERIOR

JANITOR

KITCHEN

LAMINATE

LAVATORY

MILMIXAM

MINIMUM

MECHANICAL

MF77ANINF

MANUFACTURER

JOIST

INCH OR INCHES

INSIDE DIAMETER (DIM.)

GALVANIZED SHEET METAL

EDGE OF SLAE

DISHWASHER

EXPANSION JOINT

DIAMETER

CLEAR

ARCHITECTURA

CONTROL JOINT

ACOUS

A.F.F.

ARCH.

BLDG.

BM.

CAB.

C.J.

CLG.

CLO.

CLR.

C.O.

COL.

C.T.

C.W.

DBL.

DEPT

DET.

DIM.

DWG.

E.J.

ENCL

E.O.S.

FQUIF

EXP.

GYP.

H.B.

H.M.

HTR.

H.W.

INT.

LAV.

HDWD.

HORIZ.

G.S.M.

EXST or (E)

C.M.U.

APPROX

4 NEW UNIT DEVELOPMENTS AT 14 4TH STREET

VIEW FROM FOURTH STREET



CONSULTANTS

CLIFFORD BECHTEL AND ASSOCIATES, INC. ENGINEERING AND PROJECT MANAGEMENT 1321 254TH PLACE SE, SAMMAMISH, WA 98075 650-333-0103

EMAIL: cliffbechtel1@comcast.net SURVEY: **MOUNTAIN PACIFIC SURVEYS** 1735 ENTERPRISE DR. SUITE 109, FAIRFIELD, CA 94533

GRID LINE

DOOR SYMBOL

DOOR MARK OR

WINDOW TYPE

SEQUENCE NUMBER

PLUMBING SYMBOL

APPLIANCE SYMBOL

KEYNOTE

DETAIL

IS DRAWN

SECTION

IS DRAWN

WORK, CONTROL, OR DATUM POINT

SEE LEGEND ON DRAWINGS

FOR EXPLANATION OF EACH

DETAIL NUMBER (1/2" DIA.)

SECTION NUMBER (1/2" DIA.)

SHEET WHERE SECTION

SHEET WHERE DETAIL

SYMBOL KEY

A-1

\ A1.1 🚣

GEOTECH: EARTH SYSTEMS PACIFIC 48511 WARM SPRINGS BLVD., SUITE 210 FREMONT, CA 94539; PH: 510-353-3833

INTERIOR ELEVATION

ELEVATION NUMBER

IS DRAWN

ROOM NAME

PROPERTY LINE

ROOM NUMBER

SHEET WHERE ELEVATION

ROOM IDENTIFICATION

DIMENSION @ FACE OF STUD,

DIMENSION @ CENTERLINE

DIMENSION @ FACE OF FINISH

NEW OR FINISHED CONTOURS

CHANGE IN FLOOR FINISHES

"CLOUD" INDICATES REVISED

ALIGN FACE OF FINISH

REVISION NUMBER

PARTITION TYPE

AREA ON DRAWINGS

EXISTING CONTOURS

MASONRY OR FRAMING (U.O.N.)

JOINT TRENCH:

OFFICE←

101

STRUCTURAL & MEP ENGINEERING: XL ENGINEERING

13620 LINCOLN WAY STE #200, AUBURN, CA 95603 925-803-9756 EMAIL STRUCTURAL: BRIANC@XL-ENGINEERING.NET EMAIL MEP: DINETHK@XL-ENGINEERING.NET

LANDSCAPE: GREGORY LEWIS LANDSCAPE ARCHITETURE

736 PARK WAY, SANTA CRUZ, CA 95065 831-425-4747 EMAIL: lewislandscape@sbcglobal.net

ARCHITECT: CKA ARCHITECTS

2089 AVY AVE. MENLO PARK. CA 94025 650-380-2760 EMAIL: chris@cka-architects.com

INTERIOR DESIGN: **ZAHARIAS DESIGN** 2043 OAKLEY AVE, MENLO PARK, CA 94025 650-906-8451

EMAIL: stephanie@zahariasdesign.com

PROJECT SUMMARY

APN No.: 167-38-061 LAND USE MAP: MEDIUM DENSITY MULTI-FAMILY (MDMF) **ZONING MAP:** MULTIPLE FAMILY (R3-1) <u>DOWNTOWN VISION PLAN:</u> EDITH AVENUE DISTRICT <u>LOT SIZE:</u> 7,038 SF (0.1616 ACRES)

TYPE OF CONSTRUCTION: V-B OCCUPANCY TYPE: R-2 AUTOMATIC FIRE SPRINKLERS REQUIRED: YES

NOTE: EXISTING ±1,302 SF RESIDENCE AND ±493 SF GARAGE TO BE DEMOLISHED

PARKING:

4 PROPOSED 2-BEDROOM DWELLING UNITS 8 PROPOSED UNDERGROUND, OFF-STREET PARKING SPACES (2 PER UNIT) 1 PROPOSED ON-SITE VISITOR PARKING SPACE (1 PER 4 UNITS)

SETBACKS: (SEE SHEET A1.1)

FRONT SETBACK: 20'-0" REAR SETBACK: 25'-0" SIDE SETBACKS: 7'-6" 2ND STORY SIDE SETBACK: 12'-6"

EXCEPTIONS INCLUDE 4'-0" MAXIMUM ENCROACHEMENT FOR CANOPIES, CHIMNEYS CORNICES, EAVES, OVERHANGS

MAXIMUM HEIGHT: 35'-0"


PROPOSED MAXIMUM HEIGHT: ±30'-10 1/2"

MAXIMUM ALLOWABLE COVERAGE: 2,815 SF (40% OF SITE) (14.02.070 DEFINITIONS NET SITE AREA COVERED IN STRUCTURES IN EXCESS OF 6 FEET IN HEIGHT MEASURED TO THE OUTSIDE OF SURFACES OF EXTERIOR WALLS AND THE PERIMETER OF ANY SUPPORTS.

PROPOSED COVERAGE: 2,716.3 SF

AFFORDABLE HOUSING REQUIREMENTS APPLY TO PROJECTS WITH 5 OR MORE DWELLING UNITS

VICINITY MAP



GENERAL INFORMATION

RENDERINGS

STREET ELEVATIONS

A1.2 FLOOR AREA CALCULATIONS

BASEMENT PLAN

1ST FLOOR PLAN

EXTERIOR ELEVATIONS

EXTERIOR ELEVATIONS

ARBORIST REPORT SHEET

ARBORIST REPORT SHEET 2

AR4 ARBORIST REPORT SHEET 4

C-1.0 GRADING AND DRAINAGE PLAN

MATERIALS IMAGERY

BUILDING SECTION

A2.2 2ND FLOOR PLAN

ROOF PLAN

A5.1 DESIGN CONTROL

A5.2 DESIGN CONTROL 2

CLIMATE ACTION CHECKLIST AND

CONSTRUCTION MANAGEMENT PLAN

WALL SECTION & SECTION ELEVATION

C-2.0 EROSION & SEDIMENT CONTROL & STAGING

CMP CONSTRUCTION MANAGEMENT PLAN

VTM 1 VESTING TENTATIVE PARCEL MAP

VTM 2 VESTING TENTATIVE PARCEL MAP

PLANT IMAGES

BMP-1 BEST MANAGEMENT PRACTICES SHEET

LANDSCAPE SITE / PLANTING PLAN

TRASH / SHORING DIAGRAMS

HARDSCAPE / CIRCULATON / FIRE DIAGRAMS

A0.0 COVER SHEET

<u>ARCHITECTURAL</u>

A1.0 SITE PLAN

A0.1

A2.1

A2.3

A4.1

CIVIL

SURVEY

C-1.1 UTILITY PLAN

LANDSCAPE

PROJECT DESCRIPTION | SHEET INDEX

THIS PROJECT INVOLVES: CONSTRUCTION OF 4 MARKET RATE CONDOMINIUM UNITS WITH A **CONDO MAP AND SEMI-SUBTERRANEAN PARKING**

ADDRESS: 14 4TH STREET LOS ALTOS, CA 94022 OWNERS: 14 4TH STREET LLC ARCHITECT: CHRIS KUMMERER, ARCHITECT PH: (650) 233-0342

E-MAIL: CHRIS@CKA-ARCHITECTS.COM

FIRE SPRINKLER NOTE

A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN ACCORDANCE WITH NFPA 13D AND STATE AND LOCAL REQUIREMENTS. PROVIDE A FULL FIRE SPRINKLER SYSTEM LISTED FOR RESIDENTIAL USE(CRC R313.3.2) AND SHALL BE INSTALLED IN ACCORDANCE WITH SPRINKLER MANUFACTURER'S INSTALLATIONS INSTRUCTIONS UNDER SEPARATE PERMIT. AUTOMATIC RESIDENTIAL FIRE SPRINKLER SYSTEM SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH CFMO-SP6 THROUGHOUT THE DWELLING TO INCLUDE ANY ACCESSORY STRUCTURE IN EXCESS OF 1,000 SQ.FT . SPRINKLER PLAN TO INDICATE LOCATION OF WATER SUPPLY, SPRINKLER AND PIPING MATERIALS PER CRC R313.3.1.1. R313.3.2. R313.3.2.2 & R313.3.2.4. CONTRACTOR TO PROVIDE FIRE SPRINKLER FLOW RATE AND PIPE SIZING CALCULATION FOR REVIEW PER R313.3.2 & R313.3.6 FINAL SPRINKLER INSTALLATION SHALL INCLUDE THE SIGN OR VALVE TAG REQUIRED BY CRC R313.3.7 AND THE OWNER'S MANUAL FOR THE SYSTEM PER CRC313.3.8.2.

GEOTECHNICAL NOTE

EARTH SYSTEMS PACIFIC IS THE GEOTECHNICAL ENGINEER FOR THE PROJECT. THE CONTRACTOR SHALL REVIEW THE GEOTECHNICAL REPORT PRIOF TO BEGINNING EXCAVATION. THE CONTRACTOR SHALL CONSULT WITH THE GEOTECHNICAL ENGINEER DURING EXCAVATION TO DETERMINE OPTIMAL FOUNDATION DEPTH BASED UPON FIELD CONDITIONS, SLABS, FOOTINGS AND PAVING SHALL BE CONSTRUCTED IN CONFORMANCE WITH GEOTECHNICAL ENGINEERING SPECIFICATIONS SOILS ENGINEER SHALL BE RETAINED TO PROVIDE OBSERVATION AND TESTING SERVICES DURING THE GRADING AND FOUNDATION PHASE OF CONSTRUCTION PER SOIL REPORT RECOMMENDATIONS.

DEFERRED SUBMITTALS

- SOLAR POWER CONDOMINIUM MAP SUBMITTAL - DEMOLITION PERMIT SUBMITTAL - FIRE SPRINKLER DESIGN SUBMITTAL

APPLICABLE CODES

2019 CALIFORNIA BUILDING CODE, VOLUMES 1 & 2 2019 CALIFORNIA RESIDENTIAL CODE 2019 CALIFORNIA ENERGY CODE 2019 CALIFORNIA ELECTRICAL CODE

2019 CALIFORNIA PLUMBING CODE 2019 CALIFORNIA MECHANICAL CODE 2019 CALIFORNIA FIRE CODE 2019 CALIFORNIA GREEN BUILDING CODE AND CURRENT LOCAL BUILDING AND ZONING

CODES INCLUDING THE GREEN BUILDING <u>ORDINANCE</u>

CALCULATIONS OF HARDSCAPE & SOFTSCAPE AREAS TOTAL AREA 7,046.72 100% HARDSCAPE (BUILDING FOOTPRINT 4.871.61 69% DRIVEWAY & EASEMENT) HARDSCAPE (CONCRETE 770.95 11% WALKWAYS & TRASH ENCLOSURE) SOFTSCAPE (PERMEABLE DG & 1,404.16 20% PLANTED AREAS

ARCHITECTS

CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS: 2.16.2022 PRELIMIMARY PLANNING **COMMISSION SUBMITTAL** 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL

RECEIVED

Date: 10/15/2022

CITY OF LOS ALTOS PLANNING

CONSULTANTS

STAMP: KUMMERER

PAGE NUMBER

COVER SHEET

Los Altos Climate Action Plan

	Best Management Practice Required	Applicable to	Describe Project Compliance	
1.1 Improve Non-Motorized Transportation		n		
NA	Provide end-of-trip facilities to encourage alternative transportation, including showers, lockers, and bicycle racks.	Nonresidential projects greater than 10,000 square feet		
NA	Connect to and include non- motorized infrastructure on-site.	Nonresidential projects greater than 10,000 square feet		
NA	Where appropriate, require new projects to provide pedestrian access that internally links all surrounding uses. Applicable to all new commercial and multiple-family development.	Nonresidential projects greater than 10,000 square feet		
1.2	Expand Transit and Commute Options			
NA	Develop a program to reduce employee VMT.	Nonresidential projects greater than 10,000 square feet (or expected to have more than 50 employees)		
1.3	Provide Alternative-Fuel Vehicle Infras			
NA	Comply with parking standards for EV pre-wiring and charging stations.	New and substantially remodeled residential units Nonresidential projects greater than 10,000 square feet		
2.2	Increase Energy Efficiency			
X	Comply with the Green Building Ordinance.	All new construction and remodels greater than 50%	BINDING ORDINANCES COVER SHEET, A0.0	
X	Install higher-efficiency appliances.	All new construction and remodels greater than 50%	HIGHER EFFICIENCY A THE FLOOR PLANS, A2	.0, A2.1, A2.2, AND A2.3
X	Install high-efficiency outdoor lights.	All new construction and remodels greater than 50%	ON THE FIRST FLOOR	
X	Obtain third-party HVAC commissioning.	All new nonresidential construction and remodels greater than 50%	THIRD-PARTY HVAC CO IN KEYNOTES.	OMMISSIONING NOTED
3.1	Reduce and Divert Waste			
X	Develop and implement a Construction & Demolition (C&D) waste plan.	All demolition or new construction projects	A CONSTRUCTION & DI WILL BE INCLUDED IN I	EMOLITION WASTE PLAI PERMIT SUBMITTAL.
3.2	Conserve Water			
X	Reduce turf area and increase native plant landscaping.	All new construction	NO TURF AREA SHALL LANDSCAPE PLAN.	BE INCLUDED IN THE
3.3	Use Carbon-Efficient Construction Equ	ipment		
	Best Management Practice Required	Applicable to	Describe Project Compliance	
X	Implement applicable BAAQMD construction equipment best practices.	All new construction	BAAQMD CONSTRUCTI PRACTICES SHALL BE	
4.1	Sustain a Green Infrastructure System	-		
NA	Create or restore vegetated common space.	Residential or nonresidential projects greater than 10,000 square feet		
NA	Establish a carbon sequestration project or similar off-site mitigation strategy.	Residential or nonresidential projects greater than 10,000 square feet		
X	Plant at least one well-placed shade tree per dwelling unit.	New residential construction	4 NEW SHADE TREES, UNIT ARE PROVIDED. S	ONE PER DWELLING SEE LANDSCAPE PLAN.
5.1	Operate Efficient Government Facilities			
NA	Incorporate the use of high-albedo or porous pavement treatments into City projects to reduce the urban heat island effect.			

	Best Management Practice	Applicable to	Projec	t Com	pliance	
1.1	Improve Non-Motorized Transportation					
NA	Provide end-of-trip facilities to encourage alternative transportation, including showers, lockers, and bicycle racks.	Nonresidential projects over 10,000 square feet	Yes	No	N/A)	
NA	Connect to and include non-motorized (bicycle and pedestrian) infrastructure onsite.	Nonresidential projects over 10,000 square feet	Yes	No	N/A)	
NA	Where appropriate, require new projects to provide pedestrian access that internally links all surrounding uses. Applicable to all new commercial and multiple-family development.	Nonresidential projects over 10,000 square feet	Yes	No	N/A)	
1.2	Expand Transit and Commute Options					
NA	Develop a program to reduce employee vehicle miles traveled (VMT).	Nonresidential projects over 10,000 square feet (or over 50 employees)	Yes	No	N/A)	
1.3	Provide Alternative-Fuel Vehicle Infrastru	ıcture				
X	Provide electric vehicle (EV) pre-wiring and/or charging stations.	All projects	Yes	ELEC' SHOV	TRIC VEH	IICLE CHARGING STATIONS IE A2.0 BASEMENT PLAN.
2.2	Increase Energy Efficiency					
X	Install higher-efficiency appliances.	All new construction	Yes			IENCY APPLIANCES NOTED ON ANS, A2.0, A2.1, A2.2, AND A2.3
X	Install high-efficiency outdoor lights.	All new construction	Yes			ICY OUTDOOR LIGHTS NOTED FLOOR PLAN, A2.1
X	Obtain third-party heating, ventilating and air conditioning (HVAC) commissioning.	All new nonresidential construction	Yes		D-PARTY YNOTES.	HVAC COMMISSIONING NOTED
	Best Management Practice	Applicable to	Projec	t Com	pliance	
3.1	Reduce and Divert Waste					
X	Develop and implement a Construction and Demolition (C&D) waste plan.	All new projects	Yes	A COI WILL	NSTRUCT BE INCLU	 TION & DEMOLITION WASTE PLAN DED IN PERMIT SUBMITTAL.
3.2	Conserve Water					
X	Reduce turf area and increase native plant landscaping.	All new projects	Yes	NO TU LAND	JRF AREA SCAPE PI	I A SHALL BE INCLUDED IN THE LAN.
3.3	Use Carbon-Efficient Construction Equipm	nent				
X	Implement applicable Bay Area Air Quality Management District construction equipment best practices. <i>Tables 8-1 and 8-2 in the District's Air Quality Guidelines (separate handout)</i> .	All new projects	Yes	BAAQ PRAC	MD CONS	STRUCTION EQUIPMENT BEST HALL BE IMPLEMENTED.
4.1	Sustain a Green Infrastructure System an	d Sequester Carbon				
NA	Create or restore vegetated common space.	Projects over 10,000 sq ft	Yes	No	N/A)	
NA	Establish a carbon sequestration project or similar off-site mitigation strategy.	Projects over 10,000 sq ft	Yes	No	N/A)	
X	Plant at least one well-placed shade tree per dwelling unit.	New residential projects	Yes	4 NEV	V SHADE ARE PRO	 TREES, ONE PER DWELLING VIDED. SEE LANDSCAPE PLAN.






CHRIS KUMMERER & ASSOCIATES

p 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:
2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL
10.25.2022 DESIGN REVIEW SUBMITTAL

14 4TH STREET

CONSULTANTS:



PAGE NUMBER:


A0.

THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCH ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY AND MAY NOT BE REPRODUCED IN MAY MANINER OR USED FOR OTHER LOCATION











CKa ARCHITECTS

CHRIS KUMMERER & ASSOCIATES

p 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

R E V I S I O N S:

2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL

5.9.2022 DESIGN REVIEW SUBMITTAL

10.25.2022 DESIGN REVIEW SUBMITTAL

22 DESIGN REVIEW SUBMI 2022 DESIGN REVIEW SUBMI

14 4TH STREET

CONSULTANTS:

STAMP:

CHRISTOPHER

L.

KUMMERER

NO. C-29207


REN. 11-30-21


P. CALIE


PAGE NUMBER:

STREET ELEVATIONS

THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AND ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY AND MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS WITHOUT THE WRITTEN APPROVAL OF CHRIS KUMMERER.







NEW AREA - EXISTING AREA =

3,886 SF

(NOTE: GROSS FLOOR AREA INCLUDES BASEMENT AND

EXTERIOR STAIRWAYS)

ADDED ASSESSABLE SPACE =

CKa ARCHITECTS

CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

R E V I S I O N S:

2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL

5.9.2022 DESIGN REVIEW SUBMITTAL

10.25.2022 DESIGN REVIEW SUBMITTAL

4TH STREET

CONSULTANTS:

STAMP:

CHRISTOPHER

L

KUMMERER

NO. C-29207

REN. 11-30-21


OF CALL


PAGENUMBER:

A1.2

FLOOR AREA DIAGRAMS

THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITE:
ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY
AND MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS
WITHOUT THE WRITTEN APPROVAL OF CHRIS KUMMERER.





		1				
CALCULATIONS OF HARDSCAPE & SOFTSCAPE AREAS						
TOTAL AREA	7,046.72	100%				
HARDSCAPE (BUILDING FOOTPRINT, DRIVEWAY & EASEMENT)	4,871.61	69%				
HARDSCAPE (CONCRETE WALKWAYS & TRASH ENCLOSURE)	770.95	11%				
SOFTSCAPE (PERMEABLE DG & PLANTED AREAS	1,404.16	20%				



CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM

REVISIONS:

2.16.2022 PRELIMIMARY PLANNING COMMISSION SUBMITTAL 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL

CKA-ARCHITECTS.COM


CONSULTAN**T**S:


STAMP: KUMMERER

PAGE NUMBER:

CONSTRUCTION MANAGEMENT PLAN

THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AN ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY AND MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS WITHOUT THE WRITTEN APPROVAL OF CHRIS KUMMERER.





- 1 NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING WATER HEATER AND HVAC UNIT.
- NEW HIGHER EFFICIENCY APPLIANCES -INCLUDING REFRIGERATOR, MICROWAVE,
- RANGE AND DISHWASHER.

 NEW HIGHER EFFICIENCY APPLIANCES -INCLUDING STACKABLE WASHER AND DRYER.
- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING AC CONDENSER.




CHRIS KUMMERER & ASSOCIATES

p 650.233.0342 2089 avy avenue, menlo park ca 94025 CHRIS@CKA-ARCHITECTS.COM

REVISIONS:
2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL

CKA-ARCHITECTS.COM



- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING WATER HEATER AND HVAC UNIT.
- NEW HIGHER EFFICIENCY APPLIANCES -INCLUDING REFRIGERATOR, MICROWAVE,
- RANGE AND DISHWASHER.

 NEW HIGHER EFFICIENCY APPLIANCES -INCLUDING STACKABLE WASHER AND DRYER.
- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING AC CONDENSER.




CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:

2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL



- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING WATER HEATER AND HVAC UNIT.
- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING REFRIGERATOR, MICROWAVE,
- RANGE AND DISHWASHER.
- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING STACKABLE WASHER AND DRYER. NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING AC CONDENSER.




Chris Kummerer & associates

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:

2.16.2022 PRELIMIMARY PLANNING COMMISSION SUBMITTAL 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL



- 1 NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING WATER HEATER AND HVAC UNIT.
- NEW HIGHER EFFICIENCY APPLIANCES --INCLUDING REFRIGERATOR, MICROWAVE, RANGE AND DISHWASHER.
- NEW HIGHER EFFICIENCY APPLIANCES -INCLUDING STACKABLE WASHER AND DRYER.
- NEW HIGHER EFFICIENCY APPLIANCES -- INCLUDING AC CONDENSER.




Chris Kummerer & associates

p 650.233.0342 2089 avy avenue, menlo park ca 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM


REVISIONS:

2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL









EXTERIOR ELEVATIONS (ALLEY SIDE)



REVISIONS: 2.16.2022 PRELIMIMARY PLANNING COMMISSION SUBMITTAL 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL


TREET, LOS ALTOS, APN# 167-38-061

STAMP: PAGE NUMBER:


CONSULTANTS:

EXTERIOR ELEVATIONS

TERRACOTTA BRICK/TILE PALETTE







IMAGES AND COLORS ARE SUBJECT TO PRINTING AND COMPUTER **INACURACIES. THEY ARE** REPRESENTATIONAL ONLY

VERTICAL WOOD SIDING







CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS: 2.16.2022 PRELIMIMARY PLANNING

BRICK/TILE & STUCCO COMBINED






























SE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AND INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS HOUT THE WRITTEN APPROVAL OF CHRIS KUMMERER.


D. Window Design.

ARCHITECTS


CHRIS KUMMERER & ASSOCIATES

2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM


REVISIONS: 2.16.2022 PRELIMIMARY PLANNING **COMMISSION SUBMITTAL** 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL




ELEVATION 3 - DRIVEWAY SIDE		
TOTAL AREA	2,094.04	100%
Primary - WOOD GRAIN	1,044.45	50%
Secondary - STUCCO COLOR 1	636.74	30%
Tertiary - STUCCO COLOR 2	280.60	13%
PAINTED WOOD	128.05	6%
GARAGE DOORS	114.94	5%
TILE	4.62	0%
GARAGE DOORS	114.94	



ELEVATION 2 - WALKWAY SIDE		
TOTAL AREA	2,501.22	100%
Primary - WOOD GRAIN	1,287.63	51%
Secondary - STUCCO COLOR 1	761.20	30%
Tertiary - STUCCO COLOR 2	199.93	8%
Accent - PAINTED WOOD	96.18	4%
Accent - Tile	78.43	3%
Accent - PAINTED DOOR	79.27	3%



ELEVATION 4 - REAR		
TOTAL AREA	845.96	100%
Primary - WOOD GRAIN	468.94	55%
Secondary - STUCCO	249.95	30%
Tertiary - TILE	107.1	13%
Accent - PAINTED WOOD	23.39	3%



ELEVATION 4 EDONT		
ELEVATION 1 - FRONT		
TOTAL AREA	786.13	100%
Primary - WOOD GRAIN	391.73	50%
Secondary - TILE	234.44	30%
Tertiary - STUCCO	156.55	20%
Accent - PAINTED WOOD	30.88	4%

e. Arcades. Arcades shall be supported by columns or piers in concrete/cast stone, fiberglass, or stucco. Archivolts and imposts shall be expressed using similar materials/appearance.

f. Structural elements. Structural elements visible on the building exterior (e.g. rafters, purlins, posts, beams, balconies, brackets, trusses, columns, arches, etc.), even when ornamental, shall be sized and spaced according to the corresponding structural role, and materials shall be selected accordingly (see A. Architectural Integrity).

corresponding structural role, and materials shall be selected accordingly (see A. Architectural Integrity).

5. Materials Allowed for Building Details/Ornament.

a. Wood.b. Metal (wrought iron, copper, aluminum, tin).

5. Metai (Wrought Iron, copper, aidminum, tin).

c. Glass fiber reinforced concrete (GERS)/fiberglass.

d. Terra Cotta. e. Tile.

f. Plaster.

E. Colors.1. A maximum of four colors shall be applied to be the building façade:

a. One primary color comprising fifty (50) percent or more of the façade excluding transparent surfaces.

b. One secondary color comprising no more than thirty (30) percent of the façade excluding transparent surfaces.

c. One tertiary color comprising no more than twenty (20) percent of the façade excluding transparent surfaces.

d. One accent color for use on trim and architectural details.

2. Materials with intrinsic, naturally-occurring coloration shall not count towards this maximum. Such materials are limited to copper, Corten steel, unpainted wood, tile, and brick. Materials with prefinished color (stucco, cement fiberboard, colorized metal) shall count towards the maximum.

3. Changes in color may occur:

a. To articulate changes between base, body, and top portions of a façade, which must be separated by a cornice or profile or a change in material and must remain consistent across the length of the façade bay.

b. When a portion of the elevation is articulated as a separate building with a break in the roof form and a step back in the façade plane five feet or greater or step up in façade height at least ten (10) feet.

c. On attached elements, such as bay windows, orioles, and balconies.

F. Façade Lighting. Façade lighting shall be incorporated into all storefront design and all façades facing an R-1 district. Fixtures shall be:

1. Shielded and directed onto the building façade.

2. Consistent in style with the primary building.

G. Habitable Outdoor Space. Private, habitable outdoor space supported by the building structure, such as balconies or terraces, shall be either uncovered or sheltered. The following patterns are strongly recommended:

Pergola: Posts supporting beams with brackets, which in turn support purlins and/or rafters. Posts shall be no narrower in any dimension than 3.5" or 1/20 of the unbraced post length, whichever is greater.
 Trabeation: Posts or columns supporting beams with or without brackets, which in turn support either an additional floor level (for multi-story porches/balconies) or a full roof system based on rafters and/or purlins with decking and finish

material. Posts shall be no narrower in any dimension than 3.5" or 1/20 of the unbraced post length, whichever is greater. The distance between posts shall be no wider than the total post height.

3. Arcuation: Encompassed by walls that are penetrated by arched openings bounded by either columns or piers. The ratio of column diameter [at lowest part of shaft] to column height shall be no less than 1:10 and no greater than 1:7. Width of

piers at corners [abutments] shall be no less than 1/3 of the opening width; piers between multiple arched openings may be narrower.

4. Rectilinear: Bounded by square/rectangular piers framing rectilinear wall openings. If lintels are expressed on the façade, they shall extend over the piers by 4"—6" at each end. Piers shall be no narrower in any dimension than 15.5" or 1/6 of

the opening width, whichever is greater. Piers at corners shall be wider than piers between openings.

5. Fabric Shading: Shaded by fabric elements such as awnings or stretched canvas, secured to the building structure, sheltered by Main Roof Form, supported by other building volumes.

3. Fabric Shading. Shaded by fabric elements such as awilings of stretched canvas, secured to the building struct

a. Cantilevered balconies shall be secured architecturally to the wall below by brackets.b. Bracket material shall be consistent with that of the balcony's floor structure.

H. Historic Preservation.

1. Additions to buildings with historic designation shall be identifiable from original construction. Additions shall employ similar or complementing materials and colors and shall exhibit similar opening proportions, façade rhythms and colors are complementing materials.

2. Original transom windows shall be maintained or restored where possible. If the ceiling inside the structure has been lowered, the ceiling shall be stepped up to meet the transom so that light will penetrate building interior.

3. Deteriorated architectural features shall be repaired rather than replaced wherever possible. If replacement is necessary, new materials shall match the original in design, color, texture, and other visual qualities. If the original was painted

3. Deteriorated architectural features shall be repaired rather than replaced wherever possible. If replacement is necessary, new materials shall match the original in design, color, texture, and other visual qualities. If the original was painted, the

substitute materials shall be painted as well.

I. Sustainability in Design.

1. All new construction shall incorporate landscaping and fenestration to passively cool the building; energy-efficient HVAC; and energy efficient lighting.

2. All energy generation devices must blend in with the building color.

3. All on-site landscaping shall be drought-resistant and require minimal irrigation.

Trees proposed within street-facing setbacks must be selected from the Los Altos Street Tree Planting List.

Trees planted on the south side of the building must be deciduous.

Species shall be selected and located according to direct sunlight needs.

4. Vegetation shall be installed along all exposed east and west facing walls.

5. Groundcovers shall be planted over a minimum fifty (50) percent of landscaped areas to prevent ground reflection and keep surfaces cool

6. When parking is tucked under a building, landscape planters must be provided to break up the continuous paving at the building's edge.

K. Screening.


1. Rooftop mechanical equipment must be screened from public view.

Barbed wire, chain-link, and razorwire are not permitted.

14.66.275 - Entrance type standards.

A. Stoop.







NOT APPLICABLE

WOOD IS 50%

STUCCO IS 30%

NOT APPLICABLE

DARK METAL ACCENT COLOR

ORNAMENT IS TERRA COTTA TILE, WOOD AND METAL

COLORS ARE 1: WOOD, 2: STUCCO 3: TILE, 4: WINDOWS/ GUTTERS/ METAL/ STUCCO SKIRT ON SIDES

NO FACADE LIGTHING- ONLY DOWNLIGHTS FROM EAVES AT PORCHES, BALCONIES AND ENTRIES.

CROSS VENTILATION PASSIVELY COOLS THIS BUILDING. EAVE AT PORCHES BLOCKS HEAT GAIN,

FRONT ENTRY CONFORMS WITH STOOP DIMENSIONS (ALTHOUTH THESE ENTRY OPTIONS SEEM TO BE

WESTERN FACADE HAS MINIMAL WINDOWS REDUCING HEAT GAIN

PLANTS WILL BE DROUGHT TOLERANT

PLANTS WILL COMPLY WITH THIS SECTION

ROOFTOP MECHANICAL IS SCREENED BY PARAPET

AIMED AT COMMERCIAL USES - NOT RESIDENTIAL)

THE APPLICANT HAS DECIDED NOT TO USE RAZOR WIRE IN THIS PROJECT

ENERGY GENERATION IS NOT VISIBLE (ON ROOF BEHIND PARAPET)

BALCONIES ARE COVERED (SHELTERED) FOR BETTER USE AND WATERPROOFING

CHRIS KUMMERER & ASSOCIATES


P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:
2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL

COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL
10.25.2022 DESIGN REVIEW SUBMITTAL

14 4TH STREET

14 4TF



THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AND ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY AND MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS

DESIGN CONTROL

Tree Inventory, Assessment, and Protection Report

14 Fourth Street Los Altos, CA 94022

Prepared for:

14 Fourth Street LLC

May 19, 2022 Revised August 4, 2022

Prepared By:

Richard Gessner

ASCA - Registered Consulting Arborist ® #496 ISA - Board Certified Master Arborist® WE-4341B



Monarch Consulting Arborists

Richard Gessner P.O. Box 1010 – Felton, CA 95018 1 831 331 8982 www.monarcharborists.com

© Copyright Monarch Consulting Arborists LLC, 2021

Table of Contents

Summary	3
Introduction	3
Background	3
Assignment	3
Limits of the Assignment	4
Purpose and Use of the Report	4
Observations	5
Tree Inventory	5
Discussion	6
Condition Rating	6
Suitability for Preservation	7
Expected Impact Level	7
Tree Protection	9
Conclusion	10
Recommendations	11
Bibliography	12
=g. ap,	12
Glossary of Terms	
	13
Glossary of Terms	13 14
Glossary of Terms Appendix A: Tree Locations and Proposed Plan	13 14 14
Glossary of Terms Appendix A: Tree Locations and Proposed Plan	13 14 15
Glossary of Terms Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1	13 14 15 16
Appendix A: Tree Locations and Proposed Plan	13 14 15 16
Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1 Appendix B: Tree Inventory and Assessment Tables Appendix C: Photographs	1314151617
Glossary of Terms Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1 Appendix B: Tree Inventory and Assessment Tables Appendix C: Photographs C1: Street Tree #2, Pittosporum #3, and Coast Redwood #4	1314151617
Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1 Appendix B: Tree Inventory and Assessment Tables Appendix C: Photographs C1: Street Tree #2, Pittosporum #3, and Coast Redwood #4 C2: Coast Redwood #9 and #10	131415161717
Glossary of Terms	13141516171719
Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1 Appendix B: Tree Inventory and Assessment Tables Appendix C: Photographs C1: Street Tree #2, Pittosporum #3, and Coast Redwood #4 C2: Coast Redwood #9 and #10 C3: Plums #11 and #12 C4: Coast Redwoods #6 and #7	13141516171919
Appendix A: Tree Locations and Proposed Plan A1: Tree Locations A2: Proposed Site Plan C-1 Appendix B: Tree Inventory and Assessment Tables Appendix C: Photographs C1: Street Tree #2, Pittosporum #3, and Coast Redwood #4 C2: Coast Redwood #9 and #10 C3: Plums #11 and #12 C4: Coast Redwoods #6 and #7 Appendix D: Tree protection specifications	131415161719192021

Certification of Performance	29
Qualifications, Assumptions, and Limiting Conditions	28
E2: Spanish	27
E1: English	26
Appendix E: Tree Protection Signs	26
Tree Protection Signs	25
Tree Pruning and Removal Operations	25
Timing	25
Boring or Tunneling	25
Root Pruning	24
Restrictions Within the Tree Protection Zone	24
Monitoring	24
Tree Protection Zones and Fence Specifications	24
Pre-Construction Meeting with the Project Arborist	23
Prohibited Activities	23

This revision is a response to comment 16 provided by the City of Los Altos which is as follows:


16. **Arborist Report.** Staff appreciates the provided arborist report. Please find the following comments for staff:

A. As recommended by the subject arborist, tree numbers shall be provided on the site plan and civil plans, consistent with the numbering in the arborist's report.

MCA: to be rectified by the design team an applicant.

B. Staff has concerned <sic> that the arborist did not fully considered <sic> impacts from the basement's excavation to the trees. As the requested excavation/shoring plan provided comments 5G.a above, the subject arborist shall update the arborist's report to discuss the tree protection measures from the excavation/shoring plan.

MCA: The applicant provided the A1.5 sheet and the shoring plan as provided below:





I have reviewed the plans regarding the proximity of the trenching and shoring adjacent to the trees.

I have suggested within the report in the "Expected Impacts", "Tree Protection" and "Recommendations" sections to pre-trench and selectively remove roots as necessary. TO reiterate Recommendation #4 states the following:

4. Pre-trench along the proposed soil cut adjacent to the trees (#4 and #5). Have an ISA Certified Arborist® observe the trenching and provide guidance to selectively remove any significant roots (roots greater than one inch in diameter (1") if encountered. Selective root removal requires pre-excavation, typically by hand or with a pneumatic excavating equipment such as an Air Spade®, Air Knife®, or similar tools. Selective removal allows for the roots to be exposed prior to cutting at the appropriate locations. This is the type of root removal that will need to occur at the building foundation. Roots greater than one inch in diameter should be pruned rather than left torn or crushed so as to leave "a clean flat surface with intact surrounding bark" (Costello, L., Watson, G., Smiley, E. T.. 2017).

Recommendations #1, #2, and #3 also include mulch to protect the soil surface, supplemental irrigation to help reduce impacts of potential root loss, and exclusionary fence where possible. Within the "Tree Protection Guidelines" there are provisions for root pruning, monitoring, and pre-construction meetings.

It is the responsibility of the owners or contractors to schedule meetings and monitoring and to adhere to the recommendations. The proposed shoring encroaches six and ten percent into the suggested TPZ and is not expected to compromise the health or integrity of the trees.

C. For the applicants information the tree protection will be further conditioned on the approval letter recommended by the City Council.

MCA: Understood.

Summary

The plans are to demolish the existing structure and construct four new residences. The inventory includes twelve trees comprised of six different species. The trees are located around the perimeter of the property and either on the street or adjacent sites except for a few. Six trees are in good condition, three fair, and three are in poor shape. One "Street Tree" is expected to be removed Chinese pistache (*Pistacia chinensis*) #2. The two coast redwoods (*Sequoia sempervirens*) (#4 and #5) along the north side of the property could be moderately to highly impacted and tree protection will be required. There is a privacy fence between the neighbor's trees and the proposed construction for #9, #10, #11, and #12 which is adequate protection. Mitigation aside from tree protection fence for this project will include exploratory trenching and selective root removal if necessary. Supplemental irrigation will be required. Coast redwoods #4 and #5 should have tree protection fence placed around them at the edge of the existing sidewalk and into the property where possible. Shoring techniques may be required to prevent over-excavation into the tree protection zone.

Introduction

Background

14 Fourth Street LLC asked me to assess the site, trees, proposed footprint plan, and to provide a report with my findings and recommendations to help satisfy the City of Los Altos planning requirements. The plan is to renovate the existing house and create a few additions.

Assignment

- 1. Provide an arborist's report including an assessment of the trees within the project area. The assessment is to include the species, size (trunk diameter), condition (health, structure, and form), and suitability for preservation ratings.
- 2. Provide tree protection guidelines, specifications, and impact ratings for those affected by the project.

Limits of the Assignment

- 1. No tree risk assessments were performed.
- 2. The information in this report is limited to the condition of the trees during my inspection on, April 29, 2022.
- 3. The plans reviewed for this assignment were as follows:

Table 1: Plans Reviewed Checklist

Plan	Date	Sheet	Reviewed	Source
Existing Site Topographic Map or A.L.T.A with tree locations				
Proposed Site Plan	02/16/2022	A1.0	Yes	CKA Architects
Demolition Plan				
Construction Staging				
Grading and Drainage	01/06/2021	C-1	Yes	Cliff Bechtel & Associates
Utility Plan and Hook-up locations	01/06/2022	C-1.1	Yes	Cliff Bechtel & Associates
Exterior Elevations				
Landscape Plan				
Irrigation Plan				
T-1 Tree Protection Plan				

Purpose and Use of the Report

The report is intended to identify all the trees within the plan area that could be affected by a project. The report is to be used by the property owners, owner's agents, and the City of Los Altos as a reference for existing tree conditions to help satisfy planning requirements.


Observations

Tree Inventory

The City of Los Altos Tree Ordinance Chapter 11.08 states protection criteria as the following:

- 1. Any tree that is 48-inches (four feet) or greater in circumference when measured at 48-inches above the ground.
- 2. Any tree designated by the Historical Commission as a Heritage Tree or any tree under official consideration for a Heritage Tree designation. (All Canary Island Palm trees on Rinconada Court are designated as Heritage Trees.)
- 3. Any tree which was required to be either saved or planted in conjunction with a development review approval (i.e. new two-story house).
- 4. Any tree located within a public right-of-way.
- 5. Any tree located on property zoned other than single-family residential.

The inventory includes twelve trees comprised of six different species. The trees are located around the perimeter of the property and either on the street or adjacent sites (Chart 1).



cka architects

CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:
2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL

10.25.2022 DESIGN REVIEW SUBMITTAL

REET LOS ALTOS CA 94022

CONSULTANTS:

STAMP:

CHRISTOPHER

L.

KUMMERER

NO. C-29207

REN. 11-30-21

F CALI

AR1

ARBORIST REPORT SHEET 1

THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AND ARE INTENDED FOR USE AT THE PROJECT LOCATION STIPULATED ABOVE ONLY AND MAY NOT BE REPRODUCED IN ANY MANNER OR USED FOR OTHER LOCATIONS


Discussion

Condition Rating

A tree's condition is a determination of its overall health, structure, and form. The assessment considered all three characteristics for a combined condition rating.

- 100% Exceptional = Good health and structure with significant size, location or quality.
 61-80% Good = Normal vigor, well-developed structure, function and aesthetics not compromised with good longevity for the site.
- 41-60 % Fair = Reduced vigor, damage, dieback, or pest problems, at least one significant structural problem or multiple moderate defects requiring treatment. Major asymmetry or deviation from the species normal habit, function and aesthetics compromised.
- deviation from the species normal habit, function and aesthetics compromised.
 21-40% Poor = Unhealthy and declining appearance with poor vigor, abnormal foliar color, size or density with potential irreversible decline. One serious structural defect or multiple significant defects that cannot be corrected and failure may occur at any time. Significant
- asymmetry and compromised aesthetics and intended use.
 6-20% Very Poor = Poor vigor and dying with little foliage in irreversible decline. Severe defects with the likelihood of failure being probable or imminent. Aesthetically poor with little or no function in the landscape.
- 0-5% Dead/Unstable = Dead or imminently ready to fail.

Six trees are in good condition, three fair, and three are in poor shape including coast redwood #9, silk oak #10, and purple plum #12 all originating on adjacent properties (Chart 2).



Suitability for Preservation

A tree's suitability for preservation is determined based on its health, structure, age, species and disturbance tolerances.

- Good = Trees with good health, structural stability and longevity after construction.
- Fair = Trees with fair health and/or structural defects that may be mitigated through treatment. These trees require more intense management and monitoring, before, during, and after construction, and may have shorter life expectancy after development.
- Poor = Trees are expected to decline during or after construction regardless of management. The species or individual may possess characteristics that are incompatible or undesirable in landscape settings or unsuited for the intended use of the site.

The suitability for preservation is irrelevant in this circumstance because none of the trees are under control of the property owner (street trees and those on adjacent sites).

Expected Impact Level

Impact level defines how a tree may be influenced by construction activity and proximity to the tree, and is described as low, moderate, or high. The following scale defines the impact rating:

- Low = The construction activity will have little influence on the tree.
- Moderate = The construction may cause future health or structural problems, and steps must be taken to protect the tree to reduce future problems.

 High = Tree structure and health will be compressized and removal is recommended or other
- High = Tree structure and health will be compromised and removal is recommended, or other actions must be taken for the tree to remain. The tree is located in the building envelope.

One "Street Tree" is expected to be removed (#2). One pittosporum shrub (#3) in front of the building and the two water gum (#7 and #8) in back with trunk diameters less than four inches in diameter are to be removed. The two coast redwoods #4 and #5 along the north side of the property could be moderately to highly impacted and tree protection, pre trenching, shoring and selective root removal will be required (Chart 3).

The snapshot below indicates the proximity of trees #4 and #5 to the proposed building and soil cut (Image 1).




IMAGE 1: TREES #4 AND #5 IN RELATION TO THE PROPOSED CONSTRUCTION.

Tree Protection

The tree protection zone (TPZ) is the defined area in which certain activities are prohibited to minimize potential injury to the tree. The TPZ can be determined by a formula based on species tolerance, tree age, and diameter at breast height (DBH) (Matheny, N. and Clark, J. 1998) (Fite, K, and Smiley, E. T., 2016) or as the drip line in some instances. Preventing mechanical damage to the main stems from equipment or hand tools can be accomplished by wrapping the trunk with straw wattle or bracing with timbers (Appendix D). Tree protection will focus on four protected trees

There is a privacy fence between the neighbor's trees and the proposed construction for #9, #10, #11, and #12.

Coast redwoods #4 and #5 should have tree protection fence placed around them at the edge of the existing sidewalk and into the property where possible. Protecting the trees could require exploratory trenching along the proposed foundation adjacent to #4 and #5. Selective root removal may be necessary to accommodate the foundation. Due to the size of the trees and the close proximity it is not possible to obtain the typical tree protection zones of six to eighteen times the trunk diameter distances or more in radius. The ANSI A300 Part 5, 2019 Standard Practices (Management of Trees and Shrubs During Site Planning, Site Development, and Construction) states the following:

Section 55.1.3

The (Tree Protection Zone) TPZ radius should be 6-18 times the trunk diameter (DBH)

Section 55.1.4

When the minimum TPZ radius cannot be achieved, appropriate mitigation shall be recommended.

In accordance with the ANSI Standard, mitigation for this project will include exploratory trenching around the building perimeter, selective root removal if necessary. Supplemental irrigation will be required along with trunk protection.

Conclusion

The plans are to demolish the existing structure and construct four new residences. The inventory includes twelve trees comprised of six different species. The trees are located around the perimeter of the property and either on the street or adjacent sites except for a few. Six trees are in good condition, three fair, and three are in poor shape including coast redwood #9, silk oak #10, and purple plum #12 all originating on adjacent properties. One "Street Tree" #2 is expected to be removed. One pittosporum shrub #3 in front of the building and the two water gum #7 and #8 in back with trunks less than four inches in diameter are to be removed. The two coast redwoods #4 and #5 along the north side of the property could be moderately to highly impacted and tree protection, pre trenching, shoring and selective root removal will be required. There is a privacy fence between the neighbor's trees and the proposed construction for #9, #10, #11, and #12 which is adequate protection. In accordance with the ANSI Standard part 5, mitigation for this project will include exploratory trenching around the building perimeter if within 30 feet of the coast redwoods and selective root removal if necessary. Supplemental irrigation will be required along with trunk protection. Coast redwoods #4 and #5 should have tree protection fence placed around them at the edge of the existing sidewalk and into the property where possible. Shoring techniques and selective root removal may be required.

Recommendations

- 1. Place tree numbers and protection schemes on all the plans. Fence shall be placed around trees #4 and #5 (radius of 30 feet) where possible.
- 2. Place 2-4 inches of bark, wood chips, or course woody debris generated from tree pruning operations in the TPZ. Install supplemental irrigation in the TPZ of trees #4 and #5.
- 3. Install temporary irrigation or soaker hoses in the TPZs and provide supplemental watering during construction (Trees #4 and #5). Monitor watering times or amounts to ensure adequate soil saturation. (A 5/8" soaker hose requires about 200 minutes to deliver one inch of water to a garden. This number is affected by the length of the hose and the overall rate of flow from the faucet. A good rule of thumb is to expect about ½ GPM as a standard faucet flow rate.). Infrequent deeper watering is preferred and could be as much as 400 gallons per soaking.
- 4. Pre-trench along the proposed soil cut adjacent to the trees (#4 and #5). Have an ISA Certified Arborist® observe the trenching and provide guidance to selectively remove any significant roots (roots greater than one inch in diameter (1") if encountered. Selective root removal requires pre-excavation, typically by hand or with a pneumatic excavating equipment such as an Air Spade®, Air Knife®, or similar tools. Selective removal allows for the roots to be exposed prior to cutting at the appropriate locations. This is the type of root removal that will need to occur at the building foundation. Roots greater than one inch in diameter should be pruned rather than left torn or crushed so as to leave "a clean flat surface with intact surrounding bark" (Costello, L., Watson, G., Smiley, E. T.. 2017).
- 5. Refer to Appendix D for general tree protection guidelines including recommendations for arborist assistance while working under trees, trenching, or excavation within a trees drip line. Copy Appendix A, B, and D of the arborist report to the final set of plans, which will serve as part of the Tree Preservation Plan.
- 6. All tree maintenance and care shall be performed by a qualified arborist with a C-61/D-49 California Contractors License. Tree maintenance and care shall be specified in writing according to American National Standard for Tree Care Operations: *Tree, Shrub and Other Woody Plant Management: Standard Practices* parts 1 through 10 and adhere to ANSI Z133.1 safety standards and local regulations.
- 7. Provide a copy of this report to all contractors and project managers, including the architect, civil engineer, and landscape designer or architect. It is the responsibility of the owner to ensure all parties are familiar with this document.

Bibliography

- American National Standard for Tree Care Operations: Tree, Shrub and Other Woody Plant Management: Standard Practices (Management of Trees and Shrubs During Site Planning, Site Development, and Construction)(Part 5). Londonderry, NH: Secretariat, Tree Care Industry Association, 2019. Print.
- Fite, Kelby, and Edgar Thomas. Smiley. *Managing trees during construction*, second edition. Champaign, IL: International Society of Arboriculture, 2016.
- ISA. *Guide For Plant Appraisal 10th Edition*. Savoy, IL: International Society of Arboriculture, 2018. Print.
- Matheny, Nelda P., Clark, James R. Trees and development: A technical guide to preservation of trees during land development. Bedminster, PA: International Society of Arboriculture1998.
- Smiley, E, Matheny, N, Lilly, S, ISA. *Best Management Practices: Tree Risk Assessment:* International Society of Arboriculture, 2017. Print

Glossary of Terms

Defect: An imperfection, weakness, or lack of something necessary. In trees defects are injuries, growth patterns, decay, or other conditions that reduce the tree's structural strength.

Diameter at breast height (DBH): Measures at 1.4 meters (4.5 feet) above ground in the United States, Australia (arboriculture), New Zealand, and when using the Guide for Plant Appraisal, 9th edition; at 1.3 meters (4.3 feet) above ground in Australia (forestry), Canada, the European Union, and in UK forestry; and at 1.5 meters (5 feet) above ground in UK arboriculture.

Drip Line: Imaginary line defined by the branch spread or a single plant or group of plants.

Form: describes a plant's habit, shape or silhouette defined by its genetics, environment, or management.

Health: Assessment is based on the overall appearance of the tree, its leaf and twig growth, and the presence and severity of insects or disease.

Mechanical damage: Physical damage caused by outside forces such as cutting, chopping or any mechanized device that may strike the tree trunk, roots or branches.

Scaffold branches: Permanent or structural branches that for the scaffold architecture or structure of a tree.

Straw wattle: also known as straw worms, bio-logs, straw noodles, or straw tubes are man made cylinders of compressed, weed free straw (wheat or rice), 8 to 12 inches in diameter and 20 to 25 feet long. They are encased in jute, nylon, or other photo degradable materials, and have an average weight of 35 pounds.

Structural evaluation: focused on the crown, trunk, trunk flare, above ground roots and the site conditions contributing to conditions and/or defects that may contribute to failure.

Tree Protection Zone (TPZ): Defined area within which certain activities are prohibited or restricted to prevent or minimize potential injury to designated trees, especially during construction or development.

Tree Risk Assessment: Process of evaluating what unexpected things could happen, how likely it is, and what the likely outcomes are. In tree management, the systematic process to determine the level of risk posed by a tree, tree part, or group of trees.

Trunk: Stem of a tree.

CKa ARCHITECTS

CHRIS KUMMERER & ASSOCIATES

P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS: 2.16.2022 PRELIMIMARY PLANNING

COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL
10.25.2022 DESIGN REVIEW SUBMITTAL

14 4TH STREET

STAMP:

STAMP:

CHRISTOPHER

L.

KUMMERER

NO. C29207


REN. 11-30-21

PAGENUMBER:


THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF CHRIS KUMMERER ARCHITECT AND

ARBORIST REPORT SHEET 2

Tree locations not survey accurate.



A2: Proposed Site Plan C-1



Appendix B: Tree Inventory and Assessment Tables

Table 2: Tree Inventory Summary

Tree Species	I.D. #	Trunk Diameter (in.)	Condition	Expected Impact	Ordinance Protected Tree	TPZ Radius (ft.)/Plan
birch (<i>Betula pendula</i>)	1	4	Good	Low	Yes (Street Tree)	2
Chinese pistache (<i>Pistacia chinensis</i>)	2	12	Good	High	Yes (Street Tree)	Remove
Pittosporum (<i>Pittosporum</i> <i>tenuifolium</i>)	3	Multi - 4	Good	High	No	Remove
coast redwood (Sequoia sempervirens)	4	28	Good	Moderate	Yes	14
coast redwood (Sequoia sempervirens)	5	60	Fair	Moderate	Yes	30
coast redwood (Sequoia sempervirens)	6	60	Fair	Low	Yes	30
water gum (<i>Tristaniopsis</i> laurina)	7	3	Good	High	No	Remove
water gum (<i>Tristaniopsis</i> laurina)	8	3	Good	High	No	Remove
coast redwood (Sequoia sempervirens)	9	14	Poor	Low	Yes	7
silk oak (<i>Grevillea</i> robusta)	10	20	Poor	Low	Yes	10
purple plum (<i>Prunus</i> cerasifera)	11	8	Fair	Low	No	4
purple plum (<i>Prunus</i> cerasifera)	12	8	Poor	Low	No	4

Appendix C: Photographs C1: Street Tree #2, Pittosporum #3, and Coast Redwood #4




C2: Coast Redwood #9 and #10




C3: Plums #11 and #12



C4: Coast Redwoods #6 and #7



Appendix D: Tree protection specifications





Plan Sheet Detail S-X


ARCHITECTS

CHRIS KUMMERER & ASSOCIATES


p 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS:
2.16.2022 PRELIMIMARY PLANNING
COMMISSION SUBMITTAL
5.9.2022 DESIGN REVIEW SUBMITTAL
10.25.2022 DESIGN REVIEW SUBMITTAL


CONSULTANTS:



ARBORIST REPORT SHEET 3



TRUNK PROTECTION WITH WATTLE



11.08.120 - Tree protection during construction.

Protected trees designated for preservation shall be protected during development of a property by compliance with the following, which may be modified by the planning director:

- A. Protective fencing shall be installed no closer to the trunk than the dripline, and far enough from the trunk to protect the integrity of the tree. The fence shall be a minimum of four feet in height and shall be set securely in place. The fence shall be of a sturdy but open material (i.e., chainlink), to allow visibility to the trunk for inspections and safety. There shall be no storage of any kind within the protective fencing.
- B. The existing grade level around a tree shall normally be maintained out to the dripline of the tree. Alternate grade levels may be approved by the planning director.
- C. Drain wells shall be installed whenever impervious surfaces will be placed over the root system of a tree (the root system generally extends to the outermost edges of the branches).
- D. Trees that have been damaged by construction shall be repaired in accordance with accepted arboriculture methods.
- E. No signs, wires, or any other object shall be attached to the tree.

(Ord. 07-314 § 2 (part); prior code § 10.2.26513)

Prohibited Activities

The following are prohibited activities within the TPZ:

- Grade changes (e.g. soil cuts, fills);
- Trenches;
- Root cuts;
- Pedestrian and equipment traffic that could compact the soil or physically damage roots;
- Parking vehicles or equipment;
- Burning of brush and woody debris;
- Storing soil, construction materials, petroleum products, water, or building refuse; and,
- Disposing of wash water, fuel or other potentially damaging liquids.

Pre-Construction Meeting with the Project Arborist

Tree protection locations should be marked before any fencing contractor arrives.

Prior to beginning work, all contractors involved with the project should attend a pre construction meeting with the project arborist to review the tree protection guidelines. Access routes, storage areas, and work procedures will be discussed.

Tree Protection Zones and Fence Specifications

Tree protection fence should be established prior to the arrival of construction equipment or materials on site. Fence should be comprised of six-foot high chain link fence mounted on eightfoot tall, 1 7/8-inch diameter galvanized posts, driven 24 inches into the ground and spaced no more than 10 feet apart. Once established, the fence must remain undisturbed and be maintained

The fence should be maintained throughout the site during the construction period and should be inspected periodically for damage and proper functions. Fence should be repaired, as necessary,

Monitoring

Any trenching, construction or demolition that is expected to damage or encounter tree roots should be monitored by the project arborist or a qualified ISA Certified Arborist and should be

The site should be evaluated by the project arborist or a qualified ISA Certified Arborist after construction is complete, and any necessary remedial work that needs to be performed should be

Restrictions Within the Tree Protection Zone

No storage of construction materials, debris, or excess soil will be allowed within the Tree Protection Zone. Spoils from the trenching shall not be placed within the tree protection zone either temporarily or permanently. Construction personnel and equipment shall be routed outside the tree protection zones.

Root Pruning

are encountered they should be pruned by hand with loppers, handsaw, reciprocating saw, or should be kept moist with burlap or backfilled within one hour.

Boring or Tunneling

Boring machines should be set up outside the drip line or established Tree Protection Zone. Boring may also be performed by digging a trench on both sides of the tree until roots one inch in diameter are encountered and then hand dug or excavated with an Air Spade® or similar air or water excavation tool. Bore holes should be adjacent to the trunk and never go directly under the main stem to avoid oblique (heart) roots. Bore holes should be a minimum of three feet deep.

Timing

If the construction is to occur during the summer months supplemental watering and bark beetle treatments should be applied to help ensure survival during and after construction.

Tree Pruning and Removal Operations

All tree pruning or removals should be performed by a qualified arborist with a C-61/D-49 California Contractors License. Tree pruning should be specified in writing according to ANSI A-300A pruning standards and adhere to ANSI Z133.1 safety standards. Trees that need to be removed or pruned should be identified in the pre-construction walk through.

Tree Protection Signs

All sections of fencing should be clearly marked with signs stating that all areas within the fencing are Tree Protection Zones and that disturbance is prohibited. Text on the signs should be in both English and Spanish (Appendix E).

Appendix E: Tree Protection Signs E1: English

rotection

throughout the construction process until final inspection.

to provide a physical barrier from construction activities.

Root pruning shall be supervised by the project arborist. When roots over two inches in diameter chain saw rather than left crushed or torn. Roots should be cut beyond sinker roots or outside root branch junctions and be supervised by the project arborist. When completed, exposed roots

E2: Spanish

rizado Sin sera removida rbo **U**0 S cerca ona sta

without 7 Q Q mov are ∇ Φ authoriz this Φ Ŏ not enter Shall Only

may ence approv

antol ಹ sonal er 0 00 Φ aprobacion

Qualifications, Assumptions, and Limiting Conditions

Any legal description provided to the consultant is assumed to be correct. Any titles or ownership of properties are assumed to be good and marketable. All property is appraised or evaluated as though free and clear, under responsible ownership and competent management.

All property is presumed to be in conformance with applicable codes, ordinances, statutes, or other regulations.

Care has been taken to obtain information from reliable sources. However, the consultant cannot be responsible for the accuracy of information provided by others.

The consultant shall not be required to give testimony or attend meetings, hearings, conferences, mediations, arbitration, or trials by reason of this report unless subsequent contractual arrangements are made, including payment of an additional fee for such services.

This report and any appraisal value expressed herein represent the opinion of the consultant, and the consultant's fee is not contingent upon the reporting of a specified appraisal value, a stipulated result, or the occurrence of a subsequent event.

Sketches, drawings, and photographs in this report are intended for use as visual aids, are not necessarily to scale, and should not be construed as engineering or architectural reports or surveys. The reproduction of information generated by architects, engineers, or other consultants on any sketches, drawings, or photographs is only for coordination and ease of reference. Inclusion of said information with any drawings or other documents does not constitute a representation as to the sufficiency or accuracy of said information.

Unless otherwise expressed: a) this report covers only examined items and their condition at the time of inspection; and b) the inspection is limited to visual examination of accessible items without dissection, excavation, probing, or coring. There is no warranty or guarantee, expressed or implied, that structural problems or deficiencies of plants or property may not arise in the

Certification of Performance

I Richard Gessner, Certify:

That I have personally inspected the tree(s) and/or the property referred to in this report, and have stated my findings accurately. The extent of the evaluation and/or appraisal is stated in the attached report and Terms of Assignment;

That I have no current or prospective interest in the vegetation or the property that is the subject of this report, and I have no personal interest or bias with respect to the parties involved;

That the analysis, opinions and conclusions stated herein are my own;

That my analysis, opinions, and conclusions were developed and this report has been prepared according to commonly accepted Arboricultural practices;

That no one provided significant professional assistance to the consultant, except as indicated within the report.

That my compensation is not contingent upon the reporting of a predetermined conclusion that favors the cause of the client or any other party, nor upon the results of the assessment, the attainment of stipulated results, or the occurrence of any other subsequent events;

I further certify that I am a Registered Consulting Arborist® with the American Society of Consulting Arborists, and that I acknowledge, accept and adhere to the ASCA Standards of Professional Practice. I am an International Society of Arboriculture Board Certified Master Arborist®. I have been involved with the practice of Arboriculture and the care and study of trees since 1998.

ISA Board Certified Master Arborist® WE-4341B

Richard J. Gessner huhmen of these ASCA Registered Consulting Arborist® #496





© Copyright 2022, Monarch Consulting Arborists LLC. Other than specific exception granted for copies made by the client for the express uses stated in this report, no parts of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, recording, or otherwise without the express, written permission of the author.

ARCHITECTS


CHRIS KUMMERER & ASSOCIATES


P 650.233.0342 2089 AVY AVENUE, MENLO PARK CA 94025 CHRIS@CKA-ARCHITECTS.COM CKA-ARCHITECTS.COM

REVISIONS: 2.16.2022 PRELIMIMARY PLANNING COMMISSION SUBMITTAL 5.9.2022 DESIGN REVIEW SUBMITTAL 10.25.2022 DESIGN REVIEW SUBMITTAL

CONSULTANTS STAMP: CUMMERER PAGE NUMBER:

ARBORIST REPORT SHEET 4





AND ASSOCIATES, JIC Engineering and Project Manageme

1321 254th Place, SE SAMMAMISH, WA 98075 650-333-0103 cliffbechtel1@comcast.net


GRADING AND DRAINAGE **PLAN**

10/06/22


CHECKED C.B.

JOB No. 2021772

SHEET NO.



Engineering and Project Managemen




Engineering and Project Managemen 1321 254th Place, SE

SAMMAMISH, WA 98075 cliffbechtel1@comcast.net

EROSION & SEDIMENT CONTROL & STAGING

10/06/22

JOB No. 2021772



AND ASSOCIATES IT Engineering and Project Manageme 1321 254th Place, SE

SAMMAMISH, WA 98075 650-333-0103 cliffbechtel1@comcast.net

TREE ORTH S FOURTH

CONSTRUCTION **MANAGEMEN PLAN**

10/06/22

SCALE AS NOTEI

CHECKED C.B.

JOB No. 2021772

Heavy Equipment Operation

Best Management Practices for the Construction Industry



Best Management Practices for the

Vehicle and equipment operators

Storm water Pollution from Heavy Equipment on **Construction Sites**

Doing the Job Right

cleanup is easier.

any onsite cleaning.

Site Planning and Preventive Vehicle

☐ Maintain all vehicles and heavy equipment.

Inspect frequently for and repair leaks.

Perform major maintenance, repair jobs, and

☐ If you must drain and replace motor oil, radiator

vehicle and equipment washing off site where

coolant, or other fluids on site, use drip pans or

drop cloths to catch drips and spills. Collect all

spent fluids, store in separate containers, and

properly dispose as hazardous waste (recycle

parts, or clean equipment. Use only water for

Cover exposed fifth wheel hitches and other oily

or greasy equipment during rain events.

Do not use diesel oil to lubricate equipment

Poorly maintained vehicles and heavy equipment that leak fuel, oil, antifreeze or other fluids on the construction site are common sources of storm drain pollution. Prevent spills and leaks by isolating equipment from runoff channels, and by watching for leaks and other maintenance problems. Remove construction equipment from the site as soon as possible

Spill Cleanup

Clean up spills immediately when they

■ Never hose down "dirty" pavement or impermeable surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags) whenever possible and properly dispose of absorbent materials.

Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.

☐ Use as little water as possible for dust control. Ensure water used doesn't leave silt or discharge to storm drains.

Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.

☐ Report significant spills to the appropriate local spill response agencies immediately.

If the spill poses a significant hazard to human health and safety, property or the environment, you must also report it to the State Office of Emergency

Roadwork **Paving**

Best Management Practices for the Construction Industry



Best Management Practices for the

- Road crews Driveway/sidewalk/parking lot construction
- Seal coat contractors Operators of grading equipment, paving machines, dump trucks, concrete mixers Construction inspectors
- General contractors

 Home builders Developers

Doing The Job Right

General Business Practices

- Develop and implement erosion/sediment control plans for roadway embankments.
- ☐ Schedule excavation and grading work during dry weather.
- ☐ Check for and repair leaking equipment. ☐ Perform major equipment repairs at designated areas in your maintenance yard, where
- cleanup is easier. Avoid performing equipment repairs at construction sites. ☐ When refueling or when vehicle/equipment
- methods (with absorbent materials maintenance must be done on site, designate and/or rags), or dig up, remove, and a location away from storm drains and creeks. properly dispose of contaminated soil. Do not use diesel oil to lubricate equipment ☐ Collect and recycle or appropriately parts or clean equipment.
- dispose of excess abrasive gravel or Recycle used oil, concrete, broken asphalt, etc.

■ Avoid over-application by water trucks for dust control.

Avoid creating excess dust when

contact with rainfall or runoff.

☐ When making saw cuts, use as little

water as possible. Shovel or vacuum

Cover or protect storm drain inlets

during saw-cutting. Sweep up, and

Sweep, never hose down streets to

clean up tracked dirt. Use a street

vacuumed liquor in storm drains.

Painting Cleanup

Paint Removal

sweeper or vacuum truck. Do not dump

brushes to the extent possible, and rinse

into a drain that goes to the sanitary

sewer. Never pour paint down a storm

☐ For oil-based paints, paint out brushes to

the extent possible and clean with thinner

or solvent in a proper container. Filter and

reuse thinners and solvents. Dispose of

excess liquids and residue as hazardous

Paint chips and dust from non-hazardous

and disposed of as trash

properly dispose of, all residues.

saw-cut slurry and remove from the site

Asphalt/Concrete Removal

☐ Never wash excess material from

exposed- aggregate concrete or simila

treatments into a street or storm drain.

Collect and recycle, or dispose to dirt

☐ Cover stockpiles (asphalt, sand, etc.)

plastic sheets and berms.

catch drips when not in use.

and other construction materials with

plastic tarps. Protect from rainfall and

prevent runoff with temporary roofs or

Park paving machines over drip pans or

☐ Clean up all spills and leaks using "dry"

absorbent material (cloth, rags, etc.) to

Avoid paving and seal coating in wet weather, or when rain is forecast, to prevent fresh materials from contacting stormwater runoff.

whenever possible, or dispose of properly.

During Construction

- breaking asphalt or concrete. Cover and seal catch basins and manholes After breaking up old pavement, be sure when applying seal coat, slurry seal, fog seal, to remove all chunks and pieces. Make or similar materials. sure broken pavement does not come in
- Protect drainage ways by using earth dikes. sand bags, or other controls to divert or trap


Storm Drain Pollution from Roadwork

Road paving, surfacing, and pavement removal happen right in the street, where there are numerous opportunities for asphalt, saw-cut slurry, or excavated material to illegally enter storm drains. Extra planning is required to store and dispose of materials properly and guard against pollution of storm drains, creeks, and the Bay.

Doing The Job Right

Fresh Concrete and Mortar **Application**

Construction Industry



Best Management Practices for the

- Sidewalk construction crews
- Construction inspectors General contractors
- Home builders
- Developers

Masons and bricklayers

- Patio construction workers

- Concrete delivery/pumping workers

Doing The Job Right

General Business Practices

- ☐ Wash out concrete mixers only in designated wash-out areas in your yard, away from storm drains and waterways, where the water will flow into a temporary waste pit in a dirt area. Let water percolate through soil and dispose of settled, hardened concrete as garbage. Whenever possible, recycle washout by pumping back into mixers for reuse.
- ☐ Wash out chutes onto dirt areas at site that do not flow to streets or drains.
- Always store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Protect dry materials from wind.
- Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from streets, gutters, storm drains, rainfall, and
- Do not use diesel fuel as a lubricant on concrete forms, tools, or trailers.

Storm Drain Pollution from Fresh **Concrete and Mortar Applications**

Fresh concrete and cement-related mortars that wash into lakes, streams, or estuaries are toxic to fish and the aquatic environment. Disposing of these materials to the storm drains or creeks can block storm drains, causes serious problems, and is prohibited by law.

During Construction

- Don't mix up more fresh concrete or cement than you will use in a two-hour
- ☐ Set up and operate small mixers on

the street or storm drain.

tarps or heavy plastic drop cloths. ☐ When cleaning up after driveway or sidewalk construction, wash fines onto

dirt areas, not down the driveway or into

- Protect applications of fresh concrete and mortar from rainfall and runoff until the material has dried.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) be vacuumed from a catchment created by blocking a storm drain inlet. If necessary, divert runoff with temporary berms. Make sure runoff does not reach gutters or storm drains.
- ☐ When breaking up pavement, be sure to pick up all the pieces and dispose of properly. Recycle large chunks of broken concrete at a landfill.
- ☐ Never bury waste material. Dispose of small amounts of excess dry concrete, grout, and mortar in the trash.
- Never dispose of washout into the street, storm drains, drainage ditches, or

Spill Response Agencies

DIAL 9-1-1

this drawing sheet.

State Office of Emergency Services Warning 800-852-7550 Center (24 hours):

Preventing Pollution:

It's Up to Us

In the Santa Clara Valley, storm drains

transport water directly to local creeks

and San Francisco Bay without treatment.

Storm water pollution is a serious problem

for wildlife dependent on our waterways

and for the people who live near polluted

streams or bay lands. Some common

sources of this pollution include spilled oil,

fuel, and fluids from vehicles and heavy

equipment; construction debris; sediment

created by erosion; landscaping runoff

containing pesticides or weed killers; and

materials such as used motor oil

pour or spill into a street or storm drain.

antifreeze, and paint products that people

Thirteen valley municipalities have joined

together with Santa Clara County and the

Santa Clara Valley Water District to

educate local residents and businesses

and fight storm water pollution. TO

comply with this program, contractors

most comply with the practices described

Santa Clara County Environmental Health (408) 299-6930 Services:

Local Pollution Control Agencies

County of Santa Clara Pollution Prevention (408) 441 - 1195

County of Santa Clara Integrated Waste Management Program: (408) 441-1198

County of Santa Clara District Attorney Environmental Crimes Hotline:

(408) 299-TIPS

Santa Clara County Recycling Hotline:

1-800-533-8414 Santa Clara Valley Water

(408) 265-2600 District: Santa Clara Valley Water District Pollution 1-888-510-5151

Regional Water Quality Control Board San (510) 622-2300 Francisco Bay Region:

Palo Alto Regional Water Quality Control Plant:

(650) 329-2598 Serving East Palo Alto Sanitary District, Los Altos, Los Altos Hills, Mountain View, Palo Alto, Stanford

City of Los Altos

Building Department: (650) 947-2752 Engineering Department: (650) 947-2780

Gardening, and **Pool Maintenance**

Construction Industry



Best Management Practices for the

- Landscapers
- General contractors
- Home builders
- Developers

General

And Site

Doing The Right Job

General Business Practices ☐ Protect stockpiles and landscaping materials

or secured plastic sheeting ☐ Store pesticides, fertilizers, and other chemicals indoors or in a shed or storage

from wind and rain by storing them under tarps

- ☐ Schedule grading and excavation projects ☐ Use temporary check dams or ditches to divert
- runoff away from storm drains. Protect storm drains with sandbags or other sediment controls.

Re-vegetation is an excellent form of erosion control for any site

- Use pesticides sparingly, according to instructions on the label. Rinse empty containers, and use rinse water as product Dispose of rinsed, empty containers in the trash. Dispose of unused pesticides as
- hazardous waste Collect lawn and garden clippings, pruning waste, and tree trimmings. Chip if necessary,
- ☐ In communities with curbside pick-up of yard to a landfill that composts yard waste. No curbside pickup of yard waste is available for

Storm Drain Pollution From Landscaping and

Many landscaping activities expose soils and increase the likelihood that earth and garden chemicals will run off into the storm drains during irrigation or when it rains. Swimming pool water containing chlorine and copper-based algaecides should never be discharged to storm drains. These chemicals are toxic to aquatic life.

for recycling (allowed by San Jose and

Pool/Fountain/Spa Maintenance **Draining Pools Or Spas**

- Landscaping/Garden Maintenance

Do not blow or rake leaves, etc. into the unincorporated County only). Sweep up

☐ In San Jose, leave yard waste for curbside the flow line to any storm drain.

- waste, place clippings and pruning waste at the curb in approved bags or containers. Or, take

commercial properties

Swimming Pool Maintenance

street, or place yard waste in gutters or on dirt shoulders, unless you are piling them any leaves, litter or residue in gutters or on

recycling pickup in piles in the street, 18 inches from the curb and completely out of

- When it's time to drain a pool, spa, or fountain, please be sure to call your local wastewater treatment plant before you start for further guidance on flow rate restrictions, backflow prevention, and handling special cleaning waste (such as acid wash). Discharge flows shall not exceed 100 gallon per minute.
- Never discharge pool or spa water to a street or storm drain; discharge to a If possible, when emptying a pool or spa, let chlorine dissipate for a few days and
 - gradually onto a landscaped area. Do not use copper-based algaecides. Control algae with chlorine or other alternatives, such as sodium bromide.

Filter Cleaning Never clean a filter in the street or near a storm drain. Rinse cartridge and diatomaceous earth filters onto a dirt area.

then recycle/reuse water by draining it

of spent diatomaceous earth in the

If there is no suitable dirt area, call your

local wastewater treatment plant for

or rinse water to the sanitary sewer.

instructions on discharging filter backwash

and spade filter residue into soil. Dispose

Painting and **Application of** Solvents and Adhesives

Best Management Practices for the Construction Industry

- Painters Paperhangers

Storm Drain Pollution from



Homeowners

Best Management Practices for the

 Graphic artists Dry wall crews

General contractors

Home builders

Construction Industry

Developers

the sanitary sewer, or if you must send it offsite for disposal as hazardous waste.

dry weather

Paints, Solvents, and Adhesives All paints, solvents, and adhesives contain chemicals that are harmful to wildlife in local creeks, San Francisco Bay, and the Pacific Ocean. Toxic chemicals may come from liquid or solid products or from cleaning residues or rags. Paint material and wastes, adhesives and cleaning fluids should be recycled when possible, or disposed of properly to prevent these materials from flowing into storm drains and watercourses.

■ Never clean brushes or rinse paint containers into a street, gutter, storm drain, French drain, or stream.

Handling Paint Products ☐ Keep all liquid paint products and wastes For water-based paints, paint out

- away from the gutter, street, and storm drains. Liquid residues from paints, thinners, solvents, glues, and cleaning fluids are hazardous wastes and must be disposed of at a hazardous waste collection facility (contact your local stormwater program listed on the back of this brochure).
- ☐ When thoroughly dry, empty paint cans, used brushes, rags, and drop cloths may be disposed of as garbage in a sanitary landfill. Empty, dry paint cans also may be recycled as Wash water from painted buildings constructed

before 1978 can contain high amounts of lead,

even if paint chips are not present. Before you

begin stripping paint or cleaning pre-1978

building exteriors with water under high

pressure, test paint for lead by taking paint scrapings to a local laboratory. See Yellow Pages for a state-certified laboratory. ☐ If there is loose paint on the building, or if the paint tests positive for lead, block storm drains. Check with the wastewater treatment plant to determine whether you may discharge water to

Recycle or donate excess water-based (latex) paint, or return to supplier. Reuse leftover oil-based paint. Dispose

of non-recyclable thinners, sludge and

dry stripping and sand blasting may be swept up or collected in plastic drop cloths Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury or tributyl tin

Lead based paint removal requires a state-certified contractor. ■ When stripping or cleaning building exteriors with high-pressure water, block storm drains. Direct wash water onto a dirt area and spade into soil. Or, check with the local wastewater treatment authority to find out if you can collect (mop or vacuum) building cleaning water and dispose to the sanitary sewer. Sampling of the water may be required to assist the wastewater

must be disposed of as hazardous wastes.

treatment authority in making its decision. Recycle/Reuse Leftover Paints Whenever Possible

unwanted paint, as hazardous waste. Unopened cans of paint may be able to be returned to the paint vendor. Check with the vendor regarding its "buy-back" policy.

- 1. Check for Toxic Pollutants Check for odors, discoloration, or an oily sheen on groundwater.
- water tested by a certified laboratory. allowed to discharge pumped groundwater

to the storm drain (if no sediments

disposal at an appropriate treatment

- pump water to the street or storm drain. If the pumping time is more than 24 hours and the flow rate greater than 20 gpm, call your local wastewater treatment plant for guidance.
- for filtering include: sunk part way into a small pit filled with gravel:
- When discharging to a storm drain, protect the inlet using a barrier of burlap bags filled with drain rock, or cover inlet with filter fabric anchored under the grate. OR pump water through a grassy swale prior to discharge.

permitted by a discharge permit or unless exempted pursuant to guidelines published by the superintendent. Threatened discharges. It shall be unlawful to cause hazardous materials, domestic waste, or industrial waste to be deposited in

- A spill response plan for hazardous waste, hazardous materials and uncontained construction materials shall be prepared and available at the construction sites for all projects where the proposed construction site is equal to or greater than one acre of of the plan shall be in accordance with guidelines published by the city engineer.
- B. A storm water pollution prevention plan shall be prepared and available at the construction sites for all projects greater than one acre of disturbed soil and for any other projects for which the city engineer determines that a storm water management plan is necessary to protect surface waters. Preparation of the plan shall be in accordance with guidelines published by the city engineer. C. Prior approval shall be obtained from the city engineer or designee to discharge water pumped from construction sites to the storm drain. The city engineer or designee may require gravity settling and filtration upon a determination that either or both would
- D. No cleanup of construction debris from the streets shall result in the discharge of water to the storm drain system; nor shall any construction debris be deposited or allowed to be deposited in the storm drain system. (Prior code § 5-5.643)

Los Altos Municipal Code Chapter 10.08.390 Non-storm water discharges

Los Altos Municipal Code Requirements

- A. Unlawful discharges. It shall be unlawful to discharge any domestic waste or industrial waste into storm drains, gutters, creeks, or San Francisco Bay. Unlawful discharges to storm drains shall include, but not be limited to, discharge from toilets; sinks; industria processes; cooling systems; boilers; fabric cleaning; equipment cleaning; vehicle cleaning; construction activities, including, but no limited to, painting, paving, concrete placement, saw cutting and grading; swimming pools; spas; and fountains, unless specifically
- such a manner or location as to constitute a threatened discharge into storm drains, gutters, creeks or San Francisco Bay. A "threatened discharge" is a condition creating a substantial probability of harm, when the probability and potential extent of harm make it reasonably necessary to take immediate action to prevent, reduce or mitigate damages to persons, property or natural resources. Domestic or industrial wastes that are no longer contained in a pipe, tank or other container are considered to be threatened discharges unless they are actively being cleaned up.

Los Altos Municipal Code Section 10.08.430 Requirements for construction operations

- disturbed soil and for any other projects for which the city engineer determines is necessary to protect surface waters. Preparation
- improve the water quality of the discharge. Contaminated groundwater or water that exceeds state or federal requirements for discharge to navigable waters may not be discharged to the storm drain. Such water may be discharged to the sewer, provided that the requirements of Section 10.08.240 are met and the approval of the superintendent is obtained prior to discharge.

Criminal and judicial penalties can be assessed for non-compliance.




Blueprint for a Clean Bay

Remember: The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site You may be held responsible for any environmental damage caused by your subcontractors or employees.

Best Management Practices for the Construction Industry



Santa Clara **Urban Runoff Pollution Prevention Program**



APPROVED BY: CITY OF LOS ALTOS N.T.S. SHEETS

DESIGNED BY OCTOBER, 2003 LARRY LIND DRAWN BY: SCALE: VICTOR CHEN CHECKED BY: DRAWING NO:

Site supervisors General contractors Home builders Developers Landscaping,

Best Management Practices for the



Gardeners Swimming pool/spa service and repair

Homeowners

Supervision

Construction



Best Management Practices for the

General contractors

Site supervisors

Inspectors

Home builders **Storm Drain Pollution from Construction Activities**

Construction sites are common sources of storm water pollution. Materials and wastes that blow or wash into a storm drain, gutter, or street have a direct impact on local creeks and the Bay. As a contractor, or site supervisor, owner or operator of a site, you may be responsible for any environmental damage caused by your subcontractors or employees.

Doing The Job Right

Maintain equipment properly.

- General Principals
- ☐ Keep materials away from streets, storm drains and drainage channels. ☐ Ensure dust control water doesn't leave site or discharge to storm drains. Advance Planning To Prevent Pollution

☐ Schedule excavation and grading activities for

plant temporary vegetation or place other

dry weather periods. To reduce soil erosion,

erosion controls before rain begins. Use the

Erosion and Sediment Control Manual, available

☐ Keep an orderly site and ensure good

housekeeping practices are used.

Cover materials when they are not in use.

from the Regional Water Quality Control Board, Control the amount of runoff crossing your site (especially during excavation!) by using berms or temporary or permanent drainage ditches to divert water flow around the site. Reduce storm water runoff velocities by constructing temporary check dams or berms where appropriate.

Train your employees and subcontractors.

Make these best management practices

available to everyone who works on the

construction site. Inform subcontractors about

- the storm water requirements and their own responsibilities. Good Housekeeping Practices Designate one area of the site for auto parking. vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets,
- sheeting or temporary roofs. Before it rains, sweep and remove materials from surfaces that drain to storm drains, creeks, or channels. Keep pollutants off exposed surfaces. Place trashcans and recycling receptacles around the site to minimize litter.

bermed if necessary. Make major repairs off

☐ Keep materials out of the rain – prevent runoff

contamination at the source. Cover exposed

piles of soil or construction materials with plastic

Clean up leaks, drips and other spills immediately so they do not contaminate soil or groundwater or leave residue on paved surfaces. Use dry cleanup methods whenever possible. If you must use water,

use just enough to keep the dust down.

frequently for leaks. Place dumpsters under

roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. Never clean out a dumpster by hosing it down on the construction site. Set portable toilets away from storm drains. Make sure portable toilets are in good working order. Check frequently for leaks.

Practice Source Reduction -- minimize

Materials/Waste Handling

Cover and maintain dumpsters. Check

waste when you order materials. Order only the amount you need to finish the job. Use recyclable materials whenever possible. Arrange for pick-up of recyclable materials such as concrete, asphalt, scrap metal, solvents, degreasers, cleared vegetation, paper, rock, and vehicle maintenance materials such as used oil, antifreeze, batteries, and tires.

Dispose of all wastes properly. Many

construction materials and wastes,

including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation can be recycled. Materials that cannot be recycled must be taken to an appropriate landfill or disposed of as hazardous waste. Never bury waste materials or leave them in the street or near a creek or stream bed. In addition to local building permits, you

will need to obtain coverage under the

Storm water Permit if your construction

site disturbs one acre or more. Obtain

information from the Regional Water


Quality Control Board.

State's General Construction Activity

Floor covering installers

Earth-Moving And Dewatering

Activities Best Management Practices for the



Best Management Practices for the

 Dump truck drivers Site supervisors General contractors

Home builders

Developers

· Bulldozer, back hoe, and grading machine

without treatment is prohibited

Doing The Job Right **General Business Practices Dewatering Operations** Schedule excavation and grading work during

Do not use diesel oil to lubricate equipment parts, or clean equipment. **Practices During Construction** Remove existing vegetation only when absolutely necessary. Plant temporary vegetation for erosion control on slopes or

Perform major equipment repairs away from the

maintenance must be done on site, designate a

where construction is not immediately planned

Protect down slope drainage courses, streams

and storm drains with wattles, or temporary

to divert runoff around excavations. Refer to

drainage swales. Use check dams or ditches

☐ When refueling or vehicle/equipment

location away from storm drains.

the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control **Storm Drain Pollution** from Earth-Moving Activities

and Dewatering

Soil excavation and grading operations loosen large

amounts of soil that can flow or blow into storm

drains when handled improperly. Sediments in runoff

can clog storm drains, smother aquatic life, and

destroy habitats in creeks and the Bay. Effective

erosion control practices reduce the amount of runoff

crossing a site and slow the flow with check dams or roughened ground surfaces. Contaminated groundwater is a common problem in the Santa Clara Valley. Depending on soil types and site history, groundwater pumped from construction sites may be contaminated with toxics (such as oil or solvents) or laden with sediments. Any of these pollutants can harm wildlife in creeks or the Bay, or nterfere with wastewater treatment plant operation. Discharging sediment-laden water from a dewatering site into any water of the state

Cover stockpiles and excavated soil with secured tarps or plastic sheeting.

Call your local wastewater treatment agency and ask whether the groundwater must be tested. If contamination is suspected, have the Depending on the test results, you may be

present) or sanitary sewer. OR, you may

be required to collect and haul pumped

groundwater offsite for treatment and

- 2. Check for Sediment Levels If the water is clear, the pumping time is less than 24 hours, and the flow rate is less than 20 gallons per minute, you may
- settling tank prior to discharge. Options Pumping through a perforated pipe Pumping from a bucket placed below

☐ If the water is not clear, solids must be


filtered or settled out by pumping to a

water level using a submersible pump;


such as a swimming pool filter or filter

fabric wrapped around end of suction

Pumping through a filtering device



EXISTING CONDITIONS LEGEND /////// Building Line Gas Meter ---- Concrete Hose Bib ---- Concrete Grade Break Irrigation Valve Box Sanitary Sewer Cleanout Spot Elevation Concrete Tree Size/Species (Arborist Report Designation) Existing Structures/Improvements to be Demolished Utility Valve – Gas Existing Tree to be Removed Building Setback Line Water Valve Communication Box Book L of Maps, Page 99 Drain Inlet Book 472 of Maps, Page 53 Electric Box Book 888 of Maps, Page 37 Electrical Panel Book 437 of Maps, Page 25



PROJECT DATA

OWNER/SUBDIVIDER: 14 Fourth Street LLC 412 Olive Avenue Palo Alto, CA 94306 Contact: John Suppes Tel. 650-322-7069

SURVEYOR/TENTATIVE MAP PREPARER:

Mountain Pacific Surveys 1735 Enterprise Drive, #109 Fairfield, CA 94533 Contact: Charles Weakley Tel. 707.425.6234

ENGINEERING/GRADING/UTILITY DESIGN:

Cliff Bechtel & Associates 1321 254th Place, SE Sammamish, WA 98075 Contact: Cliff Bechtel Tel. 650.333.0103

ASSESSOR'S PARCEL NUMBER: 167-38-061

ZONING DESIGNATION: R3-1 Multiple Family District
(4 units maximum for first 7,100 ft² of lot size)

ALCITE ADEA, 7.042 ft² / 0.462 l Associated by field associated

TOTAL SITE AREA: 7,042 ft² / 0.162± Acres (determined by field survey)

EXISTING USE: Single Family Residential

PROPOSED USE: 4 unit multi-family residential condominium ownership development.

EXISTING AND PROPOSED UTILITIES:

Sewer/Storm Drain: City of Los Altos

Water: California Water Service Company

Trash & Recycling: Mission Trails Waste System

Gas & Electric: Pacific Gas & Electric Co.

Cable/Phone/Internet: AT&T and Comcast

FLOOD ZONE DESIGNATION:

Zone X (shaded), areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 sq. mile; and areas protected by levees from 1% annual chance flood.

GENERAL NOTES

1) This Vesting Tentative Parcel Map is a One-Lot Subdivision for Condominium Purposes for the creation of 4 new residential condominium ownership units.

2) The existing single family residence, detached garage, utilities serving the residence, associated landscape/site improvements, and 4 trees will be demolished as a part of this project, all of which is identified on the Existing Conditions/Demolition Plan herein.

3) This Vesting Tentative Parcel Map is being processed concurrently with a Development Application for the project based upon plans prepred by:

cka Architects, Menlo Park, CA. (building and site improvements)

Cliff Bechtel & Assoc., Sammamish, WA. (civil engineering - grading, drainage, and utility improvements)

Refer to the concurrent application materials for additional information and specifics regarding proposed site improvements and architectural elements associated with this subdivision.

4) A Arborist Report depicting the disposition of all trees prepared by Monarch Consulting Arborists was prepared for the site and is included as a separate attachment to this Vesting Tentative Parcel Map. Note trees identified therein as numbers 1, 4-6, and 9-12 are located on neighboring properties, not the Subject Parcel, and may not be shown on this map.

5) A Historical Evaluation Report prepared by Archeological Resource Management was prepared for the site and is included as a separate attachment to this Vesting Tentative Parcel Map.

PROJECT DATUMS

1) Bearings shown hereon are based upon the monumented centerline of West Edith Avenue as shown in Book 888 of Surveys at Page 37; said bearing taken as North 89°45'00" East between found mounuments located at 3rd and 4th Streets.

2) Vertical datum is based upon Los Altos benchmark 15, a brass disc set in the top of curb at the east side of San Antonio Road on the projected centerline of West Edith Ave. Top of disk elevation taken as 175.17' per "City of Los Altos Bench Mark Circuit Map".

SURVEYOR'S STATEMENT

This Vesting Tentative Parcel Map was prepared by me or under my direction in conformance with the requirements of the Land Surveyor's Act and the Subdivision Map Act.

Charles M. Weakley, LS Exp. 12/31/22

L.S. 6421

O6-22-22
CALE
1" = 10'

10-

< >

ا ۳

Z

OW

MAP

TENTATIVE PARCEL division for Condominium Purp


VES⁻

JOB NO. 521082

CMW

VTM 1


SHEET NO.



GRAPHIC SCALE

0 5 10 20 35

1 inch = 10 ft.



GENERAL NOTES

1) This Vesting Tentative Parcel Map is a One-Lot Subdivision for Condominium Purposes for the creation of 4 new residential condominium ownership units.

2) The existing single family residence, detached garage, utilities serving the residence, associated landscape/site improvements, and 4 trees will be demolished as a part of this project, all of which is identified on the Existing Conditions/Demolition Plan herein.

3) This Vesting Tentative Parcel Map is being processed concurrently with a Development Application for the project based upon plans prepred by:

cka Architects, Menlo Park, CA. (building and site improvements)

Cliff Bechtel & Assoc., Sammamish, WA. (civil engineering - grading, drainage, and utility improvements)

Refer to the concurrent application materials for additional information and specifics regarding proposed site improvements and architectural elements associated with this subdivision.

4) A Arborist Report depicting the disposition of all trees prepared by Monarch Consulting Arborists was prepared for the site and is included as a separate attachment to this Vesting Tentative Parcel Map. Note trees identified therein as numbers 1, 4-6, and 9-12 are located on neighboring properties, not the Subject Parcel, and may not be shown on this map.

5) A Historical Evaluation Report prepared by Archeological Resource Management was prepared for the site and is included as a separate attachment to this Vesting Tentative Parcel Map.

PARCEL CONFIGURATION NOTES

1) All of Proposed Parcel 1 is Common Area

 All area outside of the building footprint shall be subject to a new Private Access and Utility Easement for the mutual benefit of all condominium Unit owners.

3) All Units shall be subject to recorded Covenants, Conditions, and Restrictions (CC&R's) and a recorded Condominium Plan.


4) Each Unit shall have 2 off-street parking spaces provided within an enclosed garage which is a part of the Unit.


5) Each unit shall have a private balcony area to be specified as a part of the Condominium Plan.

EASEMENT NOTES

1) A Public Utility Easement along the route of the existing pole line and proposed undergounding is proposed hereon. The width of this Public Utility Easement will be modified as necessary to accommodate PG&E requirements.

2) Dependant upon final water meter & appurtenance locations, easements will be granted to Cal Water Service if required by the agency; final easement configuration shall be coordinated with Cal Water.





PROVED DATE

MOUNTAIN PACIFIC

S U R V E Y S

1735 Enterprise Dr, Suite 109 PH (707) 425-6234
Fairfield, CA 94533 FAX (707) 425-1969


ENTATIVE PARCEL MAP vision for Condominium Purposes
1 Fourth Street
ot 18 of Block 4, Book L of Maps, Page 99 sor's Parcel No. 167-38-061


VESTING TENTATIVE
A 1-Lot Subdivision for Condo
14 Fourth St
Being a division of Lot 18 of Block 4, E
Assessor's Parcel No. 1

TE 06-22-22
ALE 1" = 10'

CMW
CHECKED

521082 ET NO. **VTM 2**







Lagerstroemia indica - LI Crape Myrtle



Salvia leucantha Santa Barbara - SL Mexican Sage



Podocarpus gracilior - PG Afrocarpus falcatus - Fern Pine



Nandina - N Heavenly Bamboo



Lomandra Platinum - LP



Pistacia chinensis - mature - PC Chinese Pistache



Iris douglasiana - option for J Native Iris



Lomandra Breeze - LB



Rosa banksiae - R Lady Banks Rose



Myrtus communis - MC Myrtle



Aeonium canariense Mint Saucer - D



Juncus patens - J, JP Gray Rush



Chondropetalum tectorum - CT Small Cape Rush