PROJECT INFORMATION

PROJECT ADDRESS: 15860 - 15894 WINCHESTER BLVD., LOS GATOS. CALIFORNIA 95030

ACCESSOR PARCEL NUMBERS: 529-11-13 529-11-38 529-11-39 529-11-40

TYPE OF CONSTRUCTION: **IB - FULLY SPRINKLERED PER NFPA 13**

(SEPARATE PERMIT)

OCCUPANCY GROUP: R2.1

SITE AREA: 56,889 S.F. (1.31 ACRES)

NO PUBLIC FUNDS FOR THIS PROJECT

APPLICABLE CODES:

2019 CALIFORNIA GREEN BUILDING STANDARDS CODE (MANDATORY MEASURES)

2019 CALIFORNIA BUILDING CODE

2019 CALIFORNIA MECHANICAL CODE

2019 CALIFORNIA ELECTRICAL CODE 2019 CALIFORNIA PLUMBING CODE

2019 CALIFORNIA FIRE CODE 2019 CALIFORNIA ENERGY CODE

DEFERRED SUBMITTALS LIST:

THE FOLLOWING ITEMS ARE A DEFERRED SUBMITTAL:

FOR THE PURPOSES OF THIS SECTION, DEFERRED SUBMITTALS ARE DEFINED AS THOSE PORTIONS OF THE DESIGN THAT ARE NOT SUBMITTED AT THE TIME OF THE APPLICATION AND THAT ARE TO BE SUMBITTED TO THE BUILDING OFFICIAL WITHIN A SPECIFIED PERIOD.

DEFERRAL OF ANY SUBMITTAL ITEMS SHALL HAVE PRIOR APPROVAL OF THE BUILDING OFFICIAL. THE ARCHITECT OR ENGINEER OF RECORD SHALL LIST THE DEFERRED SUBMITTALS ON THE PLANS AND SHALL SUBMIT THE DEFERRED SUBMITTAL DOUCMENTS FOR REVIEW BY THE BUILDING OFFICIAL

SUBMITTAL DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND

THE FOLLOWING ITEMS WILL BE DEFERRED SUBMITTALS:

- 1. FIRE SPRINKLERS
- 2. FIRE ALARM SYSTEM 3. EMERGENCY RESPONDER RADIO COVERAGE
- 4. TWO-WAY COMMUNICATION SYSTEM

VICINITY MAP:





PROJECT DIRECTORY:

DEVELOPMENT

SWENSON 777 NORTH FIRST STREET, 5TH FLR SAN JOSE, CA 95112

MIKE BLACK mike@swenson.com PH: (408) 938-6322 FX: (408) 998-1737

JESSIE BRISTOW jbristow@swenson.com PH: (831) 475-7100 FX: (831) 475-4544

ARCHITECT

SWENSON 777 NORTH FIRST STREET, 5TH FLR SAN JOSE, CA 95112

DANIEL SELL dan@swenson.com PH: (408) 938-6338 FX: (408) 287-2356

DAVID MEADS dmeads@swenson.com PH: (408) 938-6384 FX: (408) 287-2356

CIVIL ENGINEER BKF ENGINEERS 980 9th STREET, SUITE 2300

SACRAMENTO, CA 95814 **KEVIN WONG**

kwong@bkf.com PH: (916) 556-5800 FX: (916) 556-5899

LANDSCAPE **DILLION DESIGN ASSOCIATES** LANDSCAPE ARCHITECTURE 849 ALMAR AVE., #C162

MIKE DILLION ddastudio@ddasite.com PH: (408) 221-2516

SANTA CRUZ CA 95060

GEOTECHNICAL ENGINEER CORNERSTONE EARTH GROUP 1259 OAKMEAD PARKWAY SUNNYVALE, CA 94085

STEPHEN OHLSEN, P.E. sohlsen@cornerstoneearth.com PH: (408) 245-4600 - EXT. 125

SHEET INDEX:

SCHEMATIC LANDSCAPE

SCHEMATIC LEGENDS

SCHEMATIC MATERIAL

LS-6.0 SCHEMATIC PLANTING

- 1					
	0 - GENEF	RAL	4 - ARCHI	TECTURAL	
	A-0.0	TITLE SHEET	A-1.1	SITE PLAN 1	
	A-0.1	BLUEPRINT FOR A CLEAN BAY	A-1.3	SITE - DEMOLITION	
	A-0.2	PROJECTION INFORMATION	A-1.4	SHADOW STUDY	
	T-1	SITE - EXISTING TREES	A-1.5	OVERALL EXISTING ELEVATIONS	
	T-2	ARBORIST REPORT	A-1.6	OVERALL EXISTING ELEVATIONS	
	T-3	ARBORIST REPORT	A-1.7	OVERALL EXISTING ELEVATIONS	
	T-4	ARBORIST REPORT	A-1.8	FIRE ACCESS PLAN	
		1	A-1.9	FIRE ACCESS SECTIONS	
	2 - CIVIL		A-1.10	STREETSCAPE ELEVATIONS &	
	C1.1	EXISTING CONDITION		PHOTOS	
	C2.1	LOT MERGER SITE PLAN	A-2.0	GROUND FLOOR	
	C3.1	SITE GRADING PLAN	A-2.1	1ST FLOOR	
	C3.2	SECTIONS	A-2.2	2ND FLOOR	
	C4.1	SITE UTILITY PLAN 4	A-2.3	3RD FLOOR	
	C4.2	SITE UTILITY PLAN	A-2.4	ROOF	
	C5.1	STORMWATER CONTROL PLAN	A-2.5	ROOF DRAIN AREA PLAN	
	C5.2	TYPICAL STORMWATER DETAILS	A-3.0	RENDERING - NORTH ELEVATIONS	
	C6.1	EROSION CONTROL PLAN		COMPARISION	
	C6.2	EROSION CONTROL DETAILS	A-3.1	RENDERING - EAST ELEVATIONS COMPARISION	
	C6.3	POLLUTION PREVENTION	A-3.2	NORTH - SHELBURNE ELEVATION -	
			A-3.2	VARIANCE EXHIBIT	
	3 - LANDS		A-3.3	SOUTH - FACING RESIDENTIAL	
	LS-1.0	SCHEMATIC LANDSCAPE	0.0	ELEVATIONS - VARIANCE EXHIBIT	^
	LS-2.0	SCHEMATIC LANDSCAPE	A-3.4	BUILDING SECTIONS	3
	1000				

BUILDING SECTIONS ROOF SCREEN ANALYSIS -

BUILDING SECTIONS

WINCHESTER MEMORY CARE / ASSISTED LIVING

15860 - 15894 WINCHESTER BLVD., LOS GATOS, CALIFORNIA 95030

WINCHESTER

ROOF SCREEN ANALYSIS -PERSPECTIVES OVERALL BUILDING ELEVATIONS **BUILDING ELEVATIONS - WEST BUILDING ELEVATIONS - NORTH BUILDING ELEVATIONS - SOUTH**

BUILDING ELEVATIONS - EAST COURTYARD ELEVATIONS -ASSISTED LIVING COURTYARD ELEVATIONS -MEMORY CARE

RENDERING - WEST ELEVATON RENDERING - PERSPECTIVE FROM WINCHESTER

RENDERING - SOUTH ELEVATION RENDERING - PERSPECTIVE FROM GARDEN/GROUND LEVEL UNIT RENDERING - NORTH ELEVATON (SHELBURNE WAY) RENDERING - PERSPECTIVE FROM

SHELBURNE RENDERING - AERIAL FROM **SHELBURNE** RENDERING - AERIAL FROM

MATERIALS AND COLORS PHOTOS OF PROPERTY

PROJECT DESCRIPTION:

THE DESIGN INTENT FOR THIS PROJECT WAS TO CONVEY A HILLSIDE ESTATE FEEL WITH AN ITALIAN REVIVAL INFLUENCE THAT FEATURES SUCH ELEMENTS AS A TILED ROOF WITH DEEP SET DECORATIVE EAVES, PICTURE FRAMED WINDOWS, SYMMETRICAL FACADES, COLUMNS, AND BALUSTRADES. WHEN PLANNING THIS PROJECT WE WANTED TO MAINTAIN THE ORIGINAL RHYTHM OF THE NEIGHBORHOOD BY REPLACING THE EXISTING THREE HOMES ON THE SITE WITH A STRUCTURE THAT REFLECTED THE SAME THREE PART RHYTHM FACING ONTO WINCHESTER BOULEVARD. THESE THREE SEGMENTS OF THE BUILDING ARE LOCATED IN ROUGHLY IN THE SAME LOCATION AS THE ORIGINAL HOMES WITH THE MOST SOUTHERN OF THESE WINGS STEPPING DOWN TO SECOND STORY THIS WAS DONE AS A WAY OF CREATING VISUAL INTEREST THROUGH ASYMMETRY AS WELL AS A WAY TO SEGUE BETWEEN OUR PROJECT AND THE NEIGHBORING TOWNHOMES TO THE SOUTH OF OUR DEVELOPMENT. OUR PROJECT STEPS DOWN EVEN FURTHER ON EITHER END OF THE BUILDING ENTRANCE WITH A FRAMED ENTRY / EXIT TO THE PORTE

THIS SENIOR HOUSING PROJECT CONSIST OF 18 MEMORY CARE UNITS AND 107 ASSISTED LIVING UNITS FOR A COMBINED TOTAL OF 125 UNITS. IN ADDITION TO THESE LIVING UNITS, THIS PROJECT HAS TWO SEPARATE DINING ROOMS, A COMMERCIAL KITCHEN, THEATER, LIBRARY, GREAT ROOM, AND OTHER COMMON USE SPACES THROUGHOUT. THE OUTDOOR SPACES INCLUDE BOTH COMMON USE AREAS WHICH CONSIST OF THREE DIFFERENT LANDSCAPED COURTYARDS AT THE FIRST FLOOR PODIUM LEVEL AS WELL AS PRIVATE USE PATIOS OFF OF THE GROUND FLOOR GARDEN UNITS TO THE SOUTH AND EAST OF OUR PROJECT.

Consultant:

Revisions:

Planning Response #1 |07/20/21 Planning Response #3 | 12/10/21 Planning Response #4 | 04/04/22

Revision Schedule


COPYRIGHT © 2022 **SWENSON BUILDER**

WINCHES AS

APRIL 01, 2021 **AS NOTED** DM, EY, IL 20-9215


A-0.0

Pollution Prevention — It's Part of the Plan



Make sure your crews and subs do the job right!

Runoff from streets and other paved areas is a major source of pollution in San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep dirt, debris, and other construction waste away from storm drains and local creeks. Following these guidelines will ensure your compliance with local ordinance requirements.



Materials storage & spill cleanup

Non-hazardous materials management

- ✓ Sand, dirt, and similar materials must be stored at least 10 feet from catch basins, and covered with a tarp during wet weather or when rain is forecast
- ✓ Use (but don't overuse) reclaimed water for dust control as needed.
- ✓ Sweep streets and other paved areas daily. Do not wash down streets or work areas with water!
- ✓ Recycle all asphalt, concrete, and aggregate base material from demolition activities.
- ✓ Check dumpsters regularly for leaks and to make sure they don't overflow. Repair or replace leaking dumpsters promptly.

Hazardous materials management

- ✓ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, state, and federal regulations.
- ✓ Store hazardous materials and wastes in secondary containment and cover them during wet weather.
- ✓ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ✓ Be sure to arrange for appropriate disposal of all hazardous wastes.

Spill prevention and control

Bay Area Stormwater Management

Agencies Association (BASMAA)

1-888-BAYWISE

- ✓ Keep a stockpile of spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- ✓ When spills or leaks occur, contain them immediately and be particularly careful to prevent leaks and spills from reaching the gutter, street, or storm drain. Never wash spilled material into a gutter, street, storm drain, or creek!
- ✓ Report any hazardous materials spills immediately! Dial 911 or your local emergency response number.

Vehicle and equipment maintenance & cleaning

- ✓ Inspect vehicles and equipment for leaks frequently. Use drip pans to catch leaks until repairs are made; repair leaks promptly.
- ✓ Fuel and maintain vehicles on site only in a bermed area or over a drip pan that is big enough to prevent runoff.
- ✓ If you must clean vehicles or equipment on site, clean with water only in a bermed area that will not allow rinsewater to run into gutters, streets, storm drains, or creeks.
- ✓ Do not clean vehicles or equipment on-site using soaps, solvents, degreasers, steam cleaning equipment, etc.

Earthwork & contaminated soils

- ✓ Keep excavated soil on the site where it is least likely to collect in the street. Transfer to dump trucks should take place on the site, not in the street.
- ✓ Use hay bales, silt fences, or other control measures to minimize the flow of silt off the site.



- ✓ Avoid scheduling earth moving activities during the rainy season if possible. If grading activities during wet weather are allowed in your permit, be sure to implement all control measures necessary to prevent erosion.
- ✓ Mature vegetation is the best form of erosion control. Minimize disturbance to existing vegetation whenever possible.
- ✓ If you disturb a slope during construction, prevent erosion by securing the soil with erosion control fabric, or seed with fast-growing grasses as soon as possible. Place hay bales down-slope until soil is secure.
- ✓ If you suspect contamination (from site history, discoloration, odor, texture, abandoned underground tanks or pipes, or buried debris), call your local fire department for help in determining what testing should be done.
- ✓ Manage disposal of contaminated soil according to Fire Department instructions.

Dewatering operations

- ✓ Reuse water for dust control, irrigation, or another on-site purpose to the greatest extent possible.
- ✓ Be sure to call your city's storm drain inspector before discharging water to a street, gutter, or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ✓ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the city inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.

Saw cutting

- ✓ Always completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, hay bales, sand bags, or fine gravel dams to keep slurry out of the storm drain system.
- ✓ Shovel, absorb, or vacuum saw-cut slurry and pick up all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ✓ If saw cut slurry enters a catch basin, clean it up immediately.

Paving/asphalt work



- ✓ Do not pave during wet weather or when rain is forecast.
- ✓ Always cover storm drain inlets and manholes when paving or applying seal coat, tack coat, slurry seal, or fog seal.
- ✓ Place drip pans or absorbent material under paving equipment when not in use.
- ✓ Protect gutters, ditches, and drainage courses with hay bales, sand bags, or earthen berms.
- ✓ Do not sweep or wash down excess sand from sand sealing into gutters, storm drains, or creeks. Collect sand and return it to the stockpile, or dispose of it as trash.

✓ Do not use water to wash down fresh asphalt concrete pavement.

Concrete, grout, and mortar storage & waste disposal

- ✓ Be sure to store concrete, grout, and mortar under cover and away from drainage areas. These materials must never reach a storm drain.
- ✓ Wash out concrete equipment/trucks off-site or designate an on-site area for washing where water will flow onto dirt or into a temporary pit in a dirt area. Let the water seep into the soil and dispose of hardened concrete with trash.



- ✓ Divert water from washing exposed aggregate concrete to a dirt area where it will not run into a gutter, street, or storm drain.
- If a suitable dirt area is not available, collect the wash water and remove it for appropriate disposal off site.

Painting

- ✓ Never rinse paint brushes or materials in a gutter or street
- ✓ Paint out excess water-based paint before rinsing brushes, rollers, or containers in a sink. If you can't use a sink, direct wash water to a dirt area and spade it in.
- ✓ Paint out excess oil-based paint before cleaning brushes in thinner.
- ✓ Filter paint thinners and solvents for reuse whenever possible. Dispose of oil-based paint sludge and unusable thinner as hazardous waste.



APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215

WINCHESTER MEMOR ASSISTED LIVIN

PLANNING RE-15894 WINCHEST

A-0.1


Revision Schedule


Planning Response #1 07/20/21

COPYRIGHT © 2022

SWENSON BUILDER

Storm drain polluters may be liable for fines of up to \$10,000 per day!





WINCHESTER ASSISTED LIVING

15860 WINCHESTER BLVD LOS GATOS, CALIFORNIA

Submitted to:

777 North 1st Street, 5th Floor San José, CA 95112

Prepared by:

David L. Babby Registered Consulting Arborist® #399 Board-Certified Master Arborist #WE-4001B

February 10, 2021

p.o. box 25295, san mateo, california 94402 • email: arborresources@comcast.net

3.0 SUITABILITY FOR TREE PRESERVATION

February 10, 2021

Each tree has been assigned either a "high," "moderate" or "low" suitability for preservation rating as a means to cumulatively measure its existing health; structural integrity; anticipated life span; remaining life expectancy; prognosis; location; size; particular species; tolerance to construction impacts; growing space; frequency of care needed; and safety to property and persons within striking distance. Descriptions these ratings are presented below; the high category is comprised of 9 trees (or 26%), the moderate category 24 (or 68%), and the low category 2 (or 6%).

High: Applies to #3, 9, 16-18, 24, 34, 39, 39 and 42.

David L. Babby, Registered Consulting Arborist®

These trees appear relatively healthy and structurally stable; have no apparent, significant health issues or structural defects; present a good potential for contributing long-term to the site; and seemingly require only periodic or regular care and monitoring to maintain their longevity and structural integrity. They are typically the most suitable for retaining and incorporating into the future landscape.

Moderate: Applies to #1, 2, 5, 78, 11-15, 19-23, 25, 27, 29, 38, 40, 41 and 43-45. These trees contribute to the site, but at levels less than those assigned a high suitability; might have health and/or structural issues which may or may not be reasonably addressed and properly mitigated; and frequent care is typically required for their remaining lifespan. They may be worth retaining if provided proper care, but not seemingly at significant expense or major design revisions.

Low: Applies to #4 and 10.

These trees have weak, multi-trunk structures comprised of stump sprouts, and there are no tree care measures to reasonably mitigate the risk (i.e. beyond likely recovery). As a general guideline, these trees should be removed regardless of future development, and any which are retained require frequent monitoring and care throughout their remaining lifespans to minimize risk to any persons or property within striking distance.

15860 Winchester Boulevard, Los Gatos

David L. Babby, Registered Consulting Arborist® February 10, 2021

6.0 TREE PROTECTION MEASURES

Recommendations presented within this section consider plans reviewed, and serve as protection measures to help mitigate or avoid impacts to trees being retained. They should be carefully followed and incorporated into project plans, and I (hereinafter "project arborist") should be consulted in the event any cannot be feasibly implemented.

6.1 Design Guidelines

- 1. The Tree Protection Zone (TPZ) for each retained tree shall be up to or within 6 feet from the proposed building foundation, and distances in all other directions from the trunks equal to 7 to 10 times the trunk diameters (all distances are intended to be obtained the closest edge, face of, their outer perimeter at soil grade). A TPZ is intended to restrict or highly limit the following activities within the specified distances: overexcavation, subexcavation, trenching, compaction, mass and finishgrading, soil scraping, tilling, ripping, swales, bioswales, storm drains, dissipaters, equipment cleaning, stockpiling and dumping of materials, and equipment and vehicle operation. In the event an impact encroaches slightly within a setback, it can be reviewed on a case-by-case basis by the project arborist to determine whether measures can sufficiently mitigate the impacts to less-than-significant levels.
- 2. For trees being retained, review setbacks proposed on plans for grading, utility, hardscape, compaction, trenching, subexcavation and overexcavation, and compare to the TPZ parameters specified above. Where conflicts exist, consult with the project arborist to identify opportunity for increasing setbacks and/or possibly mitigating impacts to achieve a reasonable assurance of protection.
- 3. Per Section 29.10.1000(C.1) of the Ordinance, a copy of this or a future report providing tree protection measures must be incorporated into the final set of project plans; titled Sheets T-1, T-2, etc. ("Tree Protection Instructions"); and referenced on all site-related project plans. Additionally, all site-related plans should contain notes referring to this report for tree protection measures.

15860 Winchester Boulevard, Los Gatos Page 9 of 16

David L. Babby, Registered Consulting Arborist®

TABLE OF CONTENTS

February 10, 2021

February 10, 2021

February 10, 2021

<u>TITLE</u> PA	GE
INTRODUCTION	. 1
TREE COUNT AND COMPOSITION	. 2
SUITABILITY FOR PRESERVATION	4
POTENTIAL TREE DISPOSITION	5
Proposed Removals	5
APPRAISED TREE VALUES	8
TREE PROTECTION MEASURES	9
Design Guidelines	9
Before Demolition, Grading and Construction	. 11
During Demolition, Grading and Construction	. 13
ASSUMPTIONS AND LIMITING CONDITIONS	16
	INTRODUCTION

EXHIBITS

<u>EXHIBIT</u>	TITLE
Α	TREE INVENTORY TABLE (five sheets)

PHOTOGRAPHS (seven sheets)

SITE MAP (one sheet)

David L. Babby, Registered Consulting Arborist®

4.0 POTENTIAL TREE DISPOSITION

Implementing the proposed progress plan will result in the following tree disposition:

• **Remove** (26 in total): #4, 5, 7-21, 24, 25, 34, 38, 39 and 42-45.

• **Retain** (9 in total): #1-3, 22, 23, 27, 29, 40 and 41.

4.1 Proposed Removals

The table below, and continued on the next page, summarizes underlying reasons for removing the 26 trees (and on the map in Exhibit B, an "X" is placed across each trunk); reasons are solely based on my review of the architectural progress plan set, and additional impacts will likely be realized once civil plans are reviewed. Protection measures to help mitigate or avoid impacts to the 9 trees planned for retention are presented within Section 6.0 of this report.

TREE #	NAME	DIAM. (in.)	REASON(S) FOR REMOVAL
4	N. California black walnut	10, 8, 8, 7	Weak structure, site improvements
5	London plane tree	7	Site improvements
7	London plane tree	7	Site improvements
8	Coast live oak	10	Within building footprint
9	Coast live oak	30	Within building footprint
10	Holly oak	8, 7, 6	Weak structure, within building footprint
11	Coast live oak	11, 8	Within building footprint
12	Coast live oak	26	Within building footprint
13	Coast live oak	8, 6	Within driveway footprint
14	London plane tree	7	Within driveway apron
15	London plane tree	7	Site improvements
16	Coast live oak	26	Severe impacts from building construction, grading, and site improvements

15860 Winchester Boulevard, Los Gatos

David L. Babby, Registered Consulting Arborist®

- 4. Add assigned tree numbers and locations to the architectural, civil and landscape siterelated plans.
- 5. Construction of the driveway immediately east of #1's trunk shall require no excavation or compaction beyond the driveway/wall limit. Any fill placed beyond the driveway/wall (i.e. towards the tree) shall not exceed 24 inches from the edge.
- 6. Specify on the demolition plan to abandon and cut off at existing soil grade all existing, unused lines, pipes and manholes within a TPZ.
- 7. Route all underground utilities and services (e.g. electrical) beyond TPZs. Where this is not feasible, the section of line(s) within a TPZ should be directionally-bored by at least 4 feet below existing grade, tunneled using a pneumatic air device (such as an AirSpade®), or installed by other means (e.g. pipe-bursting) to avoid an open trench. The ground above any tunnel must remain undisturbed, and access pits and aboveground infrastructure (e.g. splice boxes, meters and vaults) established beyond TPZs.
- 8. The permanent and temporary drainage design, including downspouts, should not require water being discharged within the trees' driplines.
- 9. Bioswales, storm drains and swales shall be established well-beyond TPZs.
- 10. On the erosion control design, specify that any straw wattle or rolls shall require a maximum vertical soil cut of 2 inches for their embedment, and are established as close to canopy edges as possible (and not against a trunk).
- 11. Avoid specifying the use of herbicides use within a TPZ; where used on site, they should be labeled for safe use near trees. Also, liming shall not occur within 50 feet from a tree's canopy.
- 12. On the final site plan, represent the future staging area and route(s) of access to be beyond unpaved areas beneath or near canopies.

15860 Winchester Boulevard, Los Gatos Page 10 of 16

David L. Babby, Registered Consulting Arborist®

1.0 INTRODUCTION

Swenson is planning to construct a three-story, assisted living facility at 15860 Winchester Blvd, Los Gatos. The site occupies the southeast corner of Shelburne Way and Winchester Blvd, and is comprised of three separate parcels with the addresses of 15860, 15880 and 15894 Winchester Blvd (each parcel contains single-family residences and accessory structures to be demolished). As part of their planning submittal, Swenson has retained me to prepare this Arborist Report, and specific tasks executed are as follows (to conform with 29.10.1000 and 29.10.1005 of the Town Code):

- Visit the site, performed on 1/14/21, 1/18/21 and 2/8/21, to identify and obtain photos of "protected trees" located within and immediately adjacent to where development activities are planned (captures the entire project site).
- Determine each tree's trunk diameter at 54 inches above natural grade (rounded to the
- nearest inch). Trees with more than one diameter listed are formed by multiple trunks.
- Estimate each tree's height and average canopy spread (rounded to nearest fifth). Ascertain each tree's health and structural integrity, and assign an overall condition
- rating (e.g. good, fair, poor or dead). Designate each tree's suitability for preservation (e.g. high, moderate or low). Utilize tree numbers assigned for a prior office building proposal from nearly 10
- years ago. Tags with engraved, corresponding numbers were affixed onto any trees with missing or non-readable ones.
- Identify tree numbers, recommended fencing locations and anticipated removals on
- the site map in Exhibit B; base map is a copy of A-1.2, dated 11/4/20, by Swenson. Identify which are defined by Town Code as a "large protected tree."²
- Appraise the monetary values of protected trees planned for retention. Review the progress plan set by Swenson to ascertain potential impacts and removals
- (the set contains various dates from October 2020 to January 2021).
- Provide protection measures to help mitigate or avoid impacts to retained trees. • Prepare a written report that presents the aforementioned information, and submit via email as a PDF document.

¹ Section 29.10.0960 of the Town Code defines a protected tree as having a ≥4" diameter trunk at 54" above natural grade. Exempt from this provision are fruit- and nut-bearing trees with trunk diameters <18", as well as select tree types listed within Section 29.10.0970(2) and having trunk diameters <24" (pursuant to Section 29.10.0955 of the Town Code defines a large protected tree as any Quercus sp., Aesculus californica or Arbutus menziesii with a diameter >24", or any other species with a diameter of >48"

(measured at 54" above natural grade). 15860 Winchester Boulevard, Los Gatos Swenson, San José

David L. Babby, Registered Consulting Arborist® February 10, 2021

Table continued:

TREE #	NAME	DIAM. (in.)	REASON(S) FOR REMOVAL
17	Coast live oak	23	Severe impacts from building construction, grading, parking lot and site improvements
18	Coast live oak	29	Within building footprint
19	Lemon bottlebrush	7	Within building footprint
20	Coast live oak	7	Within building footprint
21	Coast live oak	20, 14, 13	Within building footprint
24	Coast live oak	17, 16	Within building footprint
25	Coast live oak	17	Within excavation footprint for building and site wall
34	Coast live oak	16	Within building footprint
38	Goldenrain tree	20	Site improvements
39	Coast live oak	26	Within building footprint
42	Valley oak	23	Within building footprint
43	Coast live oak	14	Within building footprint
44	Coast live oak	4	Within building footprint
45	Coast live oak	5	Within excavation footprint for site wall

4.2 Potential Impacts to Retained Trees

My review of the architectural progress plans reveals the 9 oak trees proposed for retention can likely be sufficiently protected by adhering to recommendations presented within Section 6.0 of this report; they include #1-3, 22, 23, 27, 29, 40 and 41. An analysis of impacts, as derived by my review of the progress plan set, follows.

15860 Winchester Boulevard, Los Gatos

Page 6 of 16

David L. Babby, Registered Consulting Arborist®

- 13. Adhere to the following additional landscape guidelines:
- a. Plant material installed beneath oak canopies must be drought-tolerant, limited in amount, and placed at least 5+ feet from their trunks. Plant material installed beneath canopies of other trees should be at least 24 inches from their trunks.

February 10, 2021

Page 11 of 16

- b. Introducing regular irrigation within the root zones of oaks can, overtime, impose adverse impacts and should be avoided. Rather, irrigation installed for new plant material beneath their canopies should be low-volume, applied irregularly (such as only once or twice per week), and temporary (such as <three years). Irrigation should not strike within 6 inches from the trunks of existing trees, and not applied against trunks of new trees.
- c. Establish irrigation and lighting features (e.g. main line, lateral lines, valve boxes, wiring and controllers) to avoid trenching within a TPZ. In the event this is not feasible, route them in a radial direction to a tree's trunk, and terminate a specific distance from a trunk (versus crossing past it). In certain instances, an AirSpade® may be required to avoid root damage, and any Netafim tubing used should be placed on grade, and header lines installed as mentioned above. Note that routes
- shall be reviewed with the project arborist prior to any trenching occurring. d. Design any new site fencing or fence posts to be at least 2 to 5 feet from a tree's
- trunk (depends on the trunk size, growth pattern and prior impacts).
- e. Avoid tilling, ripping and compaction within TPZs.
- f. Establish any bender board or other edging material within TPZs to be on top of existing soil grade (such as by using vertical stakes).
- g. Utilize a 3- to 4-inch layer of coarse wood chips or other high-quality mulch for new ground cover beneath canopies (gorilla hair, bark or rock, stone, gravel, black plastic or other synthetic ground cover should be avoided).

6.2 Before Demolition, Grading and Construction

15860 Winchester Boulevard, Los Gatos

14. Supply water to the root zones of oaks being retained. The methodology, frequency and amounts can be reviewed with the project arborist, and several possible methodologies including flooding the ground inside an 8-inch tall berm, soaker hoses, or deep-root injection. Note in the event dewatering is required for this project, the watering program shall be more intensive than otherwise needed (i.e. will require greater frequency and/or volume).

Thirty-five (35) trees of seven various species were inventoried for this report. They are sequentially numbered as 1-5, 7-25, 27, 29, 34 and 38-45,³ and the table below identifies their names, assigned numbers, counts and percentages.

2.0 TREE COUNT AND COMPOSITION

David L. Babby, Registered Consulting Arborist®

NAME	TREE NUMBER(S)	COUNT	% OF TOTAL
Coast live oak	1-3, 8, 9, 11-13, 16-18, 20-25, 27, 29, 34, 39, 41-45	26	74%
Goldenrain tree	38	1	3%
Holly oak	10	1	3%
Lemon bottlebrush	19	1	3%
London plane tree	5, 7, 14, 15	4	11%
N. California black walnut	4	1	3%
Valley oak	40	1	3%
	Total	35	100%

Specific information regarding each tree is presented within the inventory table in Exhibit A. The trees' locations and assigned numbers are identified on the site map in Exhibit B, and photographs are presented in Exhibit C.

specifically coast live (with 74% of the total) and valley oak (an additional 3%).

February 10, 2021

February 10, 2021

As illustrated on the above table, the site is populated predominantly by native oaks,

The gaps in sequential numbering are due to a select number of trees either being exempt from inclusion per the Town Code or having been removed; they include #6, 26, 28, 30-33 and 35-37. Swenson, San José

David L. Babby, Registered Consulting Arborist®

Tree #1, a 19-inch diameter coast live oak aligning Shelburne Way, will sustain a high level of impacts. Root loss will occur during excavation for the parking garage and building foundation at 14 feet south of its trunk, as well as building the parking lot entry a short distance of only 7 feet east of is trunk. To minimize root loss, it is critical that no overexcavation or compaction is needed beyond the wet section of drive entry between the street and building. Also, quite notably, roughly 40-percent of the tree's southern canopy will require pruning for building construction clearance, to encompass a 14-inch diameter limb, an 8-inch diameter limb, and reduction of a 9-inch diameter one.

Tree #2, a multi-trunk (33" and 15") coast live oak along Shelburne Way, will sustain a moderate level of impacts. Root loss will occur around 12 feet south of its trunk for the parking garage and building foundation. Pruning to achieve clearance for building construction will account for a roughly 20-percent of its total canopy, to include removing the low southeast limb overhanging the existing driveway, and several branches 3 to 5 inches in diameter.

Tree #3, a multi-trunk (28" and 20") coast live oak also along Shelburne Way, will sustain a moderate to high level of impacts. Root loss for the underground garage will occur around 10 feet from its trunk. Pruning to achieve building clearance will account for a tolerable 15-percent of its total canopy, to consider removing two, south-growing limbs with diameters of 11 and 12 inches, as well as several other small ones.

Tree #22, a 15-inch diameter coast live oak along the rear boundary, grows with a pronounced directly towards the future building, extending nearly 10 west from its base. When considering the proposed building is around 15 feet from its base, building clearance may become an issue during construction and/or long-term, requiring nearly all branches along the canopy's west side being pruned away. Root loss for excavation will occur at a tolerable distance of nearly 11 feet away. If protected, I estimate a high to moderate level of potential impacts.

15860 Winchester Boulevard, Los Gatos

David L. Babby, Registered Consulting Arborist®

15. Stake the limits of grading, utility routes, irrigation routes, etc. (whether all at once or

various phases) for review by the project arborist prior to ground disturbance.

16. Conduct a site meeting with the general contractor and project arborist several weeks or months prior to demolition for the purpose of reviewing protections measures

access, staging, pruning, staking, watering, mulching, tree removals, etc.

presented in this report, such as tree fencing and trunk wrap protection, routes of

- 17. Prior to demolition, install tree protection fencing where shown on the map in Exhibit B. Fencing shall consist of 6-foot tall chain link mounted on 2-inch diameter, galvanized iron posts driven at least 2 feet into the ground, kept in place throughout construction, and removed or modified only under the knowledge and direct consent of the project arborist. Note fencing may require reconfiguration for several additional phases, such as demolition, grading, utility installation and building
- 18. Prior to demolition, affix and maintain 8.5- by 11-inch warning signs along each side of fencing opposite the trees' trunks (can be discussed with project arborist beforehand): "WARNING - Tree Protection Zone - this fence shall not be removed and is subject to penalty according to Town Code 29.10.1025."

construction, etc. (all to be reviewed with the project arborist).

- 19. Prune retained trees prior to demolition and/or shoring. The work shall be highly selective, targeted, and performed under direction of the project arborist. Additionally, all work shall be conducted in accordance with the most recent ANSI A300 standards, and by a California state-licensed tree service contractor (D-49) that has an ISA certified arborist in a supervisory role, carries General Liability and Worker's Compensation insurance, and abides by ANSI Safety Operations.
- 20. Prior to removing trees and the initial site meeting, paint an "X" on their trunks to allow review and confirmation with the project arborist (tree tags correspond with tree numbers). Also, ensure the removal process does not damage retained trees.

15860 Winchester Boulevard, Los Gatos Page 12 of 16 David L. Babby, Registered Consulting Arborist® February 10, 2021

Seven (7) trees are located within the public right-of-way and are regarded as street trees; they include #1-3, 5, 7, 14 and 15. Trees #1 thru 3 are large coast live oaks along Shelburne Way, and their trunks span the property boundary. The other four, namely #5, 7, 14 and 15, are relatively small London planes aligning Winchester Blvd, within the Town's planter strip between the street curb and sidewalk.

As previously mentioned, all 35 are defined as protected trees per Town Code. Of these, the following 10 are defined as large protected trees: #2, 3, 9, 12, 16, 18, 21, 24, 39 and 41 (see footnote 2, page 1, of this report).

Note that the trunk locations of trees #44 and 45 were added to the map in Exhibit B and represent only rough approximations (versus surveyed locations)

On the map in Exhibit B, I have denoted trees already removed, as well as those exempt from inclusion within the tree inventory.

Consultant:

Revisions: Revision Schedule

Planning Response #1 |07/20/21

COPYRIGHT © 2022

SWENSON BUILDER

MEMOR

5.0 APPRAISED TREE VALUES

Tree #23, a 17-inch diameter coast live oak also along the rear boundary, is roughly the same distance from the building as #22, and potential impacts appear low. Only small

branches will require pruning to achieve building clearance, and my root loss estimation is

Trees #27 and 29, both coast live oaks with trunk diameters of 15 and 17 inches,

respectively, are setback sufficiently from the building to be adequately protected with

only minor impacts. Regarding pruning, #27 will require one 5-inch diameter limb to be

Trees #40 and 41 are situated only a few feet apart at grade, #40 being a valley oak with a

17-inch trunk diameter, and #41 a coast live oak with a 26-inch trunk diameter. Root loss

during building excavation is tolerable. For pruning, #40 will lose roughly 30-percent of

its total canopy to achieve building clearance, namely, three south-growing limbs with

diameters between 5 and 7 inches. Tree #41 will only require the loss of small branches

removed for building and construction clearance, representing a minor section for the tree.

The monetary values of the nine trees planned for retention have been appraised to conform with Section 29.10.1000(c)(3a) of the Los Gatos Town Code. Individual values are listed within the last column of Exhibit A, and their combined total equals \$52,000. Values were calculated using the Trunk Formula Technique derived from the Guide for Plant Appraisal, 10th Edition, 2019.

15860 Winchester Boulevard, Los Gatos Swenson, San José

David L. Babby, Registered Consulting Arborist®

15860 Winchester Boulevard, Los Gatos

David L. Babby, Registered Consulting Arborist®

overhanging the existing shed below.

Swenson, San José

the same as for #22.

February 10, 2021 21. Establish the staging and cleanout area(s), as well as all routes of access beyond unpaved areas beneath tree canopies. Where challenges arise, review them

Page 3 of 16

February 10, 2021

22. Spread, and replenish as needed throughout the entire construction process, a 4- to 5inch layer of coarse wood chips (1/4- to 3/4-inch in size) from a tree-service company over unpaved ground within designated-fenced areas.

employed to sufficiently mitigate the potential impacts.

beforehand with the project arborist to determine whether any measures can be

- 23. The removal of stumps, whether old or new, located within TPZs shall be performed with a stump grinder (versus being extracted with heavy equipment and inadvertently damaging roots of trees otherwise being retained).
- 24. Where applicable, ivy should be manually cleared off and at least 5 feet from the trees' trunks (or manually removed from planters altogether). Also, the removal of existing groundcover, plants, shrubs, etc. within TPZs shall only be manually done.
- 25. Clear soil to expose the buried root collars⁴ of trees #1, 23, 27, 40 and 41 This work must be manually and carefully performed to avoid damaging the trunk and roots during the process, and preferably by a tree-service company using an AirSpade to avoid unnecessary root and/or trunk damage.
- 26. Fertilization may benefit a tree's health, vigor and appearance. If applied, however, soil samples should first be obtained to identify the pH levels and nutrient levels so a proper fertilization program can be established. I further recommend any fertilization is performed under the direction and supervision of a certified arborist, and in accordance with the most recent ANSI A300 Fertilization standards.


6.3 During Demolition, Grading and Construction


27. Abandon the portions of chain link fence embedded within the trunks of #1 thru 3, as well as the top rail within #2's trunk; the material can be cut at the trunk, and avoid damaging the bark during the process.

⁴ A "root collar" is the distinct swollen area near the ground where buttress roots and the main trunk merge. 15860 Winchester Boulevard, Los Gatos Swenson, San José

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

DEVELOPMENT REVIEW RESUBMITTAL #4: APRIL 4, 2022





15860 Winchester Boulevard, Los Gatos Swenson, San José

Page C-6

15860 Winchester Boulevard, Los Gatos Swenson, San José




Consultant:

Revisions:

Revision Schedule

Planning Response #1 07/20/21

COPYRIGHT © 2022 SWENSON BUILDER



ABBREVIATIONS ? LEGEND

BLACK WALNUT BACK OF WALK CHAIN LINK FENCE COAST LIVE OAK CONCRETE CABLE TELEVISION ENGLISH WALNUT ELECTRIC EDGE OF PAVEMENT FACE OF CURB INSIDE OF BOUNDARY OUTSIDE OF BOUNDARY LONDON PLANE LEMON BOTTLE BRUSH MILE PER HOUR STORM DRAIN MANHOLE SIGNAL

SANITARY SEWER MANHOLE TOP OF CURB

WOOD FENCE WALNUT GUY WIRE

> FIRE HYDRANT WATER VALVE SIGN

POWER POLE


ALL DISTANCES AND DIMENSIONS ARE IN FEET AND DECIMALS THEREOF.

LG 21: DISC IN MONUMENT WELL AT THE EASTERLY INTERSECTION OF UNIVERSITY


ELEVATION = 351.65' (TOWN OF LOS GATOS DATUM)


BASIS OF BEARINGS

THE BEARING N615'00"E OF THE CENTERLINE OF WINCHESTER BOULEVARD, BETWEEN FOUND MONUMENTS, AS SAID BEARING IS SHOWN ON PARCEL MAP, FILED FOR RECORD ON JANUARY 21, 1975 IN BOOK 350 OF MAPS AT PAGE 46, RECORDS OF SANTA CLARA COUNTY, WAS TAKEN AS THE BASIS OF BEARINGS FOR THIS SURVEY.











Consultant:



300 FRANK OGAWA PLAZA SUITE 380 OAKLAND, CA 94612 (510) 899-7300 www.bkf.com

Revisions:

COPYRIGHT © 2021

SWENSON BUILDER

PLANNING RESUBMITTAL NOVEMBER 1, 2021

11/01/21


WINCHESTER


1" = 20'-0"

Job #: 9215-70-103

Drawn by: AR

C-1.1







PROJECT DATA

- 1. PROJECT ADDRESS: 15860, 15880, 15894 WINCHESTER BLVD., AND SHELBURNE WAY, LOS GATOS, CA
- 2. ASSESSORS PARCEL NO.: 529-11-013, 038, 039 AND 040
- 3. EXISTING LAND USE: RESIDENTIAL/COMMERCIAL
- 4. PROPOSED LAND USE: COMMERCIAL
- EXISTING ZONING: O—OFFICE
- 6. PROPOSED ZONING: O-PD
- 7. GROSS ACREAGE: 1.31 ACRES
- 9. EXISTING NUMBER OF BUILDINGS: 9 RESIDENTIAL/CARPORTS/SHEDS
- 10. NUMBER OF BUILDINGS REMOVED: 9
- 11. PROPOSED NUMBER OF HOMES: 1 MULTI-FAMILY FACILITY
- 12. PROPOSED NUMBER OF PARKING GARAGE: 1
- 13. FLOOD ZONE: X, FIRM PANEL 376 OF 830, MAP NUMBER 06085C0376H, DATED 05/18/2009.
- 14. PROJECT WATERSHED: VASONA RESERVOIR AND LOS GATOS CREEK
- 15. BASIS OF BEARINGS:
- THE BEARING S83°18'46"E OF THE MONUMENT LINE OF THE SHELBURNE WAY, AS SHOWN ON THAT CERTAIN MAP FILED IN THE OFFICE OF THE RECORDER OF SANTA CLARA COUNTY, STATE OF CALIFORNIA, IN BOOK "U" OF MAPS AT PAGES 34 AND 35, WAS USED AS THE BASIS OF BEARINGS SHOWN ON THIS MAP.
- INTERSECTION OF UNIVERSITY AVENUE AND SHELBURNE WAY. ELEVATION: 351.65 (TOWN OF LOS GATOS DATUM)
- 17. COVENANTS, CONDITIONS AND RESTRICTIONS (CC&R'S) WILL BE PROVIDED TO CLARIFY RIGHTS ACROSS COMMON AREAS, ACCESS RIGHTS, MAINTENANCE RESPONSIBILITIES, PARKING USE, ETC. 18. AVERAGE SLOPE OF EXISTING SITE: 7%

PRELIMINARY EARTHWORK QUANTITY

PRELIMINARY EARTHWORK QUANTITIES								
	CUT (CY)	FILL (CY)	NET (CY)	ر (
GARAGE	6845	0	6845 CUT	\ \				
DRIVEWAY	85	132	47 FILL	\ \				
WALKWAY	272	28	244 CUT	\ \				
LANDSCAPE	215	150	65 CUT	\ \				
TOTAL	7417	310	7287 CUT	_ く				


*EARTHWORK QUANTITIES ARE SHOWN FOR PLANNING PURPOSES ONLY. CONTRACTOR SHALL PERFORM THEIR OWN EARTHWORK CALCULATION.

GENERAL INFORMATION


GREEN VALLEY CORP. D.B.A SWENSON 777 N. 1ST STREET, 5TH FLOOR SAN JOSE, CA 95112 (408) 287-0246

MAP PREPARED BY:

BKF ENGINEERS ENGINEERS, SURVEYORS & PLANNERS (510) 899-7300 300 FRANK OGAWA PLAZA, SUITE 380 OAKLAND, CA 94612



GRAPHIC SCALE





Consultant:



300 FRANK OGAWA PLAZA SUITE 380 OAKLAND, CA 94612 (510) 899-7300 www.bkf.com

Revisions:

COPYRIGHT © 2021 **SWENSON BUILDER**


PLANNING RESUBMITTAL **NOVEMBER 1, 2021**

11/01/21

1" = 20'-0" Scale:

Job #: 9215-70-103

Drawn by: AR



GRADING NOTES

1. PROPOSED SITE PLAN AND UTILITIES HAS BEEN SCREENED

- CONSTRUCTION.
- 5. CONTRACTOR SHALL TAKE CAUTION WHEN GRADING ADJACENT TO EXISTING BUILDINGS, TO PROTECT EXISTING FOUNDATIONS AND TO NOT TO COVER EXISTING VENTS.
- FINISHED GRADE IN AREAS OF RE-GRADING. IN PAVED AREAS, ELEVATION DIFFERENCE SHALL NOT BE MORE THAN 1/2 INCH BETWEEN RIMS AND ADJACENT SURFACE.
- CONTRACTOR'S ATTENTION IS DIRECTED TO THE FOLLOWING PARAMETERS THAT NEED TO BE MET WITH THE FINISHED CONSTRUCTION:
- OF 4.9% AND A MAXIMUM CROSS SLOPE OF 2%. b. LANDINGS SHALL HAVE A MAXIMUM SLOPE OF 2% IN ALL
- c. ADA PARKING STALLS AND STRIPED AISLE SHALL HAVE A MAXIMUM SLOPE OF 2% IN ALL DIRECTIONS, INCLUDING DIAGONAL.
- d. TRANSITIONS BETWEEN PROPOSED IMPROVEMENTS AND EXISTING CONDITIONS SHALL BE SMOOTH AND FREE OF ABRUPT CHANGES.
- * CONTRACTOR SHALL FIELD VERIFY EXISTING GRADES AT CONFORMS PRIOR TO FORMING/AC WORK.

LEGEND

---- OVERLAND RELEASE

ABBREVIATIONS

ASPHALT CONCRETE

BACK OF WALK CC CONCRETE

DCDA DOUBLE CHECK DETECTOR ASSEMBLY

DMA DRAINAGE MANAGEMENT AREA

EX EXISTING

FDC FIRE DEPARTMENT CONNECTION

FINISH FLOOR FIRE HYDRANT FLOW LINE

FIRE WATER GRADE BREAK

INVERT LINEAR FEET

POINT RPPA REDUCE PRESSURE PRINCIPLE ASSEMBLY

STORM DRAIN SDCO STORM DRAIN CLEANOUT

SDDI STORM DRAIN DROP INLET SDMH STORM DRAIN MANHOLE


SS SANITARY SEWER SSCO SANITARY SEWER CLEANOUT

SSMH SANITARY SEWER MANHOLE STORMWATER TREATMENT MEASURE


TOP OF CURB THRESHOLD

WATER

WATER METER WV WATER VALVE (GATE VALVE)



GRAPHIC SCALE





FOR CLARITY.

2. GRADING WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE TECHNICAL SPECIFICATIONS AND THE REQUIREMENTS AND RECOMMENDATIONS CONTAINED IN THE PROJECT GEOTECHNICAL REPORT.

3. THE CONTRACTOR SHALL EXERCISE EXTREME CARE TO CONFORM TO THE LINES, GRADES, SECTIONS, AND DIMENSIONS AS SET FORTH ON THESE PLANS. GRADED AREAS SHALL CONFORM TO THE VERTICAL ELEVATIONS SHOWN WITHIN TOLERANCE OF ONE—TENTH OF A FOOT IN LANDSCAPED AREAS AND TWO-HUNDREDTHS OF A FOOT IN HARDSCAPED OR PAVED AREAS. WHERE GRADED AREAS DO NOT CONFORM TO THESE TOLERANCES, THE CONTRACTOR SHALL BE REQUIRED TO DO CORRECTIVE GRADING, AT NO EXTRA COST TO THE OWNER.

4. CONTRACTOR SHALL FIELD VERIFY FINISHED FLOOR ELEVATIONS OF EXISTING BUILDINGS PRIOR TO STARTING

6. RIMS OF UTILITY STRUCTURES SHALL BE ADJUSTED TO

7. WHERE IMPROVEMENTS INVOLVE ADA ACCESSIBILITY.

a. WALKWAYS SHALL HAVE A MAXIMUM LONGITUDINAL SLOPE

DIRECTIONS, INCLUDING DIAGONAL.

COPYRIGHT © 2021 SWENSON BUILDER

Consultant:

SUITE 380

Revisions:

300 FRANK OGAWA PLAZA

OAKLAND. CA 94612

(510) 899-7300

www.bkf.com

SITE

PLANNING RESUBMITTAL NOVEMBER 1, 2021

11/01/21

Scale: 1'' = 20'-0''


Drawn by: AR


WINCHEST


Job #: 9215-70-103


Sheet


C-3.1














SECTION F
SCALE: 1"=5'



Consultant:



Revisions:

COPYRIGHT © 2021 SWENSON BUILDER

SSISTED LIVING
AND SHELBURN

WINCHESTER

SECTIONS

PLANNING RESUBMITTAL NOVEMBER 1, 2021

Date: 11/01/21


Scale: 1" = 20'-0"

Drawn by: AR

Job #: 9215-70-103

Sheet

C-3.2



LEGEND AND SYMBOLS

--- SD --- PR STORM DRAIN LINE, SEE DETAIL X/CX.X

— PR PERFORATED PIPE, SEE DETAIL X/CX.X

- SS - PR SANITARY SEWER LINE, SEE DETAIL X/CX.X

FW PR FIRE WATER LINE, SEE DETAIL X/CX.X

---- w ---- PR DOMESTIC WATER LINE, SEE DETAIL X/CX.X

DDI
PR STORM DRAIN DROP INLET, SEE DETAIL X/CX.X

DAD O PR AREA DRAIN, SEE DETAIL X/CX.X

MH PR STORM DRAIN MANHOLE, SEE DETAIL X/CX.X

SDCO PR STORM DRAIN CLEANOUT, SEE DETAIL X/CX.X

SSCO PR STORM DRAIN CLEANOUT, SEE DETAIL X/CX.X

SSMH PR SANITARY SEWER MANHOLE, SEE DETAIL X/CX.X

BFV► PR BACKWATER VALVE, SEE DETAIL X/CX.X

WV⊗ PR GATE VALVE, SEE DETAIL X/CX.X

PR WATER METER, SEE DETAIL X/CX.X

RPPA NO PR RPPA BACKFLOW PREVENTER, SEE DETAIL X/CX.X

DCDA DE PR DCDA BACKFLOW PREVENTER, SEE DETAIL X/CX.X


FDC PR FIRE DEPARTMENT CONNECTION, SEE DETAIL X/CX.X

PR POST INDICATOR VALVE, SEE DETAIL X/CX.X

FH+●+ PR FIRE HYDRANT, SEE DETAIL X/CX.X

UTILITY NOTES

- 1. PROPOSED SITE PLAN HAS BEEN SCREENED FOR CLARITY.
- 2. RIM ELEVATIONS FOR EXISTING UTILITY STRUCTURES SHALL BE RAISED TO PROPOSED SURFACE ELEVATIONS. EXISTING STRUCTURES LOCATED WITHIN PROPOSED VEHICULAR ROADWAY, AN H-20 TRAFFIC-RATED TOP SHALL BE USED TO REPLACE THE EXISTING TOP OF THE ADJUSTED STRUCTURE.
- 3. PROTECT ALL EXISTING UTILITIES AND SITE FEATURES FROM BEING DAMAGED, UNLESS OTHERWISE NOTED. ALL UTILITIES AND IMPROVEMENTS THAT BECOME DAMAGED DURING CONSTRUCTION SHALL BE COMPLETELY RESTORED AT NO ADDITIONAL COST TO THE OWNER AND TO THE SATISFACTION OF THE ENGINEER.
- 4. THE EXISTING UTILITY LINES AND STRUCTURES SHOWN ON THESE PLANS ARE DERIVED FROM RECORD DATA, UNDERGROUND UTILITY SURVEY AND/OR SURFACE OBSERVATION AND ARE APPROXIMATE ONLY. ACTUAL LOCATION AND SIZE, TOGETHER WITH THE PRESENCE OF ANY ADDITIONAL UTILITY LINES AND STRUCTURES NOT SHOWN ON THIS PLAN, SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR DURING CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY UPON DISCOVERY OF ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS IN THE FIELD AND INFORMATION SHOWN ON THESE PLANS.
- 5. THRUST BLOCKS SHALL BE INSTALLED AT ALL BENDS AND TEES ON WATER MAINS & FIRE SERVICE LINES. CONTRACTOR MAY USE RESTRAIN JOINTS INSTEAD OF THRUST BLOCKS AT ALL BENDS AND TEES. CONTRACTOR SHALL BE RESPONSIBLE TO CALCULATE THE RESTRAIN JOINT LENGTH.
- 6. EXISTING UNDERGROUND UTILITIES, INCLUDING THOSE MARKED UNKNOWN, ARE BASED ON SURVEY COMPLETED BY OTHERS AND PROVIDED TO BKF ENGINEERS FOR INCLUSION IN PLANS.
- 7. EXISTING PIPE LINES MAY HAVE CATHODIC PROTECTION. CONTRACTOR SHALL ENSURE THAT ALL CONNECTIONS TO EXISTING PIPE LINES ARE ELECTRICALLY COMMON WITH THE PIPE LINE.
- 8. CONTRACTOR SHALL FIELD VERIFY LOCATION AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO THE START OF CONSTRUCTION.
- 9. LENGTH OF PIPES ARE HORIZONTAL DISTANCES FROM CENTER TO CENTER OF STRUCTURES, ROUNDED TO THE NEAREST FOOT AND ARE SHOWN FOR ENGINEERING CALCULATIONS ONLY. CONTRACTOR SHALL ESTIMATE THEIR OWN PIPE LENGTHS PRIOR TO BIDDING.
- 10. FIRE SERVICE SIZE IS SHOWN FOR REFERENCE ONLY. FIRE SERVICE SIZE SHALL BE CONFIRMED BY A LICENSED FIRE PROTECTION ENGINEER OR DESIGN—BUILD CONTRACTOR IN CONJUNCTION WITH THE FIRE SPRINKLER SYSTEM DESIGN AND CALCULATIONS. CONTRACTOR IS CAUTIONED NOT TO ORDER ANY MATERIALS RELATED TO THE FIRE SERVICE UNTIL SAID SIZING IS CONFIRMED. IF REQUIRED BY THE AUTHORITY HAVING JURISDICTION (AHJ), SHOP DRAWINGS OF THE FIRE SERVICE SHALL BE SUBMITTED TO THE AHJ BY THE INSTALLING CONTRACTOR. SHOP DRAWINGS OF THE FIRE SERVICE ARE NOT REQUIRED TO BE SUBMITTED TO THE CIVIL ENGINEER OF RECORD.
- 11. ALL STORM DRAIN INLETS AND CATCH BASINS SHALL BE LABELED





Consultant:



300 FRANK OGAWA PLAZA SUITE 380 OAKLAND, CA 94612 (510) 899-7300 www.bkf.com

Revisions:

COPYRIGHT © 2021 SWENSON BUILDER

HESTER AND SHELBURN

SITE

PLANNING RESUBMITTAL NOVEMBER 1, 2021

ate: 11/01/21

MIN


Scale: 1" = 20'-0"

Drawn by: AR

Job #: 9215-70-103

Sheet

C-4.1



LEGEND AND SYMBOLS

--- SD --- PR STORM DRAIN LINE, SEE DETAIL X/CX.X

--- PR PERFORATED PIPE, SEE DETAIL X/CX.X

--- SS --- PR SANITARY SEWER LINE, SEE DETAIL X/CX.X

FW PR FIRE WATER LINE, SEE DETAIL X/CX.X

---- w ---- PR DOMESTIC WATER LINE, SEE DETAIL X/CX.X

SDDI PR STORM DRAIN DROP INLET, SEE DETAIL X/CX.X

SDAD OP PR AREA DRAIN, SEE DETAIL X/CX.X

SDMH PR STORM DRAIN MANHOLE, SEE DETAIL X/CX.X

SDCO ● PR STORM DRAIN CLEANOUT, SEE DETAIL X/CX.X

SSCO PR STORM DRAIN CLEANOUT, SEE DETAIL X/CX.X

SSMH PR SANITARY SEWER MANHOLE, SEE DETAIL X/CX.X

BFV► PR BACKWATER VALVE, SEE DETAIL X/CX.X

WV⊗ PR GATE VALVE, SEE DETAIL X/CX.X

M PR WATER METER, SEE DETAIL X/CX.X

RPPA DE PR RPPA BACKFLOW PREVENTER, SEE DETAIL X/CX.X

DCDA DCDA BACKFLOW PREVENTER, SEE DETAIL X/CX.X


PR FIRE DEPARTMENT CONNECTION, SEE DETAIL X/CX.X

PIV PR POST INDICATOR VALVE, SEE DETAIL X/CX.X

FH+●+ PR FIRE HYDRANT, SEE DETAIL X/CX.X

UTILITY NOTES

- 1. PROPOSED SITE PLAN HAS BEEN SCREENED FOR CLARITY.
- 2. RIM ELEVATIONS FOR EXISTING UTILITY STRUCTURES SHALL BE RAISED TO PROPOSED SURFACE ELEVATIONS. EXISTING STRUCTURES LOCATED WITHIN PROPOSED VEHICULAR ROADWAY, AN H-20 TRAFFIC-RATED TOP SHALL BE USED TO REPLACE THE EXISTING TOP OF THE ADJUSTED STRUCTURE.
- 3. PROTECT ALL EXISTING UTILITIES AND SITE FEATURES FROM BEING DAMAGED, UNLESS OTHERWISE NOTED. ALL UTILITIES AND IMPROVEMENTS THAT BECOME DAMAGED DURING CONSTRUCTION SHALL BE COMPLETELY RESTORED AT NO ADDITIONAL COST TO THE OWNER AND TO THE SATISFACTION OF THE ENGINEER.
- 4. THE EXISTING UTILITY LINES AND STRUCTURES SHOWN ON THESE PLANS ARE DERIVED FROM RECORD DATA, UNDERGROUND UTILITY SURVEY AND/OR SURFACE OBSERVATION AND ARE APPROXIMATE ONLY. ACTUAL LOCATION AND SIZE, TOGETHER WITH THE PRESENCE OF ANY ADDITIONAL UTILITY LINES AND STRUCTURES NOT SHOWN ON THIS PLAN, SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR DURING CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY UPON DISCOVERY OF ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS IN THE FIELD AND INFORMATION SHOWN ON THESE PLANS.
- 5. THRUST BLOCKS SHALL BE INSTALLED AT ALL BENDS AND TEES ON WATER MAINS & FIRE SERVICE LINES. CONTRACTOR MAY USE RESTRAIN JOINTS INSTEAD OF THRUST BLOCKS AT ALL BENDS AND TEES. CONTRACTOR SHALL BE RESPONSIBLE TO CALCULATE THE RESTRAIN JOINT LENGTH.
- 6. EXISTING UNDERGROUND UTILITIES, INCLUDING THOSE MARKED UNKNOWN, ARE BASED ON SURVEY COMPLETED BY OTHERS AND PROVIDED TO BKF ENGINEERS FOR INCLUSION IN PLANS.
- 7. EXISTING PIPE LINES MAY HAVE CATHODIC PROTECTION. CONTRACTOR SHALL ENSURE THAT ALL CONNECTIONS TO EXISTING PIPE LINES ARE ELECTRICALLY COMMON WITH THE PIPE LINE.
- 8. CONTRACTOR SHALL FIELD VERIFY LOCATION AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO THE START OF CONSTRUCTION.
- 9. LENGTH OF PIPES ARE HORIZONTAL DISTANCES FROM CENTER TO CENTER OF STRUCTURES, ROUNDED TO THE NEAREST FOOT AND ARE SHOWN FOR ENGINEERING CALCULATIONS ONLY. CONTRACTOR SHALL ESTIMATE THEIR OWN PIPE LENGTHS PRIOR TO BIDDING.
- 10. FIRE SERVICE SIZE IS SHOWN FOR REFERENCE ONLY. FIRE SERVICE SIZE SHALL BE CONFIRMED BY A LICENSED FIRE PROTECTION ENGINEER OR DESIGN—BUILD CONTRACTOR IN CONJUNCTION WITH THE FIRE SPRINKLER SYSTEM DESIGN AND CALCULATIONS. CONTRACTOR IS CAUTIONED NOT TO ORDER ANY MATERIALS RELATED TO THE FIRE SERVICE UNTIL SAID SIZING IS CONFIRMED. IF REQUIRED BY THE AUTHORITY HAVING JURISDICTION (AHJ), SHOP DRAWINGS OF THE FIRE SERVICE SHALL BE SUBMITTED TO THE AHJ BY THE INSTALLING CONTRACTOR. SHOP DRAWINGS OF THE FIRE SERVICE ARE NOT REQUIRED TO BE SUBMITTED TO THE CIVIL ENGINEER OF RECORD.



SWEET San Jose, CA 95112 - (408) 287-0246

Consultant:



300 FRANK OGAWA PLAZA SUITE 380 OAKLAND, CA 94612 (510) 899-7300 www.bkf.com

Revisions:

COPYRIGHT © 2021 SWENSON BUILDER

ED LIVING HELBURN

NCHESTER AND SHEL

PLANNING RESUBMITTAL NOVEMBER 1, 2021

ate: 11/01/21

Scale: 1" = 20'-0"


Drawn by: AR

MIN

Job #: 9215-70-103

heet

C-4.2





Consultant:



Revisions:

www.bkf.com

COPYRIGHT © 2021 SWENSON BUILDER

SSIS

PLANNING RESUBMITTAL NOVEMBER 1, 2021


STORMWATER


11/01/21

1" = 20'-0"

Job #: 9215-70-103

C-5.1





STORM DRAIN INLET PROTECTION

FIBER ROLL




STABILIZED CONSTRUCTION ENTRANCE/EXIT

——×— TREE PROTECTION FENCING

TREES TO BE REMOVED. TREE REMOVAL FOR REFERENCE, SEE ARCHITECTURAL TREE PROTECTION PLAN AND ARBORIST REPORT.

EROSION CONTROL NOTES:

- 1. ALL TREE TO BE PRESERVED SHALL BE PROTECTED WITH MINIMUM 5-FOOT HIGH FENCES. FENCES ARE TO BE MOUNTED ON 2-INCH DIAMETER GALVANIZED IRON POSTS, DRIVEN INTO THE GROUND TO A DEPTH OF AT LEAST 2 FEET, AT NO MORE THAN 10 FOOT SPACING. TREE FENCING SHALL BE ERECTED BEFORE ANY DEMOLITION, GRADING OR CONSTRUCTION BEGINS AND REMAIN IN PLACE UNTIL THE FINAL INSPECTION.
- 2. REFERENCE: "CALIFORNIA STORM WATER BEST MANAGEMENT PRACTICE (BMP) HANDBOOK", LATEST EDITION.
- 3. CONSTRUCTION AREAS SHOWN ARE CONCEPTUAL. ACTUAL PLACEMENT TO BE DETERMINED BY CONTRACTOR BASED ON CURRENT BEST MANAGEMENT PRACTICES. CONTRACTOR SHALL SUBMIT A CONSTRUCTION STAGING PLAN.
- 4. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN EFFECT AND MAINTAINED BY THE CONTRACTOR ON A YEAR-ROUND BASIS UNTIL ALL DISTURBED AREAS ARE STABILIZED UNLESS OTHERWISE PERMITTED BY THE CITY INSPECTOR.
- 5. AS PART OF THE GRADING OPERATIONS, THE CONTRACTOR SHALL ENSURE THAT THE SITE IS WATERED PRIOR TO THE COMMENCEMENT OF GRADING.
- 6. ALL INLETS RECEIVING STORM WATER RUNOFF FROM THE PROJECT AREA MUST BE EQUIPPED WITH REQUIRED INLET PROTECTION.
- 7. ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIALS AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT LADEN RUNOFF ENTERING THE STORM DRAIN SYSTEM.
- 8. ALL CONCRETE SLURRY SHALL BE CONTAINED IN CONCRETE WASH-OUT AREAS DESIGNATED ON-SITE.
- 9. STOCKPILED EARTHEN MATERIAL SHALL BE EITHER COVERED WITH A TARP OR WATERED SUFFICIENTLY TO ELIMINATE DUST.
- 10. TEMPORARY EROSION CONTROLS TO STABILIZE ALL DENUDED AREAS UNTIL PERMANENT EROSION CONTROLS ARE ESTABLISHED.
- 11. DELINEATE WITH FIELD MARKERS CLEARING LIMITS, EASEMENTS, SETBACKS, SENSITIVE OR CRITICAL AREAS, BUFFER ZONES, TREES, AND DRAINAGE
- 12. PERFORM CLEARING AND EARTH MOVING ACTIVITIES ONLY DURING DRY
- 13. USE SEDIMENT CONTROLS OR FILTRATION TO REMOVE SEDIMENT WHEN DEWATERING AND OBTAIN ALL NECESSARY PERMITS.
- 14. PROTECT ALL STORM DRAIN INLETS IN VICINITY OF SITE USING SEDIMENT CONTROLS SUCH AS BERMS, FIBER ROLLS, OR FILTERS.
- 15. TRAP SEDIMENT ON-SITE, USING BMPS SUCH AS SEDIMENT BASINS OR TRAPS, EARTHEN DIKES OR BERMS, SILT FENCES, CHECK DAMS, SOIL BLANKETS OR MATS, COVERS FOR SOIL STOCK PILES, ETC.
- 16. DIVERT ON-SITE RUNOFF AROUND EXPOSED AREAS; DIVERT OFF-SITE RUNOFF AROUND THE SITE (E.G., SWALES AND DIKES).
- 17. PROTECT ADJACENT PROPERTIES AND UNDISTURBED AREAS FROM CONSTRUCTION IMPACTS USING VEGETATIVE BUFFER STRIPS. SEDIMENT BARRIERS OR FILTERS, DIKES, MULCHING, OR OTHER MEASURES AS APPROPRIATE.
- 18. LIMIT CONSTRUCTION ACCESS ROUTES AND STABILIZE DESIGNATED ACCESS
- 19. NO CLEANING, FUELING, OR MAINTAINING VEHICLES ON—SITE, EXCEPT IN A DESIGNATED AREA WHERE WASHWATER IS CONTAINED AND TREATED.
- 20. STORE, HANDLE, AND DISPOSE OF CONSTRUCTION MATERIALS/WASTES PROPERLY TO PREVENT CONTACT WITH STORMWATER.
- 21. CONTRACTOR SHALL TRAIN AND PROVIDE INSTRUCTION TO ALL
- 22. CONTROL AND PREVENT THE DISCHARGE OF ALL POTENTIAL POLLUTANTS, INCLUDING PAVEMENT CUTTING WASTES, PAINTS, CONCRETE, PETROLEUM PRODUCTS, CHEMICALS, WASHWATER OR SEDIMENTS, RINSE WATER FROM ARCHITECTURAL COPPER, AND NON-STORMWATER DISCHARGES TO STORM DRAINS AND WATERCOURSES.
- LOCATION OF CONSTRUCTION ACTIVITIES IS PRELIMINARY AND SHALL BE CSUPERSEDED SHBYL FIRMALDZEDILECONSTRUCTION ATACHIVITYARILGICATIONS, REAM





Consultant:



300 FRANK OGAWA PLAZA SUITE 380 OAKLAND, CA 94612 (510) 899-7300 www.bkf.com

Revisions:

COPYRIGHT © 2021 SWENSON BUILDER

CONTROL SIS **EROSION**

PLANNING RESUBMITTAL NOVEMBER 1, 2021

11/01/21

1" = 20'-0" Scale:

Drawn by: AR

MIN

Job #: 9215-70-103

C-6.1

INTERIM EROSION CONTROL MEASURES (USE AS APPLICABLE TO YOUR PROJECT.)

NOTES:

1. IT IS THE RESPONSIBILITY OF THE OWNER/CONTRACTOR TO INSURE THAT NO MUD OR SILTATION LEAVES THE PROJECT SITE.

- 2. INTERIM EROSION CONTROL MEASURES MUST BE COMPLETED AND IN PLACE BY OCTOBER 1.
- 3. ALL INTERIM EROSION CONTROL MEASURES MUST BE CONTINUOUSLY MAINTAINED THROUGHOUT THE OCTOBER 1 TO APRIL 15 RAINY SEASON.
- 4. CALL THE INSPECTION LINE AT (408) 399-5760 BY SEPTEMBER 15 FOR INSPECTION OF EROSION
- 5. IF EROSION CONTROL MEASURES ARE NOT IN PLACE AS REQUIRED OR NOT MAINTAINED, ALL WORK SHALL CEASE UNTIL EROSION CONTROL MEASURES ARE REMEDIED.

CONTROL DEVICES. CALL 24 HOURS IN ADVANCE. INCLUDE GRADING PERMIT NUMBER.

- MEASURES:
- 1. INSTALL SILT FENCE. PROVIDE DETAIL, SHOW LOCATION ON PLANS AND ADD NOTES AS NEEDED. 2. SEED EXPOSED AREAS PER TOWN SPECIFICATIONS. SEE BELOW.
- 3. INSTALL DRAINAGE MEASURES INCLUDING CATCH BASINS, ENERGY DISSIPATORS, ETC. PROVIDE
- DETAIL, SHOW LOCATIONS ON PLANS, AND ADD NOTES AS NEEDED. 4. INSTALL CHECK DAMS, SEDIMENT TRAPS AND BASINS, TEMPORARY SWALES.
- 5. INSTALL JUTE NETTING OVER SEEDED AND MULCHED SLOPES.
- 6. COVER BARE SLOPES WITH STRAW BLANKETS.

SEEDING SPECIFICATIONS:

- 1. SEED AND MULCH WILL BE APPLIED BY OCT 1 TO ALL DISTURBED SLOPES AND TO ALL CUTS AND FILL SLOPES WITHIN OR ADJACENT TO PUBLIC RIGHTS-OF-WAY AS DIRECTED BY TOWN ENGINEER.
- 2. SEED AND FERTILIZER WILL BE APPLIED HYDRAULICALLY OR BY HAND AT THE RATES SPECIFIED BELOW. ON SLOPES, STRAW WILL BE APPLIED BY BLOWER OR BY HAND AND ANCHORED IN PLACE BY PUNCHING OR WITH JUTE NETTING.

ITEM	POUNDS/ACRE
"Blando" brome	30
Annual rye grass	20
Fertilizer (16-20-0 & 15% sulfur)	500
Straw	4,000

3. SEEDED AREAS WILL BE REPAIRED, RESEEDED AND MULCHED, IF DAMAGED.

LENGTH OF CRUSHED ROCK

APPROVED BY	DATE		INTERIM EROSION CONTROL NOTES	STD. PLAN NO.
	JUNE 2004			255
TOWN ENGINEER				200

APPROVED BY **TEMPORARY** JUNE 2004 STOCKPILE COVER TOWN ENGINEER

N.T.S.

STOCKPILE COVER


OVERLAP

SWALE OR BERM

TO DIVERT SHEET


FABRIC 2' (TYP) ___

FABRIC



— ROPE

WEDGE LOOSE STRAW BETWEEN BALES STRAW BALES 12 MIL PLASTIC REUSABLE ROUGH WOODEN FRAME WEIGHT IN CORNERS <u>PLAN</u> 2 WOODEN STAKES OR REBAR PER -BALE (TYP) 12 MIL PLASTIC LINING STAPLE AS REQUIRED BALES (BEYOND) ROUGH WOODEN BINDING WIRE STRAW BALES (2) ASPHAL1 ► WEIGHT IN CORNERS NATIVE MATERIAL SECTION A-A TEMPORARY STD. PLAN NO APPROVED BY CONCRETE WASHOUT JUNE 2004 FACILITY TOWN ENGINEER



TEMPORARY CONCRETE WASHOUT FACILITY

N.T.S.



N.T.S.

 $-\times-\times-$

1. FOR USE IN AREAS WHERE GRADING HAS BEEN COMPLETED AND FINAL SOIL STABILIZATION

AND SEEDING ARE PENDING SHAPE BASIN SO THAT LONGEST INFLOW AREA FACES LONGEST

- SILT FENCE PER SE-01

— GEOTEXTILE BLANKET

SECTION A-A

SHEET FLOW LESS THAN 1 ACRE

LENGTH OF TRAP

2. NOT APPLICABLE IN PAVED AREAS

3. NOT APPLICABLE WITH CONCENTRATED FLOWS

- DRAIN INLET

GEOTEXTILE BLANKET

6' MIN OVERLAP AT ENDS OF SILT FENCE

- SILT FENCE PER SE-01

INTERIM EROSION CONTROL NOTES


ATB







NOT TO SCALE



(A) 4" CRUSHED ROCK WITH GEOTEXTILE MATERIAL UNDERNEATH.


© ATB DRIVEWAY RAMP, OR SITE ACCESS ROAD 20' WIDE MIN. SEE TABLE ABOVE FOR REQUIRED


D INSTALL ORANGE BARRIER FENCE TO DIRECT TRAFFIC ONTO CONSTRUCTION ENTRANCE © INSTALL 12" MIN. DIA. CULVERT IF A ROADSIDE DITCH IS PRESENT.


NOTES:

4 PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

APPROVED BY	DATE	STABILIZED	STD. PLAN N
	JUNE 2004	CONSTRUCTION	250
TOWN ENGINEER		ENTRANCE	250







STRAW ROLL N.T.S.

JUNE 2004

TOWN ENGINEER

STRAW ROLL

SILT FENCE



Consultant:



Revisions:

(510) 899-7300

www.bkf.com

COPYRIGHT © 2021 SWENSON BUILDER

SSIS

PLANNING RESUBMITTAL NOVEMBER 1, 2021

EROSION

11/01/21


1" = 20'-0"

Drawn by: AR Job #: 9215-70-103

Sheet

C-6.2

Pollution Prevention — It's Part of the Plan



Make sure your crews and subs do the job right!

Runoff from streets and other paved areas is a major source of pollution in San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep dirt, debris, and other construction waste away from storm drains and local creeks. Following these guidelines will ensure your compliance with local ordinance requirements.



Materials storage & spill cleanup

Non-hazardous materials management

- ✓ Sand, dirt, and similar materials must be stored at least 10 feet from catch basins, and covered with a tarp during wet weather or when rain is forecast
- ✓ Use (but don't overuse) reclaimed water for dust control as needed.
- ✓ Sweep streets and other paved areas daily. Do not wash down streets or work areas with water!
- ✓ Recycle all asphalt, concrete, and aggregate base material from demolition activities.
- ✓ Check dumpsters regularly for leaks and to make sure they don't overflow. Repair or replace leaking dumpsters promptly.

Hazardous materials management

- ✓ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, state, and federal regulations.
- ✓ Store hazardous materials and wastes in secondary containment and cover them during wet weather.
- ✓ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ✔ Be sure to arrange for appropriate disposal of all hazardous wastes.

Spill prevention and control

- ✓ Keep a stockpile of spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- ✓ When spills or leaks occur, contain them immediately and be particularly careful to prevent leaks and spills from reaching the gutter, street, or storm drain. Never wash spilled material into a gutter, street, storm drain, or creek!
- ✓ Report any hazardous materials spills immediately! Dial 911 or your local emergency response number.

Vehicle and equipment maintenance & cleaning

- ✓ Inspect vehicles and equipment for leaks frequently. Use drip pans to catch leaks until repairs are made; repair leaks
- Fuel and maintain vehicles on site only in a bermed area or over a drip pan that is big enough to prevent runoff.
- ✓ If you must clean vehicles or equipment on site, clean with water only in a bermed area that will not allow rinsewater to run into gutters, streets, storm drains, or creeks.
- ✓ Do not clean vehicles or equipment on-site using soaps, solvents, degreasers, steam cleaning equipment, etc.

Earthwork & contaminated soils

- ✓ Keep excavated soil on the site where it is least likely to collect in the street. Transfer to dump trucks should take place on the site, not in the street.
- ✓ Use hay bales, silt fences, or other control measures to minimize the flow of silt off the site.



- ✓ Avoid scheduling earth moving activities during the rainy season if possible. If grading activities during wet weather are allowed in your permit, be sure to implement all control measures necessary to prevent erosion.
- Mature vegetation is the best form of erosion control. Minimize disturbance to existing vegetation whenever possible.
- If you disturb a slope during construction, prevent erosion by securing the soil with erosion control fabric, or seed with fastgrowing grasses as soon as possible. Place hay bales down-slope until soil is secure.
- ✓ If you suspect contamination (from site history, discoloration, odor, texture, abandoned underground tanks or pipes, or buried debris), call your local fire department for help in determining what testing should be done.
- Manage disposal of contaminated soil according to Fire Department instructions.

Dewatering operations

- ✓ Reuse water for dust control, irrigation, or another on-site purpose to the greatest extent possible.
- ✓ Be sure to call your city's storm drain inspector before discharging water to a street, gutter, or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ✓ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the city inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal

Saw cutting

- ✓ Always completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, hay bales, sand bags, or fine gravel dams to keep slurry out of the storm drain system.
- ✓ Shovel, absorb, or vacuum saw-cut slurry and pick up all waste as soon as you are finished in one location or at the end of each work day (whichever is
- ✓ If saw cut slurry enters a catch basin, clean it up immediately.

Paving/asphalt work



- ✓ Do not pave during wet weather or when rain is forecast.
- Always cover storm drain inlets and manholes when paving or applying seal coat, tack coat, slurry seal, or fog seal.
- ✓ Place drip pans or absorbent material under paving equipment when not in use.
- Protect gutters, ditches, and drainage courses with hay bales, sand bags, or earthen berms.
- ✓ Do not sweep or wash down excess sand from sand sealing into gutters, storm drains, or creeks. Collect sand and return it to the stockpile, or dispose of it as trash.
- ✓ Do not use water to wash down fresh asphalt concrete pavement.

Concrete, grout, and mortar storage & waste disposal

- Be sure to store concrete, grout, and mortar under cover and away from drainage areas. These materials must never reach a
- ✓ Wash out concrete equipment/trucks off-site or designate an on-site area for washing where water will flow onto dirt or into a temporary pit in a dirt area. Let the water seep into the soil and dispose of hardened concrete with trash.



- ✓ Divert water from washing exposed aggregate concrete to a dirt area where it will not run into a gutter, street, or storm drain.
- If a suitable dirt area is not available, collect the wash water and remove it for appropriate disposal off site.

Painting

- ✓ Never rinse paint brushes or materials in a gutter or street!
- ✓ Paint out excess water-based paint before rinsing brushes, rollers, or containers in a sink If you can't use a sink, direct wash water to a dirt area and spade it in.



- ✓ Paint out excess oil-based paint before cleaning brushes in thinner.
- Filter paint thinners and solvents for reuse whenever possible. Dispose of oil-based paint sludge and unusable thinner as hazardous waste.

Consultant:



Revisions:

COPYRIGHT © 2021

ASSISTED

WINCHESTER

VENTION SHEL] PRE

PLANNING RESUBMITTAL **NOVEMBER 1, 2021**


11/01/21

1" = 20'-0"


9215-70-103

Drawn by: AR

C-6.3



Storm drain polluters may be liable for fines of up to \$10,000 per day!



Consultant:

DILLON DESIGN ASSOCIATES LANDSCAPE ARCHITECTURE 849 ALMAR AVE #C-162 SANTA CRUZ CA 95060 E-MAIL ddastudio@ddasite.com (831) 420-1648 URBAN DESIGN

SITE PLANNING GREEN BUILDING

Revisions:

COPYRIGHT © 2020


SWENSON BUILDER

H LIVINC SSISTED

WINCHESTER

WINCHESTER

SEE SHT LS-4.0 FOR PLANTER / POT, IRR1GATION & PLANTING LEGENDS SEE SHT LS-5.0 & LS-6.0 FOR MATERIAL & PLANTING IMAGES



02/28/21

AS SHOWN


Drawn by: MBD

Sheet LS-1.0


SITE LEGEND

SYMBOL

DESCRIPTION



PROPOSED PODIUM & GROUND SCAPE EQUIPMENT 4.1



PROPOSED BENCHES, TABLES & BARBEQUE 4.0 COUNTER TOP.






PROPOSED CONCRETE PAVING / PAVER STONES PROPOSED PERVIOUS CONCRETÉ PAVING / PAVERS, SEE


PROPOSED TUFF-TURF PLAY AREA RESILIENT SURFACE 3.1



PROPOSED STEEL FENCING / GATES TO MATCH ARCH. RAIING 2.1 PROPOSED GOOD NEIGHBOR FENCE @ PL TYP.



POTS & CMU PODIUM PLANTERS W/ DRAINS 2.2





CIVIL PLANS FOR LOCATIONS

SITE SCHEDULE

1.0 HARDSCAPE & PLANTING

PROVIDE ACCESSIBLE PATH OF TRAVEL FROM COMMON AREAS TO STREET SCAPE AREAS. PROVIDE PATH TO PODIUM AREAS, TRASH ENCLOSURES & MAILBOXES. SEE ARCH & CIVIL

1.1 PROVIDE PLANTING & IRRIGATION

2.0 STRUCTURES & FENCING

2.0 PROVIDE FLOW THROUGH PLANTER. SCD

2.1 PROVIDE FENCING / GATES. SEE ARCH & CIVIL

2.2 PROVIDE TREE GRATES, POTS & PLANTERS

3.0 AMENITY EQUIPMENT

3.0 PROVIDE ACCESSIBLE EQUIPMENT

3.1 PROVIDE RECREATIONAL TUFF TURF AREA

3.2 PROVIDE LANDSCAPE LIGHTING

4.0 SITE FURNISHING

[4.0] PROVIDE ACCESSIBLE BENCH, TABLES & BARBEQUE GRILLS & TRASH RECEPTICLES

4.1 BIKE RACKS & SURF RACKS

SEE SHT LS-4.0 FOR LIGHTES / POTS, IRR1GATION & PLANTING LEGENDS SEE SHT LS-5.0 & LS-6.0 FOR MATERIAL & PLANTING IMAGES



Consultant:



DILLON DESIGN ASSOCIATES LANDSCAPE ARCHITECTURE 849 ALMAR AVE #C-162 SANTA CRUZ CA 95060 E-MAIL ddastudio@ddasite.com (831) 420-1648 URBAN DESIGN SITE PLANNING

GREEN BUILDING

Revisions:

COPYRIGHT © 2020 SWENSON BUILDER

LIVING

ASSISTED

SHELBURN ANDSC, SCHEMATIC WINCHESTER

WINCHESTER EXPIRES 04/30/24


02/28/21

AS SHOWN

Drawn by: MBD

Job #:


Sheet LS-2.0




SITE LEGEND

SYMBOL


DESCRIPTION




PROPOSED PODIUM & GROUND SCAPE EQUIPMENT 4.1



PROPOSED BENCHES, TABLES & BARBEQUE 4.0 COUNTER TOP.




PROPOSED TUFF-TURF PLAY AREA RESILIENT SURFACE 3.1




PROPOSED CONCRETE PAVING / PAVER STONES PROPOSED PERVIOUS CONCRETE PAVING / PAVERS, SEE CIVIL PLANS FOR LOCATIONS




PROPOSED STEEL FENCING / GATES TO MATCH ARCH. RAIING 2.1 PROPOSED GOOD NEIGHBOR FENCE @ PL TYP.



POTS & CMU PODIUM PLANTERS W/ DRAINS 2.2





PROPOSED FLOW THROUGH & PLANTING AREAS 1.1

SITE SCHEDULE

1.0 HARDSCAPE & PLANTING

PROVIDE ACCESSIBLE PATH OF TRAVEL FROM COMMON AREAS TO STREET SCAPE AREAS. PROVIDE PATH TO PODIUM AREAS, TRASH ENCLOSURES & MAILBOXES. SEE ARCH & CIVIL

1.1 PROVIDE PLANTING & IRRIGATION

2.0 STRUCTURES & FENCING

2.0 PROVIDE FLOW THROUGH PLANTER. SCD

2.1 PROVIDE FENCING / GATES. SEE ARCH & CIVIL

2.2 PROVIDE TREE GRATES, POTS & PLANTERS

3.0 AMENITY EQUIPMENT

3.0 PROVIDE ACCESSIBLE EQUIPMENT

3.1 PROVIDE RECREATIONAL TUFF TURF AREA

3.2 PROVIDE LANDSCAPE LIGHTING

4.0 SITE FURNISHING

4.0 PROVIDE ACCESSIBLE BENCH, TABLES & BARBEQUE GRILLS & TRASH RECEPTICLES

4.1 BIKE RACKS & SURF RACKS

SEE SHT LS-4.0 FOR LIGHTES / POTS, IRR1GATION & PLANTING LEGENDS SEE SHT LS-5.0 & LS-6.0 FOR MATERIAL & PLANTING IMAGES

Consultant: DILLON DESIGN ASSOCIATES LANDSCAPE ARCHITECTURE 849 ALMAR AVE #C-162 SANTA CRUZ CA 95060 E-MAIL ddastudio@ddasite.com (831) 420-1648 URBAN DESIGN SITE PLANNING GREEN BUILDING

Revisions:

COPYRIGHT © 2020

SWENSON BUILDER LIVING

ASSISTED

WINCHESTER

WINCHESTER

02/28/21

AS SHOWN

Drawn by: MBD

Sheet

LS-3.0

IRRIGATION LEGEND

SYM.	MANUFAC.	MODEL NO.	DESCRIPTION PSI RAD./SPAC GPM
• 0.50	RAINBIRD	NEW 1400 SERIES ADJ. FULL	BUBBLERS - INSTALL IN WATER 18" DEEP TUBES 15 GAL 2-0.5 GPM SIZE & ADJUST AS NEEDED @ 40 PSI TYP. 24" BX 2-0.5 GPM
	RAINBIRD SDI 6" UNDER SOIL & MULCH, 3" UNDER SOD	XFS-06-12	LAWN TUBING W/ 12" OC @ 0.6 GPH & 12" ROW SPACING 20 psi @ 0.6 gph GRND COVER TUBING W/ 12" OC @ 0.6 GPH & 18" ROW SPACING INSTALL PER MANUFACTURERS SPECIFICATIONS. SEE TYP DETAILS. CONTRACTOR TO DESIGN BUILD SSI-LINE, VALVE & LATERAL SYSTEM W/ MANF'R REP.
	HUNTER ECO-MAT SDI 4" UNDER SOIL	PLD TUBING - 14" w/ check valveS	DRIPPER TUBING W/ 14" OC @ .6 GPH @ 14" ROW SPACING 20 psi @ 0.6 gph install per manufacturers specifications. See typ details. CONTRACTOR TO DESIGN BUILD SDI-LINE, VALVE & LATERAL SYSTEM W/ MANF'R REP.
•	RAINBIRD	XCZ-LF-100-PRB	REMOTE CONTROL VALVE -SIZE AS NOTED © SDI VALVES USE LOW FLOW XCZ-LF-100-PRB-COM W/ 1 QUICK CHECK BASKET FILTERS & POP-UP SDI OPERATION INDICATORS
H	NIBCO		LINE SIZED GATE VALVE
	WILKINS	(E)-2" SIZE	PRESSURE BACKFLOW PREVENTER W/ PRESSURE REG. & FROST BLANKET SEE PLUMBING DRAWINGS FOR LOCATION ON WALL INSTALLATION
	RAINBIRD	33DNP	3/4" QUICK COUPLER VALVES FOR MAINTENANCE
	PVC & COPPER	1 1/2" MAIN	SCH 40 AS NEEDED IN BULG & @ GRADE, SPD
	PVC & COPPER	LATERAL LINE	LATERAL LINE - 3/4" MIN. SIZE COPPER & SCH 40 PVC TYPICAL SEE PLUMBING PLAN FOR BUILDING PENETRATIONS ETC.
	RAINBIRD CONTROL WIRE	FLOW SENSOR & VALVES	RUN WIRE FOR C1 UNDER WALKS & IN PLANTERS IN 1" SCH 80 CONDUIT USE METAL CONDUIT INTO BLDG TO CONNECT TO CONTROLLER
	PW PIPE OR =	_	CLASS 315 PVC SLEEVE -2" LARGER THAN PIPE RUNNING THROUGH IT
С	RAINBIRD 18	ESP-LXMEF W/ ESP-LXMSM18 ETC-LX-ET ETM-RMK & RG	INSTALL ET MANAGER & FLOW SENSOR @ MASTER VALVE MODULES INSTALL MOISTURE SENSOR CARTRIDGE RUM TO LAWN / STATION 10 RUN WIRE TO FLOW SENSOR, MASTER VALVE & RAIN GAUGE
W	WATER METER	1 1/2" SIZE	VERIFY W/ WATER DEPARTMENT SIZE & STATIC PRESSURE @ (E)
S	RAINBIRD FLOW SENSOR	FS100B	1" FLOW SENSOR W/ MASTER VALVE, CLOSED 2 GPM SENSOR MINIMUM MAY REQUIRE 2 STATIONS RUN COMBINATION
M	RAINBIRD	1" BRASS	MASTER VALVE, OPRN
POC	CONNECTION	WATER METER	SEE BACKFLOW DEVICE FOR PRESSURE REGULATOR

MWELO / AB 1881 IRRIGATION PLAN NOTES:

- 1. LANDSCAPE MAINTENANCE IRRIGATION TO BE INSPECTED AS FOLLOWS:
- A) APRIL OCTOBER, WEEKLY & NOVEMBER MARCH, MONTHLY.
- B) TWICE A YEAR AT A MINIMUM FOR INSPECTING HEADS, FILTERS & VALVES. 2. PLANT ESTABLISHMENT PERIOD TO BE 1 YEAR WHICH INCLUDES APRIL — OCTOBER.
- 3. IRRIGATION SCHEDULE (BY AUDITOR) SHALL CONSIDER EACH OF THE FOLLOWING:
- A) IRRIGATION INTERVAL & RUN TIMES. B) NUMBER OF CYCLES, ESPECIALLY FOR BUBBLERS, TO AVOID RUNOFF
- C) AMOUNT OF APPLIED WATER SCHEDULED TO BE APPLIED PER MONTH.
-) APPLICATION RATE STTINGS E) ROOT DEPTH SETTINGS TO BE VERIFIED AS 12" FOR SMALL SHRUBS & 24" FOR TREES. F) PLANT TYPE VIA HYDROZONE SETTINGS IE SHADE (NORTH) & WIND (NORTH WEST)
- G) SOIL ANALYSIS AND AMENDED SOIL TYPE SETTINGS.
- H) IRRIGATION UNIFORMITY FOR BUBBLERS PER PLANT CONTAINER SIZE & STATURE. 4. IRRIGATION SCHEDULE TO INCLUDE NON PEAK TIMES VERIFY BETWEEN 11 PM & 3 AM
- 5. VERIFY WEATHER SENSOR IS AUTOMATICALLY INTEGRATED WITH CONTROLLERS.

PLANTER / POT LEGEND — MEDITERREAN (MT)

ŀ	KEY	PRODUCT NAME	DESCRIPTION		Length	Width	Heigth	Quan.
	1	MT ROUND	COLOR TERRA 10, GLOSS FINISH COLOR , ORANGE PEEL FINISH*					
	2	MT RECTANGULAR	FIRST FLOOR / COURTYARD COLOR TERRA 10, GLOSS FINISH					
	3	MT RECTANGULAR	FIRST FLOOR / COURTYARD COLOR TERRA 10, GLOSS FINISH					
	4	MT RECTANGULAR	FIRST FLOOR / COURTYARD COLOR TERRA 10, GLOSS FINISH					


- NOTE: SPACING BETWEEN ADJACENT PLANTERS TO BE 6" TYP. OR AS APPROVED PRIOR TO FILLING. SUBMIT SAMPLE OF FINISHES TO MATCH ADJACENT ARCHITECTURAL FEATURES
- ALL PLANTERS TO BE MANUFACTURED AND SUPPLIED BY:
- OLD TOWN FIBERGLASS, INC.
- 767 NORTH HARITON STREET ORANGE, CA 92868 OLDTOWNFIBERGLASS.COM (714) 633-3732
- PLANTER SOIL MIX TO BE AS SPECIFIED FOR TREES & SHRUBS AS FOLLOWS: USE TMT 'TERRA VIDA LIVING SOIL' MIX FROM GRADE TO 18" DEPTH.
- USE TMT PLANTER SOIL BASE MEDIA MIX FROM 18" DEPTH TO BOTTOM OF PLANTER.
- TMT ENTERPRISES, INC., 1996 OAKLAND ROAD, SAN JOSE, CA 95131 (408) 432-0429 ALL CONTAINERS TO BE COMPACTED W/ SOIL MIX PER IRRIGATION DRAÎNAGE & WP DETAILS


PLANT LEGEND (options) - NATURALIZED AREAS (OAK WOODLAND & MIXED EVERGREEN FOREST PLANT COMMUNITIES)


										,
	SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QUAN	WUCOLS ZONE	NATIVE PLANT	DROUGHT TOLERANT	INVASIVE SPECIES	NOTES
THE WHITE IT HE	TREES									
	AES CAL	AESCULUS californica	CALIFORNIA BUCKEYE	24" BX	Х	VL	Υ	Υ	N	SUN TO PT SUN, SPRING BLOOM 20-40' X 30', STRESS DECIDUOUS
	QUE AGR	QUERCUS agrifolia, Standard	COAST LIVE OAK	48" BX 60" BX	X	VL	Υ	Υ	N	SUN, WIND RESISTANT 50' X 60', EVERGREEN
	SEQ SEM	SEQUOIA sempervirens 'Aptos Blue'	COAST REDWOOD	36" BX	Х	Н	Υ	N	N	SUN TO PT SUN, WIND BREAK 70-100' X 15-20', EVERGREEN
	SMALL TREES & SHRUBS									
	ARC DEN	ARCTOSTAPHYLOS d. 'H. McMinn'	HOWARD MCMINN MANZANITA	15 GAL	Х	L	Υ	Υ	N	SUN, SCREEN 7-10' x 7-10', EVERGREEN, CLAY OK
	CEA RAY	CEANOTHUS 'Ray Hartman' multi	RAY HARTMAN CEANOTHUS	24" BX	Х	L	Υ	Y	N	SUN TO PT SHADE, SPRING BLOOM 15' X 12', EVERGREEN, CLAY OK
	CER OCC	CERCIS occidentalis multi	WESTERN REDBUD	24" BX	Х	VL	Υ	Y	N	SUN TO PT SUN, SPRING BLOOM 15' X 10', DECIDUOUS, CLAY
	HET ARB	HETEROMELES arbutifolia	TOYON	15 GAL	Х	VL	Υ	Υ	N	SUN/PT SHADE, SCREEN 15'x 10', EVERGREEN, CLAY
	RHA CAL	RHAMNUS californica	COFFEEBERRY	15 GAL	X	L	Υ	Υ	N	SUN TO PT SHADE 8' x 8', EVERGREEN, CLAY
	GROUNDCOVER & BIORETENTION									
	ACH MIL	ACHILLEA millefolium White	COMMON YARROW	1 GAL	Х	L	Y	Y	N	SUN 2' x 3', EVERGREEN
	JUN PAT	JUNCUS patens 'Elk Blue'	ELK BLUE CALIFORNIA RUSH	1 GAL	Х	L	Υ	Υ	N	SUN TO PT SHADE 2' X 2'
	POL MUN	POLYSTICHUM munitum	WESTERN SWORD FERN	5 GAL	Х	М	Υ	Υ	N	SHADE, UNDER REDWOOD 4' x 3', EVERGREEN
24142 24142	BIO RET	BIORETENTION PLANTING IRIS douglasiana JUNCUS patens 'Elk Blue' BOUTELOUA gracilis DESCHAMPSIA cespitosa MUHLENBERGIA rigens	DOUGLAS IRIS ELK BLUE CALIFORNIA RUSH BLUE GRAMA GRASS TURFED HAIR GRASS DEERGRASS	4" POT MIN.	X	L	Y	Y	N	NO MULCH TO BE PLACED IN BIORETENTION AREA BIORETENTION SOD W/ DELTA BLUEGRASS
عللد		MIMULUS aurantiacus MIMULUS cardinalis PENSTEMON spp.	COMMON MONKEYFLOWER SCARLET MONKEYFLOWER BEARDED TONGUE		7"					WOON DECYCLING (074) 470 7057
عللد	MULCH	MULCH (IN ALL PLANTERS EXCEPT BIORETENTION AREA)	PREMIUM MULCH DK BROWN		3" DEPTH					VISION RECYCLING (831) 479-7857 USE JUTE MESH UNDER MULCH @ > 4:1


PLANT LEGEND - DEVELOPED AREAS (PROJECT ENTRY & COURTYARDS)

				_						
	SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QUAN	WUCOLS	NATIVE PLANT	DROUGHT	INVASIVE SPECIES	NOTES
	TREES									
	ACE PAL	ACER palmatum 'Aoyagi'	AOYAGI JAPANESE MAPLE	24" BX	Х	М	N	N	N	FULL TO PT SUN, FALL COLOR 10' X 8', DECIDUOUS, ADD SANGOKAKU
	ACE RUB	ACER rubrum 'Armstrong'	ARMSTRONG RED MAPLE	48" BX	Х	М	N	N	N	FULL SUN TO PT, SHADE, FALL COLOR 50-60' X 15-25', DECIDUOUS
	BET NIG	BETULA nigra 'Little King'	RIVER BIRCH DWARF	15 GAL	Х	Н	N	N	N	PART TO FULL SUN 10' X 8', DECIDUOUS
, }	COR FLO	CORNUS florida 'Rubra'	RUBRA DOGWOOD	36" BX	Х	М	N	N	N	SHADE 25' X 20', DECIDUOUS
<i>ک</i> ر	PLA ACE	PLATANUS acerifolia 'Columbia'	LONDON PLANE TREE	24" BX	Х	L	N	Y	N	SUN TO PT SUN 40' X 30', DECIDUOUS
	SHRUBS, PERENNIALS, VINES									
	DIS BUC	DISTICTUS buccinatoria	BLOOD RED TRUMPET VINE	5 GAL	Х	М	N	Υ	N	SUN TO PT SUN 25', EVERGREEN
~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~	FIC PUM	FICUS pumila	CREEPING FIG	5 GAL	Х	М	N	Υ	N	SUN TO PT SUN 25', EVERGREEN
	LOR PET	LOROPETALUM chinense 'Suzanne'	SUZANNE FRINGE FLOWER	5 GAL	Х	L	N	Y	N	PT SUN TO SHADE 3-4 X 3-4, EVERGREEN
	NAN DOM	NANDINA domestica 'Gulf Stream'	DWARF HEAVENLY BAMBOO	5 GAL	Х	L	N	Y	N	PT SUN 3 1/2' X 3', EVERGREEN
	PAR TRI	PARTHENOCISSUS tricuspidata	BOSTON IVY	5 GAL	Х	L	N	Y	N	PT SUN TO PT SHADE 30' LONG, DECIDUOUS
	POL MUN	POLYSTICHUM munitum	WESTERN SWORD FERN	5 GAL	Х	М	Υ	Y	N	SHADE, UNDER REDWOOD 4' x 3', EVERGREEN
	RHO SNE	RHODODENDRON x 'Sneezy'	RHODODENDRON	5 GAL	Х	М	N	Y	N	PT SHADE TO FULL SHADE 4' x 4', EVERGREEN
	RIB SAN	RIBES sanguineum glutinosum	PINK FLOWERING CURRANT	5 GAL	Х	L	Y	Y	N	PT SUN TO SHADE 5' X 4', DECIDUOUS
	ROS NOA	ROSA x 'Noaschnee'	WHITE GROUNDCOVER ROSE	1 GAL	Х	М	N	N	N	SUN 2' X 3', EVERGREEN
	TRA JAS	TRACHELOSPERMUM jasminoides	STAR JASMINE	5 GAL	Х	М	N	Υ	N	PT SUN TO PT SHADE 4' X 4', EVERGREEN
	WOO FIM	WOODWARDIA fimbriata	GIANT CHAIN FERN	5 GAL	Χ	М	Υ	Y	N	PT SUN TO DEEP SHADE 4-5' X 3'
, A A A A A A	GROUNDCOVER & BIOSWALE									
~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~	HEU MIC	HEUCHERA micrantha	CREVICE ALUMROOT	1 GAL	Χ	М	Υ	Υ	N	PT SUN TO SHADE, LOW H20 IN SHADE 1-2' X 3'
	{ IRI DOU }	IRIS douglasiana	DOUGLAS IRIS	1 GAL	Х	L	Υ	Υ	N	SUN TO PT SUN 2' X 2'
	RIB VIB	RIBES viburnifolium	CATALINA CURRANT	1 GAL	Χ	L	Υ	Y	N	SHADE, UNDER OAKS 3 X 5, EVERGREEN
	SEM TEC	SEMPERVIVUM 'Hardy Mix'	HARDY MIX HENS & CHICKS	FLAT	Χ	L	N	Y	N	SUN TO PT SHADE 2"-5", EVERGREEN
'	CAR TUM	CAREX tumulicola	FOOTHILL SEDGE	1 GAL	Χ	L	Υ	Y	N	SUN/PT SHADE 1-2 X 1-2
, A	* * \$ \$ OD	SOD RECREATIONAL TURF GRASS	90% - 10% TALL FESQUE W/ 10% BLUE GRASS	SOD	Χ	Н	N	N	N	SHADE TOLERANT BY DELTA BLUEGRASS
22 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	MULCH	MULCH (IN ALL PLANTERS EXCEPT BIORETENTION AREA)	PREMIUM MULCH DK BROWN	3" DEPTH						VISION RECYCLING (831) 479-7857 USE JUTE MESH UNDER MULCH @ > 4:1









LED BOLLARD LIGHT

SEE SHT LS-5.0 & LS-6.0 FOR MATERIAL & PLANTING IMAGES

Consultant:



LANDSCAPE ARCHITECTURE 849 ALMAR AVE #C-162 SANTA CRUZ CA 95060 E-MAIL ddastudio@ddasite.com (831) 420-1648 URBAN DESIGN SITE PLANNING

GREEN BUILDING

Revisions:

COPYRIGHT © 2020 SWENSON BUILDER

> NIN STED TER

EXPIRES 04/30/24

WINCHE

02/28/21 AS SHOWN

Drawn by: MBD

LS-4.0


LS-5.0

















Spaces for Active Recreation



Indoor-Outdoor Connection




- Provide spaces for resident physical activity.
- Bring Nature into the space for resident mental health & well-being.



DESIGN CONCEPT










Spaces for Quiet Contemplation

- Create strong indoor-outdoor connections to encourage residents to use & enjoy community spaces.
- Create a hierarchy of spaces for public, semi-public & private use experiences.






Revisions:

WINCHESTER





Drawn by: MBD

LS-6.0





JUNCUS, IRUS & CARIX



ARBUTUS 'MARINA'



CERCIS CANADENSIS





LAGERSTROEMIA INDICA



PYRUS CALLERYANA 'CHANTICLEER PEAR'



ITALIAN CYPRESS



LANTANA

QUERCUS AGRIFOLIA — EXISTING OAKS



Bio Retention and Flow through Planters



AGAVE & FLAX



WISTERIA VINE







BOSTON IVY VINE


Familiar Plant Species of Regional Significance


Create strong indoor-outdoor connections to encourage residents to use & enjoy community spaces.


Bring Nature into the space for resident mental health & well-being. **DESIGN CONCEPT**











3 SHADOW STUDY - JUNE 21 - 3PM 1" = 50'-0"

COPYRIGHT © 2022

Consultant:

Revisions:


SWENSON BUILDER


Revision Schedule

Planning Response #1 07/20/21

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

A-1.4







4 SHADOW STUDY - DECEMBER 21 - 9AM 1" = 50'-0"

WINCHESTER BLVD.

(E) MEDICAL OFFICE
-1 STORY
15861 WINCHESTER BLVD.,
LOS GATOS, CA 95030

LOS GATOS, CA 95030

1 SHADOW STUDY - JUNE 21 - 9AM 1" = 50'-0"

z

5 SHADOW STUDY - DECEMBER 21 - 12PM 1" = 50'-0"

z



15884 WINCHESTER BLVD.

15880 WINCHESTER BLVD.

15880 WINCHESTER BLVD.

17484 SHELBURNE WAY

2 EAST - FACING RESIDENTIAL ELEVATION 3/32" EXISTING 3/32" = 1'-0"

ELEVATON KEYNOTE:

- EXISTING BUILDING AND FOUNDATION TO BE DEMOLISHED
- 2 EXISTING TREE TO REMAIN. SEE SHEET 1 / T-1
- MAXIMUM PROPOSED BUILDING HEIGHT 35'-0" ABOVE GRADE
- 4 EXISTING TREE TO BE REMOVED. SEE SHEET 1 / T-1

APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215

Consultant:

Revisions:


Revision Schedule

Planning Response #1 07/20/21
Planning Response #2 11/01/21

COPYRIGHT © 2022 SWENSON BUILDER



2 SOUTH - FACING RESIDENTIAL (NEIGHBOR VIEW) EXISTING 1/8" = 1'-0"



NORTH SHE RUNN FE REVATION FXSTING

187 = 1/0

15880 WINCHESTER BLVD.

ELEVATON KEYNOTE:

- EXISTING BUILDING AND FOUNDATION TO BE DEMOLISHED
- 2 EXISTING TREE TO REMAIN. SEE SHEET 1 / T-1
 - MAXIMUM PROPOSED BUILDING HEIGHT 35'-0" ABOV
- 4 EXISTING TREE TO BE REMOVED. SEE SHEET 1 / T-1

Date: APRIL 01, 2021

AS NOTED

Drawn by:

DM, EY, IL

Job #:

20-9215


Consultant:

Revisions:

Revision Schedule

Planning Response #1 07/20/21

COPYRIGHT © 2022 SWENSON BUILDER



FIRE DEPARTMENT GENERAL NOTES:

1. FIRE SPRINKLERS REQUIRED: APPROVED AUTOMATIC SPRINKLER SYSTEMS IN NEW AND EXISTING BUILDINGS AND STRUCTURES SHALL BE PROVIDED IN THE LOCATIONS DESCRIBED IN THIS SECTION OR IN SECTIONS 903.2.1 THROUGH 903.2.19 WHICHEVER IS THE MORE RESTRICTIVE. FOR THE PURPOSES OF THIS SECTION, FIREWALLS AND FIRE BARRIERS USED TO SEPARATE BUILDING AREAS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CALIFORNIA BUILDING CODE AND SHALL BE WITHOUT OPENINGS OR PENETRATIONS. 1. IN OTHER THAN RESIDENTIAL BUILDINGS WHICH REQUIRE THE INSTALLATION OF FIRE SPRINKLERS FOR ALL NEW BUILDINGS ACCORDING TO THE CALIFORNIA RESIDENTIAL CODE, AN AUTOMATIC SPRINKLER SYSTEM SHALL BE PROVIDED THROUGHOUT ALL NEW BUILDINGS AND STRUCTURES.

2. FIRE ALARM SYSTEM REQUIRED: A MANUAL AND AUTOMATIC FIRE ALARM SYSTEM SHALL BE INSTALLED IN GROUP R-2, R-2.1, R-2.2 OCCUPANCIES.

TIMING OF INSTALLATION: WHEN FIRE APPARATUS ACCESS ROADS OR A WATER SUPPLY FOR FIRE PROTECTION IS REQUIRED TO BE INSTALLED, SUCH PROTECTION SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DURING THE TIME OF CONSTRUCTION EXCEPT WHEN APPROVED ALTERNATIVE METHODS OF PROTECTION ARE PROVIDED. TEMPORARY STREET SIGNS SHALL BE INSTALLED AT EACH STREET INTERSECTION WHEN CONSTRUCTION OF NEW ROADWAYS ALLOWS PASSAGE BY VEHICLES IN ACCORDANCE WITH SECTION 505.2. CONSTRUCTION DOCUMENTS. CONSTRUCTION DOCUMENTS FOR PROPOSED FIRE APPARATUS ACCESS, LOCATION OF FIRE LANES. SECURITY GATES ACROSS FIRE APPARATUS ACCESS AND CONSTRUCTION DOCUMENTS AND HYDRAULIC CALCULATIONS FOR FIRE HYDRANT SYSTEMS SHALL BE SUBMITTED TO THE FIRE DEPARTMENT FOR REVIEW AND APPROVAL PRIOR TO

4. TWO-WAY COMMUNICATION SYSTEM: TWO-WAY COMMUNICATION SYSTEMS SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH ALL CURRENT EDITIONS OF NFPA 72, THE CALIFORNIA ELECTRICAL CODE. THE CALIFORNIA FIRE CODE. THE CALIFORNIA BUILDING CODE, AND THE CITY OR TOWN ORDINANCES, POLICIES, AND STANDARDS WHERE A TWO-WAY SYSTEM IS BEING INSTALLED. [SCCFD STANDARD DETAILS & SPECIFICATIONS, C-1]. OTHER STANDARDS ALSO CONTAIN DESIGN/INSTALLATION CRITERIA FOR SPECIFIC LIFE SAFETY RELATED EQUIPMENT. THESE OTHER STANDARDS ARE REFERRED TO IN NFPA 72.1

5. EMERGENCY RESPONDER RADIO COVERAGE IN NEW **BUILDINGS:** ALL NEW BUILDINGS SHALL HAVE APPROVED RADIO COVERAGE FOR EMERGENCY RESPONDERS WITHIN THE BUILDING BASED UPON THE EXISTING COVERAGE LEVELS OF THE PUBLIC SAFETY COMMUNICATION SYSTEMS OF THE JURISDICTION AT THE EXTERIOR OF THE BUILDING. THIS SECTION SHALL NOT REQUIRE IMPROVEMENT OF THE EXISTING PUBLIC SAFETY COMMUNICATION SYSTEMS. REFER TO CFC SEC. 510 FOR FURTHER REQUIREMENTS. EMERGENCY RADIO RESPONDER COVERAGE REQUIREMENTS APPLIES TO ALL BUILDINGS. [SCCFD STANDARD DETAILS & SPECIFICATIONS, C-2].

6. WATER SUPPLY REQUIREMENTS: POTABLE WATER SUPPLIES SHALL BE PROTECTED FROM CONTAMINATION CAUSED BY FIRE PROTECTION WATER SUPPLIES. IT IS THE RESPONSIBILITY OF THE APPLICANT AND ANY CONTRACTORS AND SUBCONTRACTORS TO CONTACT THE WATER PURVEYOR SUPPLYING THE SITE OF SUCH PROJECT, AND TO COMPLY WITH THE REQUIREMENTS OF THAT PURVEYOR. SUCH REQUIREMENTS SHALL BE INCORPORATED INTO THE DESIGN OF ANY WATER-BASED FIRE PROTECTION SYSTEMS. AND/OR FIRE SUPPRESSION WATER SUPPLY SYSTEMS OR STORAGE CONTAINERS THAT MAY BE PHYSICALLY CONNECTED IN ANY MANNER TO AN APPLIANCE CAPABLE OF CAUSING CONTAMINATION OF THE POTABLE WATER SUPPLY OF THE PURVEYOR OF RECORD. FINAL APPROVAL OF THE SYSTEM(S) UNDER CONSIDERATION WILL NOT BE GRANTED BY THIS OFFICE UNTIL COMPLIANCE WITH THE REQUIREMENTS OF THE WATER PURVEYOR OF RECORD ARE DOCUMENTED BY THAT PURVEYOR AS HAVING BEEN MET BY THE APPLICANT(S). 2016 CFC SEC. 903.3.5 AND HEALTH AND SAFETY CODE

ADDRESS IDENTIFICATION: NEW AND EXISTING BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR NUMBERS SHALL BE A MINIMUM OF 4 INCHES (101.6 MM) HIGH WITH A MINIMUM STROKE WIDTH OF 0.5 INCH (12.7 MM). WHERE ACCESS IS BY MEANS OF A PRIVATE ROAD AND THE BUILDING CANNOT BE VIEWED FROM THE PUBLIC WAY, A MONUMENT, POLE OR OTHER SIGN OR

USED TO IDENTIFY THE STRUCTURE. ADDRESS NUMBERS SHALL BE MAINTAINED. CFC SEC. 505.1

Consultant:


Revisions:

Revision Schedule

Planning Response #1 | 07/20/21 Planning Response #2 11/01/21

COPYRIGHT © 2022 **SWENSON BUILDER**

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215







Consultant: Revisions: Revision Schedule Planning Response #1 07/20/21 Planning Response #2 11/01/21 COPYRIGHT © 2022 SWENSON BUILDER


APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215














TO HELP REDUCE THE BUILDING MASS, WE REMOVED THIS PORTION OF THE BUILDING AND LOWERED THE THIRD FLOOR UNITS ABOVE IT DOWN TO THIS LEVEL



RENDERING - NORTH ELEVATON (SHELBURNE WAY) WITHOUT REDUCE UNITS 12" = 1'-0"



2 RENDERING - NORTH ELEVATON (SHELBURNE WAY) REDUCE UNITS 12" = 1'-0"

Consultant:

Revisions:

Revision Schedule

COPYRIGHT © 2022 SWENSON BUILDER

ASSISTED LIVING
PLANNING REVIEW NO. 21 1724
50 - 15894 WINCHESTER BLVD., LOS GATOS, C
RENDERING - NORTH ELEVATIONS
COMPARISION

APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215

A-3.0

A-3.1







NORTH - SHELBURNE PERSPECTIVE 1/8" = 1'-0"



2 NORTH - SHELBURNE ELEVATON 1/8" = 1'-0"

LEGEND: MAXIMUM ALLOWED HEIGHT (35' ABOVE NATURAL GRADE) **NATURAL GRADE**

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215 A-3.2

Revision Schedule

COPYRIGHT © 2022 SWENSON BUILDER

FINISH GRADE

VARIANCE AREA

1 SOUTH - FACING RESIDENTIAL (NEIGHBOR VIEW) - VARIANCE EXHIBIT 1/8" = 1'-0"



2 SOUTH - FACING RESIDENTIAL 1/8" = 1'-0"

LEGEND:

MAXIMUM ALLOWED HEIGHT (35' ABOVE NATURAL GRADE)

NATURAL GRADE

FINISH GRADE

VARIANCE AREA

WINCHESTER MEMORY CARE /
ASSISTED LIVING
PLANNING REVIEW NO. 21 1724
15860 - 15894 WINCHESTER BLVD., LOS GATOS
SOUTH - FACING RESIDENTIAL
ELEVATIONS - VARIANCE EXHIBIT

APRIL 01, 2021

A-3.3

AS NOTED

DM, EY, IL

20-9215


Consultant:


Revisions:


Revision Schedule

2 Planning Response #2 11/01/21

COPYRIGHT © 2022 SWENSON BUILDER








ROOFTOP MECHANICAL EQUIPMENT

2 NORTH / SOUTH SECTION 1 - SIGHT LINE EXHIBIT 1/16" = 1'-0"



3 NORTH / SOUTH SECTION 2 - SIGHT LINE EXHIBIT 1/16" = 1'-0"

Consultant: Revisions: Revision Schedule 3 Planning Response #3 12/10/21 COPYRIGHT © 2022 SWENSON BUILDER SCREEN ANALYSIS SECTIONS APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

A-3.6














5 3D View 8



CARE

Consultant:

Revisions:

Revision Schedule

Planning Response #3 | 12/10/21


COPYRIGHT © 2022 SWENSON BUILDER

DF SCREEN ANALYSIS PERSPECTIVES

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

A-3.7







GENERAL NOTES:

ROOF RAINWATER LEADERS ARE TO BE DISCHARGED ONTO ENERGY DISSIPATERS (SPLASH BLOCKS) AT ALL LOCATIONS. NO IMPROVEMENTS SHALL OBSTRUCT OR DIVERT RUNOFF TO THE DETRIMENT OF AN ADJACENT DOWNSTREAM OR DOWN SLOPE PROPERTY. INSTEAD, STORMWATER TO BE TREATED ONSITE BY MEANS OF BIOTREATMENT. PLEASE SEE CIVIL STORMWATER MANAGEMENT PLAN FOR MORE INFORMATION.

ELEVATION KEYNOTE: (1) SPANISH TILE ROOF

2 RAFTER TAIL (3) CORNICE (4) ROOF GUTTER CEMENT PLASTER WITH PAINT FINISH - SHERMAN WILLIAMS 7066 GRAY MATTERS CEMENT PLASTER WITH PAINT FINISH- SHERMAN

WILLIAMS 7067 CITYSCAPE (7) EXTERIOR WALL TRIM

(8) FIXED WINDOW 9 SINGLE HUNG WINDOW (10) CASEMENT WINDOW (11) SINGLE DOOR

(12) DOUBLE DOOR

LINEAR CARRIAGE LIGHT **BELLY BAND** PATIO METAL RAILING COURTYARD WALL CHIMNEY - CEMENT PLASTER FINISH, EXTERIOR TRIM, SPLIT FACE CMU WALL ADJACENT TO NEIGBOR'S WALL, 6'-0" TYP.

BRACED WOOD TRELLIS

EXTERIOR CHANDELIER

CORNICE CROWN

CURTAIN WALL

24 NOT USED

ARCHITECTURAL COLUMN

25 ROLL UP GATE GEOMETRIC SCREEN (27) CORBEL - SPANISH ROLL UP DOOR WITH FROSTED GLASS PANELS LOCATION OF TRASH / RECYCLE PAD FOR ON SITE BIN STAGING FOR COLLECTION DAY USE ONLY. BINS TO BE STORED IN TRASH ROOM BEHIND LOADING ROOM ON NON COLLECTION DAYS. (30) EXISTING GRADE PROPOSED GRADE 32 MAXIMUM ALLOWED HEIGHT (35' ABOVE NATURAL GRADE)

MAXIMUM ALLOWED HEIGHT (35' ABOVE NATURAL GRADE) FINISH GRADE

LEGEND:

NATURAL GRADE VARIANCE AREA

APRIL 01, 2021 **AS NOTED** DM, EY, IL 20-9215 A-4.2

Consultant:

Revisions:

ARE

WINCHESTER MEMORY C ASSISTED LIVING PLANNING REVIEW NO. 21 1 50 - 15894 WINCHESTER BLVD., LOS

Revision Schedule


Planning Response #1 07/20/21

Planning Response #2 11/01/21

Planning Response #3 | 12/10/21

COPYRIGHT © 2022 SWENSON BUILDER












RENDERING - WEST ELEVATON (WINCHESTER BOULEVARD)



WINCHESTER MEMORY CARE
ASSISTED LIVING
PLANNING REVIEW NO. 21 1724
15860 - 15894 WINCHESTER BLVD., LOS GAT

RENDERING


Revision Schedule

COPYRIGHT © 2022 SWENSON BUILDER

APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215



RENDERING - PERSPECTIVE FROM WINCHESTER BOULEVARD LOOKING NORTH - EAST



RENDERING - PERSPECTIV WINCHESTER

Revision Schedule

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215



RENDERING - SOUTH ELEVATION

WINCHESTER BLVD.

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

Revision Schedule

SWENSON BUILDER



Consultant:

Revision Schedule

COPYRIGHT © 2022 SWENSON BUILDER

RENDERING - PERSPECTIV GARDEN/GROUND LEVEL

APRIL 01, 2021 AS NOTED

Orawn by: DM, EY, IL
Job #: 20-9215 A-5.4 WINCHESTER BLVD.

RENDERING - PERSPECTIVE OF GARDEN / GROUND LEVEL UNITS

DEVELOPMENT REVIEW RESUBMITTAL #4: APRIL 4, 2022

APRIL 01, 2021 AS NOTED DM, EY, IL 20-9215

A-5.5



RENDERING - NORTH ELEVATON (SHELBURNE WAY)

Revision Schedule







RENDERING - AERIAL FROM SHELBURNE

Revisions:

COPYRIGHT © 2022 SWENSON BUILDER

APRIL 01, 2021

A-5.8

AS NOTED

DM, EY, IL

20-9215


WINCHESTER BLVD.




RENDERING - AERIAL FROM WINCHESTER

DEVELOPMENT REVIEW RESUBMITTAL #4: APRIL 4, 2022

MATERIALS ARE REFERENCED BY LETTER



A: CEMENT PLASTER FINISH: SAND



B: VINYL WINDOW



C: STUCCO FOAM TRIM



D: METAL RAILING



E: PERCAST BALUSTERS

BALUSTERS TO HAVE SQUARED PROFILE TO MATCH COLMNS



F: SPANISH TILE ROOF COLOR:



G: COPPER CHIMMEY CAP



H: TUSCAN COLUMN CAPITAL
COLUMN TO HAVE SQUARED PROFILE

COLORS ARE REFERENCED BY NUMBER:



1: SHERWIN-WILLIAMS
SW 7757
HIGH REFLECTIVE WHITE



3: SHERWIN-WILLIAMS SW 7067 CITYSCAPE



2: SHERWIN-WILLIAMS SW 7674 PEPPERCORN




4: SHERWIN-WILLIAMS SW 7066 GRAY MATTERS

APRIL 01, 2021
Scale:
AS NOTED
Drawn by:
DM, EY, IL
Job #:
20-9215

Revision Schedule

A-6.1



APRIL 01, 2021 AS NOTED

Orawn by: DM, EY, IL 20-9215

A-7.1
















Z