








The Jellinek Residence

OWNER:

PATIOS & PATHS

DRIVEWAY TOTAL SITE COVERAGE

POOL & SPA



ARCHITECT KOHLSAAT & ASSOCIATES 51 UNIVERSITY AVENUE, SUITE L LOS GATOS, CA 95030

CIVIL ENGINEER: HANNA-BRUNETTI 7651 EIGLEBERRY STREET GILROY, CA 95020

NOTES

PROJECT DIRECTORY

1. AN AUTOMATIC FIRE SPRINKLER SYSTEM WILL BE INSTALLED THROUGHOUT, AS A DEFERRED SUBMITTAL.

SCOPE OF WORK

A REMODEL AND ADDITION OF A PRE-1941 SINGLE FAMILY RESIDENCE AND A NEW DETACHED GARAGE, WHICH INCLUDE A NEW SECOND STORY & BASEMENT. SCOPE INCLUDES 5 TOTAL BEDROOMS, 5½ BATHS, A GAME ROOM, AN OFFICE AND A COVERED LOGGIA. ALSO INCLUDES SITE RETAINING WALLS AND A POOL. REQUESTING REMOVAL OF 8 PROTECTED TREES, TWO OF WHICH ARE IN POOR CONDITION. 4 UNPROTECTED TREES ARE ALSO PROPOSED FOR REMOVAL.

323 PENNSYLVANIA AVENUE LOS GATOS, CA 95030 PROJECT ADDRESS:

510-43-044 R-1:8 ZONING: OCCUPANCY GROUP: CONSTRUCTION TYPE: R-3/U V-B / SPRINKLERED GROSS & NET SITE AREA: AVERAGE SLOPE: 9,002 SF 8.8%

.35 - [<u>(9-5)</u> X .20)] ALLOWABLE F.A.R.- RESIDENCE: .32 X 9,002 = 2,881 SF .10 - [<u>(9-5)</u> × .07] ALLOWABLE F.A.R.- GARAGE:

PROJECT DATA

MEGAN JELLINEK

.089 X 9,002 = 801 SF ALLOMABLE BUILDING COVERAGE: 40% = 3,601 SF ALLOMABLE ACC. STR. COVERAGE: 15% OF BUILDABLE AREA =15% OF 4,623 = 693 SF

FLOOR AREAS: EXISTING STRUCTURES TO BE DEMOLISHED: EXISTING ADDITION MAIN FLOOR 559 SF 1,860 SF 410 SF 219 SF BASEMENT CARPORT DETACHED GARAGE SITE AREAS: EXISTING PROPOSED RESIDENCE COVERED PORCH & PATIOS 1,3*0*1 SF 127 SF 1,860 SF 367 SF 0 SF 410 SF 327 SF 0 SF LIGHTWELLS CARPORT/ DET. GARAGE TOTAL BUILDING COVERAGE 219 SF 2,057 SF

70 SF 0 SF

1,058 SF 557 SF 917 SF 5,746 SF

COVER SHEET

EXISTING PHOTOS

NEIGHBORHOOD PLAN & STREETSCAPES

SITE PLAN & LANDSCAPE PLAN

CIVIL COVER SHEET

CONSTRUCTION BEST MANAGEMENT PRACTICES

EXISTING TOPOGRAPHIC SURVEY & DEMOLITION PLAN

SHEET INDEX

GRADING & DRAINAGE PLAN

EROSION CONTROL PLAN

AS-BUILT/DEMO FLOOR PLAN & ROOF PLAN

AS-BUILT/DEMO ELEVATIONS & DEMO CALCULATIONS

PROPOSED MAIN & LOWER FLOOR PLAN

PROPOSED ROOF PLAN

PROPOSED FRONT & LEFT ELEVATIONS


A-10 PROPOSED REAR & RIGHT ELEVATIONS

CROSS SECTIONS

GARAGE PLANS

A-13 SHADOW STUDIES

1 OF -



Front View



Front Gable




Porch Left Side



Front Porch




Front Left View



Left Side View



Rear View




Right Side



Right Side




ADU



Carport

A. 09/25/23B. 11/02/23



ADDITION & REMODEL FOR:
LLINEK RESIDENC

EXISTING PHOTOS

DATE: 07/05/23
SCALE: AS SHOWN
SHEET





11, 15 & 6 Peralta Garages

6 Peralta

4 Palm

324

REVISIONS

A. 09/25/23

B. 11/02/23

D. 02/01/24

KOHLSAATTES AATTES ASSOCIATES

AN ADDITION & REMODEL FOR:

THE JELLINEK RESIDENC

NEIGHBORH OOD PLAN & STREETSCAPE


DATE: 07/05/23

SCALE: AS SHOWN

SHEET

A-3


STREETSCAPE 2



- ALL WORK SHALL BE PERFORMED IN CONFORMANCE WITH THE FOLLOWING: a. TOWN OF LOS GATOS ENGINEERING DESIGN STANDARDS AND SPECIFICATIONS (UNLESS SPECIFICALLY STATED OTHERWISE ON THE PLANS).
- b. ALL TOWN OF LOS GATOS CONDITIONS OF APPROVAL RELATED TO THE PROJECT c. THESE PLANS AND DETAILS.
- d. RECOMMENDATIONS OF THE PROJECT SOILS INVESTIGATION SOILS ENGINEER
- REFERENCE REPORT NO. WITH. BOTH THE MENTIONED REPORT AND ALL UPDATES/ADDENDUMS/LETTERS ARE HEREBY APPENDED AND MADE A PART OF THESE PLANS.
- NO WORK MAY BE STARTED ON-SITE WITHOUT AN APPROVED GRADING PLAN AND A GRADING PERMIT ISSUED BY THE TOWN OF LOS GATOS, PARKS AND PUBLIC WORKS DEPARTMENT LOCATED AT 41 MILES AVENUE, LOS GATOS, CA 95030.
- A PRE-JOB MEETING SHALL BE HELD WITH THE TOWN ENGINEERING INSPECTOR FROM THE PARKS AND PUBLIC WORKS DEPARTMENT PRIOR TO ANY WORK BEING DONE. THE CONTRACTOR SHALL CALL THE INSPECTIONS LINE AT (4080 399-5771 AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO ANY GRADING OR ONSITE WORK. THIS MEETING SHOULD INCLUDE:
- CONDITIONS OF APPROVAL WILL BE POSTED ON SITE AT ALL TIMES DURING
- APPROVAL OF PLANS DOES NOT RELEASE THE DEVELOPER OF THE RESPONSIBILITY FOR DURING THE COURSE OF CONSTRUCTION OF THE IMPROVEMENTS, PUBLIC INTERES AND SAFETY REQUIRES A MODIFICATION OR DEPARTURE FROM THE TOWN SPECIFICATIONS OR THESE IMPROVEMENT PLANS. THE TOWN ENGINEER SHALL HAVE FULL AUTHORITY TO REQUIRE SUCH MODIFICATION OR DEPARTURE AND TO SPECIFY TH MANNER IN WHICH THE SAME IS TO BE MADE
- APPROVAL OF THIS PLAN APPLIES ONLY TO THE GRADING, EXCAVATION, PLACEMENT AND COMPACTION OF NATURAL EARTH MATERIALS. THIS APPROVAL DOES NOT CONFER ANY RIGHTS OF ENTRY TO EITHER PUBLIC PROPERTY OR THE PRIVATE PROPERTY OF OTHERS AND DOES NOT CONSTITUTE APPROVAL OF ANY OTHER IMPROVEMENTS.
- IT SHALL BE THE RESPONSIBILITY OF THE PERMITTEE OR CONTRACTOR TO IDENTIFY LOCATE AND PROTECT ALL UNDERGROUND FACILITIES. PERMITTEE OR CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-227-2600 A MINIMUM OF FORTY-EIGHT (48) HOURS BUT NOT MORE THAN FOURTEEN (14) DAYS PRIOR TO COMMENCING ALL WORK.
- 7. ALL WORK SHALL BE PERFORMED IN SUCH A MANNER AS TO COMPLY WITH THE STANDARDS ESTABLISHED BY THE AIR QUALITY MANAGEMENT DISTRICT FOR AIRBORNE
- THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL STATE AND FEDERAL LAWS, CODES RULES AND REGULATIONS GOVERNING THE WORK IDENTIFIED ON THESE PLANS. THESE SHALL INCLUDE, WITHOUT LIMITATION, SAFETY AND HEALTH RULES AND REGULATIONS ESTABLISHED BY OR PURSUANT TO THE OCCUPATIONAL SAFETY AND HEALTH ACT OR ANY OTHER APPLICABLE PUBLIC AUTHORITY.
- 9. THE GENERAL CONTRACTOR SHALL PROVIDE QUALIFIED SUPERVISION ON THE JOB SITE AT ALL TIMES DURING CONSTRUCTION.
- 10. CONTRACTOR SHALL EXERCISE ALL NECESSARY CAUTION TO AVOID DAMAGE TO ANY EXISTING TREES, SURFACE IMPROVEMENTS, DRAINAGE, WATER, SEWER, ELECTRICAL OR TELECOMMUNICATION FACILITIES WHETHER ABOVE GROUND OR UNDERGROUND. CONTRACTOR SHALL BEAR FULL RESPONSIBILITY FOR ANY DAMAGE THERETO.
- 11. HORIZONTAL AND VERTICAL CONTROLS SHALL BE SET AND CERTIFIED BY A LICENSED SURVEYOR OR REGISTERED CIVIL ENGINEER QUALIFIED TO PRACTICE LAND SURVEYING.
- 12. DURING CONSTRUCTION, ALL APPLICABLE WORK (SUBGRADE, PAVING, ETC.) SHALL BE INSPECTED BY THE APPLICANT'S SOILS ENGINEER. THE ENGINEER SHALL BE NOTIFIED AT LEAST 48 HOURS BEFORE BEGINNING SUCH WORK. THE ENGINEER SHALL BE ON-SITE TO VERIFY CONDITIONS AS REQUIRED IN HIS REPORT. SHOULD ANY CHANGES TO THE REPORT RECOMMENDATIONS BE NECESSARY, TOWN APPROVAL SHALL BE OBTAINED PRIOR TO ANY ASSOCIATED WORK.
- 13. THE RESULTS OF THE CONSTRUCTION OBSERVATION AND TESTING SHALL BE DOCUMENTED IN AN "AS-BUILT" LETTER/REPORT PREPARED BY THE APPLICANTS' SOILS ENGINEER AND SUBMITTED FOR THE TOWN'S REVIEW AND ACCEPTANCE BEFORE FINAL RELEASE OF ANY OCCUPANCY PERMIT IS GRANTED.
- 14. ALL PRIVATE AND PUBLIC STREETS ACCESSING PROJECT SITE SHALL BE KEPT OPEN AND IN A SAFE, DRIVABLE CONDITION THROUGHOUT CONSTRUCTION. IF TEMPORARY CLOSURE IS NEEDED, THEN FORMAL WRITTEN NOTICE TO THE ADJACENT NEIGHBORS AND THE TOWN OF LOS GATOS PARKS AND PUBLIC WORKS DEPARTMENT SHALL BE PROVIDED AT LEAST ONE WEEK IN ADVANCE OF CLOSURE, AND NO CLOSURE SHALL BE GRANTED WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE TOWN. NO MATERIAL OR EQUIPMENT SHALL BE STORED IN THE PUBLIC OR PRIVATE RIGHT-OF-WAY.
- 15. THE CONTRACTOR SHALL INSTALL AND MAINTAIN FENCES, BARRIERS, LIGHTS AND SIGNS THAT ARE NECESSARY TO GIVE ADEQUATE WARNING AND PROTECTION TO THE PUBLIC

16. OWNER/APPLICANT:	PHONE:

- 17. GENERAL CONTRACTOR:
- 18. A TOWN ENCROACHMENT PERMIT IS REQUIRED FOR ANY WORK WITHIN THE PUBLIC RIGHT-OF-WAY. A STATE ENCROACHMENT PERMIT IS REQUIRED FOR ANY WORK WITHIN STATE RIGHT-OF-WAY (IF APPLICABLE). THE PERMITTEE AND/OR CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING INSPECTION PERFORMED BY OTHER GOVERNMENTAL
- 19. GOOD HOUSEKEEPING PRACTICES SHALL BE OBSERVED AT ALL TIMES DURING THE COURSE OF CONSTRUCTION. SUPERINTENDENCE OF CONSTRUCTION SHALL BE DILIGENTLY PERFORMED BY A PERSON OR PERSONS AUTHORIZED TO DO SO AT ALL TIMES DURING WORKING HOURS. THE STORING OF GOODS AND/OR MATERIALS ON THE SIDEWALK AND/OR THE STREET WILL NOT BE ALLOWED UNLESS A SPECIAL PERMIT IS ISSUED BY THE ENGINEERING DIVISION. THE ADJACENT PUBLIC RIGHT-OF-WAY SHALL BE KEPT CLEAR OF ALL JOB RELATED DIRT AND DEBRIS AT THE END OF THE DAY. FAILURE TO MAINTAIN THE PUBLIC RIGHT-OF-WAY ACCORDING TO THIS CONDITION MAY RESULT IN PENALTIES AND/OR THE TOWN PERFORMING THE REQUIRED MAINTENANCE AT THE DEVELOPER'S EXPENSE.



TOWN OF LOS GATOS NPDES NOTES

- 1. SEDIMENT FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON SITE USING STRUCTURAL CONTROLS AS REQUIRED BY THE STATEWIDE GENERAL CONSTRUCTION STORMWATER PERMIT.
- 2. STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING, OR WIND AS REQUIRED BY THE STATEWIDE GENERAL CONSTRUCTION STORMWATER PERMIT.
- 3. APPROPRIATE BEST MANAGEMENT PRACTICES (BMPS) FOR CONSTRUCTION-RELATED MATERIALS, WASTES, SPILL OR RESIDES SHALL BE IMPLEMENTED TO MINIMIZE TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJOINING PROPERTY BY WIND OR RUNOFF AS REQUIRED BY THE STATEWIDE GENERAL CONSTRUCTION STORMWATER PERMIT.
- 4. RUNOFF FROM EQUIPMENT AND VEHICLE WASHING SHALL BE CONTAINED AT CONSTRUCTION SITES AND MUST NOT BE DISCHARGED TO RECEIVING WATERS OR TO THE LOCAL STORM DRAIN SYSTEM.
- 5. ALL CONSTRUCTION CONTRACTOR AND SUBCONTRACTOR PERSONNEL ARE TO BE MADE AWARE OF THE REQUIRED BEST MANAGEMENT PRACTICES (BMPS) AND GOOD HOUSEKEEPING MEASURES FOR THE PROJECT SITE AND ANY ASSOCIATED CONSTRUCTION STAGING AREAS.
- 6. AT THE END OF EACH DAY OF CONSTRUCTION ACTIVITY, ALL CONSTRUCTION DEBRIS AND WASTE MATERIALS SHALL BE COLLECTED AND PROPERLY DISPOSED IN TRASH OR
- 7. CONSTRUCTION SITES SHALL BE MAINTAINED IN SUCH A CONDITION THAT A STORM DOES NOT CARRY WASTE OR POLLUTANTS OFF OF THE SITE. DISCHARGES OF MATERIAL OTHER THAN STORMWATER (NON-STORMWATER DISCHARGES) ARE PROHIBITED EXCEPT AS AUTHORIZED BY AN INDIVIDUAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT OR THE STATEWIDE GENERAL CONSTRUCTION STORMWATER PERMIT. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SOLID OR LIQUID CHEMICAL SPILLS; WASTES FROM PAINTS, STAINS, SEALANTS, SOLVENTS, DETERGENTS, GLUES, LIME, PESTICIDES, HERBICIDES, FERTILIZERS, WOOD PRESERVATIVES AND ASBESTOS FIBERS, PAINT FLAKES OR STUCCO FRAGMENTS; FUELS, OILS, LUBRICANTS, AND HYDRAULIC, RADIATOR OR BATTERY FLUIDS; CONCRETE AND RELATED CUTTING OR CURING RESIDUES: FLOATABLE WASTES: WASTES FROM ENGINE/EQUIPMENT STEAM CLEANING OR CHEMICAL DEGREASING: WASTES FROM STREET CLEANING: AND SUPERCHLORINATED POTABLE WATER FROM LINE FLUSHING AND TESTING. DURING CONSTRUCTION, DISPOSAL OF SUCH MATERIALS SHOULD OCCUR IN A SPECIFIED AND CONTROLLED TEMPORARY AREA ON-SITE PHYSICALLY SEPARATED FROM POTENTIAL STORMWATER RUNOFF, WITH ULTIMATE DISPOSAL IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REQUIREMENTS.
- 8. DISCHARGING CONTAMINATED GROUNDWATER PRODUCED BY DEWATERING GROUNDWATER THAT HAS INFILTRATED INTO THE CONSTRUCTION SITE IS PROHIBITED. DISCHARGING OF CONTAMINATED SOILS VIA SURFACE EROSION IS ALSO PROHIBITED. DISCHARGING NON-CONTAMINATED GROUNDWATER PRODUCED BY DEWATERING ACTIVITIES REQUIRES A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT FROM THE RESPECTIVE STATE REGIONAL WATER QUALITY CONTROL BOARD.

WHERE THE FIRM OF HANNA & BRUNETTI DOES NOT PROVIDE CONSTRUCTION STAKES, SAID FIRM WILL ASSUME NO RESPONSIBILITY WHATSOEVER FOR IMPROVEMENTS CONSTRUCTED THEREFROM.

NOTE TO CONTRACTOR

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS: AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

ADVANCE NOTICE SHALL BE PROVIDED TO NEIGHBORING PROPERTY OWNERS AND SCHOOLS OF HEAVY CONSTRUCTION ACTIVITIES AND HEAVY CONSTRUCTION SHALL NOT START BEFORE 8:30 AM ON DAYS WHEN SCHOOLS ARE IN SESSION. NO CONSTRUCTION IS ALLOWED ON SUNDAYS.

UTILITY INFORMATION: SAN JOSE WATER COMPANY SANITARY SEWER WEST VALLEY SANITATION DISTRICT GAS & ELECTRIC SERVICES PACIFIC GAS & ELECTRIC GARBAGE COLLECTION CO. WEST VALLEY COLLECTION & RECYCLING, LLC TELEPHONE FRONTIER COMMUNICATIONS TOWN OF LOS GATOS STORM DRAIN

PRELIMINARY PLANS NOT FOR CONSTRUCTION

	,
AD	AREA DRAIN
ARV	AIR RELEASE VALVE
	BACK OF CURB
BFP	BACKFLOW PREVENTER
BW	BOTTOM OF WALL
CATV	CABLE TELEVISION
CB	CATCH BASIN
CFS	CUBIC FEET PER SECOND
C/L	CENTERLINE
CMP	CORRUGATED METAL PIPE
CO	CLEANOUT
CY	CUBIC YARD
	DOUBLE CHECK VALVE ASSEMBLY
DI	DROP INLET
DIA	DIAMETER
DIP	DUCTILE IRON PIPE
DWY	DRIVEWAY
(E)	EAST
	EXISTING GRADE
	ELECTRICAL
	EDGE OF PATH
	EMERGENCY VEHICLE ACCESS EASEMENT
	EXISTING
	FACE OF CURB
	FIRE DEPARTMENT CONNECTION
	FINISHED FLOOR ELEVATION
	FINISHED GRADE
FH	FIRE HYDRANT
	FLOW LINE
	FORCED MAIN
FS	FIRE SERVICE

FEET

FT

AGGREGATE BASE

ASPHALT CONCRETE


Pennsy	State Little True of the state
VI.	CINITY MAP

SHEET INDEX

- TOWN NOTES, PROJECT DATA, LEGEND & ABBREVIATIONS
- BLUEPRINT FOR A CLEAN BAY SHEET
- EXISTING TOPOGRAPHY AND DEMOLITION PLAN
- GRADING & DRAINAGE PLAN

EROSION CONTROL PLAN

TABLE 1 - MAXIMUM GRADED CUTS AND FILLS				
SITE ELEMENT	CUT	FILL		
GARAGE	2.87'	0'		
POOL	0.52'	1.71'		
DRIVEWAY	0.62'	1.74'		



ADDDEVIATIONS

GA

GB

GM

PIEE

REINFORCED CONCRETE PIPE

RIM RIM ELEVATION

ABBREVIATIONS						
	GAUGE	R/W	RIGHT-OF-WAY	DATE	8/30/23	
	GRADE BREAK	(S)	SOUTH	۵	/8	
	GAS METER		SLOPE		Σ	111111
	GAS SERVICE		SANTA CLARA COUNTY	BY	AM/TM	
E	HIGH-DENSITY POLYETHYLENE		SANTA CLARA COUNTY FIRE DEPARTMENT	10.00	4	
	HIGH POINT		STORM DRAIN			101 0
	INGRESS/EGRESS EASEMENT	SDCO	STORM DRAIN CLEANOUT			
	INCH	SDE	STORM DRAIN EASEMENT			
	INVERT ELEVATION		STORM DRAIN MANHOLE			
	LATERAL	SDR	STANDARD DIMENSION RATIO			
	LIP OF GUTTER		SQUARE FEET			
	LOW POINT	SJWC	SAN JOSE WATER COMPANY		ENTS	
	MAXIMUM	SS	SANITARY SEWER		z	
	MANHOLE	SSCO	SANITARY SEWER CLEANOUT		$ \overline{\square} $	
	MINIMUM	SSE	SANITARY SEWER EASEMENT		≥	
1	MILES PER HOUR	SSMH	SANITARY SEWER MANHOLE		N N N	
	NORTH	STD	STANDARD	S	lö l	
S.	NOT TO SCALE	S/W	SIDEWALK	REVISIONS		
	ON CENTER	TC	TOP OF CURB	<u>S</u>		
	ON CENTER OUTSIDE DIAMETER PAD ELEVATION	TELE	TELEPHONE	Ε	\ 	
	PAD ELEVATION	TLG	TOWN OF LOS GATOS	<u>~</u>		
	PORTLAND CEMENT CONCRETE	TW	TOP OF WALL		2	
	PERFORATED	TYP	TYPICAL		<u>п</u>	
E	PACIFIC GAS & ELECTRIC COMPANY	VCP	VITRIFIED CLAY PIPE			
	PRIVATE INGRESS/EGRESS EASEMENT	(W)	WEST	11-11	S	
	PROPERTY LINE		WATER			
	PROPOSED	WM	WATER METER			
E	PRIVATE STORM DRAIN EASEMENT	WS	WATER SERVICE		2	
	PUBLIC SERVICE EASEMENT	WV	WATER VALVE		15,34	
	PRIVATE SANITARY SEWER EASEMENT	WVSD	WEST VALLEY SANITATION DISTRICT	\triangle		
	PUBLIC UTILITY EASEMENT	XING	CROSSING	\vee		
	POLYVINYL CHLORIDE			1		
	RADIUS			0		
					/	1 ^

AVENUI

PENNSYLVANIA 32 32 N 5 VE ¥


JELLIN 0

SHEET 1 OF 5

Construction Best Management Practices (BMPs)

Construction projects are required to implement year-round stormwater BMPs.

Materials & Waste Management



Non-Hazardous Materials

- Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- Use (but don't overuse) reclaimed water for dust control.
- Ensure dust control water doesn't leave site or discharge to storm drains.

Lazardous Materials

- Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with City, County, State and Federal regulations.
- Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- Example 10 Keep site free of litter (e.g. lunch items, cigarette butts).
- Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control




Maintenance and Parking

- Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking, and storage.
- Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- Report significant spills to the appropriate local spill response agencies immediately. If the spill poses a significant hazrd to human health and safety, property or the environment, you must report it to the State Office of Emergency Services. (800) 852-7550 (24 hours).

Earthmoving



Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for crosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (i.e. silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Comtaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or crash.
- If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not distrurbed by construction activities.

Landscaping

- Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- U Stack bagged material on pallets and under cover.
- O Discontinue application of any crodible landscape material within 2 days before a forecast rain event or during wet weather.

Concrete Management and Dewatering




Concrete Management

- Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area onsite, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible, send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer, call your local wastewater treatment plant.
- □ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off site for treatment and proper disposal.

Paving/Asphalt Work




Paving

- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or properly dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcuting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposit and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.

Painting & Paint Removal



Painting Cleanup and Removal


- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer.


 Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste.


 Lead based paint removal requires a statecertified contractor.



Storm drain polluters may be liable for fines of up to \$10,000 per day!









D 2 0 23 PEN 510-43-04 ONTRO Z 0 S

SHEET 5 OF 5



EXTERIOR WALLS Existing 5.7 11.2 2.5 5.9 2.7 4.3 1.9 W20 0.8 W22 4.2 W23 W24 10.8 3.1 3.8 TOTAL 0.57346817 0.42653183 TOTAL WALL AREA



AS-BUILT/DEMO FLOOR PLAN

FLOOR PLAN & ROOF PLAN

DATE: 07/05/23

SCALE: AS SHOWN
SHEET

AS-BUILT/

DEMO

A-5

C. 11/22/23

D. 02/01/24


REVISIONS


09/25/23


11/02/23

KOHLSAATE SAATES TO THE STUNIVERSITY AVE, "L" • LOS GATOS, CA. • 95030 • (408) 395-255

THE JELLINEK RESIDENC
323 PENNSYLVANIA AVENUE LOS GATOS, 0







REVISIONS

A. 09/25/23 B. 11/02/23

C. 11/22/23D. 02/01/24

 $\frac{KOHLSAA}{\&ASSOCIATES}$

THE JELLINEK RESIDENCE
323 PENNSYLVANIA AVENUE LOS GATOS, CA

PROPOSED ROOF PLAN

DATE: 07/05/23 SCALE: AS SHOWN

SHEET

A-8

ELEVATION NOTES / MATERIALS

- EXISTING SMOOTH STUCCO FINISH, NEW STUCCO TO MATCH
- 2 EXISTING TURNED PLASTER COLUMN
- 3 EXISTING CIRCULAR RECESS TO REMAIN
- 4 EXISTING CROWN MOLDING
- 5 NEW CROWN MOLDING TO MATCH EXISTING
- 6 NEW STEPPED TRIM @ PARAPET
- NEW DECORATIVE CHIMNEY SHROUD



BENJAMIN MOORE

OC-18 DOVE WING


GLADDING, MCBEAN, 100 Y.O. RECLAIMED, 2-PIECE CLAY **BARREL TILE ROOF**

- 8 NEW 2-PIECE BARREL TILE @ EXISTING ROOF FRAMING
- 9 NEW 2-PIECE BARREL TILE @ NEW ROOF FRAMING



CABOT CORDOVAN BROWN SEMI-TRANSPARENT STAIN

- 10 NEW STAINED WOOD FRONT DOOR W/ SIDELITES
- 11 NEW STAINED WOOD GARAGE DOOR W/ LITES



PROPOSED FRONT ELEVATION



KOLBE HERITAGE SERIES, WOOD FRAMED WINDOWS, K-KRON FINISH, COASTAL STORM



WROUGHT IRON RAILING,



BLACK



NEW WROUGHT IRON GUARDRAIL @ LIGHTWELLS


12 NEW WOOD FRAMED

& SILL

CASEMENT WINDOWS

W/STUCCO MOLDING

- & BALCONY 14 NEW WROUGHT IRON **DECORATIVE GRILL OVER WINDOWS**
- **NEW RECESSED DECORATIVE METAL** GABLE END GRILL @ VENT
- 16 HALF ROUND COPPER GUTTERS
- 17 COPPER STANDING SEAM ROOF AT BAY WINDOW



09/25/23

11/02/23

11/22/23

D. 02/01/24

REMODE (RE THE JELLIN

PROPOSED FRONT & LEFT **ELEVATIONS**

DATE: 07/05/23 SCALE: AS SHOWN SHEET



ELEVATION NOTES / MATERIALS

- EXISTING SMOOTH STUCCO FINISH, NEW STUCCO TO MATCH
- 2 EXISTING TURNED PLASTER COLUMN
- 3 EXISTING CIRCULAR RECESS TO REMAIN
- 4 EXISTING CROWN MOLDING
- 5 NEW CROWN MOLDING TO MATCH EXISTING
- 6 NEW STEPPED TRIM @ PARAPET
- NEW DECORATIVE CHIMNEY SHROUD

BENJAMIN MOORE

OC-18 DOVE WING

GLADDING, MCBEAN, 100 Y.O. RECLAIMED, 2-PIECE CLAY **BARREL TILE ROOF**

- 8 NEW 2-PIECE BARREL TILE @ EXISTING ROOF FRAMING
- 9 NEW 2-PIECE BARREL TILE @ NEW ROOF FRAMING



- 10 NEW STAINED WOOD FRONT DOOR W/ SIDELITES
- 11 NEW STAINED WOOD GARAGE DOOR W/ LITES



PROPOSED REAR ELEVATION



KOLBE HERITAGE SERIES, WOOD FRAMED WINDOWS, K-KRON FINISH, COASTAL STORM




WROUGHT IRON RAILING, **BLACK**



12 NEW WOOD FRAMED CASEMENT WINDOWS W/STUCCO MOLDING & SILL



- 14 NEW WROUGHT IRON **DECORATIVE GRILL** OVER WINDOWS
- **NEW RECESSED DECORATIVE METAL** GABLE END GRILL @ VENT
- 16 HALF ROUND COPPER GUTTERS
- 17 COPPER STANDING SEAM ROOF AT BAY WINDOW



PROPOSED REAR & **RIGHT ELEVATIONS**

REMODE (RE

THE JELLIN

09/25/23


B. 11/02/23


C. 11/22/23

D. 02/01/24

DATE: 07/05/23 SCALE: AS SHOWN SHEET

15 OF -





REVISIONS

. 09/25/23. 11/02/23

C. 11/22/23

D. 02/01/24

KOHLSAATES
& ASSOCIATES
SI UNIVERSITY AVE. "L" • LOS GATOS, CA. • 95030 • (408) 395-2555

THE JELLINEK RESIDENCE

323 PENNSYLVANIA AVENUE LOS GATOS, CA

CROSS SECTIONS

DATE: 07/05/23
SCALE: AS SHOWN

A-11
16 OF -

