DRAWING INDEX

CIVIL

DWG#	<u>TITLE</u>	REV#
A0	COVER SHEET	R
A0.1	CONDITIONS OF APPROVAL	R
A0.2	SCCFD AMMR	R
A0.3	CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPs)	R
A0.4	CALGREEN MANDATORY MEASURES	R
T-1	TREE PROTECTION PLAN	R
A1.0	SITE PLAN - EXISTING CONDITIONS & DEMOLITION	R
A1.1	SITE PLAN	R
A1.2	SITE PLAN	R
A2.1	FLOOR PLANS	R
A2.2	ROOF PLAN & SITE ELEMENTS	R
A3.0	EXISTING EXTERIOR ELEVATIONS	R
A3.1	EXTERIOR ELEVATIONS	R
A3.2	BUILDING SECTIONS	R
A3.3	OVERALL SITE SECTION	R
A3.4	OVERALL SITE SECTION	R
A7.1	DOOR & WINDOW SCHEDULES AND DETAILS	R

STORMWATER POLLUTION CONTROL PLAN

KOLANDER RESIDENCE


GARAGE & BREEZEWAY REPLACEMENT


16511 CYPRESS WAY | LOS GATOS, CALIFORNIA 95030

ARCHITECTURE & SITE DEVELOPMENT PERMIT **S-24-045** MARCH 28, 2025

FLOOR AREA SUMMARY EXISTING PROPOSED ACTUAL MAIN FLOOR (RESIDENCE) 2,377 SQFT. 2,377 SQFT. 0 SQFT. 0 SQFT. 0 SQFT. 96 SQFT. -96 SQFT. 0 SQFT. 0 SQFT. 1,117 SQFT. ACCESSORY STRUCTURES 1,117 SQFT. BELOW GRADE AREA (EXEMPT 0 SQFT. 0 SQFT. 0 SQFT. GARAGE BEYOND EXEMPTION 187 SQFT. 652 SQFT 839 SQFT. 3,777 SQFT. 556 SQFT. 4,333 SQFT. GARAGE EXEMPTION 4,900 SQFT. MAXIMUM ALLOWED

BUILDING SETBACKS									
FRONT (NORTH) SIDE (EAST) SIDE (WEST) REAR (SOUTH)									
REQUIRED BUILDING SETBACKS	30'-0"	20'-0"	20'-0"	25'-0"					
PROPOSED BUILDING SETBACK	105'-11"	32'-3 1/4"	236'-2"	56'-10 1/4"					







SCOPE OF WORK

BUILDING DATA	
OCCUPANCY: TYPE OF CONSTRUCTION: SPRINKLERED (MAIN RESIDENCE): SPRINKLERED (GARAGE): STORIES:	R-3/U TYPE V-B NO YES, NFPA 13D ONE
APN: ZONING:	532-24-004 HR-2½
SITE AREA: (1.257 ACR (SINGLE DWELLING UNIT) AVERAGE LOT SLOPE: REDUCTION ON NET SITE AREA ON SLOPING LOTS (60%	~32% 21,849.60#
EXISTING HOUSE AREA: REMOVED ACCESSORY AREA (DETACHED GARAGE): REMOVED ACCESSORY AREA (SHED): ADDED ACCESSORY AREA (DETACHED GARAGE):	2,377# 587# 96# 1,239#
PROPOSED BUILDING ACCESSORY HEIGHT: ALLOWED MAXIMUM ACCESSORY HEIGHT:	15'-0" 15'-0"
FLOOR AREA RATIO: ALLOWED MAXIMUM FLOOR AREA RATIO: (HILLSIDE DEVELOPMENT STANDARDS & GUIDELINES)	19.83% TABLE 2 4,900#
RESIDENT PARKING GUEST PARKING	3 COVERED 4 UNCOVERED
PROJECT AREA: DEFERRED SUBMITTAL: F	1,239# TRE SPRINKLERS

REPLACE THE EXISTING DETACHED TWO-CAR GARAGE AND STORAGE AREA WITH A NEW DETACHED THREE-CAR GARAGE IN THE SAME LOCATION. REPLACE BREEZEWAY IN SAME PLACE. IN ADDITION, A 5,000 GALLON FIRE WATER TANK & FIRE DEPARTMENT CONNECTION IS BEING INSTALLED ALONG WITH NEW NFPA 13D SPRINKLERS FOR THE GARAGE.

AERIAL VIEW





GENERAL NOTES

- PERSON(S) PERFORMING THE WORK MUST BE COGNIZANT OF FIELD CONDITIONS AND VERIFY PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY CONFLICTS SHALL
- DRAWINGS TO ACCURATELY REFLECT ALL CONSTRUCTION FIELD CHANGES AS DIRECTED BY THE OWNER. THE DESIGNER IS NOT RESPONSIBLE FOR UPDATING THE DRAWINGS TO CONFORM TO CONSTRUCTION AT THE COMPLETION OF THE JOB.
- CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES. WHERE WORK OF A HIGHER DEGREE IS INDICATED ON THESE PLANS OR IN THE SPECIFICATIONS,
- THE PERSON(S) PERFORMING THE WORK ALONE IS RESPONSIBLE FOR JOBSITE
- PROPERTY WILL BE CONTINUOUSLY OWNER—OCCUPIED. PERSON(S) PERFORMING THE WORK (IF NOT THE OWNER) SHALL COORDINATE WITH OWNER FOR SEQUENCE OF WORK. PERSON(S) PERFORMING THE WORK SHALL PROVIDE 24-HOUR ADVANCE NOTICE TO OWNER FOR SHUTOFF OF ANY UTILITIES TO ACCOMMODATE WORK.
- CONSTRUCTION. THE PERSON(S) PERFORMING THE WORK SHALL DETERMINE EXACT DIMENSIONS FOR PROPER FITTING OF THE WORK. DIMENSIONS INDICATED ARE TO FACE OF EXISTING WALL SURFACE TO FACE OF NEW FINISH WALL UNLESS
- THE PERSON(S) PERFORMING THE WORK SHALL BE RESPONSIBLE FOR FIELD INSPECTING EXISTING CONDITIONS AND MAKING PROVISIONS FOR THE CAULKING AND SEALING OF ALL EXISTING PIPES AND CONDUITS WHERE THEY WILL PENETRATE NEW
- THE PERSON(S) PERFORMING THE WORK SHALL BE RESPONSIBLE TO REPAIR ALL DAMAGE CAUSED BY HIS/HER WORK AND RESTORE TO ORIGINAL CONDITIONS UNLESS PLANNED OTHERWISE.
- PERSON(S) PERFORMING THE WORK SHALL PROVIDE JOBSITE DUMPSTER AT HIS/HER DISCRETION AT A LOCATION ACCEPTABLE BY THE OWNER, AND SHALL REMOVE DUMPSTER AT COMPLETION OF WORK.
- 10. THE PERSON(S) PERFORMING THE WORK SHALL PROVIDE PROPER FIRE EXTINGUISHERS WHEN ENGAGED IN WELDING OR OTHER HAZARDOUS WORK. ALTERNATIVELY, A FIRE HOSE MAY BE USED WHERE DEEMED NECESSARY.
- WITHIN BACK OR SIDE-YARD OF OWNER PROPERTY UPON APPROVAL OF THE OWNER. NO MATERIALS SHALL BE STORED IN FRONT WITHOUT CONSENT OF THE PROPER AUTHORITIES IN WRITING. THE PERSON(S) PERFORMING THE WORK SHALL BE RESPONSIBLE FOR MAINTAINING AND PROTECTING THE STORED MATERIALS
- RESIDENTIAL AND CHAPTER 16 (40 PSF UNIFORM LIVE LOAD, 20 PSF DEAD LOAD, L/360 LIVE LOAD DEFLECTION LIMIT (CBC TABLE 1604.3,, CRC TABLE R301.7), DOUGLAS FIR LARCH #2 W/ MODULUS OF ELASTICITY AT E=1.6).
- 14. ALL CEILING LOADS ARE BASED ON CBC CHAPTER 16 AND TABLE 1607.1 (CRC TABLE R301.5) FOR RESIDENTIAL (20 PSF UNIFORM LIVE LOAD, 10 PSF DEAD LOAD, L/240 LIVE LOAD DEFLECTION LIMIT (CBC TABLE 1604.3,, CRC TABLE R301.7), DOUGLAS FIR LARCH #2 W/ MODULUS OF ELASTICITY AT E=1.6).
- 15. ALL ROOF LOADS ARE BASED ON CBC TABLE 1607.1 (CRC TABLE R301.6) FOR RESIDENTIAL AND CHAPTER 16 (16 PSF UNIFORM LIVE LOAD, 12 PSF DEAD LOAD, L/240 LIVE LOAD DEFLECTION LIMIT FOR SUPPORTING NONPLASTER CEILINGS AND L/180 LIVE LOAD DEFLECTION LIMIT FOR NOT SUPPORTING CEILINGS (CBC TABLE 1604.3, CRC TABLE R301.7), DOUGLAS FIR LARCH #2 WITH MODULUS OF ELASTICITY AT E=1.6).
- 16. WIND SPEED (CBC 1609, ASCE 7-16) $V_{ULT} = 92 MPH, EXPOSURE B$ $\lambda = 1$; q = 11 PSF; qz = 25 PSF
- 17. SEISMIC LOADING (CBC 1613; ASCE 7-16) SEISMIC DESIGN CATEGORY E SITE CLASS C - VERY DENSE SOIL AND SOFT ROCK RISK CATEGORY II IMPORTANCE FACTOR 1.0 $S_{DS} = 2.051$; $S_{D1} = 0.838$; R = 6.5; $\rho = 1.3$; $\Omega = 3.0$
- 18. FLOOD ZONE (FEMA) ZONE D - AREA OF UNDETERMINED FLOOD HAZARD REF. PANEL 06085C0380H (5/18/2009)
- WHERE INSULATION IS INSTALLED, PERSON(S) PERFORMING THE WORK SHALL SUBMIT FORM CF2R-ENV-03-E "INSULATION CERTIFICATE" TO TOWN OF LOS GATOS PER REQUIREMENTS PRIOR TO OBTAINING OCCUPANCY. REFERENCE CALIFORNIA TITLE 24 COMPLIANCE FORMS.
- 20. DISPOSAL OF MATERIALS DURING DEMOLITION AND CONSTRUCTION SHALL BE DIVERTED FROM THE LANDFILL AT A RATE OF 100% OR GREATER FOR CONCRETE AND ASPHALT AND 65% OR GREATER FOR ALL OTHER MATERIALS COMPOSITE. THE PERSON(S) PERFORMING THE WORK SHALL COMPLETE A CONSTRUCTION & DEMOLITION DEBRIS RECYCLING SUMMARY REPORT AT THE CONCLUSION OF THE PROJECT INDICATING ACTUAL QUANTITIES RECYCLED, REUSED AND/OR DISPOSED. WEIGHT TAGS ARE REQUIRED TO DOCUMENT TONNAGE DIVERTED AND DISPOSED. REFER TO SHEET A1.0 FOR FURTHER REQUIREMENTS.
- 21. REFERENCE GEOTECHNICAL STUDY (SOILS) FROM C2EARTH, DATED JUNE 13, 2024.
- 22. REFERENCE COUNTY OF SANTA CLARA FIRE DEPARTMENT PLAN REVIEW #25-0682 AND AMMR APPROVAL #25-0417. SEE SHEET A0.1A FOR AMMR.
- 23. A PRIVATE FIRE PROTECTION SYSTEM WILL BE PROVIDED AS PART OF THE APPROVED AMMR CONDITION. THIS INCLUDES A WHARF HYDRANT, 5,000 GALLON WATER TANK AND ASSOCIATED SIGNAGE POSTED ON THE WHARF HYDRANT INDICATING IT IS SUPPLIED BY A 5,000 GALLON TANK.

BUILDING CODES

- CALIFORNIA BUILDING CODE (CBC) 2022 EDITION
- CALIFORNIA RESIDENTIAL CODE (CRC) 2022 EDITION CALIFORNIA TITLE 24 ENERGY EFFICIENCY STANDARDS 2022 EDITION
- CALIFORNIA GREEN BUILDING CODE (CGC) 2022 EDITION
- CALIFORNIA FIRE CODE (CFC) 2022 EDITION
- CALIFORNIA MECHANICAL CODE (CMC) 2022 EDITION
- CALIFORNIA PLUMBING CODE (CPC) 2022 EDITION CALIFORNIA ELECTRICAL CODE (CEC) 2022 EDITION
- TOWN OF LOS GATOS CODE OF ORDINANCES ALONG WITH ANY OTHER APPLICABLE LOCAL AND STATE LAWS AND REGULATIONS.

PROJECT TITLE

REVISIONS PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS | PLANNING COMMENTS PLANNING COMMENTS


CONDITIONS & RESTRICTIONS instruments of service and shall remain property of the designer. No revisions, reproductions, or use of of the architect. All existing conditions represented in these plans are to be field verified and all

SHEET TITLE

Do not scale from these plans, follow dimensions

indicated or consult the architect.

COVER SHEET



24111/6285

	DRAFT CONDITIONS OF APPROVAL - COMPLIANCE MATRIX
Item	Description
	WATER QUALITY: The project will implement the following conditions to minimize impacts on water quality within the ephemeral drainage (many of these conditions are overlapping conditions with what will be required for compliance with the California Regional Water Quality Board, San Francisco Bay Region, Municipal Regional Stormwater NPDES Permit):
	a) All construction activities in the ephemeral drainage shall be avoided. Within the Slope Stability Protection Area, grading will be minimized to the extent necessary and existing contours and slopes shall be maintained. b) Existing native vegetation adjacent the drainage shall be retained by removing only as much vegetation as necessary to accommodate the construction of the retaining wall. When possible, a vegetated buffer strip between staging/excavation areas and the drainage shall be maintained.
	c) Appropriate erosion control measures (e.g., fiber rolls, filter fences, vegetative bugger strips) shall be used on site to reduce siltation and runoff of contaminants into the ephemeral drainage. Fiber rolls used for erosion control will be certified as free of noxious weed seed. Filter fences and mesh will be of material that will not entrap reptiles and amphibians. Erosion control measures will be placed at the top of bank of the drainage or the edge of the Slope Stability Protection Area where possible. The erosions control measures should follow the approaches and details outlined in the Bank Protection/Erosion Repair Design Guide in the Santa Clara Valley Water Resources Protection Collaborative's User Manual: Guidelines & Standards for Land Use Near Streams (Valley Water 2006).
19	d) All disturbed soils shall be revegetated with native plans and/or grasses or sterile nonnative species suitable for the altered soil conditions upon completion of construction. Local watershed native plants will be used if available. If sterile nonnative species are used for temporary erosion control, native seed mixtures must be used in subsequent treatments to provide long-term erosion control and slow colonization by invasive nonnatives. All disturbed areas that have been compacted shall be de-compacted prior to planting or seeding. Cut-and-fill slopes will be planted with local native or non-invasive plants suitable for the altered soil conditions. Again, revegetation of disturbed soils shall follow the recommendations of the Santa Clara Valley Water Resources Protection Collaborative's User Manual: Guidelines & Standards for Land Use Near Streams (Valley Water 2006). e) No stockpiling or placement of erodible materials shall be allowed within 20 feet of the ephemeral drainage or along areas of natural stormwater flow where materials could be washed into waterways. f) No equipment servicing shall be done within 20 feet of the ephemeral drainage, unless equipment stationed in these locations cannot be readily relocated (i.e., pumps, generators.)
	g) Construction personnel shall prevent the accidental release of chemicals, fuels, lubricants, and non-storm drainage water into channels. Spill prevention kits shall always be in close proximity when using hazardous materials (e.g., crew trucks and other logical locations). Personnel shall implement measures to ensure that hazardous materials are properly handled, and all construction waste will be disposed of in designated areas to prevent stormwater from flowing onto or off these areas.
	h) Potential contaminating materials must be stored in covered storage areas or secondary containment that is impervious to leaks and spills. Runoff pathways shall be free of trash containers or trash storage areas. Trash storage areas shall be screened or walled.
	i) Vehicles and equipment shall be parked on pavement, existing roads, and previously disturbed areas.
	The above notes are included on Sheet A1.2. WATER AGENCY PERMTTING: Prior to start of any work along or within a water agency's right-of-way/easement, the Owner and/or Applicant shall obtain necessary encroachment permit(s) and/or plan check review(s) from said
20	Agency(ies) corresponding with the proposed work. A copy of any necessary permit(s) is required to be submitted to the Engineering Division of the Parks and Public Works Department prior to Grading or Building Permit issuance.
	Noted. Since all work is being performed on site, it is not expected that an encroachment permit will be necessary. If for some reason one is required, the owner will comply with the above conditions.
21	TOWN INDEMNITY: Applicants are notified that Town Code Section 1.10.115 requires that any applicant who receives a permit or entitlement from the Town shall defend, indemnify, and hold harmless the Town and its officials in Noted.
22	COMPLIANCE MEMORANDUM: A memorandum shall be prepared and submitted with the building plans detailing how the Conditions of Approval will be addressed. Noted. Please refer to Sheet A0.1 addressing the final Conditions of Approval for compliance.

	DRAFT CONDITIONS OF APPROVAL - COMPLIANCE MATRIX
Item	Description APPROVAL: This application shall be completed in accordance with all of the conditions of approval and in substantial compliance with the approved plans. Any changes or modifications to the approved plans and/or business
1	operation shall be approved by the Community Development Director, DRC or the Planning Commission depending on the scope of the changes.
2	Noted EXPIRATION: The approval will expire two years from the approval date pursuant to Section 29.20.320 of the Town Code, unless the approval has been vested.
	Noted. OUTDOOR LIGHTING: Exterior lighting shall be kept to a minimum and shall be down-directed fixtures that will not reflect or encroach onto adjacent properties. No floodlights shall be used unless it can be demonstrated that they
3	are needed for safety or security.
4	Note is included on Sheet A1.1 TREE REMOVAL PERMIT: A Tree Removal Permit shall be obtained for any trees to be removed, prior to the issuance of a building or grading permit.
	A tree removal permit will be applied for under the conditions noted. EXISTING TREES: All existing trees shown on the plan and trees required to remain or to be planted are specific subjects of approval of this plan, and must remain on the site.
5	Noted.
6	TREE FENCING: Protective tree fencing and other protection measures shall be placed at the drip line of existing trees prior to issuance of demolition and building permits and shall remain through all phases of construction. Include a tree protection plan with the construction plans.
	Noted. Please refer to Sheet A1.0 for tree removal and tree protection. In addition, please refer to Sheet T-1.
7	TREE STAKING: All newly planted trees shall be double-staked using rubber tree ties. Noted.
8	FRONT YARD LANDSCAPE: Prior to issuance of a Certificate of Occupancy the front yard must be landscaped. The existing front yard is already landscaped with no proposed modifications nor disturbances due to the project location. A note has been included on Sheet A1.1.
	ARBORIST REQUIREMENTS: The developer shall implement, at their cost, all recommendations identified in the Arborist's report for the project, on file in the Community Development Department. These recommendations must be incorporated in the building permit plans, and completed prior to issuance of a building permit where applicable. A Compliance Memorandum shall be prepared by the applicant and submitted with the building permit application
9	detailing how the recommendations have or will be addressed. These recommendations must be incorporated in the building permit plans, and completed prior to issuance of a building permit where applicable.
9	Recommendations have been added to new Sheet T-1 Tree Protection Plan. Tree replacement is not being proposed due to WUI requirements as planting new trees will result in a greater fire hazard than the original condition, especially when the trees are fully mature. Tree canopies in Zone 1 shall not touch in order to accommodate a reasonable fire break. Planting any new tree would not accommodate this. In-lieu fees are being
2	requested instead of planting any new trees.
10	SEPTIC SYSTEM: The proposed septic system, shown conceptually at this stage, will be reviewed in detail for compliance with Town Code and the Hillside Development Guidelines and Standards at time of building permit submittal. Town Arborist review will be required.
	There is no septic system being proposed as part of this project.
11	WATER EFFECIENCY LANDSCAPE ORDINANCE: The final landscape plan shall meet the Town of Los Gatos Water Conservation Ordinance or the State Water Efficient Landscape Ordinance, whichever is more restrictive. A review fee based on the current fee schedule adopted by the Town Council is required when working landscape and irrigation plans are submitted for review.
	Noted.
12	EXTERIOR COLORS: The exterior colors of all structures shall comply with the Hillside Development Standards & Guidelines. Noted. Proposed colors of the garage to match the existing residence. See A3.0 and A3.1. An exemption has been requested since the colors are already established on site.
13	LRV DEED RESTRICTION: Prior to the issuance of a building permit, a deed restriction shall be recorded by the applicant with the Santa Clara County Recorder's Office that requires all exterior materials be maintained in conformance with the Town's Hillside Development Standards & Guidelines.
	A LRV Deed restriction will be filed with the County Recorder's Office as requested. A note has been included on Sheet A1.1 to include the requirement.
14	STORY POLES: The story poles on the project site shall be removed within 30 days of approval of the Architecture & Site application. Story poles (and netting) are not required for this project since it is an accessory building and less than 18-feet in height.
	NESTING BIRDS: To avoid impacts to nesting birds, the removal of trees and shrubs shall be minimized to the greatest extent feasible. Construction activities that include any tree removal, pruning, grading, grubbing, or demolition shall be conducted outside of the bird nesting season (January 15 through September 15) to the greatest extent feasible. If this type of construction starts, if work is scheduled to start or if work already occurring during the nesting
	season stops for at least two weeks and is scheduled to resume during the bird nesting season, then a qualified biologist shall conduct a pre-construction surveys for nesting birds to ensure that no nests would be disturbed during
	project construction. If project-related work is scheduled during the nesting season (February 15 to August 30 for small bird species such as passerines; January 15 to September 15 for other raptors), a qualified biologist shall conduct nesting bird surveys. Two surveys for active nests of such birds shall occur within 14 days prior to start of construction, with the second survey conducted with 48 hours prior to start of construction. Appropriate minimum
	survey radius surrounding each work area is typically 250 feet for passerines, 500 feet for smaller raptors, and 1,000 feet for larger raptors. Surveys shall be conducted at the appropriate times of day to observe nesting activities. If the qualified biologist documents active nests within the project site or in nearby surrounding areas, an appropriate buffer between each nest and active construction shall be established. The buffer shall be clearly marked and
15	maintained until the young have fledged and are foraging independently. Prior to construction, the qualified biologist shall conduct baseline monitoring of each nest to characterize "normal" bird behavior and establish a buffer
	distance, which allows the birds to exhibit normal behavior. The qualified biologist shall monitor the nesting birds daily during construction activities and increase the buffer if birds show signs of unusual or distressed behavior (e.g. defensive flights and vocalizations, standing up from a brooding position, and/or flying away from the nest). If buffer establishment is not possible, the qualified biologist or construction foreman shall have the authority to cease all
	construction work in the area until the young have fledged and the nest is no longer active.
	A biologist will conduct pre-construction surveys 14 days before and 48 hours before construction starts on the project property site only. Visual observations for adjacent sites that occur within the mentioned ranges of 250', 500' and 1,000' shall occur within project property lines only to the maximum extent feasible. Access to adjacent properties will not occur due to logistics and is considered unreasonable for the scope of the project. Please
	note that at 250' three (3) adjacent properties are within this range; at 500' eighteen (18) adjacent properties are within this range; and at 1,000' sixty (60) adjacent properties are within this range. SPECIAL-STATUS BATS: Approximately 14 days prior to tree removal or structure demolition activities, a qualified biologist shall conduct a habitat assessment for bats and potential roosting sites in trees to be removed, in trees
	within 50 feet of the development footprint, and within and surrounding any structures that may be disturbed by the project. These surveys will include a visual inspection of potential roosting features (bats need not be present) and
	a search for presence of guano within the project site, construction access routes, and 50 feet around these areas. Cavities, crevices, exfoliating bark, and bark fissures that could provide suitable potential nest or roost habitat for bats shall be surveyed. Assumptions can be made on what species is present due to observed visual characteristics along with habitat use, or the bats can be identified to the species level with the use of a bat echolocation detector
	such as an "Anabat" unit. Potential roosting features found during the survey shall be flagged or marked.
	If no roosting sites or bats are found, a letter report confirming absence will be prepared and no further measures are required.
	If bats or roosting sites are found, a letter report and supplemental documents will be prepared prior to grading permit issuance and the following monitoring, exclusion, and habitat replacement measures will be implemented:
	a) If bats are found roosting outside of the nursery season (May 1 through October 1), they will be evicted as described under (b) below. If bats are found roosting during the nursery season, they will be monitored to determine if
16	the roost site is a maternal roost. This could occur by either visual inspection of the roost bat pups, if possible, or by monitoring the roost after the adults leave for the night to listen for bat pups. If the roost is determined to not be a maternal roost, then the bats will be evicted as described under (b) below. Because bat pups cannot leave the roost until they are mature enough, eviction of a maternal roost cannot occur during the nursery season.
	Therefore, if a maternal roost is present, a 50-foot buffer zone (or different size if determined in consultation with the CDFW) will be established around the roosting site within which no construction activities including tree removal or structure disturbance will occur until after the nursery season.
	b) If a non-breeding bat hibernaculum is found in a tree or snag scheduled for removal or on any structures scheduled to be disturbed by project activities, the individuals will be safely evicted, under the direction of a qualified bat
	biologist. If pre-construction surveys determine that there are bats present in any trees to be removed, exclusion structures (e.g. one-way doors or similar methods) shall be installed by a qualified biologist. The exclusion structures shall not be placed until the time of year in which young are able to fly, outside of the nursery season. Information on placement of exclusion structures shall be provided to the CDFW prior to construction.
	If needed, other methods conducted under the direction of a qualified bat biologist could include: carefully opening the roosting area in a tree or snag by hand to expose the cavity and opening doors/windows on structures, or
	creating openings in walls to allow light into the structures. Removal of any trees or snags and disturbance of any structures will be conducted no earlier than the following day (i.e., at least one night will be provided between initial roost eviction disturbance and tree removal/structure disturbance). This action will allow bats to leave during dark hours, which increases their chance of finding new roosts with a minimum of potential predation.
	A biologist investigation will occur approximately 14 days prior to any tree removal or demolition and within 50 feet of the impacted area only on the project site. Visual observations for adjacent sites that occur within the
	noted buffer zone shall occur within project property lines only to the maximum extent feasible. ARCHAEOLOGICAL RESOURCES AND HUMAN REMAINS:
	a) In the event that archaeological traces are encountered, all construction within a 50- meter radius of the find will be halted, the Community Development Director will be notified, and an archaeologist will be retained to
	examine the find and make appropriate recommendations. b) If human remains are discovered, the Santa Clara County Coroner will be notified. The Coroner will determine whether or not the remains are Native American. If the Coroner determines the remains are not subject to his
112521	authority, he will notify the Native American Heritage Commission, who shall attempt to identify descendants of the deceased Native Americans. c) If the Community Development Director finds that the archaeological find is not a significant resource, work will resume only after the submittal of a preliminary archaeological report and after provisions for reburial and
17	ongoing monitoring are accepted. Provisions for identifying descendants of a deceased Native American and for reburial will follow the protocol set forth in CEQA Guidelines Section 15064.5(e). If the site is found to be a
	significant archaeological site, a mitigation program will be prepared and submitted to the Community Development Director for consideration and approval, in conformance with the protocol set forth in Public Resources Code Section 21083.2.
	d) A final report shall be prepared when a find is determined to be a significant archaeological site, and/or when Native American remains are found on the site. The final report will include background information on the completed work, a description and list of identified resources, the disposition and curation of these resources, any testing, other recovered information, and conclusions.
ć	If encountered, the contractor shall proceed as such. DUSKY-FOOTED WOODRATS: This project will implement the following standard measures to minimize impacts on woodrats and active woodrat nests on the project site.
	a) PRECONSTRUCTION SURVEY. A qualified biologist will conduct a preconstruction survey for San Francisco dusky-footed woodrat nests within 30 days of the start of work activities. If active woodrat nests are determined to be
	present in, or within 10 feet of the impact areas, the conditions below (Avoidance and/or Nest Relocation) will be implemented, as appropriate. If no active woodrat nests are present on or within 10 feet of impact areas, no further conditions are warranted.
	b) AVOIDANCE. Active woodrat nests that are detected within the work area will be avoided to the extend feasible. Ideally, a minimum 10-foot buffer will be maintained between project activities and woodrat nests to avoid
18	disturbance. In some situations, a small buffer may be allowed if, in the opinion of a qualified biologist, nest relocation (below) would represent a greater disturbance to the woodrats than the adjacent work activities. c) NEST RELOCATION. If avoidance of active woodrat nests within and immediately adjacent to (within 10 feet of) the work areas is not feasible, then nest materials will be relocated to suitable habitat as close to the project site
10	as possible (ideally, within or immediately adjacent to the project site). Relocation efforts will avoid the peak nesting season (February-July) to the maximum extent feasible. Prior to the start of construction activities, a qualified biologist will disturb the woodrat nest to the degree that all woodrats
	leave the nest and seek refuge outside of the construction area. Disturbance of the woodrat nest will be initiated no earlier than one hour before dusk to prevent the exposure of woodrats to diurnal predators. Subsequently,
	the biologist will dismantle and relocate the nest material by hand. During the deconstruction process, the biologist will attempt to assess if there are juveniles in the nest. If immobile juveniles are observed, the deconstruction process will be discontinued until a time when the biologist believes the juveniles will be capable of independent survival (typically after 2 to 3 weeks). A no-disturbance buffer will be established around the nest until the
	juveniles are mobile. The nest may be dismantled once the biologist has determined that adverse impacts on the juveniles would not occur. A biologist preconstruction survey will be supplied within 30 days of construction and within 10 feet of the impacted areas.





PROJECT TITLE

REVISIONS F PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC M PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS Q PLANNING COMMENTS

PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

CONDITIONS OF APPROVAL



NONE

PROJECT NUMBER: 24111/6285



Fire department (engine) driveway turnaround of 40 feet. The existing area at the top of the driveway does not accommodate a 40-foot radius turnaround. The current turnaround space is 16-foot radius. Significant modifications and retaining walls would be required in order to achieve this. The added cost would be disproportionate to the total cost of the entire project without this element.

Wildland Urban Interface Compliance

There are several Wildland Urban Interface compliance items being implemented into the project. In the end, the garage will be safer and more ignition resistant than before the project. The following items are being incorporated into the project.

Exterior cladding - ignition resistant materials - stucco Roof materials - Class A asphalt roof tiles Closed eaves

Ember resistant soffit vents Ember resistant ridge vents Ember resistant gable-end vents

Metal-cladded door assemblies with tempered windows

All doors have perimeter weather stripping and door bottoms to reduce ember intrusion

Vegetation management & defensible breaks


Windows double-paned and tempered

Zone 0 (5'-0") will be concrete on the back of the garage, asphalt in the front of the garage, mostly existing pavement on the west side and concrete or rock-line swale on the east. There is a 3' section that a rock-gravel surface may be added to ensure no landscaping. Also removing 2 trees currently next to structure.

Zone 1 (30'-0") - existing trees to remain; owner to maintain ground cover to remove dead weeds.

Zone 2 (100'-0") - existing trees to remain; no proposed modifications.

3360 De La Cruz Blvd. | Santa Clara, CA 95054 | 408-648-4500 | CA Lic 443949 | www.ba-builders.com



Justification for Alternate Compliance

The presence of fire sprinklers in a structure offer the best form of protection against fire. The fire water tank supplies enough water to accommodate fire-fighting for the size of the structure in lieu of a fire

The addition of fire sprinklers would provide additional protection for the structure and assist in extinguishing or holding a fire inc heck until firefighters arrive. The fire-barrier would slow the rate of fire growth between structures.

The combination of adding fire sprinklers in the garage along with 2-hour fire-barrier will slow the rate of the fire's growth and contain the spread of fire to one part of the building. The dedicated fire water storage tank allows additional water to assist with fighting fire.

Implementation of Wildland Urban Interface requirements along with the addition of fire sprinklers creates a greater resistance to fires by slowing the burning and spread. Additionaly, the same occurs with a two-hour fire barrier between a protected and unprotected structure.

Fire sprinkler systems are generally expected to last 40-50 years, however with regular inspections, testing

and maintenance, the life of the system will be extended. Compliance with NFPA 13D & SCCFD requirements will accommodate these requirements.

Adding fire sprinklers allows a greater protection for the structure and increases the time to allow occupants to evacuate the structure. A two-hour fire-rated barrier also increases the time for a fire to burn through a sprinklered protected. Overall life-safety is increased.

3360 De La Cruz Blvd. | Santa Clara, CA 95054 | 408-648-4500 | CA Lic 443949 | www.ba-builders.com



Use of Alternate Materials or Method of Construction



Santa Clara County Fire Department Fire Prevention Department 14700 Winchester Blvd. | Los Gatos, CA 95032 www.sccfd.org

SCCFD Plan Check: 24-3772 Los Gatos Planning: S-24-045 Address: 16511 Cypress Way | Los Gatos, CA

Description: Garage & Breezeway Replacement

In Lieu of the following items:

Brief Project Summary The proposed project is to replace an existing single-story two-car garage of 587 square feet and shed of 96 square feet with a new single-story three-car garage of 1,239 square feet. The new garage will be in the same location. In addition, the existing breezeway will be replaced in the same location. The project site is located in a very high fire hazard severity zone (VHFHSZ) and will incorporate Wildland Urban Interface requirements as specified in the California Residential Code.

Proposed Use of Alternate Materials or Method of Construction

- Fire apparatus access roadway clearances (CFC Section 503) street width of 20'-0" clear by 13'-
- 6" high actual road is 12'-0" wide and doesn't achieve height requirements • Fire department driveway turnaround clearance (CFC Section 503) - driveway area does not accommodate 40' minimum outside turning radius.
- Fire hydrant distance within 400' or 600' if fully sprinklered (CFC Section 507.5.1)— actual fire hydrant is approx. 1,975' away from the property line.

The following is being proposed due to the scale of the project. Please note that this approach has been discussed with the County Fire Department and is part of the AMMC application process.

- NFPA 13D fire sprinkler system in garage structure only. The main residence will remain unsprinklered.
- Inclusion of a 2-hour fire-barrier wall assembly at garage between breezeway to act as a fire break. 5,000 gallon fire water storage polyethylene tank (no pump) located at least 10'-0" from garage structure with 4" diameter underground water line and connection to a new wharf hydrant located at the northeasterly corner of the property adjacent to the driveway access. Impact protection bollards will be included to prevent accidental damage.
- Address directional and identification signage visible from the approaching corner (east corner) of Cypress Way where the road splits in two directions. This accommodates greater visibility to limit the time to find the residence.

3360 De La Cruz Blvd. | Santa Clara, CA 95054 | 408-648-4500 | CA Lic 443949 | www.ba-builders.com

Expanded Description for in lieu Items

Fire Apparatus Road – requires a minimum width of 20 feet width 13 feet 6 inches vertical clearance. The section of Cypress Way from the main section to the residence is a 12-foot wide country road about 0.325 miles (1,750 feet) with significant barriers to accommodate a 20-foot minimum width such as existing residences along with inclines and declines at the cross sections that would require significant retaining walls, removal of several trees/foliage and possibly eminent domain in order to achieve. This is an extremely expensive compliance item and is significantly disproportionate to the total cost of the project.





Driveway entrance to accommodate a turning radius of 50 feet outside and 30 feet inside with a maximum slope of 15%. Slopes at the driveway exceed 15% and turning radii currently does not exist on the property without significant demolition, grading, paving and retaining walls in order to achieve. Alternatively, providing a turnout along Cypress Way resulting in significant retaining walls at the front portion of the property. The added cost would be disproportionate to the total cost of the entire project without this element.





3360 De La Cruz Blvd. | Santa Clara, CA 95054 | 408-648-4500 | CA Lic 443949 | www.ba-builders.com

Codes Affected: Building Code ✓ Fire Code Mechanical Code ☐ Electrical Code Other:

Applicant's Address: 3360 De La Cruz Blvd. | Santa Clara, CA 95054 Suite

FIRE DEPARTMENT SANTA CLARA COUNTY

Project Address: 16511 Cypress Way | Los Gatos, CA 95030

Applicant's Name: Michael Harris, Bay Area Builders

✓ Use of Alternate Materials or Method of Construction

The applicant hereby requests the following:

Telephone: (408) 690-6877

☐ Modification of Code

14700 Winchester Blvd., Los Gatos, CA 95032-1818

(408) 378-4010 (408) 378-9342 (fax) www.sccfd.org

APPLICATION FOR USE OF ALTERNATE MATERIALS, METHODS OF

CONSTRUCTION, OR MODIFICATION OF CODE

Specific section(s) of the code involved: 2022 CFC Section 503 & 507.5.1 Brief description of the request: In lieu of fire apparatus roadway, driveway turnaround and fire hydrant req'ts,

the following is being proposed: NFPA 13D sprinklers in garage only with 2-hour fire-rated wall at breezeway, new

5,000 gallon fire water storage tank and address directional sign where Cypress Way splits into two directions The Building and Fire Official must evaluate information that the material(s), method of work, and/or modification is equal to the intent of the code in strength, effect, fire-resistance, durability, safety, etc. RECEIVED

25-0417

Email: mharris@ba-builders.com

SANTA CLARA COUNTY Organized as the Santa Clara County Central Fire Protection FRET PEPARTMENT Serving Santa Clara County and the communities of Campbell, Cupertino, Los Altos, Los Altos Hills, Los Gatos, Monte Serena, and Saratoga

Please complete the following information as applicable to support your request. Use additional

The presence of fire sprinklers in a structure offer the best form of protection against fire. The 1. Quality: The presence of the spinicles in a structure of the structure fire water tank supplies enough water to accommodate fire-fighting for the size of the structure

- The addition of fire sprinklers would provide additional protection for the structure and assist in 2. Strength extinguishing or holding a fire inc heck until firefighters arrive. The fire-barrier would slow the rate of fire growth between structures.
- The combination of adding fire sprinklers in the garage along with 2-hour fire-barrier will 3. Effectiveness: slow the rate of the fire's growth and contain the spread of fire to one part of the building. The dedicated fire water storage tank allows additional water to assist with fighting fire.
- Implementation of Wildland Urban Interface requirements along with the addition of 4. Fire Resistance: fire sprinklers creates a greater resistance to fires by slowing the burning and spread. Additionaly, the same occurs with a two-hour fire barrier between a protected and unprotected structure.
- 5. Durability: inspections, testing and maintenance, the life of the system will be extended. Compliance with NFPA 13D & SCCFD requirements will accommodate these requirements. Adding fire sprinklers allows a greater protection for the structure and increases the time to allow

Fire sprinkler systems are generally expected to last 40-50 years, however with regular

6. Safety: occupants to evacuate the structure. A two-hour fire-rated barrier also increases the time for a fire to burn through a sprinklered protected. Overall life-safety is increased.

Additional evidence of proof: Please refer to attached for consideration.

Applicant Signature: Michael Harris Digitally signed by Michael Harris Date: 2025.01.24 12:00:16 -08'00' Date: 1/24/2025 *************

The above application has been reviewed and has been:

Alternative materials/ss/12.31.14



DEVELOPMENTAL REVIEW COMMENTS Plans and Scope of Review:

This project shall comply with the following

The California Fire (CFC) & Building (CBC) Code, 2022 edition, as adopted by the Town of Los Gatos Town

The scope of this project includes the following:

Code (LGTC), California Code of Regulations (CCR) and Health & Safety Code.

Alternate Means/Methods Application - Proposed demolition and 652 SF attached garage addition to an existing one-story single-family residence.

Plan Status:

The alternate means/methods request is Approved.

This AMMR proposes to install a NFPA 13D sprinkler system in the new garage with a 2-hour fire-rated wall between the new breezeway. A new 5.000 gallon water tank located 10' away from garage with 4" diameter underground water line connection and a new wharf hydrant located outside the driveway gate at the northeast corner of the property. Vehicle impact protection bollard will be provided. Additionally, an address directional sign will also be installed where Cypress Way splits into two directions (Approaching corner of Cypress Way). Vegetation management and defensible break will be provided including Zone 0 trees removal and Zone 1 ground maintenance. These proposal are to mitigate a non-compliance roadway, turnaround and hydrant. The current road width is 12ft, the driveway area does not accommodate 40' minimum outside turning radius and the closest fire hydrant is 1975' away from the property line.

Review Comments:

1. A copy of the approved Alternate Means/Methods application form (with approval signature), justification letter, and these comments shall be made part of all subsequent submittals (Building, planning, etc.), to be routed to Santa Clara County Fire Department for final approval.

2. Sign shall be posted on the wharf hydrant indicating it is supplied by a 5,000 gallon tank.

City LGA	PLANS :	SPECS NE		L AS	R-3/U	CONST. TYPE VB	Applican	Bay Area	Builders	02/27/2025	PAGE 1 OF 2
SEC/FLOOR	4733		LOAD	1.7	PROJECT DESCRIP Residential I	TION Development			PROJECT TYPE OR Exception Re	sysтем equest - PRC-4290	
NAME OF PRO		E & ST	ORAC	E		LOCATION 1651		ess Way Los	Gatos		
TABULAR FIRE FLOW REDUCTION FO			ON FOR FIRE SPRIN	KLERS	REQUIRED FIRE FI	IRE FLOW @ 20 PSI BY Ip, Kenny					
		70.00								-47	

A California Fire Protection District serving Santa Clara County and the communities of Campbell, Cupertino, Los Altos, Los Altos Hills, Los Gatos, Monte Sereno, Saratoga and the surrounding unincorporated communities.





315 Dell Avenue, Campbell, CA 95008 1 (408) 378-4010 1 SCCFD.org

REVIEW No. 25 0417

DEVELOPMENTAL REVIEW COMMENTS

Review Comments: (con't)

3. Fire Sprinklers shall be listed as a deferred submittal item plans.

This review shall not be construed as an approval of a violation of the provisions of the California Fire Code or other laws or regulations of the jurisdiction. A permit presuming to give authority to violate or cancel the provisions of the fire code or other such laws or regulations shall not be valid. Any addition or alteration of approved construction documents shall be approved in advance. [CFC 105.3.6]

02/27/2025 2 LGA 🛛 🗖 🗖 🗖 R-3/U Bay Area Builders PROJECT TYPE OR SYSTEM Exception Request - PRC-4290 4733 Residential Development **NEW GARAGE & STORAGE** 16511 Cypress Way Los Gatos 1750 Ip, Kenny

Los Altos, Los Altos Hills, Los Gatos, Monte Sereno, Saratoga and the surrounding unincorporated communities.

A California Fire Protection District serving Santa Clara County and the communities of Campbell, Cupertino,





Q

M

0

REVISIONS | PLANNING SUBMITTAL 10/23/2024 PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS

3/5/2025

3/17/2025

3/24/2025 PLANNING COMMENTS | PLANNING COMMENTS 3/28/2025 **CONDITIONS & RESTRICTIONS**

PLANNING COMMENTS

| PLANNING COMMENTS

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions ndicated or consult the architect.

SHEET TITLE

SCCFD AMMR

COMMENTS DURING PLANNING

- REVIEW OF THIS DEVELOPMENTAL PROPOSAL IS LIMITED TO ACCEPTABILITY OF SITE ACCESS, WATER SUPPLY AND MAY INCLUDE SPECIFIC ADDITIONAL REQUIREMENTS AS THEY PERTAIN TO FIRE DEPARTMENT OPERATIONS, AND SHALL NOT BE CONSTRUED AS A SUBSTITUTE FOR FORMAL PLAN REVIEW TO DETERMINE COMPLIANCE WITH ADOPTED MODEL CODES. PRIOR TO PERFORMING ANY WORK, THE APPLICANT SHALL MAKE APPLICATION TO, AND RECEIVE FROM, THE BUILDING DEPARTMENT ALL APPLICABLE CONSTRUCTION PERMITS. NOTED.
- THE SUBJECT PROPERTY IS LOCATED WITHIN THE VERY HIGH FIRE HAZARD SEVERITY ZONE (VHFHSZ) OF THE LOCAL RESPONSIBILITY AREA (LRA). PURSUANT TO CALIFORNIA PUBLIC RESOURCES CODE (PRC) 4290, THE CALIFORNIA BOARD OF FORESTRY AND FIRE PROTECTION IS REQUIRED TO "...ADOPT REGULATIONS IMPLEMENTING MINIMUM FIRE SAFETY STANDARDS RELATED TO DEFENSIBLE SPACE" APPLICABLE TO "THE PERIMETERS AND ACCESS TO ALL RESIDENTIAL, COMMERCIAL, AND INDUSTRIAL BUILDING CONSTRUCTION." IN 2018, THE LEGISLATURE PASSED AND THE GOVERNOR SIGNED SB 901 (DODD), WHICH EXPANDED THE APPLICABILITY OF THE REGULATIONS PROMULGATED UNDER PRC 4290 TO LAND IN THE LOCAL RESPONSIBILITY AREA (LRA) VERY HIGH FIRE HAZARD SEVERITY ZONE. ALL COMMENTS BELOW THAT RESULT FROM PRC 4290 ARE IDENTIFIED BY **. WHERE A CONFLICT EXISTS BETWEEN LOCAL & 4290 REQUIREMENTS, THE MORE STRINGENT REQUIREMENT SHALL APPLY. CALIFORNIA CODE OF REGULATIONS, TITLE 14, DIVISION 1.5, CHAPTER 7, SUBCHAPTER 2, ARTICLES 1-5, § 1273.08. NOTED.
- 3. ADDITION TO AN EXISTING STRUCTURE IS CURRENTLY EXEMPTED FROM PRC 4290.
- 4. FIRE SPRINKLERS REQUIRED: APPROVED AUTOMATIC SPRINKLER SYSTEMS IN NEW AND EXISTING BUILDINGS AND STRUCTURES SHALL BE PROVIDED IN THE LOCATIONS DESCRIBED IN THIS SECTION OR IN SECTIONS 903.2.1 THROUGH 903.2.12 WHICHEVER IS THE MORE RESTRICTIVE AND SECTIONS 903.2.14 THROUGH 903.2.21. FOR THE PURPOSES OF THIS SECTION, FIREWALLS AND FIRE BARRIERS USED TO SEPARATE BUILDING AREAS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CALIFORNIA BUILDING CODE AND SHALL BE WITHOUT OPENINGS OR PENETRATIONS. FIRE SPRINKLERS PROPOSED IN NEW GARAGE AS PART OF THE AMMR CONDITIOI PC 25-0417. MAKE A NOTE ON COVERSHEET THAT A AMMR IS INCLUDED IN THIS PROJECT. A COPY OF THE APPROVED ALTERNATE MEANS/METHODS APPLICATION FORM (WITH APPROVAL SIGNATURE), JUSTIFICATION LETTER, AND THESE COMMENTS SHALL BE MADE

PART OF ALL SUBSEQUENT SUBMITTALS (BUILDING, PLANNING, ETC.), TO BE ROUTED TO SANTA CLARA COUNTY FIRE DEPARTMENT

- PLEASE REFER TO GENERAL NOTE #22 ON THE COVER SHEET ADDED TO INCLUDE THE AMMR REFERENCE. SHEET A0.2 HAS BEEN MODIFIED TO INCLUDE THE APPROVED AMMR, JUSTIFICATION AND THESE COMMENTS AS REQUESTED
- 5. PRIVATE FIRE PROTECTION SYSTEM: RESIDENTIAL FIRE PROTECTION SYSTEMS SHALL COMPLY WITH FIRE DEPARTMENT STANDARDS W-1 AND MANUFACTURER'S REQUIREMENTS. FIRE PROTECTION WATER SYSTEMS SHALL BE SUBMITTED FOR REVIEW AND APPROVAL BY SCCFD PRIOR TO INSTALLATION. THE WHARF HYDRANT SHALL BE ACCESSIBLE AT ALL TIMES, TANK SYSTEMS PROVIDING BOTH THE DOMESTIC SUPPLY AND SUPPLY TO THE SPRINKLER SYSTEM AND/OR HYDRANT MAY REQUIRE CROSS CONTAMINATION PROTECTION. CHECK WITH THE LOCAL BUILDING DEPARTMENT FOR SPECIFIC REQUIREMENTS RELATED TO PROTECTION OF THE DOMESTIC SUPPLY. NEW 5000 GALLON WATER TANKS NOTED ON SHEET A1.1. MAKE A NOTE ON COVERSHEET THAT PRIVATE FIRE PROTECTION SYSTEM L BE PROVIDED AS PART OF THE APPROVED AMMR CONDITION. SIGN SHALL BE POSTED ON THE WHARF HYDRANT INDICATING IT IS SUPPLIED BY A 5,000 GALLON TANK
- PLEASE REFER TO GENERAL NOTE #23 ON THE COVER SHEET ADDED TO REFLECT THE REQUEST. FIRE HYDRANT SYSTEMS REQUIRED: WHERE A PORTION OF THE FACILITY OR BUILDING HEREAFTER CONSTRUCTED OR MOVED INTO OR WITHIN THE JURISDICTION IS MORE THAN 400 FEET FROM A HYDRANT ON A FIRE APPARATUS ACCESS ROAD, AS MEASURED BY AN APPROVED ROUTE AROUND THE EXTERIOR OF THE FACILITY OR BUILDING, ONSITE FIRE HYDRANTS AND MAINS SHALL BE PROVIDED WHERE REQUIRED BY THE FIRE CODE OFFICIAL. EXCEPTION: FOR GROUP R-3 AND GROUP U OCCUPANCIES, EQUIPPED THROUGHOUT

WITH AN APPROVED AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3.1.1, 903.3.1.2 OR 903.3.1.3,

THE DISTANCE REQUIREMENT SHALL BE NOT MORE THAN 600 FEET. [CFC, SECTION 507.5.1] SHOW WHARF HYDRANT AND VEHICLE IMPACT PROTECTION BOLLARD ON PLANS AS PART OF THE APPROVED AMMR CONDITION. SIGN SHALL BE POSTED ON THE WHARF HYDRANT INDICATING IT IS SUPPLIED BY A 5,000 GALLON TANK. PLEASE REFER TO SHEET A1.1 SHOWING THE LOCATION OF THE WHARF HYDRANT ALONG WITH IMPACT PROTECTION AND SIGNAGE.

CONSTRUCTION SITE FIRE SAFETY: ALL CONSTRUCTION SITES MUST COMPLY WITH APPLICABLE PROVISIONS OF THE CFC CHAPTER AND OUR STANDARD DETAIL AND SPECIFICATION S1-7. PROVIDE APPROPRIATE NOTATIONS ON SUBSEQUENT PLAN SUBMITTALS, A APPROPRIATE TO THE PROJECT. CFC CHP. 33. THE APPLICABLE CONSTRUCTION SITE FIRE-SAFETY PROVISIONS ARE INCLUDED ON SHEET A1.2.




24111/6285 NONE

Construction Best Management Practices (BMPs)

Campbell . Los Gatos . Monte Sereno . Saratoga

Construction projects are required to implement year-round stormwater BMPs.

Materials, Waste, and Sediment Management



Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls, and stabilize all construction entrances and exits to sufficiently control erosion, sediment discharges and tracking of sediment offsite.
- ☐ Sweep or vacuum immediately any tracking of sediment offsite and secure sediment source to prevent further tracking. Never hose down streets or sidewalks.

Non-Hazardous Materials and Dust Control

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use. Weigh down and secure tarps
- ☐ Keep materials off the ground (e.g., store bagged materials on wood pallets, store loose materials on tarps not pavement, etc.).
- ☐ Use captured water from other activities (e.g., testing fire lines) for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains. Only use enough to control dust. Contain and dispose of excess water properly.


Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with City, County, State and Federal regulations.
- ☐ Store hazardous materials and wastes in watertight containers, store in appropriate secondary containment, and cover them at the end of every workday, during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes. Have all pertinent Safety Data Sheets (i.e., SDS/MSDS/PSDS) onsite.

Waste Management

- ☐ Inform trash-hauling contractors that you will accept only watertight dumpsters for onsite use. Repair/replace any dumpster that is not watertight or leaking.
- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. If the dumpster leaks, place a plastic liner underneath the dumpster to collect leaks. Never clean out a dumpster by hosing it down on the construction site – clean with dry methods, clean offsite or replace dumpster.
- Place portable toilets and hand wash stations away from storm drains. Make sure they are equipped with containment pans (secondary containment) and are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly per SDS and applicable regulations. Recycle or compost materials and wastes as feasible and appropriate, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste per SDS.
- ☐ Keep site free of litter (e.g., lunch items, water bottles, cigarette butts and plastic packaging).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Equipment Management & Spill Control




Vehicle and Equipment Maintenance

- ☐ Designate an area of the construction site equipped with appropriate BMPs, well away from creeks or storm drain inlets, for auto and equipment parking and storage.
- Perform major maintenance, repair jobs, and vehicle/equipment washing offsite.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or creeks.
- ☐ Do not clean vehicles or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- Always keep spill cleanup materials (e.g., rags, absorbents, and cat litter) available at the construction site.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately using dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags) and dispose of cleanup materials properly.
- Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- Report significant spills to the appropriate local spill response agencies immediately. If the spill poses a significant hazard to human health and safety, property or the environment, report it to the State Office of Emergency Services at (800) 852-7550 (24 hours).

Earthmoving



Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and creeks by installing and maintaining appropriate BMPs tailored to the site's specific characteristics and conditions. Examples of such BMPs may include silt fences, gravel bags, fiber rolls, temporary swales, compost socks, etc. Ensure that BMPs are installed in accordance with manufacturer's specifications and properly maintained throughout the duration of construction activities.
- ☐ Stabilize all denuded areas and install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established
- ☐ Remove existing vegetation only when necessary. Plant temporary vegetation to prevent erosion on slopes or in areas where construction is not immediately planned.
- ☐ Keep excavated soil and/or transfer it to dump trucks, onsite, not in the streets. Ensure all subcontractors working onsite are implementing appropriate BMPs.


Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board and the local agency: 1) Unusual soil conditions, discoloration, or odor. 2) Abandoned underground tanks. 3) Abandoned wells. 4) Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination, clearly mark areas and fence/tape them off so they are not disturbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps year-round.
- ☐ Stack bagged material on pallets and under cover. ☐ Discontinue application of any erodible landscape
- material within 2 days before a forecast rain event or during wet weather.
- ☐ Store materials onsite, not in the street.

Concrete Management & Dewatering




Concrete Management

- ☐ Store both dry and wet concrete-related materials under cover, protected from rainfall and runoff and away from storm drains or creeks. Store materials off the ground on pallets. Protect dry materials from
- Avoid pouring concrete in wet weather or when rainfall is imminent to prevent concrete that has not cured from contacting stormwater runoff.
- ☐ Wash out concrete equipment/mixers/trucks offsite, or onsite only in designated washout containers/areas where the water will flow into a temporary lined waste pit and in a manner that will prevent leaching into the underlying soils. (See CASQA Construction Stormwater BMP Handbook for temporary concrete washout facility details).
- ☐ Do not wash sweepings from exposed aggregate concrete into the street or storm drain. Collect and return sweepings to aggregate base stockpile or dispose properly.
- ☐ Make sure that construction waste (e.g., concrete, stucco, cement wastewater, or residual materials) is collected, removed, and disposed of only at authorized disposal areas. Do not dispose of construction waste in storm drains, ditches, streets, creeks, dirt areas, or the sanitary sewer.

Dewatering

- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible, send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer, obtain permission from the local wastewater treatment plant.
- ☐ Divert water originating from offsite away from all onsite disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call the local agency to determine whether the groundwater must be tested. Pumped groundwater may need to be collected and hauled offsite for treatment and proper disposal.
- ☐ For additional information, refer to the CASQA's Sheet NS-2 "Dewatering Operations."

Paving/Asphalt Work




- ☐ Avoid paving and seal coating in wet weather or when rain is forecast to prevent materials that have not cured from contacting with stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ When construction is complete, remove all covers from storm drain inlets and manholes.
- ☐ Collect and recycle or properly dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters, storm drains, streets, dirt areas, or the sanitary sewer.

Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw
- ☐ When making saw cuts, use as little water as possible.
- Residue from saw cutting, coring and grinding operations shall be picked up by means of a vacuum device.
- ☐ Shovel, absorb, or vacuum saw cut slurry deposits and dispose of all waste properly and as soon as reasonably possible. Sawcutting residue should not be left on pavement surface.
- ☐ If saw cut slurry enters a storm drain inlet, clean it up immediately and notify the local municipality.

Painting & Paint Removal



Painting Cleanup and Removal

- ☐ Never clean brushes or rinse drain, or creek.
- ☐ For water-based paints, paint out brushes to the extent possible, and then rinse into a drain connected to the sanitary sewer. Never pour paint down a storm drain inlet.
- ☐ For oil-based paints, paint out brushes to the extent possible, and then clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust generated from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead- based paint removal requires a state-certified contractor.




Copper Architectural Features

Discharges to storm drains generated by installing, cleaning, treating or washing copper architectural features, is a violation of the municipal stormwater ordinance and may be subject to a fine. These BMPs must be implemented to prevent prohibited discharges to storm drains: **During Installation**

- ☐ If possible, purchase copper materials that have been pre-patinated at the factory.
- ☐ If patination done on site, implement one or more of the following BMPs: 1. Discharge the rinse water to landscaping. Ensure that the rinse water does
 - not flow to the street or storm drain. Block off storm drain inlet if needed. 2. Collect rinse water in a tank and pump to the sanitary sewer. Contact your
 - local sanitary sewer agency before discharging to the sanitary sewer. 3. Collect the rinse water in a tank and haul off-site for proper disposal.
- ☐ Consider coating the copper materials with an impervious coating that prevents further corrosion and runoff. This will also maintain the desired color for a longer time, requiring less maintenance.

During Maintenance such as, power washing roof, re-patination, or re-application of impervious coating:

- ☐ Block storm drain inlets as needed to prevent runoff from entering storm drains.
- ☐ Discharge the wash water to landscaping or to the sanitary sewer (with permission from the local sanitary sewer agency). If this is not an option, haul the wash water off-site for proper disposal.



- paintcontainers to landscaping, dirt areas or into a street, gutter, storm



REVISIONS PLANNING SUBMITTAL 0/23/2024 PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS 2/13/2025 /5/2025 PLANNING COMMENTS PLANNING COMMENTS /17/2025 PLANNING COMMENTS PLANNING COMMENTS

PROJECT TITLE

These drawings and all related specifications are nstruments of service and shall remain property the designer. No revisions, reproductions, or use o these documents shall be made without the consent n these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions ndicated or consult the architect.

CONDITIONS & RESTRICTIONS

SHEET TITLE

CONSTRUCTION **BEST MANAGEMENT** PRACTICES (BMPs)



PROJECT NUMBER: 24111/6285 NONE **A0.3**

Storm drain polluters may be liable for fines of up to \$10,000 per day!

CALGREEN RESIDENTIAL BUILDING CODE **MANDATORY MEASURES**

	MANDATORY MEASURES									
4.5	ANY INSTALLED GAS FREPLACE SHALL BE A DIRECT-VENT SEALED-COMBUSTION TYPE. ANY INSTALLED GAS FREPLACE SHALL DE A DIRECT-VENT SEALED-COMBUSTION TYPE. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACES SHALL ALL COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACE SHALL EAST COMPLY WITH U.S. EAP PAPER. ANY INSTALLED GAS FREPLACE SHALL EAST COMPLY WITH U.S. EAP PAPER. A COVERNO OF DUCT OPENIOS AND OTHER RELATED AIR DISTRIBUTION COMMONENT OPENIOS. AND EQUIPMENT DURING CONSTRUCTION UNTIL FINAL STARTUP OF THE HAAC. EQUIPMENT DURING CONSTRUCTION UNTIL FINAL STARTUP OF THE HAAC. A COMPLIANT OF THE COMPLIANT WITH U.S. EARLY COMPLIANT WITH U.S. EARLY COMPLIANT W									
SECTION	DESCRIPTION	REQUIREMENTS SUMMARY			-	REMARKS				
4.503.1	FIREPLACES	TYPE. ANY INSTALLED WOODSTOVE OR PELLET STOVE SHALL COMPLY WITH U.S. EPA PHASE II EMISSION LIMITS WHERE APPLICABLE. WOODSTOVES, PELLET STOVES AND FIREPLACES SHALL ALSO COMPLY WITH APPLICABLE LOCAL	123	NO	+	NO FIREPLACE AT GARGAGE				
4.504.1	PROTECTION AND MECHANICAL	ARE COVERED DURING CONSTRUCTION UNTIL FINAL STARTUP OF THE HVAC			Х	_				
4.504.2.1	ADHESIVES, SEALANTS AND CAULKS		X			REF. LIMITS THIS SHEET				
4.504.2.2	PAINTS AND COATINGS	ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, UNLESS MORE	X			REF. LIMITS THIS SHEET				
4.504.2.3	AEROSOL PAINTS AND COATINGS	ARCHITECTURAL PAINTS AND COATINGS ARE COMPLIANT WITH VOC LIMITS.			X	_				
4.504.2.3	VERIFICATION		X			_				
4.504.3	CARPET SYSTEMS				X	_				
4.504.4	RESILIENT FLOORING SYSTEMS	WITH THE VOC-EMISSION LIMITS THIS SHEET AND PRODUCTS CERTIFIED UNDER THE RESILIENT FLOOR COVERING INSTITUTE (RFCI) FLOORSCORE PROGRAM OR UL GREENGUARD GOLD OR MEET CALIFORNIA DEPARTMENT OF PUBLIC HEALTH			X	_				
4.504.5	COMPOSITE WOOD PRODUCTS	COMPOSITE WOOD PRODUCTS USED ON THE INTERIOR OR EXTERIOR OF THE BUILDING SHALL MEET THE REQUIREMENTS FOR FORMALDEHYDE AS SPECIFIED IN ARB'S AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD (17 CCR 93120			X	_				
4.505.2	CONCRETE SLAB FOUNDATIONS		X							
4.505.3		FRAMING DO NOT EXCEED 19% PRIOR TO ENCLOSURE AND IS CHECKED BEFORE	×			INSPECTOR BEFORE ENCLOSURE; CONTRACTOR SHALL VERIFY MOISTURE CONTENT PRIOR TO				
4.506.1	BATHROOM EXHAUST FANS				X	_				
4.507.2			X							
702	QUALIFICATIONS	HVAC SYSTEMS INSTALLERS ARE TRAINED AND CERTIFIED IN THE PROPER INSTALLATION OF HVAC SYSTEMS. SPECIAL INSPECTORS MUST BE QUALIFIED AND ABLE TO DEMONSTRATE COMPETENCE TO THE ENFORCING AGENCY IN THE DISCIPLINE IN WHICH THEY ARE INSPECTING.	X			REFER TO CA TITLE 24 COMPLIANCE FOR VERIFICATION/QUALIFICATIONS				
703.1	DOCUMENTATION	DOCUMENTATION OF COMPLIANCE SHALL INCLUDE, BUT IS NOT LIMITED TO, CONSTRUCTION DOCUMENTS, PLANS, SPECIFICATIONS, BUILDER OR INSTALLER CERTIFICATION, INSPECTION REPORTS, OR OTHER METHODS ACCEPTABLE TO THE LOCAL ENFORCING AGENCY. OTHER SPECIFIC DOCUMENTATION OR SPECIAL INSPECTIONS NECESSARY TO VERIFY COMPLIANCE ARE SPECIFIED IN APPROPRIATE SECTIONS OF CALGREEN.	×			OWNER TO PROVIDE DOCUMENTATION AS REQUESTED BY CITY INSPECTIOR				

GENERAL NOTES

- A. REFER TO SHEET AO FOR INDEX OF DRAWINGS & GENERAL NOTES.
- B. CERTAIN PROVISIONS OF THE 2022 CALGREEN BUILDING CODE SHALL APPLY (SECTION 101.3) AND 2022 CALGREEN RESIDENTIAL MANDATORY MEASURES CHECKLIST. HOWEVER, ONLY MANDATORY MEASURES RELEVANT TO BUILDING COMPONENTS/SYSTEMS FOR NEW CONSTRUCTION APPLY (SECTION 303.1). ALL ITEMS NOT ASSOCIATED WITH THE PROJECT ARE NOTED N/A ON THIS SHEET. CALGREEN VOLUNTARY MEASURES ARE EXEMPT FROM THIS PROJECT SINCE THE PROJECT IS NOT A NEW DEVELOPMENT.
- C. FOR ITEMS MARKED "YES" UNDER COMPLIANCE WITH 2022 CALGREEN CODE SHALL APPLY TO THIS PROJECT.
- D. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO BUILDING INSPECTOR THAT COMPLIANT VOC LIMIT FINISH MATERIALS HAVE BEEN USED. REF. VOC LIMIT TABLES THIS SHEET.

FORMALDEHYDE LIMITS MAXIMUM FORMALDEHYDE EMISSIONS IN PARTS PER MILLION							
PRODUCT	CURRENT LIMIT						
HARDWOOD PLYWOOD VENEER CORE	0.05						
HARDWOOD PLYWOOD COMPOSITE CORE	0.05						
PARTICLE BOARD	0.09						
MEDIUM DENSITY FIBERBOARD	0.11						
THIN MEDIUM DENSITY FIBERBOARD	0.13						

CALGREEN RESIDENTIAL BUILDING CODE **MANDATORY MEASURES**

		WANDATORT WEASURES					
4.1	PLANNING AND DESIGN						
SECTION	DESCRIPTION	REQUIREMENTS SUMMARY	COI	MPLIA	NCE	REMARKS	
OLOTION	BEGGKII NON	NEQUINEIMENTO GOMMANT	YES	NO	N/A	TALIWATATO	
4.106.2	STORM WATER DRAINAGE AND RETENTION DURING CONSTRUCTION	A PLAN IS DEVELOPED AND IMPLEMENTED TO MANAGE STORM WATER DRAINAGE DURING CONSTRUCTION.	X			BMP AND EROSION CONTROL PROVISIONS SHALL BE IMPLEMENTED; SEE SHEET A0.2	
4.106.3	GRADING AND PAVING	CONSTRUCTION PLANS INDICATES HOW SITE GRADING OR DRAINAGE SYSTEM WILL MANAGE ALL SURFACE WATER FLOWS TO KEEP WATER FROM ENTERING BUILDINGS.	X			REFER TO C-1	
4.106.4.1	EV CHARGING	FOR NEW DWELLINGS WITH ATTACHED GARAGES AND REBUILD OF EXISTING DWELLINGS THAT INCLUDE A PANEL UPGRADE OR CONSTRUCTION BETWEEN PANEL AND PARKING AREA, A LEVEL 2 EV READY SPACE AND LEVEL 1 EV READY SPACE, IS INSTALLED.			X	SECTION APPLIES TO NEW CONSTRUCTION ONLY (ADDITIONS, ALTERATIONS OR REPAIRS EXEMPT PER SECTION 202)	
4.2	ENERGY EFFICIENCY						
SECTION DESCRIPTION REQUIREMENTS SUMMARY				MPLIA NO		REMARKS	
4.201	ENERGY EFFICIENCY (MINIMUM STANDARD)	BUILDING MEETS OR EXCEEDS THE REQUIREMENTS OF THE CALIFORNIA BUILDING ENERGY EFFICIENCY STANDARDS (TITLE 24, PART 6-2022)				REFER TO SHEETS A0.4 AND A0.5	
4.3	WATER EFFICIENCY AND CONSERVATION						
			COI	MPLIA	NCE		
SECTION	DESCRIPTION	REQUIREMENTS SUMMARY	YES	NO	N/A	REMARKS	
4.303.1	INDOOR WATER CONSERVING PLUMBING FIXTURES AND FITTINGS	PLUMBING FIXTURES & FITTINGS SHALL NOT EXCEED THE FOLLOWING: WATER CLOSETS - 1.28 GAL/FLUSH URINALS - 0.125 GAL/FLUSH SINGLE SHOWER HEADS - 1.8 GPM @ 80 PSI MULTIPLE SHOWER HEADS (SINGLE VALVE) - TOTAL 1.8 GPM @ 80 PSI LAVATORY FAUCETS - 1.2 GPM @ 60 PSI; MIN FLOW 0.8 GPM @ 20 PSI KITCHEN FAUCETS - 1.8 GPM @ 60 PSI (TEMP. INCREASE TO 2.2 GPM)			X	THERE ARE NO PLUMBING FIXTURES IN THE GARAGE	
4.303.3	STANDARDS FOR PLUMBING FIXTURES AND FITTINGS	PLUMBING FIXTURES AND FITTINGS SHALL BE INSTALLED IN ACCORDANCE WITH THE CPC AND MEET APPLICABLE STANDARDS IN CPC TABLE 1701.1.			Х	_	
4.304.1	OUTDOOR POTABLE WATER USE IN LANDSCAPED AREAS	OUTDOOR POTABLE WATER USE IN LANDSCAPE AREAS COMPLY WITH A LOCAL WATER EFFICIENT LANDSCAPE OR THE CURRENT CALIFORNIA DWR MWELO, WHICHEVER IS MORE STRINGENT.			X	_	
4.4	MATERIAL CONSERVATION AND RESOURCE	E EFFICIENCY					
SECTION	DESCRIPTION REQUIREMENTS SUMMARY		COMPLIANCE YES NO N/A			REMARKS	
4.406.1	RODENT PROOFING (JOINTS AND OPENINGS)	ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS OR OTHER OPENINGS IN PLATES AT EXTERIOR WALLS ARE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHOD ACCEPTABLE TO THE COUNTY OF SANTA CLARA.	Х			CLOSE ALL ANNULAR SPACE WITH CEMENT MORTOR AT WALLS AND FLOORS (IF ANY) AND POLYPROPYLENE CARBINATE (TPE, THEREMOPLASTIC ELASTOMER) FLASHING & CEMENT MORTOR AT ROOF	
4.408.1	CONSTRUCTION WASTE REDUCTION OF AT LEAST 65% (MODIFIED PER LOCAL ORDINANCE)	RECYCLE AND/OR SALVAGE FOR REUSE A MINIMUM OF 65% OF THE NONHAZARDOUS CONSTRUCTION AND DEMOLITION DEBRIS, OR MEET A LOCAL CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT ORDINANCE, WHICHEVER IS MORE STRINGENT. (EXCAVATED SOIL AND LAND-CLEARING DEBRIS EXCLUDED).	X			REF. SHEET A1.0	
4.408.2	CONSTRUCTION WASTE MANAGEMENT PLAN	WHERE A LOCAL JURISDICTION DOES NOT HAVE A CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT ORDINANCE, A CONSTRUCTION WASTE MANAGEMENT PLAN SHALL BE SUBMITTED FOR APPROVAL TO THE ENFORCING AGENCY.	X			REF. SHEET A1.0 COMPLY W/ LOS GATOS WASTE MANAGEMENT PROGRAM	
4.410.1	OPERATION AND MAINTENANCE MANUAL	AN OPERATION AND MAINTENANCE MANUAL SHALL BE PROVIDED TO THE BUILDING OCCUPANT OR OWNER, DESCRIBING: 1. KEEPING MANUAL WITH PROPERTY 2. O&M INSTRUCTIONS FOR EQUIPMENT AND APPLIANCES, DRAINAGE, IRRIGATION, ETC. 3. LOCAL UTILITY CONSERVATION RESOURCES 4. PUBLIC TRANSPORTATION / CARPOOL OPTIONS 5. HEALTH BENEFITS OF 30–60% RELATIVE HUMIDITY 6. LANDSCAPE WATER CONSERVATION 7. GUTTER AND DOWNSPOUT MAINTENANCE 8. ROUTINE MAINTENANCE 9. STATE SOLAR ENERGY AND INCENTIVE PROGRAMS 10. SPECIAL INSPECTION RECORDS 11. DEPARTMENT OF FORESTRY AND FIRE PROTECTION MAINTENANCE 12. GRAB BAR REINFORCEMENTS	X			THE FOLLOWING SHALL HAVE O&M'S — OWNER TO SUPPLY: 1. HVAC 2. GUTTERS/DOWNSPOUT (SEE A1.1 FOR NEW)	

COATINGS	VOC LIMIT (G/L LESS WATER, MINUS EXEMPT	- SCAQMD RULE 1168 COATINGS	VOC LIM
BOND BREAKERS	COMPOUNDS)	NONFLAT HIGH GLOSS	COMPOUND 50
CLEAR WOOD FINISHES - GENERAL	275	PIGMENTED LACQUER	275
CLEAR WOOD FINISHES - VARNISH	275	PRETREATMENT WASH PRIMERS	420
CLEAR WOOD FINISHES - SANDING	275	PRIMERS, SEALERS, UNDERCOATERS	100
SEALERS - LACQUER	275	QUICK-DRY ENAMELS	50
CLEAR BRUSHING LACQUER	275	QUICK-DRY PRIMERS, SEALERS, UNDERCOATERS	100
CONCRETE-CURING COMPOUNDS	100	REACTIVE PENETRATING SEALERS	350
CONCRETE-CURING COMPOUNDS - ROADWAYS	350	RECYCLED COATINGS	250
CONCRETE SURFACE RETARDER	50	ROOF COATINGS	50
DRIVEWAY SEALER	50	ALUMINUM ROOF COATINGS	100
DRY-FOG COATINGS	50	ROOF PRIMERS, BITUMINOUS	350
FAUX FINISHING COATINGS - CLEAR TOPCOAT	100	RUST-PREVENTITIVE COATINGS	100
FAUX FINISHING COATINGS - DECORATIVE	350	SHELLAC - CLEAR	730
FAUX FINISHING COATINGS - GLAZES	350	SHELLAC - PIGMENTED	550
FAUX FINISHING COATINGS - JAPAN	350	SPECIALTY PRIMERS	100
FAUX FINISHING COATINGS - TROWEL APPLIED	50	STAINS - GENERAL	100
FIRE-PROOFING EXTERIOR COATINGS	150	STAINS - INTERIOR	250
FIRE-RETARDANT COATINGS - CLEAR	150	STONE CONSOLIDANT	450
FIRE-RETARDANT COATINGS - PIGMENTED	150	SWIMMING POOL COATINGS - REPAIR	340
FLATS	50	SWIMMING POOL COATINGS - OTHER	340
FLOOR COATINGS	50	TRAFFIC COATINGS	100
FORM RELEASE COMPUOND	100	WATERPROOFING SEALERS	100
GRAPHIC ARTS (SIGN) COATINGS	150	WATERPROOFING CONCRETE, CMU SEALERS	100
INDUSTRIAL MAINTENANCE (IM) COATINGS	100	WOOD PRESERVATIVES - BELOW GROUND	350
HIGH TEMPERATURE (IM) COATINGS	420	OTHER	350
NON-SACRIFICIAL ANTI-GRAFFITI COATINGS	100	LOW-SOLIDS COATING	120
SACRIFICIAL ANTI-GRAFFITI COATINGS	50	ARCHITECTURAL COLARANT EXCL. IM COATINGS	50
ZINC-RICH (IM) PRIMERS	100	SOLVENT-BASED IM COLORANT	600
MAGNESITE CEMENT COATINGS	450	WATERBORNE IM COLORANT	50
MASTIC COATINGS	100	ANTI-CORROSIVE PAINTS - GLOSS	250
METALLIC PIGMENTED COATINGS	150	ANTI-CORROSIVE PAINTS - SEMI-GLOSS	250
MULTICOLOR COATINGS	250	ANTI-CORROSIVE PAINTS - FLAT	250
NONFLAT COATINGS	50		

VOC LIMITS									
SEALANT	S & ADHESIVE	S - SCAQMD RULE 1168							
ARCHITECTURAL APPLICATIONS	VOC LIMIT (G/L LESS WATER)	ARCHITECTURAL APPLICATIONS	VOC LIMIT (G/L LESS WATER						
NDOOR CARPET ADHESIVES	50	PVC WELDING	510						
ARPET PAD ADHESIVES	50	CPVC WELDING	490						
OUTDOOR CARPET ADHESIVES	150	ABS WELDING	325						
OOD FLOORING ADHESIVES	100	PLASTIC CEMENT WELDING	250						
UBBER FLOOR ADHESIVES	60	ADHESIVE PRIMER FOR PLASTIC	550						
UBFLOOR ADHESIVES	50	CONTACT ADHESIVE	80						
ERAMIC TILE ADHESIVES	65	SPECIAL PURPOSE CONTACT ADHESIVE	250						
CT AND ASPHALT ADHESIVES	50	TIRE RETREAD	100						
RYWALL AND PANEL ADHESIVES	50	ADHESIVE PRIMER FOR TRAFFIC MARKING TAPE	150						
OVE BASE ADHESIVES	50	STRUCTURAL WOOD MEMBER ADHESIVE	140						
IULTIPURPOSE CONSTRUCTION ADHESIVES	70	SHEET APPLIED RUBBER LINING OPERATIONS	850						
TRUCTURAL GLAZING ADHESIVES	100	TOP AND TRIM ADHESIVE	250						
INGLE PLY ROOF MEMBRANE ADHESIVES	250								
SUBSTRATE SPECIFIC APPLICATIONS	VOC LIMIT (G/L LESS WATER)	SEALANTS	VOC LIMIT (G/L LESS WATER						
IETAL TO METAL	30	ARCHITECTURAL	250						
LASTIC FOAMS	50	MARINE DECK	760						
OROUS MATERIAL (EXCEPT WOOD)	50	NONMEMBRANE ROOF	300						
VOOD	30	ROADWAY	250						
IBER GLASS	80	SINGLE-PLY ROOF MEMBRANE	450						
		OTHER	420						
SEALANT PRIMERS	VOC LIMIT (G/L LESS WATER)	AEROSOL ADHESIVES	VOC LIMIT (G/L LESS WATER						
RCHITECTURAL, NON-POROUS	250	GENERAL PURPOSE MIST SPRAY	65% BY WT.						
RCHITECTURAL, POROUS	775	GENERAL PURPOSE WEB SPRAY	55% BY WT.						
ODIFIED BITUMINUOUS	500	SPECIAL PURPOSE CONTACT ADHESIVE	70% BY WT.						
ARINE DECK	760								
OTHER	750								





PROJECT TITLE


REVISIONS PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS Q PLANNING COMMENTS

CONDITIONS & RESTRICTIONS These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

PLANNING COMMENTS

SHEET TITLE

CALGREEN MANDATORY **MEASURES**



PROJECT NUMBER: 24111/6285 NONE

TREE REMOVAL AND PROTECTION REQ'TS

- A. TREE REMOVAL PERMIT IS REQUIRED PRIOR TO REMOVING ANY TREE ON THE PROPERTY.
- B. PRUNING OR ROOT PRUNING MUST BE SUPERVISED BY AN ISA-CERTIFIED ARBORIST OR AN ASCA-REGISTERED ARBORIST. SEE SECTION 29.10.1010 OF THE TOWN CODE FOR SPECIFICATIONS TO DETERMINE IF A PRUNING PERMIT IS
- C. TREE PROTECTION FENCING REQUIREMENTS IN THE TREE PROTECTION ZONE (DRIPLINE):
 - SIX-FOOT HIGH CHAIN LINK FENCING MOUNTED ON TWO-INCH DIAMETER GALVANIZED IRON POSTS SHALL BE DRIVEN INTO THE GROUND AT LEAST TWO-FEET DEEP AT NO MORE THAN TEN-FOOT SPACING. WHEN STIPULATED, FOR EXISTING PAVING AREAS THAT WILL NOT BE DEMOLISHED, POSTS MAY BE SUPPORTED BY CONCRETE BASE. 2. POSTED EIGHT AND ONE-HALF-INCH BY ELEVEN-INCH SIGN ON EACH TREE FENCE STATING: "WARNING - TREE PROTECTION ZONE - THIS FENCE SHALL NOT BE REMOVED AND IS SUBJECT TO PENALTY ACCORDING TO TOWN
 - CODE 29.10.1025" A SECOND SIGN SHALL BE IN SPANISH (SEE DETAIL BELOW) 3. LABELED PHOTOGRAPHS OF THE INSTALLED FENCING SHALL BE EMAILED TO THE PROJECT PLANNER PRIOR TO
 - 4. TREE PROTECTION FENCING IS REQUIRED TO REMAIN IN PLACE THROUGHOUT CONSTRUCTION.
- D. ANY PROTECTED TREE ON-SITE WILL REQUIRE REPLACEMENT ACCORDING TO ITS APPRAISED VALUE IF IT IS DAMAGED BEYOND REPAIR AS A RESULT OF CONSTRUCTION.
- ALL TREE MAINTENANCE AND CARE SHALL BE PERFORMED BY A QUALIFIED ARBORIST WITH A C-61/D-49 CALIFORNIA CONTRACTORS LICENSE. TREE MAINTENANCE AND CARE SHALL BE SPECIFIED IN WRITING ACCORDING TO AMERICAN NATIONAL STANDARD FOR TREE CARE OPERATIONS: TREE, SHRUB AND OTHER WOODY PLANT MANAGEMENT: STANDARD PRACTICES PARTS 1 THROUGH 10 AND ADHERE TO ANSI Z133.1 SAFETY STANDARDS AND LOCAL REGULATIONS. ALL MAINTENANCE IS TO BE PERFORMED ACCORDING TO ISA BEST MANAGEMENT PRACTICES.

Tree Protection Zones and Fence Specifications

- Size and materials: Six (6) foot high chain link fencing, mounted on two-inch diameter galvanized iron posts, shall be driven into the ground to a depth of at least two (2) feet at no more than ten-foot spacing. For paving area that will not be demolished and when stipulated in a tree preservation plan, posts may be supported by a concrete base.
- 2. Area type to be fenced: Type I: Enclosure with chain link fencing of either the entire dripline area or at the tree protection zone (TPZ), when specified by a certified or consulting arborist. Type II: Enclosure for street trees located in a planter strip: chain link fence around the entire planter strip to the outer branches. Type III: Protection for a tree located in a small planter cutout only (such as downtown): orange plastic fencing shall be wrapped around the trunk from the ground to the first branch with two-inch wooden boards bound securely on the outside. Caution shall be used to avoid damaging any bark or branches.
- **Duration of Type I, II, III fencing:** Fencing shall be erected before demolition, grading or construction permits are issued and remain in place until the work is completed. Contractor shall first obtain the approval of the project arborist on record prior to removing a tree protection fence.
- 4. Warning Sign: Each tree fence shall have prominently displayed an eight and one-half-inch by eleven-inch sign stating: "Warning —Tree Protection Zone—This fence shall not be removed and is subject to penalty according to Town Code 29.10.1025." Text on the signs should be in both English and Spanish (Appendix E).

All persons, shall comply with the following precautions

- 1. Prior to the commencement of construction, install the fence at the dripline, or tree protection zone (TPZ) when specified in an approved arborist report, around any tree and/or vegetation to be retained which could be affected by the construction and prohibit any storage of construction materials or other materials, equipment cleaning, or parking of vehicles within the TPZ. The dripline shall not be altered in any way so as to increase the encroachment of the construction.
- 2. Prohibit all construction activities within the TPZ, including but not limited to: excavation, grading, drainage and leveling within the dripline of the tree unless approved by the Director.
- 3. Prohibit disposal or depositing of oil, gasoline, chemicals or other harmful materials within the dripline of or in drainage channels, swales or areas that may lead to the dripline of a protected tree.
- 4. Prohibit the attachment of wires, signs or ropes to any protected tree.
- 5. Design utility services and irrigation lines to be located outside of the dripline when feasible.
- 6. Retain the services of a certified or consulting arborist who shall serve as the project arborist for periodic monitoring of the project site and the health of those trees to be preserved. The project arborist shall be present whenever activities occur which may pose a potential threat to the health of the trees to be preserved and shall document all site visits.
- 7. The Director and project arborist shall be notified of any damage that occurs to a protected tree during construction so that proper treatment may be administered.

Prohibited Activities

The following are prohibited activities within the TPZ:

• Grade changes (e.g. soil cuts, fills);

• Burning of brush and woody debris;

- Trenches;
- Root cuts;

Monitoring

- Pedestrian and equipment traffic that could compact the soil or physically damage roots; • Parking vehicles or equipment;
- Storing soil, construction materials, petroleum products, water, or building refuse; and,

• Disposing of wash water, fuel or other potentially damaging liquids.

Any trenching, construction or demolition that is expected to damage or encounter tree roots should be monitored by the project arborist or a qualified ISA Certified Arborist and should be documented.

The site should be evaluated by the project arborist or a qualified ISA Certified Arborist after construction is complete, and any necessary remedial work that needs to be performed should be noted.

Root Pruning

Roots greater than two inches in diameter shall not be cut. When roots over two inches in diameter are encountered and are authorized to be cut or removed, they should be pruned by hand with loppers, handsaw, reciprocating saw, or chain saw rather than left crushed or torn. Roots should be cut beyond sinker roots or outside root branch junctions and be supervised by the project arborist. When completed, exposed roots should be kept moist with burlap or backfilled within one hour.


Boring or Tunneling

Boring machines should be set up outside the drip line or established Tree Protection Zone. Boring may also be performed by digging a trench on both sides of the tree until roots one inch in diameter are encountered and then hand dug or excavated with an Air Spade® or similar air or water excavation tool. Bore holes should be adjacent to the trunk and never go directly under the main stem to avoid oblique (heart) roots. Bore holes should be a minimum of three feet deep.

Tree Pruning and Removal Operations

All tree pruning or removals should be performed by a qualified arborist with a C-61/D-49 California Contractors License. Treatment, including pruning, shall be specified in writing according to the most recent ANSI A-300A Standards and Limitations and performed according to ISA Best Management Practices while adhering to ANSI Z133.1 safety standards. Trees that need to be removed or pruned should be identified in the pre-construction walk through.

		TREE IN	IVENTORY				
ID	TREE SPECIES COMMON NAME	TREE SPECIES BOTANICAL NAME	TRUNK DIAMETER"	CANOPY DIAMETER"	CONDITION	EXPECTED IMPACT	STATUS
615	HOLLY	LLEX AQUIFOLIUM	10	15	GOOD	HIGH	REMOV
616	COAST LIVE OAK	QUERCUS AGRIFOLIA	11	15	GOOD	LOW	SAVE
617	PISTACHE	PISTACIA CHINENSIS	4	10	GOOD	HIGH	REMOV
618	COAST LIVE OAK	QUERCUS AGRIFOLIA	4	10	GOOD	HIGH	REMOV
619	CANARY ISLAND PINE	PINUS CANARIENSIS	14	15	FAIR	HIGH	REMO\
620	CANARY ISLAND PINE	PINUS CANARIENSIS	17, 17	25	FAIR	MODERATE	REMO
621	BLACK PINE	PINUS JEFFREYI	8	15	GOOD	LOW	SAVE
622	MONTEREY PINE	PINUS RADIATA	19	20	FAIR	LOW	SAVE
623	COAST LIVE OAK	QUERCUS AGRIFOLIA	9,7	10	GOOD	MODERATE	REMO
624	SILK TREE	ALBIZIA JULIBRISSIN	9	10	GOOD	HIGH	REMO
NO TAG	UNKNOWN	UNKNOWN	8	8	UNKNOWN	HIGH	REMO



WARNING

TREE PROTECTION

TREE PROTECTION ZONE


THIS FENCE SHALL NOT BE REMOVED AND IS SUBJECT TO PENALTY ACCORDING TO TOWN CODE 29.10.1025 **CUIDADO**

Modified by Monarch Consultin


ZONE DE ARBOL PRETEJIDO

ESTA VALLA NO PODRÁN SER SACADOS Y ESTÁ SUJETA A SANCIÓN EN FUNCIÓN DE CÓDIGO CIUDAD DEL 29.10.1025


TREE PROTECTION SIGNAGE DETAILS BOTH SIGNS MUST BE POSTED




Trunk Protection Vertical Timber











PROJECT TITLE

REVISIONS PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC 2/13/2025 LANNING COMMENTS /5/2025 PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**

hese drawings and all related specifications are struments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent n these plans are to be field verified and all discrepancies are to be reported to the designer. dicated or consult the architect.

SHEET TITLE


PROTECTION


PLAN


TREE



PROJECT NUMBER: 24111/6285 AS NOTED








REVISIONS


CONDITIONS & RESTRICTIONS

hese drawinas and all related specifications are nstruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent the architect. All existing conditions represented n these plans are to be field verified and all discrepancies are to be reported to the designe not scale from these plans, follow dimensions

SHEET TITLE

SITE PLAN





GENERAL NOTES

- A. REFER TO SHEET AO FOR DRAWING INDEX.
- B. PERSON(S) PERFORMING THE WORK MUST BE COGNIZANT OF FIELD CONDITIONS AND VERIFY PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY CONFLICTS SHALL BE RESOLVED PRIOR TO
- C. ALL DIMENSIONS ARE TO FACE OF FINISH UNLESS OTHERWISE NOTED.
- UTILITIES SHOWN ON THIS DRAWING IS SCHEMATIC IN NATURE. ALL CODES SHALL BE STRICTLY FOLLOWED FOR ABOVE TRADE WORK.

SHEET NOTES

- 1. REFER TO WALL TYPE DESCRIPTION FOR ALL WALLS.
- 2. INSTALL DOORS AND WINDOWS AS DESIGNATED ON PLAN AND PER SCHEDULES ON A7.1.
- 3. ALL CABINETS, CASEWORK, ACCESSORIES, SHELVING, FIXTURES AND APPLIANCES SHALL BE COORDINATED WITH OWNER AND/OR AS NOTED IN THESE PLANS. COORDINATE WITH OWNER FOR BACKING FOR FUTURE CABINETS (I.E. INSTALL ADDITIONAL BLOCKING IN WALLS FOR ANTICIPATED LOCATIONS).
- 4. ADD R-19 BATT INSULATION IN ROOF RAFTERS OVER CONDITIONED SPACES ALONG WITH R-6 RIGID INSULATION. (U-FACTOR = 0.048) MAINTAIN 2" GAP AT TOP AND BOTTOM TO ALLOW MOISTURE BUILD-UP TO ESCAPE (VENTILATION)
- 5. INSTALL 3/4" PLYWOOD IN STORAGE LOFT.
- 6. INSTALL 1/2" GYPSUM BOARD BELOW ROOF RAFTERS & INSULATION. PREPARE THE SAME FINISH LEVEL AS THE WALLS.
- PROVIDE & INSTALL NEW 4" THICK CONCRETE HOUSEKEEPING PAD FOR NEW CONDENSER. ANCHOR CONDENSER TO PAD PER MANUF. RECOMMENDATIONS. SEE A2.3 FOR LOCATION.

FINISH NOTES

ALL FINISHES SHALL BE COORDINATED WITH OWNER

A. PREPARE FLOOR IN GARAGE FOR EPOXY FLOORING. FLOAT FLOOR AS REQ'D FOR LEVELING. B. PROVIDE TRANSITION STRIP BETWEEN DIFF. FLOORING MATERIALS.

A. COVE EPOXY BASE 6" UP WALL MINIMUM.

- A. PROTECT AND COVER ALL FLOORING. IMMEDIATELY CLEAN ANY SPILLS AND EXCESS PAINT.
- INSTALL TEMPORARY "WET PAINT" SIGNS ON ALL AREAS DURING WORK. PAINT ALL WALLS AND CEILINGS; PREPARE FOR LEVEL 3 KNOCK-DOWN FINISH.
- SURFACE PREPARATION OF WALLS, PRIMER, AND NUMBER OF COATS OF PAINT AS
- RECOMMENDED BY PAINT MANUFACTURER. COORDINATE COLORS WITH OWNER. ALL PAINT SHALL BE EGGSHELL
- ALL PAINTS, COATINGS, SEALANTS, ADHESIVES AND PRIMERS SHALL BE WITHIN THE VOC LIMITS PER SCAQMD RULE 1168. (VOC LIMITS: PRIMER = 100 G/L; PAINT = 50 G/L).

WALL LEGEND

BEARING EXTERIOR WALL 2X6 DF WD STUDS @ 16" O.C. W/ 1/2" GYPBD ON INTERIOR FACE, R-21 BATT INSULATION BETWEEN STUDS, AND 7/8" STUCCO (3-COATS) OVER METAL LATH OVER 2 LAYERS OF GRADE 'D' PAPER WITH RADIANT BARRIER OVER R-5 CONTINUOUS RIGID INSULATION OVER 1/2" PLYWOOD ON EXTERIOR FACE UP TO ROOF/FLOOR

BEARING EXTERIOR WALL - 2-HR FIRE BARRIER (GA FILE NO. WP-8192) 2X6 DF WD STUDS @ 16" O.C. W/ 2 LAYERS OF 5/8" TYPE 'X' GYPBD ON INTERIOR FACE, R-21 BATT INSULATION BETWEEN STUDS, AND 7/8" STUCCO (3-COATS) OVER METAL LATH OVER 2 LAYERS OF GRADE 'D' PAPER WITH RADIANT BARRIER OVER R-5 CONTINUOUS RIGID INSULATION OVER 1/2" PLYWOOD OVER 5/8" TYPE 'X' GYPSUM SHEATHING ON EXTERIOR FACE UP TO ROOF/FLOOR FRAMING ABOVE. FIRE SEAL ALL PENETRATIONS (SEE DETAILS 3 & 4 ON A7.1).

B BEARING EXTERIOR WALL
CONCRETE RETAINING WALL PER STRUCTURAL DRAWINGS. WALL TYPE 'A' ON TOP OF RETAINING WALL

C INTERIOR FURRED WALL (NON-BEARING)

2X4 DF WD STUDS @ 16" O.C. W/ 1/2" GYPBD ON EXPOSED SIDE UP TO CEILING FRAMING ABOVE.

GA FILE NO. WP 8192	GENERIC	2 HOUF FIRE	1	40 TO 44 STC SOUND
Fire Design: EXTERIOR SIDE: Base layer 5/8′ parallel to 2 × 6 fire retardant tr coated nails, 1-7/8″ long, 0.091 covered with a single layer of built at 16″ o.c. Galvanized self-furring with 8d galvanized roofing nails	'type X gypsum sheathing applied reated wood studs 16" o.c. with 6d 5" shank, 1/4" heads, 12" o.c. and ding paper stapled along each edge g wire mesh applied over sheathing a, 2-3/8" long, 0.113" shank, 9/32" applied over wire mesh in two 1/2" applied between coats.			
gypsum veneer base applied pa 1-7/8" long, 0.0915" shank, 1/4 type X gypsum wallboard or gy angles to studs with 8d coated 9/32" heads, 8" o.c. at edges a (LOAD-BEARING) Sound Design:	/8" type X gypsum wallboard or trallel to studs with 6d coated nails, theads, 12" o.c. Face layer 5/8" psum veneer base applied at right I nails, 2-3/8" long, 0.113" shank, and 12" o.c. at intermediate studs.	Thickness: Approx. Weight: Fire Test: Sound Test: OITC:	8-5/8" (Fire a 18 psf (Fire) 18.4 psf (Sour UC ES-6898, NOAL 19-082	nd) , 12-21-67

LEGEND



A WALL TYPE DESIGNATION SEE WALL TYPE DESCRIPTION THIS SHEET

DOOR MARK - REFER TO DOOR SCHEDULE ON A7.1 — DOOR NUMBER DESIGNATION - FLOOR NUMBER REFERENCE

WINDOW MARK - REFER TO WINDOW SCHEDULE ON A7.1

- WINDOW NUMBER DESIGNATION - FLOOR NUMBER REFERENCE

PROJECT TITLE

Q

 $\mathbf{\Omega}$

U


REVISIONS | PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS | PLANNING COMMENTS PLANNING COMMENTS

| PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.


SHEET TITLE

FLOOR PLANS



AS NOTED

24111/6285



GENERAL NOTES

- A. REFER TO SHEET AO FOR DRAWING INDEX.
- B. REPAIR ALL DAMAGED MATERIALS IMPACTED BY NEW CONSTRUCTION. ALIGN AND FINISH TO MATCH EXISTING ADJACENT SURFACE.
- C. WEATHER PROTECTION IS REQUIRED PRIOR TO ANY DEMOLITION OF EXTERIOR WALLS. IT SHALL
- D. PERSON(S) PERFORMING THE WORK MUST BE COGNIZANT OF FIELD CONDITIONS AND VERIFY PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY CONFLICTS SHALL BE RESOLVED PRIOR TO
- E. ALL UTILITIES SERVICES IMPACTED BY DEMOLITION AND CONSTRUCTION SHALL BE COORDINATED WITH THE ASSOCIATED UTILITY PROVIDER AND/OR AUTHORITY. CONFORM TO STANDARD EROSION CONTROL CONSTRUCTION MITIGATION MEASURES AS APPLICABLE. REFER TO CIVIL
- F. ALL NEW DOWNSPOUTS SHALL HAVE CONCRETE SPLASH BLOCKS AT THE BASE. IN TURN, WATER SHALL DRAIN ONTO THE ADJACENT LANDSCAPING WHERE POSSIBLE.

- 1. ROOF TILES AND ASSEMBLY AT GARAGE SHALL MEET THE FOLLOWING CRITERIA. NOTE, EXISTING ROOF ON MAIN HOUSE IS ASPHALT SHINGLES AND VERY SIMILAR IN NATURE. HOWEVER SELECTIONS HAVE BEEN MADE FOR THE NEW STRUCTURE TO MEET CALIFORNIA
 - A. ROOF ASPHALT TILES BY "CERTAINTEED" PRESIDENTIAL SOLARIS SHINGLES.
 - C. CRRC #0668-0132
 - COOL ROOF SPECIFICATIONS
 - SOLAR REFLECTANCE (INITIAL) SOLAR REFLECTANCE (3-YR) = 0.19
 - THERMAL EMITTANCE (INITIAL) = 0.93THERMAL EMITTANCE (3-YR) = 0.94
 - = 18 INITIAL SRI VALUE AGED SRI VALUE
 - F. SLOPE OF ROOF PER PLAN (SEE ELEVATIONS/SECTIONS ON A3.1 AND A3.2) G. INSTALL ROOF TILES PER MANUF. INSTALLATION INSTRUCTIONS TO MAINTAIN WARRANTY.
 - H. UNDERLAYMENT: 2 LAYERS OF #15 FELT PAPER OVER PLYWD SHEATHING W/ INTEGRAL RADIENT BARRIER. ROOF SHEATHING WITH TECHSHIELD RADIANT BARRIER BONDED TO UNDERSIDE OF CDX
 - PLYWOOD OR APPROVED EQUAL (SEE ROOF FRAMING ON STRUCTURAL DRAWINGS FOR
 - J. ALL ROOF FASTENERS SHALL BE CORROSION RESISTANT (CRC R905.2.5). K. FLASH ALL PENETRATIONS, IF ANY, PER MANUF. INSTRUCTIONS TO MAINTAIN
 - L. PROVIDE & INSTALL ROOF FLASHING WHERE WALLS AND ROOF MEET PER MANUF.
 - M. PROVIDE & INSTALL NEW CONTINUOUS/SEAMLESS 0.032" THICK ALUMINUM
 - BREAKSHAPE METAL GUTTER SYSTEM ATTACHED TO THE FASCIA NEW ROOF ASSEMBLIES. LOCATE APPROXIMATELY 1/2" BELOW SLOPE LINE OF BOTTOM OF BARREL, TYPICAL. DRIP EDGE FLASHING SHALL EXTEND OVER GUTTER SYSTEM AT FASCIA. STRICTLY COORDINATE WITH ROOF TILE MANUFACTURER'S INSTRUCTIONS TO MAINTAIN WARRANTY. COLOR OF GUTTER SYSTEM TO MATCH FASCIA BOARD.
 - N. PROVIDE DOWNSPOUTS AND SPLASH BLOCKS AT LOCATIONS SHOWN. ALL DOWNSPOUTS SHALL HAVE CONCRETE SPLASH BLOCKS AT THE BASE. IN TURN. WATER SHALL DRAIN ONTO NEARBY LANDSCAPING WHERE POSSIBLE. COLOR OF DOWNSPOUTS SHALL BE WHITE TO MATCH THE EXISTING HOUSE.
 - O. THE UNDERSIDE OF NEW EAVES SHALL MATCH THE UNDERSIDE OF THE EXISTING EAVES OF THE MAIN HOUSE (WITH THE EXCEPTION OF CLOSED EAVES TO MATCH EAVE TRIM COLOR). CLOSED EAVES COMPLY WITH THE WILDLAND URBAN INTERFACE
 - P. ALL SOFFIT VENTS UNDER EAVES, GABLE-END VENTS ON THE SIDE OF THE STRUCTURE AND RIDGE VENTS SHALL HAVE 1/16" NON-COMBUSTIBLE, CORROSION-RESISTANT MESH WITH OVERLAPPING BAFFLES AND HEAT ACTIVATED INTUMESCENT STRIPS TO PREVENT EMBER INTRUSION AND RESIST RADIANT HEAT. RECOMMENDED PRODUCTS BY "BRANDGUARD VENTS" OR APPROVED EQUAL; MUST
 - HAVE CALFIRE BML APPROVAL CERTIFICATION NUMBER ASSOCIATED WITH THE PRODUCT. Q. INSTALL GUTTER GUARDS WITH 1/16" NON-COMBUSTIBLE, CORROSION-RESISTANT MESH THAT COMPLY TO PREVENT EMBER INTRUSION SUCH AS "BRANDGUARD VENTS"

WILDLAND URBAN INTERFACE COMPLIANCE

EXTERIOR CLADDING - IGNITION RESISTANT MATERIALS - STUCCO

ROOF MATERIALS - CLASS A ASPHALT ROOF TILES (SEE THIS SHEET)

CLOSED EAVES - SEE SECTIONS ON A3.2

EMBER RESISTANT SOFFIT VENTS (SEE THIS SHEET) EMBER RESISTANT RIDGE VENTS (SEE THIS SHEET)

METAL-CLADDED DOOR ASSEMBLIES WITH TEMPERED WINDOWS (SEE A7.1) WINDOWS DOUBLE-PANED AND TEMPERED (SEE A7.1) ALL DOORS HAVE PERIMETER WEATHER STRIPPING AND DOOR BOTTOMS TO REDUCE EMBER INTRUSION (SEE A7.1)

VEGETATION MANAGEMENT & DEFENSIBLE BREAKS (SEE A1.2)

ALTERNATE MATERIALS, METHODS OF CONSTRUCTION OR MODIFICATION OF CODE (25-0417).

- 1. FIRE APPARATUS ACCESS ROADWAY CLEARANCES (CFC SECTION 503) STREET WIDTH OF 20'-0" CLEAR BY 13'-6" HIGH - ACTUAL ROAD IS 12'-0" WIDE AND DOESN'T ACHIEVE
- 2. FIRE DEPARTMENT DRIVEWAY TURNAROUND CLEARANCE (CFC SECTION 503) DRIVEWAY AREA DOES NOT ACCOMMODATE 40' MINIMUM OUTSIDE TURNING RADIUS. 3. FIRE HYDRANT DISTANCE WITHIN 400' OR 600' IF FULLY SPRINKLERED (CFC SECTION 507.5.1)
- ACTUAL FIRE HYDRANT IS LOCATED APPROXIMATELY 1,975' AWAY FROM THE PROPERTY LINE.
- THE FOLLOWING IS BEING PROPOSED DUE TO THE SCALE OF THE PROJECT: 1. NFPA 13D FIRE SPRINKLER SYSTEM IN GARAGE STRUCTURE ONLY. MAIN RESIDENCE WILL
- 2. 2-HOUR FIRE-BARRIER WALL ASSEMBLY AT GARAGE BETWEEN BREEZEWAY (SEE A2.1)
- 3. 5,000 GALLON FIRE WATER STORAGE POLYETHYLENE TANK (NO PUMP) LOCATED AT LEAST 10'-0" FROM GARAGE STRUCTURE WITH 4"Ø UNDERGROUND WATER LINE AND CONNECTION TO A NEW WHARF FIRE HYDRANT LOCATED AT THE NORTHEASTERLY CORNER OF THE PROPERTY ADJACENT TO THE DRIVEWAY ACCESS. IMPACT PROTECTION BOLLARDS ARE SET BETWEEN THE HYDRANT AND DRIVEWAY TO PREVENT ACCIDENTAL DAMAGE. SIGNAGE IS POSTED ON THE WHARF HYDRANT INDICATING IT IS SUPPLIED BY A 5,000 GALLON TANK
- ADDRESS DIRECTIONAL & IDENTIFICATION SIGNAGE VISABLE FROM THE APPROACHING CORNER (EAST CORNER) OF CYPRESS WAY WHERE THE ROAD SPLITS IN TWO DIRECTIONS (SEE BELOW). LETTERING SHALL BE 12" HIGH BLACK ON WHITE INDICATING "16511 CYPRESS WAY" WITH DIRECTIONAL ARROW.



PROJECT TITLE


REVISIONS PLANNING SUBMITTAL

PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**


hese drawings and all related specifications are struments of service and shall remain property o the designer. No revisions, reproductions, or use of these documents shall be made without the consent in these plans are to be field verified and all discrepancies are to be reported to the designer. not scale from these plans, follow dimensions ndicated or consult the architect.

SHEET TITLE

ROOF PLAN & SITE ELEMENTS



PROJECT NUMBER: 24111/6285 AS NOTED



DENOTES EXISTING CMU RETAINING

SCALE: 1/4" = 1'-0"

REAR EXTERIOR ELEVATION (SOUTH)

WALL AT GARAGE

+0'-0"
GARAGE FLOOR LEVEL

STUCCO, TYP -

WALL AT GARAGE

DENOTES EXISTING CMU RETAINING

SIDE EXTERIOR ELEVATION (WEST) SCALE: 1/4" = 1'-0"

LATTICE:

EXTERIOR COLOR SCHEME MODERN STYLE TEXTURE THAT MATCHES MAIN HOUSE ASPHALT SHINGLES (SEE A2.2) — SRI 18 COLOR: CHARCOAL BLACK ROOF TILES: TAN/EARTH THAT MATCHES STUCCO - LRV 69 TRIM: (STUCCO TRIM TO MATCH STUCCO COLOR) WHITE THAT MATCHES MAIN HOUSE — LRV 93 FASCIA: WHITE THAT MATCHES MAIN HOUSE - LRV 93 **GUTTERS:** DOWNSPOUTS: WHITE THAT MATCHES MAIN HOUSE - LRV 93

WOOD LATTICE PAINTED WHITE





PROJECT TITLE

REVISIONS PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**


These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

EXISTING EXTERIOR ELEVATIONS



PROJECT NUMBER: 24111/6285 AS NOTED






	REVISIONS	
F	PLANNING SUBMITTAL	7/30/2024
Н	PLANNING COMMENTS	10/23/2024
L	SCCFD AMMC	1/24/2025
М	PLANNING COMMENTS	2/13/2025
N	PLANNING COMMENTS	3/5/2025
Р	PLANNING COMMENTS	3/17/2025
Q	PLANNING COMMENTS	3/24/2025
R	PLANNING COMMENTS	3/28/2025
	CONDITIONS & RESTRICT	IONS


These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

EXTERIOR ELEVATIONS



ALL PERMANENT EXTERIOR LIGHT FIXTURES SHOULD UTILIZE SHIELDS SO THAT NO BULB IS VISIBLE AND TO ENSURE THAT LIGHT IS DIRECTED TO THE GROUND SURFACE AND DOES NOT SPILL LIGHT ONTO NEIGHBORING PARCELS OR PRODUCE GLARE WHEN SEEN FROM NEARBY HOMES.



PROJECT TITLE

REVISIONS PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC M PLANNING COMMENTS 2/13/2025 3/5/2025 PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS 3/28/2025

CONDITIONS & RESTRICTIONS

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use o these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. o not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

BUILDING SECTIONS

PROJECT NUMBER: 24111/6285

AS NOTED

A3.2







3360 De

PROJECT TITLE

PROJECT TITLI

JLANULL ESIDENCE

16511 Cypres

REVISIONS

F PLANNING SUBMITTAL 7/30/20
H PLANNING COMMENTS 10/23/20
L SCCFD AMMC 1/24/20
M PLANNING COMMENTS 2/13/20
N PLANNING COMMENTS 3/5/20
P PLANNING COMMENTS 3/17/20
Q PLANNING COMMENTS 3/24/20


PLANNING COMMENTS 3/28

CONDITIONS & RESTRICTIONS

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

OVERALL SITE SECTION







PROJECT TITLE

PROJECT TITLI

V N D L Y D E N C

RESIDENC See Way


16511 Cyr


	REVISIONS								
F	PLANNING SUBMITTAL	7/30/2024							
Н	PLANNING COMMENTS	10/23/2024							
L	SCCFD AMMC	1/24/2025							
М	PLANNING COMMENTS	2/13/2025							
N	PLANNING COMMENTS	3/5/2025							
Р	PLANNING COMMENTS	3/17/2025							
Q	PLANNING COMMENTS	3/24/2025							
R	PLANNING COMMENTS	3/28/2025							
	CONDITIONS & RESTRICTIONS								

These drawings and all related specifications are instruments of service and shall remain property of the designer. No revisions, reproductions, or use of these documents shall be made without the consent of the architect. All existing conditions represented in these plans are to be field verified and all discrepancies are to be reported to the designer. Do not scale from these plans, follow dimensions indicated or consult the architect.

SHEET TITLE

OVERALL SITE SECTION





DOOR SCHEDULE DOOR # SIZE MATERIAL **DETAILS REMARKS** HDWR FIRE VISION PNL GLAZING COUSTIC GROUP RATING LABEL LABEL RATING DR DR JB HD MAX U-VALUE = 0.20 STANDARDD1-01 $3'-6"W \times 6'-8"H$ MTL /A7.1 2/A7.1 90 D-H-90 НМ MAX U-VALUE = 0.23 WEIGHTED VALUE $9'-0"W \times 7'-0"H$ MTL /A7.1 2/A7.1 D1-02 WD SKYFOLD GARAGE DOOR WITH AUTOMATIC OPENER /A7.1 2/A7.1 D1-03 $9'-0''W \times 7'-0''H$ MTL WD SKYFOLD GARAGE DOOR WITH AUTOMATIC OPENER $9'-0''W \times 7'-0''H$ MTL |/A7.1|2/A7.1 D1-04 WD SKYFOLD GARAGE DOOR WITH AUTOMATIC OPENER

DOOR NOTES:


- 1. PAINT ALL DOORS & FRAMES. <u>DO NOT</u> PAINT OVER DOOR & FRAME LABELS.
- 2. ALL EXTERIOR DOORS (OR DOORS AT PERIMETER OF CONDITIONED SPACES) SHALL BE SOLID CORE (OR METAL CLADDED) WITH A MAX U-VALUE OF 0.50 UNLESS OTHER SPECIFIED ON DOOR SCHEDULE AND ALL INTERIOR DOORS AND FRAMES SHALL MATCH EXISTING. FOR DOORS WITH MAX U-VALUE OF 0.20 SPECIFICATION, THIS APPLIES TO DOORS WITH NO VISION PANEL OR UP TO 25% OF THE DOOR. FOR DOORS WITH VISION PANELS EXCEED 25% OF THE DOOR TO 50%, MAX WEIGHTED U-VALUE SHALL BE 0.23 (2019 T24 BUILDING ENERGY EFFICIENCY STANDARDS SECTION 150.1(C).5).
- 3. ALL EXTERIOR DOORS SHALL BE 1 3/4" THICK AND ALL INTERIOR DOORS SHALL BE 1 3/8" THICK U.O.N.
- 4. ALL EXTERIOR DOOR FRAMES SHALL BE PER ELEVATIONS.
- 5. PROVIDE JAMB & HEAD CLEARANCE OF 1/8" MAX. BOTTOM CLEARANCE SHALL NOT EXCEED 3/8" FOR SINGLE DOORS, AND 1/4" FOR PAIRS OF DOORS.
- 6. ALL FIRE-RATED DOORS SHALL BE SELF-CLOSING AND PROVIDED WITH SMOKE SEALS. IN ADDITION, BOTH THE DOOR AND FRAME SHALL BEAR AN "S" LABEL INDICATING RATING, TEST METHOD, AND SMOKE RESISTANCE.
- 7. ALL GLAZING IN DOORS SHALL BE OF TEMPERED GLASS, EXCEPT FOR FIRE-RATED DOORS SHALL BE OF LISTED FIRE GLASS. ALL EXTERIOR DOOR GLAZING SHALL MEET THE U-VALUE, SHGC AND VT VALUES OF WINDOWS AND SHALL CONTAIN A NFRC LABEL.
- 8. COORDINATE ROUGH OPENING SIZES WITH DOOR MANUF. RECOMMENDATIONS.
- 9. ALL EXTERIOR DOORS SHALL HAVE A 1" MAX. HT THRESHOLD.
- 10. ALL EXTERIOR KNOB SETS SHALL BE SCHLAGE COMMERCIAL GRADE 1 OR BETTER. ALL INTERIOR KNOB SETS SHALL BE SCHLAGE COMMERCIAL GRADE 2 OR BETTER. AT KEYED LOCATIONS. MODIFY LOCKSET SO THAT IT MATCHES ALL OTHER EXISTING EXTERIOR DOOR LOCKS.
- 11. ALL DOOR HARDWARE SHALL BE ANTIQUE BRASS 609/US5.
- 12. ALL NEW LOCKING DOOR HARDWARE SHALL BE KEYED TO MATCH MAIN RESIDENCE MASTER KEY.
- 13. GARAGE DOORS SHALL HAVE A SKYFOLD OPENING ACTION (RATHER THAN STANDARD GLIDING - CHECK CLEAR HEIGHT ABOVE DOOR FOR ACCOMMODATION) SIMILAR BY "CLOPAY" MODERN STEEL COLLECTION 2" THICK POLYURETHANE (R-18.4) #9208 MODERN FLUSH WITH STUCCO TEXTURE (OR COILING MOTORIZED DOOR OR CUSTOM VERTISTAK CONFIGURATION WITH LOW PROFILE HOOD). COLOR SHALL MATCH THE ADJACENT STUCCO (ULTRA-GRAIN). ONE DOOR SHALL HAVE SOLID PANELS IN ALL 4 SECTIONS, THE OTHER DOORS SHALL HAVE LONG WINDOWS WITH FROSTED TEMPERED GLAZING AND SOLID COMBINATION (SOL-GL) IN ALL 4 SECTIONS. INSTALL WEATHER STRIPPING AROUND PERIMETER AND BOTTOM SEALS.
- 14. GARAGE DOOR JAMBS AND HEADERS SHALL BE COVERED WITH

HARDWARE GROUPS:


- **GROUP 1:** (EXTERIOR DOOR) 1 1/2 PAIRS OF BUTTS
- 1 KNOB LOCKSET (ENTRY DOOR LOCK) 1 DEADBOLT
- 1 CONCEALED DOOR BOTTOM SET SMOKE SEAL CONTINUOUS
- 1 THRESHOLD DOOR STOP
- OPTION: KEYLESS TOUCHSCREEN LOCKING

GROUP 2: (GARAGE DOOR) SET HARDWARE PER MANUF.

- 1 SET AUTOMATIC OPENER 1 SET PERIMETER WEATHER STRIPPING
- WITH A V-2 FLAMMABLE RATING OR BETTER (UL 94) 1 SET BOTTOM SEALS




SEE DOOR SCHED



FRAME TYPES

DOOR TYPES




WINDOW SCHEDULE

WIN #	SIZE	TY	PE	DETAILS		GLAZING				FIRE LABEL	LABEL	ACOUSTIC	REMARKS		
		FR	MAT	HD	JB	SL	LOW-E DBL GL	TEMPERED	MAX U _{FACTOR}	MAX SHGC	MAX VT	RATING	TYPE	RATING	
W1-01	2'-0"W × 2'-0"H	А	MTL	5/A7.1	6/A7.1	7/A7.1	YES	YES	0.29	0.19	_	20	ı	ı	FIXED WINDOW WITH MTL THERMAL BREAK FRAME
W1-02	2'-0"W × 2'-0"H	А	MTL	5/A7.1	6/A7.1	7/A7.1	YES	YES	0.29	0.19	_	20	ı	ı	FIXED WINDOW WITH MTL THERMAL BREAK FRAME
W1-03	2'-0"W × 2'-0"H	А	MTL	5/A7.1	6/A7.1	7/A7.1	YES	YES	0.29	0.19	_	20	ı	ı	FIXED WINDOW WITH MTL THERMAL BREAK FRAME
_															

WINDOW NOTES:

- 1. ALL NEW WINDOWS SHALL BE BY "MILGARD" TUSCANY (OR MONTECITO) 8225T SUNCOATMAX TEMPERED LOW-E (OR APPROVED EQUAL) AND HAVE A NFRC LABEL RATING COMPLYING WITH OR EXCEEDING THE PERFORMANCE RATINGS IN THE WINDOW SCHEDULE. WINDOW GRILLES SHALL HAVE A PATTERN THAT MATCHES THE ELEVATIONS AND 3/4" IN WIDTH (STANDARD). INTERIOR AND EXTERIOR COLOR SHALL BE WHITE.
- 2. ALL EXTERIOR WINDOW FRAMES SHALL BE PER ELEVATIONS.

WINDOW TYPES:



PROJECT TITLE

M


REVISIONS

PLANNING SUBMITTAL PLANNING COMMENTS SCCFD AMMC PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS PLANNING COMMENTS **CONDITIONS & RESTRICTIONS**

These drawinas and all related specifications are nstruments of service and shall remain property o the designer. No revisions, reproductions, or use o these documents shall be made without the consent n these plans are to be field verified and all discrepancies are to be reported to the designer ndicated or consult the architect.

SHEET TITLE

DOOR & WINDOW SCHEDULES AND DETAILS



PROJECT NUMBER: 24111/6285 AS NOTED **A7.**′

2. THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY DISCREPANCY OCCURRING ON THE DRAWINGS OR FOUND IN HIS COORDINATION WORK. NO CHANGES IN APPROVED PLANS SHALL BE MADE WITHOUT PRIOR WRITTEN APPROVAL OF THE PROJECT

3. ANY REQUEST FOR ALTERATIONS OR SUBSTITUTIONS MUST BE PRESENTED DIRECTLY TO THE PROJECT ENGINEER, ACCOMPANIED BY A DETAILED SKETCH, FOR REVIEW, BEFORE ANY APPROVAL WILL BE GIVEN AND BEFORE PROCEEDING WITH THE WORK. ABSOLUTELY NO ALTERATIONS OF THESE DOCUMENTS OF ANY KIND WILL BE APPROVED ON ANY SHOP

4. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE PROVISIONS OF THE STATE OF CALIFORNIA STANDARD SPECIFICATIONS (CALTRANS), LATEST EDITION, THE TOWN OF LOS GATOS DESIGN CRITERIA AND ALL APPLICABLE CODES AND ORDINANCES.

THE LOCATIONS OF EXISTING UTILITIES AS SHOWN ON THE PLANS WERE OBTAINED FROM RECORD DRAWINGS AND MAY NOT REPRESENT TRUE LOCATION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION AND DEPTH OF THESE UTILITIES PRIOR TO CONSTRUCTION, AND TO NOTIFY THE PROJECT ENGINEER IN CASE OF CONFLICT.

6. THE CONTRACTOR SHALL SECURE ALL REQUIRED CONSTRUCTION PERMITS FROM THE TOWN OF LOS GATOS PRIOR TO THE START OF WORK.

7. CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERT THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD PROJECT ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED. IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. EXCEPTING LIABILITY RISING FROM THE SOLE NEGLIGENCE OF THE PROJECT ENGINEER.

8. GRADING SHALL BE DONE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL INVESTIGATIONS AND THE REQUIREMENTS OF THE TOWN OF LOS GATOS.

9. THE CONTRACTOR SHALL NOTIFY THE TOWN'S GRADING INSPECTOR, GEOTECHNICAL ENGINEER. THE CIVIL ENGINEER, & THE TOWN'S CONSTRUCTION ENGINEER AT LEAST 48 HOURS PRIOR TO TO THE START OF CONSTRUCTION.

10. WORK SHALL BE LIMITED TO 8:00 A.M. TO 5:00 PM WEEKDAYS. NON-NOISE PRODUCING ACTIVITIES, SUCH AS INTERIOR PAINTING, SHALL NOT BE SUBJECT TO THIS

11. NO LAND CLEARING, GRADING OR EXCAVATING SHALL TAKE PLACE BETWEEN OCTOBER 15 AND APRIL 15 UNLESS THE PLANNING DIRECTOR APPROVES A SEPARATE WINTER EROSION CONTROL PLAN.

12. BETWEEN OCTOBER 15 AND APRIL 15, EXPOSED SOIL SHALL BE PROTECTED FROM EROSION AT ALL TIMES. DURING CONSTRUCTION SUCH PROTECTION MAY CONSIST OF MULCHING AND/OR PLANTING OF NATIVE VEGETATION OF ADEQUATE DENSITY. BEFORE COMPLETION OF THE PROJECT, ANY EXPOSED SOIL ON DISTURBED SLOPES SHALL BE PERMANENTLY PROTECTED FROM EROSION.

13. THE CONTRACTOR SHALL APPLY WATER TO ALL EXPOSED EARTH SURFACES AT INTERVALS SUFFICIENT TO PREVENT AIRBORNE DUST FROM LEAVING THE PROJECT SITE. ALL EXPOSED EARTH SHALL BE WATERED DOWN AT THE END OF THE WORK DAY.

14. WHILE IN TRANSIT TO AND FROM THE PROJECT SITE, ALL TRUCKS TRANSPORTING FILL SHALL BE EQUIPPED WITH TARPS.

15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF CONSTRUCTION QUANTITIES PRIOR TO BIDDING ON ANY ITEM. QUANTITY REFERENCES SHOWN ON THESE PLANS. OR ENGINEER'S ESTIMATES ARE FOR ESTIMATING PURPOSES ONLY AND SHALL NOT BE CONSIDERED AS A BASIS FOR CONTRACTOR PAYMENT. CONSULTANT SHALL NOT BE RESPONSIBLE FOR ANY FLUCTUATIONS IN SUCH QUANTITIES AND ESTIMATES.

16. THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO, OR USES OF, THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.

17. UNDERGROUND UTILITY LOCATIONS SHOWN ARE COMPILED FROM INFORMATION SUPPLIED BY UTILITY AGENCIES, AND ARE APPROXIMATE ONLY. CONTRACTOR SHALL VERIFY LOCATIONS OF AFFECTED UTILITY LINES PRIOR TO ANY TRENCHING OR EXCAVATING AND POTHOLE THOSE AREAS WHERE POTENTIAL CONFLICTS EXIST OR WHERE DATA IS OTHERWISE INCOMPLETE. FOR LOCATION, CALL USA 1-800-624-1444.

18. ANY EXISTING UTILITIES THAT ARE REQUIRED TO BE RELOCATED AS A PART OF THIS CONSTRUCTION SHALL BE RELOCATED AT THE OWNER'S EXPENSE.

EARTHWORK AND GRADING

WORK SHALL CONSIST OF ALL CLEARING, GRUBBING, STRIPPING, PREPARATION OF LAND TO BE FILLED, EXCAVATION, SPREADING, COMPACTION AND CONTROL OF FILL, AND ALL SUBSIDIARY WORK NECESSARY TO COMPLETE THE GRADING TO CONFORM TO THE LINES, GRADES, AND SLOPES, AS SHOWN ON THE APPROVED PLANS.

2. ALL GRADING OPERATIONS SHALL CONFORM TO SECTION 19 OF THE CALTRANS STANDARD SPECIFICATIONS, AND SHALL ALSO BE DONE IN CONFORMANCE WITH THE REQUIREMENTS OF THE TOWN OF LOS GATOS. THE MOST STRINGENT GUIDELINE SHALL

3. REFERENCE IS MADE TO THE GEOTECHNICAL INVESTIGATIONS BY C2EARTH, INC., ENTITLED "GEOTECHNICAL STUDY FOR THE PROPOSED GARAGE REPLACEMENT FOR THE KOLANDER PROPERTY AT 16511 CYPRESS WAY IN LOS GATOS," DATED JUNE 2024. THE CONTRACTOR SHALL MAKE A THOROUGH REVIEW OF THIS REPORT AND SHALL FOLLOW ALL RECOMMENDATIONS THEREIN. THE CONTRACTOR SHALL CONTACT CZEARTH, INC. FOR ANY CLARIFICATIONS NECESSARY PRIOR TO PROCEEDING WITH THE WORK.

4. THE CONTRACTOR SHALL GRADE TO THE LINE AND ELEVATIONS SHOWN ON THE PLAN AND SHALL SECURE THE SERVICES OF A LICENSED LAND SURVEYOR OR REGISTERED CIVIL ENGINEER TO PROVIDE STAKES FOR LINE AND GRADE.

5. THE GEOTECHNICAL ENGINEER SHOULD BE NOTIFIED AT LEAST FOUR (4) DAYS PRIOR TO ANY SITE CLEARING AND GRADING OPERATIONS.

6. STRIPPED AREAS SHOULD BE SCARIFIED TO A DEPTH OF ABOUT 6", WATER-CONDITIONED TO BRING THE SOILS WATER CONTENT TO ABOUT 2% ABOVE THE OPTIMUM, AND COMPACTED TO A DENSITY EQUIVALENT TO AT LEAST 90% OF THE MAXIMUM DRY DENSITY OF THE SOIL ACCORDING TO ASTM D1557 (LATEST EDITION). SUBGRADES AND AGGREGATE BASE ROCK FOR PAVEMENTS SHOULD BE COMPACTED TO A MINIMUM OF 95%.

7. ENGINEERED FILL SHOULD BE PLACED IN THIN LIFTS NOT EXCEEDING 8" IN LOOSE THICKNESS, MOISTURE CONDITIONED, AND COMPACTED TO AT LEAST 90% RELATIVE

8. MATERIAL USED FOR ENGINEERED FILL SHALL MEET THE REQUIREMENTS OF THE AFOREMENTIONED REPORTS BY C2EARTH, INC..

). IMPORTED FILL MATERIAL USED AS ENGINEERED FILL FOR THE PROJECT SHALL MEET THE REQUIREMENTS OF THE AFOREMENTIONED GEOTECHNICAL INVESTIGATION.

10. ALL FILL MATERIAL SHALL BE APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER PRIOR TO JOBSITE DELIVERY AND PLACEMENT. NO EARTHWORK OPERATIONS SHALL BE PERFORMED WITHOUT THE DIRECT OBSERVATION AND APPROVAL OF THE GEOTECHNICAL

11. BARE GROUND WITHIN 10' OF FOUNDATIONS SHALL BE SLOPED AWAY @ 5% MINIMUM OR 2% MINIMUM FOR PAVED SURFACES.


IMPERVIOUS AREA CALCULATIONS

1,638 SF - 873 SF = 765 SF

EXISTING TO BE REMOVED: **GARAGE:** PROPOSED IMPROVEMENTS: **CONCRETE:** 265 SF TOTAL CREATED AND/OR REPLACED IMPERVIOUS AREA: 873 SF + 1.638 SF = 2.511 SF TOTAL INCREASE IN IMPERVIOUS AREA:

POST CONSTRUCTION STORM DRAIN SYSTEM MAINTENANCE SCHEDULE

ITEM	INTERVAL	INSPECTION	REPAIR
SWALES	ANNUAL	1. WASHOUTS 2. MISPLACED ROCK 3. ACCUMULATION OF TRASH & DEBRIS	REPLACE TRANSPORTED ROCK REMOVE TRASH & DEBRIS



1 INCH = 10 FEET

STORM DRAIN SYSTEM MAINTENANCE

DISCHARGE ALL DOWNSPOUTS ONTO SPLASH BLOCKS.


STORM DRAINAGE NOTES

THE HOME OWNER IS RESPONSIBLE FOR MAINTAINING THE STORM DRAINAGE SYSTEM

(OCTOBER 15TH) ALL THE CATCH BASINS AND STORM DRAIN CLEANOUTS SHALL BE

AND ALL COMPONENTS. EVERY YEAR, PRIOR TO THE WET WEATHER SEASON

INSPECTED AND CLEANED OF ANY DEBRIS, SILT, TRASH AND SEDIMENT.



VICINITY MAP

ABBREVIATIONS BOTTOM OF WALL CONCRETE DRAINAGE INLET DOWNSPOUT FINISH FLOOR FINISH GRADE FIRE SERVICE HIGH POINT LINEAR FEET MAXIMUM NOT TO SCALE **RETAINING WALI** RIM ELEVATION SANITARY SEWER CLEANOUT TOP OF WALL WATER SERVICE

LEGEND (E) AC (E) CONCRETE (E) TILE PAVING PROPOSED AC PROPOSED CONCRETE

MAJOR (E) GRADE CONTOUR LINES (E) RETAINING WALL (E) BUILDING TO REMAIN

PROPOSED GRAVEL

LEAST RESTRICTIVE DEVELOPMENT AREA (LRDA)

PROPOSED LIMIT OF GRADING

TREE TO BE REMOVED TREE NUMBER ASSIGNED BY ARBORIST PROPERTY LINE

TREE TO REMAIN

PROPOSED RETAINING WALL PROPOSED SAWCUT

PROPOSED GRASS SWALE PROPOSED ROCK SWALE

PROPOSED CONTOUR LINES

APPROXIMATE EARTHWORK QUANTITIES

PROPOSED SD

AVERAGE SLOPE: ~32%	EARTHWO	ORK (CY)	MAX CUT/FIL	L DEPTH (FT)	(CY)		
SITE ELEMENT	CUT	FILL	CUT	FILL	IMPORT	EXPORT	
LANDSCAPE	236	0	7	-	0	236	
MISC. HARDSCAPE	57	0	11	-	0	57	
GARAGE	122	0	13.5	-	0	122	
TOTAL	415	0			0	415	

*LANDSCAPE INCLUDES GRADING SOUTH OF GARAGE. *MISC. HARDSCAPE INCLUDES CONCRETE PAD AND RETAINING WALL GRADING.

DRAINAGE CONDITIONS AND NOTES

RI ENGINEERING HAS REVIEWED THE EXISTING AND PROPOSED DRAINAGE PATTERS. EXISTING DRAINAGE CONDITIONS WILL REMAIN UNCHANGED. THE PROPERTY IS LOCATED WITHIN THE TOWN OF LOS GATOS HILLSIDE AREA AND SUBJECT TO HILLSIDE DEVELOPMENT STANDARDS AND GUIDELINES.

THE EXISTING STORMWATER RUNOFF LEAVING THE PROPERTY TRAVELS NORTH & NORTHWEST, OVERLAND THROUGH HEAVILY VEGETATED LANDS WHILE MAINTAINING HARMONY WITH THE NATURAL SETTINGS AS REQUIRED BY THE HILLSIDE STANDARDS. RUNOFF FROM THE PROPERTY FLOWS TOWARDS ROSS CREEK WHICH RUNS APPROXIMATELY 1,500 NORTH EAST OF THE PROPERTY. NO FORESEEN ADVERSE IMPACT TO THE PUBLIC RIGHT OF WAY OR NEIGHBORING PROPERTIES IS ANTICIPATED.

THE PROJECT WILL RESULT IN 2,232 SF OF NEW AND/OR REPLACED IMPERVIOUS AREA. THE INCREASE IN STORMWATER RUNOFF WILL BE MITIGATED BY DISCHARGING DOWNSPOUTS ONTO SPLASH BLOCKS AND INFILTRATED IN EXISTING VEGETATED AREAS.

TOPOGRAPHIC SURVEY

THE TOPOGRAPHIC SURVEY AND BOUNDARY INFORMATION PROVIDED HEREON WAS COMPLETED BY CARNES & ASSOCIATES. RI ENGINEERING INC. MAKES NO GUARANTEE AS TO THE ACCURACY OF BOTH. THE CONTRACTOR SHALL VERIFY THE BOUNDARY LOCATION AND TOPOGRAPHIC INFORMATION PRIOR TO COMMENCING WORK.


BASIS OF BEARINGS

THE BEARINGS ON THIS MAP ARE BASED ON THE 1.457 & AND THE 1.254 ACRE PARCELS AS FOUND MONUMENTED AND RECORDED AS NORTH IN BOOK 57 OF MAPS AT PAGE 56, RECORDS OF SANTA CLARA COUNTY, CALIFORNIA.

BASIS OF ELEVATION

THE ON-SITE BENCHMARK FOR THIS PROJECT IS A 60D NAIL. ELEVATION 938.00 FEET (ASSUMED)

PLANNING SUBMITTAL




 \Box

project no. 24-033-1

FEBRUARY 2025

AS SHOWN

dwg name CIVIL3.dwg



932 932 928 928 924 924 (E) GROUND — 920 (E) AC DRIVEWAY 912 908 —(E) RETAINING WALL 908 904 904 SECTION C-C SCALE: 1"=10' HORIZONTAL, VERTICAL

952

948

944

940

936

928

924

920

916

912

960

956

948

936

928

924

920

916

912

(E) PATIO

(E) FENCE

ROOFLINE, SEE ARCHITECT — PLANS FOR DETAILS

GARAGE FF=920.8

SECTION A-A

SCALE: 1"=10' HORIZONTAL, VERTICAL

FINISHED GRADE-


2 GRASS LINED SWALE 2%


6 VALLEY GUTTER


SECTION B-B SCALE: 1"=10' HORIZONTAL, VERTICAL

(E) GROUND -

- #3 CONTINUOUS (TYP) CONCRETE SWALE SECTION







DISPERSION PAD DETAIL 4

NTS

4
C-2

LINE SWALE W/ — 4"ø avg rock

— SCARIFY UPPER 6" AND RECOMPACT TO 90% R.C.

ROCK LINED SWALE DETAIL

NTS

GRASS LINED SWALE DETAIL

(E) AC ¬

SAWCUT EDGE TO— CREATE SMOOTH LINE

FILTER FABRIC

— PLANT SWALE WITH NATIVE GRASSES

952

948

944

932

928

924

920

916

960

956

948

940

928

920

ROOFLINE, SEE ARCHITECT 936
PLANS FOR DETAILS

(E) DRIVEWAY

(E) FENCE —

(E) GROUND —

FINISHED GRADE


SITE RETAINING WALL.
SEE STRUCTURAL PLANS

CONCRETE SWALE $\frac{5}{C-2}$


— SITE RETAINING WALL. SEE STRUCTURAL PLANS


GARAGE FF=920.8


- ROCK LINED SWALE $\left(\begin{array}{c} 1 \\ C-2 \end{array}\right)$





-6" CLASS 2 AGGREGATE BASE











VIEW

FOS

🏿 RICHARD J. IRISH

Exp. 12-31-26

02/13/2025

. Cruz, C/ ng.com

303 Potrero St., Suite 831-425-3901 w

Z Z


eering,

Engin

RI

project no. 24-033-1 FEBRUARY 2025

AS SHOWN dwg name CIVIL3.dwg



SITE HOUSEKEEPING REQUIREMENTS

- CONSTRUCTION MATERIALS


 1. ALL LOOSE STOCKPILED CONSTRUCTION MATERIALS THAT ARE NOT ACTIVELY BEING USED (I.E. SOIL, SPOILS, AGGREGATE, FLY-ASH, STUCCO,
- HYDRATED LIME, ETC.) SHALL BE COVERED AND BERMED. 2. ALL CHEMICALS SHALL BE STORED IN WATERTIGHT CONTAINERS (WITH APPROPRIATE SECONDARY CONTAINMENT TO PREVENT ANY SPILLAGE OR
- LEAKAGE) OR IN A STORAGE SHED (COMPLETELY ENCLOSED). 3. EXPOSURE OF CONSTRUCTION MATERIALS TO PRECIPITATION SHALL BE MINIMIZED. THIS DOES NOT INCLUDE MATERIALS AND EQUIPMENT THAT ARE DESIGNED TO BE OUTDOORS AND EXPOSED TO ENVIRONMENTAL CONDITIONS (I.E. POLES, EQUIPMENT PADS, CABINETS, CONDUCTORS,
- INSULATORS, BRICKS, ETC.). BEST MANAGEMENT PRACTICES TO PREVENT THE OFF-SITE TRACKING OF LOOSE CONSTRUCTION AND LANDSCAPE MATERIALS SHALL BE

- LANDSCAPE MATERIALS


 1. CONTAIN STOCKPILED MATERIALS SUCH AS MULCHES AND TOPSOIL WHEN THEY ARE NOT ACTIVELY BEING USED. CONTAIN FERTILIZERS AND OTHER LANDSCAPE MATERIALS WHEN THEY
- ARE NOT ACTIVELY BEING USED. 3. DISCONTINUE THE APPLICATION OF ANY ERODABLE LANDSCAPE MATERIAL WITHIN 2 DAYS BEFORE A FORECASTED RAIN EVENT OR DURING PERIOD
- APPLY ERODABLE LANDSCAPE MATERIAL AT QUANTITIES AND APPLICATION RATES ACCORDING TO MANUFACTURE RECOMMENDATIONS OR BASED ON WRITTEN SPECIFICATIONS BY KNOWLEDGEABLE AND EXPERIENCED FIELD
- 5. STACK ERODABLE LANDSCAPE MATERIAL ON PALLETS AND COVERING OR STORING SUCH MATERIALS WHEN NOT BEING USED OR APPLIED.

VEHICLE STORAGE AND MAINTENANCE 1. MEASURES SHALL BE TAKEN TO PREVENT OIL, GREASE, OR FUEL TO LEAK IN TO THE GROUND, STORM DRAINS OR SURFACES WATERS.


- ALL EQUIPMENT OR VEHICLES. WHICH ARE THE BE FUELED. MAINTAINED AND STORED ONSITE SHALL BE IN A DESIGNATED AREA FITTED WITH
- 3. LEAKS SHALL BE IMMEDIATELY CLEANED AND LEAKED MATERIALS SHALL BE DISPOSED OF PROPERLY. WASTE MANAGEMENT
- DISPOSAL OF ANY RINSE OR WASH WATERS OR MATERIALS ON IMPERVIOUS OR PERVIOUS SITE SURFACES OR INTO THE STORM DRAIN SYSTEM SHALL BE PREVENTED.
- 2. SANITATION FACILITIES SHALL BE CONTAINED (E.G., PORTABLE TOILETS) TO PREVENT DISCHARGES OF POLLUTANTS TO THE STORM WATER DRAINAGE SYSTEM OR RECEIVING WATER, AND SHALL BE LOCATED A MINIMUM OF 20 FEET AWAY FROM AN INLET, STREET OR DRIVEWAY, STREAM, RIPARIAN AREA OR OTHER DRAINAGE FACILITY.
- SANITATION FACILITIES SHALL BE INSPECTED REGULARLY FOR LEAKS AND SPILLS AND CLEANED OR REPLACED AS NECESSARY. COVER WASTE DISPOSAL CONTAINERS AT THE END OF EVERY BUSINESS
- DAY AND DURING A RAIN EVENT.
 DISCHARGES FROM WASTE DISPOSAL CONTAINERS TO THE STORM WATER
- DRAINAGE SYSTEM OR RECEIVING WATER SHALL BE PREVENTED. 6. STOCKPILED WASTE MATERIAL SHALL BE CONTAINED AND SECURELY
- PROTECTED FROM WIND AND RAIN AT ALL TIMES UNLESS ACTIVELY BEING
- 7. PROCEDURES THAT EFFECTIVELY ADDRESS HAZARDOUS AND NON-HAZARDOUS SPILLS SHALL BE IMPLEMENTED.
- 8. EQUIPMENT AND MATERIALS FOR CLEANUP OF SPILLS SHALL BE AVAILABLE ON SITE AND THAT SPILLS AND LEAKS SHALL BE CLEANED UP IMMEDIATELY AND DISPOSED OR PROPERLY; AND
- CONCRETE WASHOUT AREAS AND OTHER WASHOUT AREAS THAT MAY CONTAIN ADDITIONAL POLLUTANTS SHALL BE CONTAINED SO THERE IS NO DISCHARGE INTO THE UNDERLYING SOIL AND ONTO THE SURROUNDING



FIBER ROLL DETAIL IN SLOPE AREA



TYPICAL FIBER ROLL INSTALLATION



EROSION CONTROL MEASURES

- EROSION IS TO BE CONTROLLED AT ALL TIMES ALTHOUGH SPECIFIC MEASURES SHOWN ARE TO BE IMPLEMENTED AT A MINIMUM BY OCTOBER 15.
- 2. UNLESS SPECIFIC MEASURES ARE SHOWN OR NOTED ON THIS PLAN, ALL COLLECTED RUNOFF SHALL BE CARRIED TO DRAINAGE COURSES IN LINED CONDUITS. DISCHARGE SHALL BE IN THE LOCATIONS SHOWN ON THE PLANS.
- 3. THE DESIRED END RESULT OF THESE MEASURES IS TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF THE SITE. IT SHALL BE THE DEVELOPER'S RESPONSIBILITY TO SEE THAT ANY ADDITIONAL MEASURES NECESSARY TO MEET THIS GOAL ARE IMPLEMENTED. IF FAILED INSPECTIONS BY COUNTY STAFF SHOW THIS GOAL IS NOT BEING MET, ADDITIONAL MEASURES MAY BE REQUIRED.
- 4. ALL DISTURBED AREAS NOT CURRENTLY BEING USED FOR CONSTRUCTION SHALL BE SEEDED WITH THE FOLLOWING SEED MIXTURE:
 - WINTER BARLEY 25#/ACRE
- 5. AFTER SEEDING, STRAW MULCH WILL BE APPLIED IN 4" (AVG.) LAYERS.
- AMMONIUM PHOSPHATE FERTILIZER, 6-3-3, SHALL BE APPLIED AT A RATE OF 30 LBS. PER ACRE. ON SLOPES GREATER THAN 20% EROSION CONTROL BLANKET (NORTH AMERICAN GREEN) SHALL BE APPLIED.
- 7. SILT BARRIERS SHALL BE PLACED END TO END AND STAKED DOWN ALONG THE BOTTOM OF ALL GRADED


ALL EROSION CONTROL MEASURES INCLUDING BUT NOT LIMITED TO SILT FENCES, FIBER ROLLS AND SLOPE PROTECTION SHALL BE IN PLACE BY OCTOBER 15TH. THE ENGINEER OF RECORD SHALL INSPECT ONCE EROSION CONTROL MEASURES HAVE BEEN INSTALLED.

EXPOSED SLOPE MEASURES

- 1. COVER ALL EXPOSED SLOPES
- 2. STRAW 2 TONS/ACRE ON SLOPES ≤ 20% WITH SOIL
- 3. USE NORTH AMERICAN GREEN C125 OR EQUAL ON SLOPES >20%.

EROSION CONTROL LEGEND

INSTALL FIBER ROLL PER DETAILS



INSTALL CATCH BASIN PROTECTION


PER DETAIL THIS SHEET




PROPOSED STOCKPILE AREA



PROPOSED STAGING AREA






PLAN VIEW

GRAVEL BAG CATCH BASIN PROTECTION

PLANNING SUBMITTAL



R Cruz,

project no. 24-033-1

FEBRUARY 2025

AS SHOWN

dwg name CIVIL3.dwg

