233 Stokes Street Unit D
Huntsville, AL 35805
Phone (256)326-9871
Fax (256)539-6482
tnbconcrete@aol.com

TNB CONSTRUCTION & CONCRETE

Footing * Driveways * Patios * Slabs * New Construction * Foundation * Remodeling

PROPOSAL

Proposal Submitted To:
Cody Wright
Madison City Engineering

Date: October 13, 2023
Phone: (256) 694-0509
Email: @.com

TNB President/Contact Info
Willie Hawkins 256-326-9871

PROJECT: Lewis Lane/ Barbara Dr. Madison, AL 35758

We hereby submit specifications and estimates for: **Concrete ADA Repairs**
1. Dig out and haul away asphalt/concrete
2. Set up and pour 8 ADA sidewalk/Pads
3. Concrete will be 5 inches thick reinforced with fiber mesh
4. Concrete will have broom finish with ADA mats
5. Back fill and sod included in price
6.TNB will provide all labor and materials

We Propose hereby to furnish labor and materials – complete in accordance with above specifications, for the sum of:

Twenty-Eight Thousand Four Hundred Fifty 00/100 **Dollars ($ 28,450)**

Comments: Concrete Truck must be allowed to pull up to area or Owner will have to Pay for a Concrete Pump.

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Signature _____

Date of Acceptance: _____