
CHORBA CONTRACTING CORPORATION

January 30, 2024

Mr. James Dyar
City of Madison
100 Hughes Rd.
Madison, AL 35758

Re: Trash Pandas Stadium Shower Area Renovations

James:

As requested, we submit the following proposal for work associated with shower area renovations. Our scope of work included is outlined as follows:

- Sawcut and removal of existing flake/epoxy floors for install of new floor drains at Officials, Visitors, and Coaches Locker Rooms.
- Pour and place concrete infill of slab at new drain locations.
- Diamond grind and apply new flake/epoxy finish to match existing shower floors at locations of new floor drains.
- Install new drainage system, connecting to existing sewer at nearest locations. Install new 40" long Zurn Z886-SVF trench drain with stainless steel top at Officials and Coaches Locker Room, and a 60" long Zurn Z886-SVF trench drain with stainless steel top at Visitors Locker Room.
- Protection of all work areas and final clean-up of all work areas.

Our total proposal as outlined above is \$65,176.00

Thank you for the opportunity to offer this proposal and please call if you have any questions regarding.

Chorba Contracting Corporation



George M. Likos
President

GML/dkh
Cc: file