

December 11, 2023

Mr. Gerald Smith
Director of Facilities and Grounds
City of Madison
100 Hughes Rd.
Madison, AL 35758

Gerald:

As requested, we submit the following proposal for Toyota Field Weight Room/Training Room Renovations. Our scope of work included is outlined as follows:

- Demo and remove existing CMU divider wall between Weight Room/Training Room.
- Demo and remove existing carpet as required for new Norament flooring extension.
- Prep slab where wall is removed to receive new flooring.
- Sawcut and demo slab for new foundation for new divider wall.
- Excavations for new wall foundations to achieve depth for 1' thick footing and 2 courses of CMU wall below finish floor (per detail provided).
- Reinforced concrete footing for new CMU wall.
- New reinforced 8" CMU wall, 16" below finish floor, 4'-8" above finish floor, 4" solid block cap. Wall to be solid filled with concrete.
- Infill slab at new wall.
- Paint new CMU wall.
- Prep floor and install new Norament athletic flooring to match existing in extended weight room area. Rework existing carpet as required to make clean transition between Weight/Training.
- Install new 4" rubber base at new CMU wall, to match existing rubber base.
- Remove and relocate existing electrical outlets in new CMU wall.
- Final cleaning of disturbed area.

Duration for project is approximately five (5) weeks.

We exclude permit drawing and relocation of any other utilities not outlined above.

Our total proposal as outlined above is..... \$62,159.00

Thank you for the opportunity to offer this proposal. Please call if you have any questions regarding.

Chorba Contracting Corporation



George M. Likos
President

GML/dkh

Cc: file