



www.baselinellc.com

Date: December 21, 2023

Attention: Mr. Randy D'Herde
City of Madison, AL
100 Hughes Road
Madison, AL 35758

Re: Intergraph Park – LED Lighting Installation

CHANGE ORDER #1 – Work Scope:

- 1) Intercept main conduits from switchgear room and install rated Quazite boxes (2).
- 2) At each pole (16) install rated Quazite boxes and run galvanized conduits above ground to MUSCO Electrical panel.
- 3) Each pole to have a home run dedicated circuit with #10 wiring to account for voltage drop and loading. Each wire will be phased taped to correlate with the Musco circuit relays.
- 4) Install separate electrical service to south field scoreboard location then daisy chain that branch circuit to the north field scoreboard. Disconnects will be mounted on both score board pedestals.
- 5) As-built sets of drawings depicting circuitry and pole locations will be laminated and installed in the MUSCO panel and switchgear panel.

Total Cost: \$71,900

Terms & Conditions:

- 1) Does not allow for rock removal if encountered during trenching operations.
- 2) Assumes adequate access and staging will be provided for work duration.

Please don't hesitate to call or email if you have any questions.

A handwritten signature in black ink, appearing to read "S Clift".

Steve Clift

(m) 423-593-8284

steve@baselinellc.com



3600 Henson Road, Knoxville, TN 37921
(800) 205-9521 (865) 588-4320 fax: (865) 588-4111
Email: info@baselineLLC.com